



Risk-Based Cost Estimating at MnDOT

CDOT Peer Exchange
May 10, 2016

We all have a stake in **A to B**



MnDOT – Methodology

- MnDOT is set up similar to CDOT in structure
 - Decentralized – 8 Districts, 1 Central Office



MnDOT – Methodology

- ▶ Districts – District Estimator/Estimating Coordinator
- ▶ Central Office
 - Cost Estimating Group
 - Provide PS&E estimates
 - NEW – Independent Estimating Group
 - Provide independent estimate reviews during project development
 - Risk-based cost estimating capabilities



Cost Management – Budget Setting

- ▶ Why?
 - MnDOT Wildly Important Goal, 2013–2015: Enhance Financial Effectiveness
 - Project Management – one focus on Project Cost Management
 - Between 2010 and 2013, only 35% of 738 projects let had bid awards within $\pm 15\%$ of STIP amount
 - Between 2010 and 2013, 51% of 738 projects let had bid awards within $\pm 10\%$ of Engineer's Estimate
 - Tool to help PMs manage scope of project
 - Goal to be on budget



Corridors of Commerce

- ▶ State funding program through special legislation, available from July 2014 to June 2018
- ▶ \$300 million total available with 10 projects identified
- ▶ Objectives of program
 - Identify baseline costs and risks for each project and the overall CoC program
 - Establish construction budgets for program delivery, projects, and program contingency
 - Develop processes and mechanisms to manage program contingency funds



Corridors of Commerce

- ▶ Initial Cost range to deliver 10 projects: \$270M – \$356M
- ▶ Projects selected in various stages of development
- ▶ Worked with WSP/PB to conduct risk management process in order to:
 - Determine if sufficient funds were available to deliver all projects
 - Recommend budgets for projects based on available funds and risks associated with project
 - Identify project risks for managing by PMs
 - Recommend process and budget for managing program contingency



Corridors of Commerce

- ▶ Risk-based cost estimates used to determine risk contingency for individual projects and overall program
- ▶ Risk contingency carried for overall program rather than in individual project budget
- ▶ Carrying risk at program level estimated 83% chance program costs would not exceed available funds



Corridors of Commerce

Distr.	Project	Route	Construction Budget	Actual Letting Cost	Difference	% Difference
1	SP 3116-142	US 169	\$ 8,264,558.00			
2	SP 1102-62	US 2	\$ 10,457,000.00	\$ 13,311,647.93	\$ 2,854,647.93	27%
3	SP 2780-66	I-94	\$ 32,352,704.00	\$ 28,327,500.00	\$ (4,025,204.00)	-12%
4	SP 0303-64	MN 34	\$ 9,951,673.00	\$ 7,918,423.51	\$ (2,033,249.49)	-20%
6	SP 7402-30	US 14	\$ 15,000,000.00	\$12,010,983.48	\$ (2,989,016.52)	-20%
7	SP 5203-104	US 14	\$ 38,460,500.00	\$ 31,659,659.79	\$ (6,800,840.21)	-18%
8	SP 4206-22	MN 23	\$ 10,339,000.00	\$ 4,100,056.00	\$ (6,238,944.00)	-60%
M	SP 2771-37	MN 610	\$ 100,309,058.00	\$ 80,725,000.00	\$ (19,584,058.00)	-20%
M	SP 6285-143	I-694	\$ 42,255,118.00	\$ 34,695,022.00	\$ (7,560,096.00)	-18%
			\$ 267,389,611.00	\$ 212,748,292.71	\$ (46,376,760.29)	



Lessons Learned

- ▶ P80 is a high confidence level to set
 - All but one project let has come in >12% under budget
- ▶ Overall methodology of using cost estimate, uncertainty and risk to determine budgets will work
- ▶ Saw support of budgets from staff who worked on CoC projects



Beyond Corridors of Commerce

- ▶ Budget setting for all projects MnDOT's program
- ▶ Started with pilot program of sampling from FY16 and FY 17 projects
 - Pavement and Bridge projects
- ▶ Brought WSP/PB on board to help
 - Budgets
 - Risk Workshops
 - Process and guidance information for cost management (risk, uncertainty, etc.)



Current MnDOT Approach

- ▶ Based on CoC idea of utilizing risk-based cost estimates to set project budget
- ▶ Project Categorization
 - Priority 1: <\$10M
 - Priority 2: \$10M to <\$25M
 - Priority 3: \$25M and up
- ▶ Include special programs, bond programs, areas of higher risk within Priority 2 requirements



Current MnDOT Approach

- ▶ Priority 2 and Priority 3 Projects
 - Cost Estimate
 - Risk Register
 - Quantitative risk analysis applied to estimate, estimate uncertainty and risks
 - Priority 3 projects also will need formal risk workshop or CRAVE workshop



Current MnDOT Approach

► Priority 1 Projects

- Data
 - Cost Estimate
 - Risk Register
- Developing scalability “analysis” of risk
 - Smaller, straight forward projects with small risk associated
 - Working to create ranges of factors for risk and uncertainty vs. general numbers off table or curve
 - Reviewing past projects of EE vs. bid
 - Categorizing by major work type



Project Development Phase	Project Maturity (% project definition completed)	Purpose of the Estimate	Estimating Methodology	Estimate Range
Scoping	10% to 30%	Design Estimating— Establish a Baseline Cost for Project and Program Projects (IRP and STIP)	Historical Bid-Based or Cost-Based (Mixed, but Primarily Stochastic)	-30% to +50%
Design	30% to 90%	Design Estimating— Manage Project Budgets against Baseline (STIP, Contingency)	Historical Bid-Based or Cost-Based (Primarily Deterministic)	-10% to +25%
Final Design	90% to 100%	PS&E Estimating— Compare with Bid and Obligate Funds for Construction	Cost-Based or Historical Bid-Based Using Cost Estimate System (Deterministic)	-5% to +10%



Other Lessons Learned

- ▶ Project Managers tend to be overconfident about estimates during scoping and preliminary design
 - Working to encourage PMs to review top pay items closely and use tighter uncertainty on those items
 - Lower pay items use higher range of uncertainty due to unknowns
- ▶ Centralized Cost Estimating
 - Pros – consistent estimating process; dedicated estimators
 - Cons – less ownership in estimates by districts



Other Items

- ▶ Continue to work with Districts to encourage buy-in for project budgeting
 - Pilot projects – met with sampling of Districts to discuss process and benefits
 - Budget setting is a change in how we do business

