# 2011
# COST DATA
## Jan. – Dec.

**Compiled By**

**Engineering Estimates and Market Analysis Unit**

**of the**

**Agreements and Market Analysis Branch**

**March 12, 2012**

# COLORADO COST DATA

## FOREWORD

**The Colorado Department of Transportation's Engineering Estimates and Market Analysis (EEMA) Unit, of the Agreements and Market Analysis Branch, publishes the Cost Data Book annually. A joint effort has been made between the Department's sections and the EEMA Unit to gather and record cost data for this publication.**

**The following data includes weighted average prices for items on highway construction projects that were bid during the 2011 calendar year. Caution should be used in applying these historical averages to specific projects. Allowances for varying geographic, climatic, social, economic conditions and type of project should be made.**

**Changes and improvements are continually being made to update and increase the usefulness for future issues. Comments and suggestions for improvements for users of this publication are welcome. A copy of this book is also available on CD-ROM upon request.**

**Copies of publications may be obtained on hard copy:**

**Colorado Department of Transportation**
**Bid Plans**
**4201 E. Arkansas Avenue**
**Denver, Colorado 80222**
**Phone: 303-757-9313**

# 2011 COST DATA

## CONSTRUCTION

# TABLE OF CONTENTS


| | # OF PAGES |
|---|---|
| **BRIDGE COST PER SQUARE FEET** | **4** |
| **LIST OF 2011 BID PROJECTS** | **6** |
| **ITEM AVERAGE BID PRICES** | **33** |
| **ITEM UNIT COSTS BY PROJECT** | **539** |
| **Appendix A – 2011 Maintenance Type Projects** | *** released on the CDOT web-site** |

2011 Cost Data
BRIDGE COST PER SQUARE FOOT
(01/01/11 THROUGH 12/31/11)

| DATE LET | PROJECT NUMBER/ PROJECT LOCATION | TERR/ BRIDGE ID | LENGTH | WIDTH | TOTAL SQUARE FT | TOTAL COST | COST PER SQUARE FOOT |
|---|---|---|---|---|---|---|---|
| | | BRIDGE REPAIR | | | | | |
| 110512 | IM0704-223 | U | | | | | |
| | I-70:HOLLY TO SAND CREEK | E-17-HX | 130.5000 | 48.0000 | 6264.0 | $90,957 | $14.52 |
| | | E-17-HW | 130.5000 | 48.0000 | 6264.0 | $90,957 | $14.52 |
| | | E-17-GD | 130.6000 | 48.0000 | 6268.8 | $90,830 | $14.49 |
| | | E-17-GC | 131.0000 | 48.0000 | 6288.0 | $90,913 | $14.46 |
| | | E-17-EW | 213.1000 | 52.0000 | 11081.2 | $372,878 | $33.65 |
| | | E-17-DF | 213.1000 | 52.0000 | 11081.2 | $372,878 | $33.65 |
| | | E-17-GB | 130.5000 | 48.0000 | 6264.0 | $166,960 | $26.65 |
| | | E-17-GA | 131.0000 | 48.0000 | 6288.0 | $167,465 | $26.63 |
| 110714 | FBR0502-066 | R | | | | | |
| | US50 GUNNISON COUNTY MM 155.37 | J-09-C | 128.0000 | 20.0000 | 2560.0 | $764,824 | $298.76 |
| | | J-09-D | 128.0000 | 20.0000 | 2560.0 | $931,509 | $363.87 |
| 111222 | IM 0702-310 | M | | | | | |
| | I-70 MP 72.3 IN GARFIELD COUNT | G-04-BE | 345.0000 | 34.0000 | 11730.0 | $339,617 | $28.95 |
| | | | WEIGHTED AVERAGE COST: | | | | |
| | | | NEW STRUCTURES | | 76649.2 | $3,479,787 | $45.40 |
| | | BRIDGE DECK REPLACEMENT | | | | | |
| 110414 | BR0701-207 | R | | | | | |
| | I-70 SKIPPERS ISLAND MULTIPLE | | 283.0000 | 39.5000 | 11178.5 | $217,664 | $19.47 |
| | | H-01-AD | 283.0000 | 39.5000 | 11178.5 | $216,332 | $19.35 |
| | | H-01-AC | 272.0000 | 39.5000 | 10744.0 | $205,184 | $19.10 |
| | | H-01-AB | 272.0000 | 39.5000 | 10744.0 | $205,017 | $19.08 |
| | | | WEIGHTED AVERAGE COST: | | | | |
| | | | NEW STRUCTURES | | 43845.0 | $844,197 | $19.25 |
| | | CONCRETE SLAB AND GIRDER | | | | | |
| 110127 | FBR089A-013 | P | | | | | |
| | ON SH 89 FROM MP 33.21 TO MP 3 | L-28-H | 508.0000 | 43.0000 | 21844.0 | $2,442,802 | $111.83 |
| 110414 | STA141A-035 | M | | | | | |
| | SH 141 UNAWEEP CANYON OVERLAY | I-02-B | 93.0000 | 24.0000 | 2232.0 | $54,854 | $24.58 |
| | | I-02-K | 70.0000 | 24.0000 | 1680.0 | $41,807 | $24.88 |
| 110414 | BR0701-207 | R | | | | | |
| | I-70 SKIPPERS ISLAND MULTIPLE | H-02-FP | 138.0000 | 39.5000 | 5451.0 | $103,006 | $18.90 |
| | | | 138.0000 | 39.5000 | 5451.0 | $102,488 | $18.80 |
| | | H-02-FN | 124.0000 | 39.5000 | 4898.0 | $91,976 | $18.78 |
| | | H-02-FM | 124.0000 | 39.5000 | 4898.0 | $91,606 | $18.70 |

2011 Cost Data
BRIDGE COST PER SQUARE FOOT
(01/01/11 THROUGH 12/31/11)

| DATE LET | PROJECT NUMBER/ PROJECT LOCATION | TERR/ BRIDGE ID | LENGTH | WIDTH | TOTAL SQUARE FT | TOTAL COST | COST PER SQUARE FOOT |
|---|---|---|---|---|---|---|---|
| 110512 | STU 2254-082 | U | | | | | |
| | US 40(COLFAX) / I-225 | F-17-JK | 231.5000 | 137.5000 | 31831.3 | $559,604 | $17.58 |
| 110811 | BR2706-036 | R | | | | | |
| | I-270 BRIDGE DECK REHABILITATI | E-17-IN | 118.0000 | 50.0000 | 5900.0 | $102,361 | $17.35 |
| | | E-17-IO | 118.0000 | 38.0000 | 4484.0 | $78,129 | $17.42 |
| 111006 | FBR0243-081 | P | | | | | |
| | SH 24 EAST, NEAR PEYTON, EL PA | H-18-AD | 229.0000 | 48.0000 | 10992.0 | $905,429 | $82.37 |
| 111215 | FBR0252-415 | R | | | | | |
| | NB I-25 SOUTH OF FOUNTAIN, MP1 | J-18-U, V, W | 92.0000 | 34.0000 | 3128.0 | $904,507 | $289.16 |
| | | | WEIGHTED AVERAGE COST: | | | | |
| | | | NEW STRUCTURES | | 102789.3 | $5,478,568 | $53.30 |
| | | CONCRETE RIGID FRAME | | | | | |
| 110414 | STA141A-035 | M | | | | | |
| | SH 141 UNAWEEP CANYON OVERLAY | I-03-A | 313.0000 | 28.0000 | 8764.0 | $186,720 | $21.31 |
| | | I-03-K | 109.0000 | 24.0000 | 2616.0 | $47,283 | $18.07 |
| 110811 | NH C460-002 | P | | | | | |
| | US 40/287 @ KIT CARSON | I-25-G | 123.5800 | 111.5000 | 13779.2 | $164,143 | $11.91 |
| | | | WEIGHTED AVERAGE COST: | | | | |
| | | | NEW STRUCTURES | | 25159.2 | $398,147 | $15.83 |
| | | PRECAST SEGMENTAL BOX GIRDER | | | | | |
| 110120 | BR0252-407 | U | | | | | |
| | SOUTH OF DOWNTOWN DENVER | | 1760.0000 | 39.0000 | 68640.0 | $6,691,822 | $97.49 |
| | | | 547.0000 | 149.0000 | 81503.0 | $7,102,517 | $87.14 |
| 110324 | BRR600-297 | U | | | | | |
| | I-25 BRIDGE OVER SOUTH PLATTE | | 371.0000 | 197.0000 | 73087.0 | $6,901,209 | $94.42 |
| 110526 | STA 0911-005 | M | | | | | |
| | SH 91 COPPER MOUNTAIN TO COUNT | F-12-AG | 308.0000 | 62.0000 | 19096.0 | $142,321 | $7.45 |
| | | | WEIGHTED AVERAGE COST: | | | | |
| | | | NEW STRUCTURES | | 242326.0 | $20,837,868 | $85.99 |
| | | PRESTRES GIRDER (BOX SECTION) | | | | | |
| 110811 | BR2706-036 | R | | | | | |
| | I-270 BRIDGE DECK REHABILITATI | E-17-IE | 309.0000 | 38.0000 | 11742.0 | $275,884 | $23.50 |

| DATE LET | PROJECT NUMBER/ PROJECT LOCATION | TERR/ BRIDGE ID | LENGTH | WIDTH | TOTAL SQUARE FT | TOTAL COST | COST PER SQUARE FOOT |
|---|---|---|---|---|---|---|---|
| 111117 | FBR-006A-049 | U | | | | | |
| | US6 AT SHERIDAN BLVD. | F-16-XQ | 217.5000 | 125.0000 | 27187.5 | $2,902,971 | $106.78 |
| | | | WEIGHTED AVERAGE COST: | | | | |
| | | | NEW STRUCTURES | | 38929.5 | $3,178,854 | $81.66 |
| | | FABRICATED STEEL GIRDER | | | | | |
| 110811 | BR2706-036 | R | | | | | |
| | I-270 BRIDGE DECK REHABILITATI | E-17-II | 369.0000 | 38.0000 | 14022.0 | $322,376 | $22.99 |
| | | E-17-IK | 349.0000 | 38.0000 | 13262.0 | $275,896 | $20.80 |
| 111027 | IM 0252-387 | U | | | | | |
| | I-25 SPEER BOULEVARD TO 20TH | E-17-EA | 239.0000 | 66.7000 | 15941.3 | $2,259,204 | $141.72 |
| | | | WEIGHTED AVERAGE COST: | | | | |
| | | | NEW STRUCTURES | | 43225.3 | $2,857,476 | $66.11 |
| | | ROLLED STEEL GIRDER | | | | | |
| 110120 | FBR R100-183 | P | | | | | |
| | US 24 EAST OF LIMON | | 78.5000 | 43.0000 | 3375.5 | $313,145 | $92.77 |
| 110811 | BR2706-036 | R | | | | | |
| | I-270 BRIDGE DECK REHABILITATI | E-17-IG | 219.0000 | 38.0000 | 8322.0 | $193,199 | $23.22 |
| 111027 | STA0072-010 | L | | | | | |
| | PARTIALLY IN BOULDER, FROM CHE | D-16-EA | 59.5800 | 20.0000 | 1191.6 | $1,034,772 | $868.39 |
| | | D-16-EB | 62.8330 | 30.0000 | 1885.0 | $966,052 | $512.50 |
| | | | WEIGHTED AVERAGE COST: | | | | |
| | | | NEW STRUCTURES | | 14774.1 | $2,507,167 | $169.70 |
| | | PRESTRES/POST-TENSION CONC I GIR | | | | | |
| 110512 | STU 2254-082 | U | | | | | |
| | US 40(COLFAX) / I-225 | F-17-WS | 177.0000 | 72.0000 | 12744.0 | $1,513,761 | $118.78 |
| 110616 | FBR 0761-209 | R | | | | | |
| | I-76 OVER S. PLATTE RIVER | E-17-AET | 359.7900 | 137.0000 | 49291.2 | $3,527,917 | $71.57 |
| | | | WEIGHTED AVERAGE COST: | | | | |
| | | | NEW STRUCTURES | | 62035.2 | $5,041,678 | $81.27 |
| | | MISCELLANEOUS | | | | | |
| 111117 | NH 0821-098 | M | | | | | |
| | SH 82 MP 20.5-39 EAGLE AND PIT | | 359.0000 | 38.0000 | 13642.0 | $60,754 | $4.45 |

2011 Cost Data
BRIDGE COST PER SQUARE FOOT
(01/01/11 THROUGH 12/31/11)

| DATE LET | PROJECT NUMBER/ PROJECT LOCATION | TERR/ BRIDGE ID | LENGTH | WIDTH | TOTAL SQUARE FT | TOTAL COST | COST PER SQUARE FOOT |
|---|---|---|---|---|---|---|---|
| | | | 304.0000 | 38.0000 | 11552.0 | $52,170 | $4.52 |
| | | | WEIGHTED AVERAGE COST: | | | | |
| | | | NEW STRUCTURES | | 25194.0 | $112,924 | $4.48 |

| BID LETTING | CONTRACTOR/ PROJECT NUMBER | LOCATION | DIST | TERRAIN | BIDS | AWARDED BID | INDEX |
|---|---|---|---|---|---|---|---|
| 20110106 | MARTINEZ WESTERN CONSTRUCTORS INC. | | | | 5 | $784,309.90 | 91.93 |
| | SHE0131-056 | SH 13 & RAILROAD AVE MP 2-3 RI | 3 | U | | | |
| 20110106 | INTERFACE COMMUNICATIONS, COMPANY | | | | 4 | $283,133.42 | 100.43 |
| | C0704-225 | I-70 EAST OF BENNETT | 1 | P | | | |
| 20110113 | ASPHALT SPECIALTIES CO., INC. | | | | 6 | $664,759.60 | 91.02 |
| | STA007A-014 | SH 7 US 287 TO RR EAST EDGE OF | 6 | R | | | |
| 20110120 | W.L. CONTRACTORS, INC. | | | | 4 | $981,412.50 | 109.72 |
| | ITS4701-121 | C470 (SANTA FE TO I-25) AND R6 | 00 | P | | | |
| 20110120 | HAMON CONTRACTORS, INC. | | | | 9 | $32,088,000.00 | 82.16 |
| | BR0252-407 | SOUTH OF DOWNTOWN DENVER | 6 | U | | | |
| | BR0252-407 | SOUTH OF DOWNTOWN DENVER | 6 | U | | | |
| | BR0252-407 | SOUTH OF DOWNTOWN DENVER | 6 | U | | | |
| | BR0252-407 | SOUTH OF DOWNTOWN DENVER | 6 | U | | | |
| 20110120 | JALISCO INTERNATIONAL, INC. | | | | 7 | $834,857.84 | 70.42 |
| | FBR R100-183 | US 24 EAST OF LIMON | 1 | P | | | |
| 20110127 | SEMA CONSTRUCTION, INC. | | | | 9 | $5,498,295.27 | 113.76 |
| | FBR089A-013 | ON SH 89 FROM MP 33.21 TO MP 3 | 2 | P | | | |
| 20110217 | HIGHWAY TECHNOLOGIES | | | | 6 | $312,130.50 | 103.95 |
| | C0703-363 | CLEAR CREEK AND JEFFERSON COUN | 1 | M | | | |
| 20110303 | A & S CONSTRUCTION CO. | | | | 6 | $2,067,766.61 | 94.67 |
| | NH 2852-017 | US 285 PONCHA PASS SOUTH RESUR | 5 | M | | | |
| 20110303 | ROCKY MOUNTAIN MATERIALS & ASPHALT, INC. | | | | 5 | $1,710,437.93 | 96.29 |
| | STA0504-061 | US 50 M.P.369.9 -M.P.373.2 | 2 | R | | | |
| 20110303 | ELAM CONSTRUCTION, INC. | | | | 6 | $2,273,283.00 | 84.18 |
| | NH 0241-056 | US 24 BUENA VISTA NORTH | 5 | R | | | |
| 20110310 | LAFARGE NORTH AMERICA, INC | | | | 5 | $2,349,462.00 | 82.86 |
| | STA0362-030 | US 36, WEST OF WATKINS (@I-70) | 1 | P | | | |
| 20110317 | AMERICAN CIVIL CONSTRUCTORS, INC. | | | | 6 | $8,967,234.00 | 101.56 |
| | IM0702-303 | I-70 WEST VAIL PASS MP 170.00- | 3 | M | | | |
| 20110324 | LAWRENCE CONSTRUCTION CO. | | | | 8 | $16,250,620.93 | 79.06 |
| | BRR600-297 | I-25 BRIDGE OVER SOUTH PLATTE | 6 | U | | | |
| 20110331 | A & S CONSTRUCTION CO. | | | | 7 | $4,223,262.05 | 96.60 |
| | NH 0402-079 | US40 MP 165.0 - 179.0 GRAND CO | 3 | M | | | |
| 20110407 | CASTLE ROCK CONST. CO. OF COLO, LLC | | | | 6 | $4,740,074.34 | 94.46 |
| | STA 1211-069 | 500' N. OF 88TH TO 104TH ON SH | 6 | R | | | |

| BID LETTING | CONTRACTOR/ PROJECT NUMBER | LOCATION | DIST | TERRAIN | BIDS | AWARDED BID | INDEX |
|---|---|---|---|---|---|---|---|
| 20110407 | ASPHALT SPECIALTIES CO., INC. | | | | 5 | $1,858,792.00 | 87.14 |
| | STA0361-095 | BROOMFIELD COUNTY | 4 | R | | | |
| 20110407 | APC SOUTHERN CONSTRUCTION COMPANY, LLC | | | | 5 | $4,264,379.83 | 93.84 |
| | STA 0911-006 | SH 91 MP 0 TO 12 | 3 | M | | | |
| 20110407 | INTERMOUNTAIN SLURRY SEAL, INC. | | | | 3 | $683,348.25 | 90.13 |
| | STA0343-032 | US 34 EAST OF AKRON | 4 | R | | | |
| 20110414 | MAYS CONSTRUCTION SPECIALTIES - JV | | | | 3 | $4,867,005.55 | 104.79 |
| | STA141A-035 | SH 141 UNAWEEP CANYON OVERLAY | 3 | M | | | |
| 20110414 | STRUCTURES, INC. | | | | 6 | $2,037,651.15 | 82.74 |
| | BR0701-207 | I-70 SKIPPERS ISLAND MULTIPLE | 3 | R | | | |
| 20110421 | AGGREGATE INDUSTRIES - WCR, INC. | | | | 6 | $941,202.45 | 78.25 |
| | STA 008A-007 | SH 8 FROM MM 0.00 TO MM 2.031 | 6 | R | | | |
| 20110421 | LAFARGE NORTH AMERICA, INC | | | | 4 | $365,332.45 | 116.19 |
| | C086A-050 | SH 86 & DEERPATH RD. | 1 | P | | | |
| 20110428 | LAWRENCE CONSTRUCTION CO. | | | | 8 | $7,996,860.67 | 103.32 |
| | FBR0704-220 | I-70 OVER SAND CREEK | 6 | R | | | |
| 20110428 | W.L. CONTRACTORS, INC. | | | | 3 | $161,340.10 | 80.75 |
| | SHE074A-001 | SH 74 - EVERGREEN - JEFFERSON | 1 | M | | | |
| 20110512 | ELAM CONSTRUCTION, INC. | | | | 2 | $2,571,896.10 | 90.56 |
| | NH 172A-017 | SH 172 MP 20 TO 24.5 | 5 | R | | | |
| 20110512 | LAFARGE NORTH AMERICA, INC | | | | 6 | $1,135,892.80 | 95.74 |
| | NH0404-049 | COLFAX AVE.: SABLE TO AIRPORT | 6 | U | | | |
| 20110512 | SEMA CONSTRUCTION, INC. | | | | 6 | $10,999,272.84 | 90.79 |
| | STU 2254-082 | US 40(COLFAX) / I-225 | 6 | U | | | |
| 20110512 | LAFARGE NORTH AMERICA, INC | | | | 6 | $3,313,754.40 | 128.41 |
| | IM0704-223 | I-70:HOLLY TO SAND CREEK | 6 | U | | | |
| 20110512 | BRANNAN SAND AND GRAVEL, LLC | | | | 4 | $2,491,375.18 | 92.16 |
| | NHR600-376 | SH 287: FEDERAL TO LAUREL | 6 | U | | | |
| 20110526 | ELAM CONSTRUCTION, INC. | | | | 3 | $3,677,038.45 | 95.76 |
| | STA 0911-005 | SH 91 COPPER MOUNTAIN TO COUNT | 1 | M | | | |
| 20110526 | AMERICAN WEST CONSTRUCTION, LLC | | | | 3 | $219,435.20 | 78.44 |
| | C0241-055 | SH 24 MP 148-152 | 3 | M | | | |
| 20110609 | CONNELL RESOURCES, INC. | | | | 8 | $6,893,218.14 | 113.16 |
| | STR131A-034 | SH131 CHOKE CHERRY SOUTH | 3 | M | | | |

| BID LETTING | CONTRACTOR/ PROJECT NUMBER | LOCATION | DIST | TERRAIN | BIDS | AWARDED BID | INDEX |
|---|---|---|---|---|---|---|---|
| 20110609 | TEZAK HEAVY EQUIPMENT CO., INC. | | | | 2 | $487,570.18 | 87.25 |
| | BR R 500-114 | US 160, US 550 | 5 | M | | | |
| 20110609 | CONCRETE EXPRESS, INC. | | | | 7 | $2,952,829.84 | 100.89 |
| | FBR0063-038 | SH 6 IN EAGLE | 3 | M | | | |
| 20110616 | OLDCASTLE SW GROUP, INC. | | | | 3 | $6,124,495.40 | 113.54 |
| | NH5502-058 | US 550B: RIDGWAY TO COLONA PAS | 5 | R | | | |
| 20110616 | APC CONSTRUCTION CO., LLC | | | | 4 | $6,956,957.21 | 88.60 |
| | NH093A-008 | SH93: SH 58 TO SH 128 | 6 | R | | | |
| 20110616 | CONCRETE EXPRESS, INC. | | | | 6 | $1,081,024.10 | 117.33 |
| | SHEM515-004 | GEORGETOWN, COLORADO | 1 | M | | | |
| 20110616 | ADARAND CONSTRUCTORS, INC. | | | | 3 | $2,005,984.16 | 103.46 |
| | FSA R600-387 | VARIOUS LOCATIONS IN REGION 6 | 6 | U | | | |
| 20110616 | SEMA CONSTRUCTION, INC. | | | | 7 | $10,508,410.15 | 94.10 |
| | FBR 0761-209 | I-76 OVER S. PLATTE RIVER | 6 | R | | | |
| 20110616 | STURGEON ELECTRIC COMPANY, INC | | | | 3 | $767,495.00 | 121.76 |
| | ITS0703-370 | EAST OF EJMT ON I-70 EB LANES, | 1 | M | | | |
| 20110616 | TECHNOLOGY CONSTRUCTORS, INC. | | | | 5 | $204,454.00 | 111.23 |
| | C083A-037 | SH 83 & PINE DR. | 1 | P | | | |
| 20110623 | EDWARD KRAEMER & SONS INC. | | | | 6 | $17,523,127.88 | 95.83 |
| | IM 392A-012 | I-25 AT SH 392 INTERCHANGE LAR | 4 | R | | | |
| 20110623 | NORTHERN COLORADO CONSTRUCTORS | | | | 5 | $421,345.70 | 109.97 |
| | FSA 0502-064 | US 50 EAST OF SARGENTS | 5 | M | | | |
| 20110630 | W.L. CONTRACTORS, INC. | | | | 2 | $637,018.85 | 117.16 |
| | FSA002A-004 | SH 2 @ 13TH AVE & 14TH AVE | 6 | U | | | |
| 20110714 | BRANNAN SAND AND GRAVEL, LLC | | | | 5 | $3,046,312.28 | 99.93 |
| | STA 052A-033 | SH 52 FROM SH 119 TO SH 287 | 4 | R | | | |
| 20110714 | GOULD CONSTRUCTION, INC. | | | | 7 | $310,000.00 | 105.09 |
| | C 0063-037 | US 6 MP 93.3 IN GARFIELD COUNT | 3 | M | | | |
| 20110714 | SEMA CONSTRUCTION, INC. | | | | 6 | $2,012,860.54 | 122.60 |
| | FBR0502-066 | US50 GUNNISON COUNTY MM 155.37 | 3 | R | | | |
| 20110714 | CONCRETE EXPRESS, INC. | | | | 4 | $224,420.50 | 124.81 |
| | C006A-051 | US 6 (LOVELAND PASS), CLEAR CR | 1 | M | | | |
| 20110721 | W.L. CONTRACTORS, INC. | | | | 3 | $598,704.20 | 109.95 |
| | SHE0063-036 | US6C & I70B, MESA CO., MAST AR | 3 | U | | | |

| BID LETTING | CONTRACTOR/ PROJECT NUMBER | LOCATION | DIST | TERRAIN | BIDS | AWARDED BID | INDEX |
|---|---|---|---|---|---|---|---|
| 20110721 | INTERFACE COMMUNICATIONS, COMPANY | | | | 4 | $1,110,509.51 | 97.09 |
| | FSA C110-032 | SH72 & 48TH; SH121 & CROSS; SH | 6 | R | | | |
| 20110721 | A HIGHER POWER ELECTRIC, INC | | | | 5 | $239,899.95 | 96.63 |
| | STM085A-014 | SH85 AND OHIO IN FOUNTAIN | 2 | R | | | |
| 20110721 | TLM CONSTRUCTORS, INC. | | | | 6 | $928,090.95 | 82.57 |
| | NH2872-018 | US 287 RUSH CREEK NORTH | 2 | R | | | |
| 20110721 | TLM CONSTRUCTORS, INC. | | | | 6 | $738,551.20 | 85.57 |
| | NH2872-018 | US 287 RUSH CREEK NORTH | 2 | R | | | |
| 20110721 | AGGREGATE INDUSTRIES - WCR, INC. | | | | 5 | $3,320,200.00 | 113.10 |
| | STA0831-113 | LINCOLN AVE. TO COTTONWOOD DRI | 1 | U | | | |
| 20110728 | YENTER COMPANIES, INC. | | | | 3 | $260,358.25 | 94.51 |
| | NH0403-053 | US 40 RETAINING WALL REPAIR | 1 | M | | | |
| 20110728 | JALISCO INTERNATIONAL, INC. | | | | 8 | $5,093,026.20 | 88.70 |
| | FBR 2873-160 | SH 287 (FEDERAL BLVD.) OVER SH | 6 | U | | | |
| 20110811 | LAWSON CONSTRUCTION COMPANY | | | | 5 | $5,797,428.17 | 105.01 |
| | NH C460-002 | US 40/287 @ KIT CARSON | 1 | P | | | |
| 20110811 | STRUCTURES, INC. | | | | 4 | $1,549,235.00 | 61.41 |
| | BR2706-036 | I-270 BRIDGE DECK REHABILITATI | 6 | R | | | |
| 20110818 | MIDWEST ROCKFALL, INC. | | | | 3 | $845,880.00 | 134.53 |
| | NH5502-070 | US 550 4 MILES SOUTH OF OURAY | 5 | M | | | |
| 20110824 | STAN MILLER, INC. | | | | 4 | $266,215.56 | 127.95 |
| | C0091-038 | SH 9 MM 81.9 BLUE RIVER EMERGE | 1 | M | | | |
| 20110825 | ELAM CONSTRUCTION, INC. | | | | 4 | $1,435,138.20 | 100.06 |
| | FSA 140A-001 | SH 140 S/W OF DURANGO | 5 | M | | | |
| 20110825 | K.E.C.I. COLORADO, INC. | | | | 5 | $301,147.00 | 107.55 |
| | C0931-030 | SH 93 SOUTH BOULDER | 4 | R | | | |
| 20110825 | CRUZ CONSTRUCTION, INC. | | | | 4 | $890,300.00 | 108.29 |
| | FSAC060-060 | SAFETY IMPROVEMENTS ON US-287 | 4 | M | | | |
| 20110901 | LAFARGE NORTH AMERICA, INC | | | | 3 | $2,614,513.52 | 111.13 |
| | STR096A-040 | SH 96 MP 193 TO MP 201 | 2 | P | | | |
| 20110908 | OLDCASTLE SW GROUP, INC. | | | | 9 | $4,491,301.90 | 91.97 |
| | STA0131-058 | SH 13 RIO BLANCO COUNTY ROAD 6 | 3 | M | | | |
| 20110915 | AMERICAN CIVIL CONSTRUCTORS, INC. | | | | 5 | $597,126.00 | 66.36 |
| | STA 145A-039 | SH145 AT TROUT LAKE | 5 | M | | | |

| BID LETTING | CONTRACTOR/ PROJECT NUMBER | LOCATION | DIST | TERRAIN | BIDS | AWARDED BID | INDEX |
|---|---|---|---|---|---|---|---|
| 20110915 | AMERICAN WEST CONSTRUCTION, LLC<br>C0703-371 | CULVERT REPAIRS ON I-70 BETWEE | 1 | M | 3 | $697,857.00 | 95.03 |
| 20110915 | TECHNOLOGY CONSTRUCTORS, INC.<br>SHE 0350-019 | DURANGO, CO | 5 | U | 2 | $554,297.00 | 119.36 |
| 20111006 | TEZAK HEAVY EQUIPMENT CO., INC.<br>NH1151-026 | SH115A MP 38.3 TO 40.3 | 2 | R | 5 | $5,960,146.41 | 85.58 |
| 20111006 | LAWRENCE CONSTRUCTION CO.<br>FBR0243-081 | SH 24 EAST, NEAR PEYTON, EL PA | 2 | P | 8 | $2,002,000.00 | 86.40 |
| 20111020 | INTERMOUNTAIN SLURRY SEAL, INC.<br>NH0501-060 | US50 MP 74.0 TO 81, 94.2 TO 10 | 3 | R | 5 | $1,117,000.00 | 90.18 |
| 20111027 | CONCRETE EXPRESS, INC.<br>STA0072-010 | PARTIALLY IN BOULDER, FROM CHE | 4 | L | 7 | $17,034,895.69 | 99.61 |
| 20111027 | HAMON CONTRACTORS, INC.<br>IM 0252-387 | I-25 SPEER BOULEVARD TO 20TH | 6 | U | 5 | $11,734,421.30 | 91.09 |
| 20111027 | FCI CONSTRUCTORS, INC.<br>IM0702-306 | HANGING LAKE TUNNEL | 3 | M | 3 | $549,568.00 | 83.27 |
| 20111027 | YENTER COMPANIES, INC.<br>SHE0402-081 | US 40 - MP 113 TO 120 ROUTT CO | 3 | P | 6 | $982,779.86 | 84.25 |
| 20111103 | IDEAL FENCING CORPORATION<br>SHE025A-013 | I 25 BETWEEN MP 122 AND MP 127 | 2 | R | 7 | $906,498.50 | 104.73 |
| 20111103 | TETRA TECH CONSTRUCTION SERVICES, INC<br>ITSSW00-928 | NB I-225 AT MM 2.28 | 00 | L | 6 | $242,500.00 | 90.00 |
| 20111110 | INTERMOUNTAIN SLURRY SEAL, INC.<br>STA0343-033 | SH 34 ECKLEY | 4 | P | 6 | $752,995.60 | 93.06 |
| 20111110 | A-1 CHIPSEAL COMPANY<br>R600-395 | REGION 6; VARIOUS LOCATIONS | 6 | R | 5 | $468,943.45 | 79.71 |
| 20111117 | ELAM CONSTRUCTION, INC.<br>C 1602-129 | INTERSECTION OF US160 AND ARCH | 5 | R | 3 | $911,492.00 | 90.85 |
| 20111117 | EDWARD KRAEMER & SONS INC.<br>FBR-006A-049 | US6 AT SHERIDAN BLVD. | 6 | U | 8 | $8,823,250.01 | 103.47 |
| 20111117 | LAWRENCE CONSTRUCTION CO.<br>FBR 1211-078 | SH 121 (WADSWORTH AVE.) OVER B | 6 | R | 8 | $5,600,000.00 | 99.12 |
| 20111117 | ELAM CONSTRUCTION, INC.<br>NH 0821-098 | SH 82 MP 20.5-39 EAGLE AND PIT | 3 | M | 2 | $5,821,934.10 | 92.70 |

| BID LETTING | CONTRACTOR/ PROJECT NUMBER | LOCATION | DIST | TERRAIN | BIDS | AWARDED BID | INDEX |
|---|---|---|---|---|---|---|---|
| 20111117 | GLASER ELECTRIC COMPANY, LLC<br>MC SW00-929 | STATEWIDE - VARIES | 00 | R | 4 | $2,158,883.20 | 114.61 |
| 20111201 | MIDWEST ROCKFALL, INC.<br>IM0703-368 | GEORGETOWN HILL CHUTES 6,7,9,& | 1 | M | 3 | $886,119.00 | 76.28 |
| 20111201 | MIDWEST ROCKFALL, INC.<br>FSAR500-119 | US 550 ON THE NORTH SIDE OF RE | 5 | M | 2 | $591,201.00 | 105.14 |
| 20111201 | ELAM CONSTRUCTION, INC.<br>NH0063-039 | US-6 MM 153.4 TO 158.2 IN EAGL | 3 | M | 4 | $2,109,617.50 | 89.61 |
| 20111201 | TONY J. BELTRAMO & SONS, INC.<br>MC0504-065 | US50B FROM MP 318 TO MP 359 | 2 | R | 3 | $471,308.50 | 125.58 |
| 20111208 | SIMON CONTRACTORS<br>STAR100-147 | SH 71 NORTH OF LIMON-NORTH | 1 | P | 5 | $8,956,400.40 | 107.76 |
| 20111208 | COLORADO CONSTRUCTORS, INC.<br>C2854-125 | US 285, ASPEN PARK TO MORRISON | 1 | R | 3 | $349,716.95 | 107.53 |
| 20111215 | LAWRENCE CONSTRUCTION CO.<br>FBR0252-415 | NB I-25 SOUTH OF FOUNTAIN, MP1 | 2 | R | 5 | $2,550,000.00 | 108.01 |
| 20111222 | SEMA CONSTRUCTION, INC.<br>IM 0702-310 | I-70 MP 72.3 IN GARFIELD COUNT | 3 | M | 9 | $8,146,412.95 | 76.28 |
| 20111222 | SEMA CONSTRUCTION, INC.<br>IM 0702-310 | I-70 MP 72.3 IN GARFIELD COUNT | 3 | M | CONTRACT REJ - NO REASON GIVEN | | |
| 20111222 | SEMA CONSTRUCTION, INC.<br>IM 0702-310 | I-70 MP 72.3 IN GARFIELD COUNT | 3 | M | CONTRACT REJ - NO REASON GIVEN | | |
| 20111222 | ELAM CONSTRUCTION, INC.<br>NH0402-082 | US 40 MP 108.100 TO MP 114.100 | 3 | P | 3 | $2,689,671.20 | 88.67 |
| | | | | TOTALS | 471 | $317,918,676.47 | 93.78 |

INDEX AND AVERAGE UNIT BID PRICES FOR 01/01/11 THROUGH 12/31/11

| ITEM NUMBER | ITEM | TOTAL QUANTITY | UNIT | TOTAL COST | AVERAGE PRICE |
|---|---|---|---|---|---|
| 201-00000 | Clearing and Grubbing | 30 | Lump Sum | 882,771.97 | 29,425.73 |
| 201-00001 | Clearing and Grubbing | 35 | Acre | 66,801.44 | 1,908.61 |
| 201-00002 | Clearing | 1 | Lump Sum | 16,000.00 | 16,000.00 |
| 202-00000 | Removal of Structures and Obstructions | 2 | Lump Sum | 21,494.63 | 10,747.32 |
| 202-00001 | Removal of Structure | 33 | Each | 27,174.14 | 823.46 |
| 202-00002 | Removal of Structure (Special) | 2 | Each | 4,470.14 | 2,235.07 |
| 202-00008 | Tree Trimming | 37 | Hour | 5,240.00 | 141.62 |
| 202-00010 | Removal of Tree | 814 | Each | 150,664.35 | 185.09 |
| 202-00011 | Tree Trimming | 51 | Each | 5,948.52 | 116.64 |
| 202-00012 | Removal of Tree Stump | 1 | Each | 500.00 | 500.00 |
| 202-00014 | Brush Clearing | 8 | Hour | 1,576.00 | 197.00 |
| 202-00015 | Removal of Headwall | 21 | Each | 13,583.08 | 646.81 |
| 202-00019 | Removal of Inlet | 136 | Each | 56,523.45 | 415.61 |
| 202-00020 | Removal of Concrete Box Culvert | 3 | Each | 18,900.00 | 6,300.00 |
| 202-00021 | Removal of Manhole | 32 | Each | 18,975.98 | 593.00 |
| 202-00023 | Removal of Embankment Protector Type 3 | 8 | Each | 2,458.00 | 307.25 |
| 202-00024 | Removal of Embankment Protector Type 5 | 5 | Each | 1,979.58 | 395.92 |
| 202-00025 | Removal of Ditch Lining | 2,601 | Lin Foot | 18,650.44 | 7.17 |
| 202-00026 | Removal of Slope and Ditch Paving | 5,138 | Sq Yard | 27,536.59 | 5.36 |
| 202-00027 | Removal of Riprap | 25 | Sq Yard | 950.00 | 38.00 |
| 202-00030 | Removal of Water Service | 16 | Each | 14,640.00 | 915.00 |
| 202-00031 | Removal of Fire Hydrant | 18 | Each | 9,000.00 | 500.00 |
| 202-00032 | Removal of Valve | 8 | Each | 3,000.00 | 375.00 |
| 202-00033 | Removal of Pipe | 55 | Each | 114,127.89 | 2,075.05 |
| 202-00035 | Removal of Pipe | 28,351 | Lin Foot | 477,278.78 | 16.83 |
| 202-00037 | Removal of End Section | 26 | Each | 4,712.06 | 181.23 |
| 202-00038 | Removal of Structural Plate Pipe | 5 | Lin Foot | 650.00 | 130.00 |
| 202-00040 | Removal of Electrical Conduit | 3,230 | Lin Foot | 10,336.00 | 3.20 |
| 202-00090 | Removal of Delineator | 9,741 | Each | 52,904.76 | 5.43 |
| 202-00150 | Removal of Wall | 2 | Each | 19,000.00 | 9,500.00 |
| 202-00155 | Removal of Wall | 3,031 | Lin Foot | 144,626.84 | 47.72 |
| 202-00160 | Removal of Wall | 781 | Sq Foot | 8,636.72 | 11.06 |
| 202-00165 | Removal of Wall | 1 | Lump Sum | 10,000.00 | 10,000.00 |
| 202-00170 | Grinding And Texturing Concrete Pavement | 31,300 | Sq Yard | 93,900.00 | 3.00 |
| 202-00190 | Removal of Concrete Median Cover Material | 4,918 | Sq Yard | 43,112.53 | 8.77 |
| 202-00195 | Removal of Median Cover | 4,326 | Sq Yard | 20,771.24 | 4.80 |
| 202-00200 | Removal of Sidewalk | 7,577 | Sq Yard | 63,401.27 | 8.37 |
| 202-00201 | Removal of Curb | 13,754 | Lin Foot | 46,835.80 | 3.41 |

INDEX AND AVERAGE UNIT BID PRICES FOR 01/01/11 THROUGH 12/31/11

| ITEM NUMBER | ITEM | TOTAL QUANTITY | UNIT | TOTAL COST | AVERAGE PRICE |
|---|---|---|---|---|---|
| 202-00202 | Removal of Gutter | 2,029 | Lin Foot | 6,746.71 | 3.33 |
| 202-00203 | Removal of Curb and Gutter | 60,771 | Lin Foot | 215,002.66 | 3.54 |
| 202-00206 | Removal of Concrete Curb Ramp | 1,695 | Sq Yard | 47,475.16 | 28.01 |
| 202-00207 | Removal of Brick Pavers | 8 | Sq Yard | 168.00 | 21.00 |
| 202-00210 | Removal of Concrete Pavement | 36,123 | Sq Yard | 215,133.81 | 5.96 |
| 202-00212 | Removal of Concrete Pavement (Special) | 3,557 | Sq Yard | 10,564.29 | 2.97 |
| 202-00220 | Removal of Asphalt Mat | 371,989 | Sq Yard | 1,354,632.28 | 3.64 |
| 202-00240 | Removal of Asphalt Mat (Planing) | 2,212,938 | Sq Yard | 3,395,562.66 | 1.53 |
| 202-00246 | Removal of Asphalt Mat (Planing) (Special) | 28,559 | Sq Yard | 260,174.95 | 9.11 |
| 202-00250 | Removal of Pavement Marking | 152,581 | Sq Foot | 220,167.01 | 1.44 |
| 202-00400 | Removal of Bridge | 17 | Each | 2,088,858.36 | 122,874.02 |
| 202-00420 | Removal of Pedestrian Rail | 288 | Lin Foot | 1,072.07 | 3.72 |
| 202-00425 | Removal of Bridge Railing | 8,791 | Lin Foot | 159,301.72 | 18.12 |
| 202-00450 | Removal of Portions of Present Structure (Class 1) | 12,900 | Sq Yard | 512,818.40 | 39.75 |
| 202-00453 | Removal of Portions of Present Structure (Class 2) | 5,759 | Sq Yard | 1,197,999.20 | 208.02 |
| 202-00460 | Removal of Portions of Present Structure (Class 3) | 602 | Sq Yard | 180,126.00 | 299.21 |
| 202-00495 | Removal of Portions of Present Structure | 5 | Lump Sum | 88,325.00 | 17,665.00 |
| 202-00500 | Removal of Portions of Present Structure | 8 | Each | 243,875.08 | 30,484.39 |
| 202-00502 | Removal of Portions of Present Structure | 2 | Cubic Yard | 11,850.00 | 5,925.00 |
| 202-00504 | Removal of Expansion Device | 724 | Lin Foot | 91,100.00 | 125.83 |
| 202-00700 | Removal of Light Standard | 24 | Each | 5,001.36 | 208.39 |
| 202-00705 | Removal of Light Standard Foundation | 32 | Each | 5,166.54 | 161.45 |
| 202-00750 | Removal of Luminaire | 16 | Each | 1,254.06 | 78.38 |
| 202-00800 | Removal of Overpass Mounted Sign Bracket | 2 | Each | 2,580.00 | 1,290.00 |
| 202-00805 | Removal of Overhead Sign Structure | 15 | Each | 71,603.74 | 4,773.58 |
| 202-00810 | Removal of Ground Sign | 472 | Each | 48,258.60 | 102.24 |
| 202-00815 | Removal of Sign (Special) | 6 | Each | 8,802.00 | 1,467.00 |
| 202-00821 | Removal of Sign Panel | 167 | Each | 12,699.07 | 76.04 |
| 202-00825 | Removal of Flashing Beacon | 9 | Each | 2,358.97 | 262.11 |
| 202-00827 | Removal of Pull Box | 21 | Each | 2,013.72 | 95.89 |
| 202-00828 | Removal of Traffic Signal Equipment | 9 | Lump Sum | 53,024.11 | 5,891.57 |
| 202-00831 | Removal of Traffic Signal Head | 13 | Each | 892.00 | 68.62 |
| 202-00840 | Removal of Traffic Signal Pole | 18 | Each | 12,730.00 | 707.22 |
| 202-00848 | Removal of Traffic Signal Controller and Cabinet | 5 | Each | 3,805.00 | 761.00 |
| 202-00858 | Removal of Pedestal Pole | 2 | Each | 620.00 | 310.00 |
| 202-00860 | Removal of Pedestrian Push Button | 4 | Each | 92.00 | 23.00 |
| 202-00895 | Removal of Impact Attenuator | 9 | Each | 15,900.86 | 1,766.76 |
| 202-00900 | Removal of Concrete Footing | 100 | Each | 20,890.87 | 208.91 |

INDEX AND AVERAGE UNIT BID PRICES FOR 01/01/11 THROUGH 12/31/11

| ITEM NUMBER | ITEM | TOTAL QUANTITY | UNIT | TOTAL COST | AVERAGE PRICE |
|---|---|---|---|---|---|
| 202-01000 | Removal of Fence | 85,268 | Lin Foot | 63,162.99 | 0.74 |
| 202-01015 | Removal of Rockfall Fence | 210 | Lin Foot | 8,400.00 | 40.00 |
| 202-01020 | Removal of Sound Barrier Fence | 2,097 | Lin Foot | 31,455.00 | 15.00 |
| 202-01130 | Removal of Guardrail Type 3 | 68,214 | Lin Foot | 162,883.81 | 2.39 |
| 202-01140 | Removal of Guardrail Type 4 | 34,905 | Lin Foot | 356,949.02 | 10.23 |
| 202-01170 | Removal of Guardrail Type 7 | 17,139 | Lin Foot | 181,657.65 | 10.60 |
| 202-01180 | Removal of Median Barrier | 436 | Lin Foot | 7,547.00 | 17.31 |
| 202-01200 | Removal of Tensioned Cable Barrier | 1,828 | Lin Foot | 5,429.08 | 2.97 |
| 202-01300 | Removal of End Anchorage | 293 | Each | 68,755.14 | 234.66 |
| 202-01400 | Removal of Cattle Guard | 2 | Each | 5,100.00 | 2,550.00 |
| 202-04000 | Plug Structure | 18 | Each | 8,759.88 | 486.66 |
| 202-04001 | Plug Culvert | 38 | Each | 62,224.72 | 1,637.49 |
| 202-04002 | Clean Culvert | 59 | Each | 137,363.57 | 2,328.20 |
| 202-04003 | Clean Culvert (Special) | 3 | Each | 3,060.00 | 1,020.00 |
| 202-04004 | Plug Culvert (Special) | 2 | Each | 8,000.00 | 4,000.00 |
| 202-04005 | Clean Valve Box | 87 | Each | 11,628.08 | 133.66 |
| 202-04010 | Clean Inlet | 3 | Each | 4,030.00 | 1,343.33 |
| 202-04100 | Abandon Well | 8 | Each | 5,480.00 | 685.00 |
| 202-05006 | Sawing Concrete (6 Inch) | 407 | Lin Foot | 2,849.00 | 7.00 |
| 202-05026 | Sawing Asphalt Material (6 Inch) | 2,351 | Lin Foot | 5,836.40 | 2.48 |
| 202-05030 | Sawing Asphalt Material (10 Inch) | 44,030 | Lin Foot | 89,650.00 | 2.04 |
| 202-05100 | Sandblasting Reinforcing Steel | 125 | Sq Yard | 4,625.00 | 37.00 |
| 202-05150 | Sandblasting | 51,467 | Sq Foot | 51,110.48 | 0.99 |
| 202-05300 | Removal and Disposal of Paint | 1 | Lump Sum | 170,800.00 | 170,800.00 |
| 203-00000 | Unclassified Excavation | 114,981 | Cubic Yard | 752,716.63 | 6.55 |
| 203-00010 | Unclassified Excavation (Complete In Place) | 847,797 | Cubic Yard | 5,410,982.86 | 6.38 |
| 203-00040 | Unclassified Excavation (Special) | 3,782 | Cubic Yard | 34,056.00 | 9.00 |
| 203-00060 | Embankment Material (Complete In Place) | 892,968 | Cubic Yard | 6,039,591.15 | 6.76 |
| 203-00061 | Embankment Material (Complete In Place) | 323 | Ton | 2,261.00 | 7.00 |
| 203-00062 | Embankment Material (Complete In Place) (Special) | 204,215 | Cubic Yard | 2,031,917.47 | 9.95 |
| 203-00100 | Muck Excavation | 26,832 | Cubic Yard | 354,708.15 | 13.22 |
| 203-00400 | Rock Excavation | 16,845 | Cubic Yard | 206,420.00 | 12.25 |
| 203-00500 | Rock Fill | 2,420 | Cubic Yard | 106,480.00 | 44.00 |
| 203-00710 | Clay Plating (Complete In Place) | 1,516 | Cubic Yard | 43,426.00 | 28.65 |
| 203-00910 | Contaminated Soil Excavation and Disposal (Off-Site) | 100 | Cubic Yard | 15,000.00 | 150.00 |
| 203-01100 | Proof Rolling | 888 | Hour | 76,188.25 | 85.80 |
| 203-01140 | Rolling | 195 | Hour | 19,236.10 | 98.65 |
| 203-01500 | Blading | 3,111 | Hour | 348,962.30 | 112.17 |

INDEX AND AVERAGE UNIT BID PRICES FOR 01/01/11 THROUGH 12/31/11

| ITEM NUMBER | ITEM | TOTAL QUANTITY | UNIT | TOTAL COST | AVERAGE PRICE |
|---|---|---|---|---|---|
| 203-01510 | Backhoe | 2,112 | Hour | 210,810.26 | 99.82 |
| 203-01550 | Dozing | 1,305 | Hour | 178,276.30 | 136.61 |
| 203-01565 | Hydraulic Excavator | 125 | Hour | 18,050.00 | 144.40 |
| 203-01582 | Truck (Dump) | 376 | Hour | 40,538.00 | 107.81 |
| 203-01590 | Front End Loader (Rubber Tire) | 380 | Hour | 52,083.40 | 137.06 |
| 203-01591 | Front End Loader (Crawler) | 200 | Hour | 26,824.00 | 134.12 |
| 203-01594 | Combination Loader | 2,122 | Hour | 198,159.20 | 93.38 |
| 203-01597 | Potholing | 3,815 | Hour | 678,993.10 | 177.98 |
| 203-01620 | Sweeping | 265 | Hour | 75,540.00 | 285.06 |
| 203-01622 | Sweeping (With Pickup Broom) | 2,320 | Hour | 351,329.00 | 151.43 |
| 203-02300 | Rock Scaler | 636 | Hour | 62,385.60 | 98.09 |
| 203-02330 | Laborer | 655 | Hour | 27,372.60 | 41.79 |
| 206-00000 | Structure Excavation | 165,349 | Cubic Yard | 1,217,723.25 | 7.36 |
| 206-00050 | Structure Backfill (Special) | 82 | Cubic Yard | 29,345.00 | 357.87 |
| 206-00065 | Structure Backfill (Flow-Fill) | 6,839 | Cubic Yard | 482,620.91 | 70.57 |
| 206-00066 | Structure Backfill (Flowable Fly Ash) | 200 | Cubic Yard | 7,000.00 | 35.00 |
| 206-00100 | Structure Backfill (Class 1) | 263,810 | Cubic Yard | 3,678,004.75 | 13.94 |
| 206-00200 | Structure Backfill (Class 2) | 8,375 | Cubic Yard | 88,799.54 | 10.60 |
| 206-00360 | Mechanical Reinforcement of Soil | 154,658 | Cubic Yard | 2,710,772.41 | 17.53 |
| 206-00505 | Filter Material (Special) | 712 | Cubic Yard | 27,056.00 | 38.00 |
| 206-00510 | Filter Material (Class A) | 1,222 | Cubic Yard | 53,376.81 | 43.68 |
| 206-00520 | Filter Material (Class B) | 1,111 | Cubic Yard | 39,970.38 | 35.98 |
| 206-00530 | Filter Material (Class C) | 397 | Cubic Yard | 13,452.36 | 33.89 |
| 206-01500 | Cofferdam | 1 | Lump Sum | 25,350.30 | 25,350.30 |
| 206-01750 | Shoring | 2 | Lump Sum | 61,000.00 | 30,500.00 |
| 206-01781 | Shoring (Area 1) | 14 | Lump Sum | 319,918.28 | 22,851.31 |
| 206-01782 | Shoring (Area 2) | 12 | Lump Sum | 147,946.54 | 12,328.88 |
| 206-01783 | Shoring (Area 3) | 7 | Lump Sum | 103,784.02 | 14,826.29 |
| 206-01784 | Shoring (Area 4) | 7 | Lump Sum | 128,749.59 | 18,392.80 |
| 206-01785 | Shoring (Area 5) | 2 | Lump Sum | 17,000.00 | 8,500.00 |
| 206-01786 | Shoring (Area 6) | 2 | Lump Sum | 116,000.00 | 58,000.00 |
| 206-01787 | Shoring (Area 7) | 2 | Lump Sum | 89,000.00 | 44,500.00 |
| 206-01788 | Shoring (Area 8) | 1 | Lump Sum | 19,000.00 | 19,000.00 |
| 206-01789 | Shoring (Area 9) | 1 | Lump Sum | 12,500.00 | 12,500.00 |
| 207-00205 | Topsoil | 93,985 | Cubic Yard | 709,804.06 | 7.55 |
| 207-00210 | Stockpile Topsoil | 10,630 | Cubic Yard | 53,551.00 | 5.04 |
| 207-00305 | Wetland Topsoil | 67 | Cubic Yard | 2,680.00 | 40.00 |
| 207-00310 | Stockpile Wetland Topsoil | 5,267 | Cubic Yard | 40,294.00 | 7.65 |

INDEX AND AVERAGE UNIT BID PRICES FOR 01/01/11 THROUGH 12/31/11

| ITEM NUMBER | ITEM | TOTAL QUANTITY | UNIT | TOTAL COST | AVERAGE PRICE |
|---|---|---|---|---|---|
| 208-00001 | Silt Dike | 110 | Lin Foot | 990.00 | 9.00 |
| 208-00002 | Erosion Log (12 Inch) | 263,523 | Lin Foot | 929,182.32 | 3.53 |
| 208-00003 | Erosion Log (18 Inch) | 9,005 | Lin Foot | 55,538.50 | 6.17 |
| 208-00005 | Erosion Log | 1,660 | Lin Foot | 8,725.00 | 5.26 |
| 208-00007 | Erosion Log (8 Inch) | 19,915 | Lin Foot | 58,759.00 | 2.95 |
| 208-00009 | Erosion Log (20 Inch) | 16,961 | Lin Foot | 97,160.80 | 5.73 |
| 208-00011 | Erosion Bales (Weed Free) | 2,699 | Each | 36,115.30 | 13.38 |
| 208-00015 | Sand Bag | 100 | Each | 2,100.00 | 21.00 |
| 208-00020 | Silt Fence | 127,920 | Lin Foot | 146,919.06 | 1.15 |
| 208-00021 | Silt Fence (Reinforced) | 11,195 | Lin Foot | 27,529.37 | 2.46 |
| 208-00030 | Sediment Basin | 10 | Each | 30,665.60 | 3,066.56 |
| 208-00033 | Sediment Trap | 12 | Each | 12,255.71 | 1,021.31 |
| 208-00034 | Gravel Bag | 30,174 | Lin Foot | 160,533.72 | 5.32 |
| 208-00040 | Check Dam | 298 | Each | 85,246.14 | 286.06 |
| 208-00045 | Concrete Washout Structure | 215 | Each | 168,089.01 | 781.81 |
| 208-00050 | Storm Drain Inlet Protection | 446 | Each | 38,443.36 | 86.20 |
| 208-00051 | Storm Drain Inlet Protection | 8,518 | Lin Foot | 37,492.03 | 4.40 |
| 208-00052 | Storm Drain Inlet Protection (Type 2) | 797 | Lin Foot | 4,347.40 | 5.45 |
| 208-00060 | Temporary Slope Drain | 90 | Lin Foot | 1,191.60 | 13.24 |
| 208-00070 | Stabilized Construction Entrance | 240 | Each | 279,025.59 | 1,162.61 |
| 208-00103 | Removal and Disposal of Sediment (Labor) | 5,395 | Hour | 212,643.45 | 39.41 |
| 208-00105 | Removal and Disposal of Sediment (Equipment) | 4,171 | Hour | 324,090.94 | 77.70 |
| 208-00106 | Sweeping (Sediment Removal) | 3,417 | Hour | 352,185.35 | 103.07 |
| 208-00107 | Removal of Trash | 2,181 | Hour | 103,255.95 | 47.34 |
| 208-00205 | Erosion Control Supervisor | 5,776 | Hour | 286,750.80 | 49.65 |
| 208-00206 | Erosion Control Supervisor | 6,454 | Day | 520,624.25 | 80.67 |
| 208-00300 | Temporary Berms | 5,150 | Lin Foot | 13,121.40 | 2.55 |
| 208-00400 | Water Control | 5 | Lump Sum | 141,533.93 | 28,306.79 |
| 209-00100 | Water (Landscaping) | 226 | M Gallon | 41,633.32 | 184.22 |
| 209-00200 | Time-Released Water Product | 9,361 | Each | 54,654.73 | 5.84 |
| 209-00600 | Dust Palliative (Magnesium Chloride) | 50,033 | Gallon | 18,421.64 | 0.37 |
| 210-00001 | Reset Structure | 36 | Each | 28,098.35 | 780.51 |
| 210-00010 | Reset Mailbox Structure | 10 | Each | 2,180.00 | 218.00 |
| 210-00011 | Reset Mailbox Structure (Type 1) | 39 | Each | 8,343.54 | 213.94 |
| 210-00012 | Reset Mailbox Structure (Type 2) | 6 | Each | 1,875.00 | 312.50 |
| 210-00013 | Reset Mailbox Structure (Type 3) | 12 | Each | 4,205.00 | 350.42 |
| 210-00015 | Reset End Section | 3 | Each | 1,233.06 | 411.02 |
| 210-00030 | Reset Water Service | 15 | Each | 30,000.00 | 2,000.00 |

INDEX AND AVERAGE UNIT BID PRICES FOR 01/01/11 THROUGH 12/31/11

| ITEM NUMBER | ITEM | TOTAL QUANTITY | UNIT | TOTAL COST | AVERAGE PRICE |
|---|---|---|---|---|---|
| 210-00035 | Reset Water Meter | 8 | Each | 1,760.00 | 220.00 |
| 210-00060 | Reset Marker | 28 | Each | 1,949.78 | 69.64 |
| 210-00065 | Reset Monument (Type 3A) | 4 | Each | 1,591.66 | 397.92 |
| 210-00090 | Reset Delineator | 41 | Each | 779.00 | 19.00 |
| 210-00440 | Repair Curb | 55 | Lin Foot | 4,070.00 | 74.00 |
| 210-00473 | Reset TV Cameras | 3 | Each | 3,612.72 | 1,204.24 |
| 210-00500 | Rebuild Portions of Present Structure | 5 | Each | 4,924.00 | 984.80 |
| 210-00750 | Reset Light Standard | 4 | Each | 5,355.00 | 1,338.75 |
| 210-00805 | Reset Overhead Sign Structure | 3 | Each | 25,486.46 | 8,495.49 |
| 210-00810 | Reset Ground Sign | 313 | Each | 69,256.86 | 221.27 |
| 210-00815 | Reset Sign Panel | 117 | Each | 11,521.20 | 98.47 |
| 210-00820 | Reset Variable Message Sign | 2 | Each | 11,456.00 | 5,728.00 |
| 210-00825 | Reset Flashing Beacon | 1 | Each | 1,160.00 | 1,160.00 |
| 210-00827 | Reset Pull Box | 2 | Each | 265.00 | 132.50 |
| 210-00831 | Reset Traffic Signal Head | 13 | Each | 1,765.01 | 135.77 |
| 210-00840 | Reset Traffic Signal Pole | 9 | Each | 14,976.00 | 1,664.00 |
| 210-00848 | Reset Traffic Signal Controller and Cabinet | 3 | Each | 10,008.97 | 3,336.32 |
| 210-00855 | Reset Traffic Signal Controller Cabinet | 2 | Each | 3,621.86 | 1,810.93 |
| 210-00858 | Reset Pedestal Pole | 2 | Each | 184.00 | 92.00 |
| 210-00860 | Reset Pedestrian Push Button | 22 | Each | 1,942.40 | 88.29 |
| 210-00865 | Reset Pedestrian Signal Head | 17 | Each | 3,269.16 | 192.30 |
| 210-00866 | Reset Fire Preemption Unit and Timer | 13 | Each | 8,007.44 | 615.96 |
| 210-00890 | Reset Intersection Detection System (Camera) | 1 | Each | 2,180.38 | 2,180.38 |
| 210-00910 | Reset Traffic Counter (Permanent) | 4 | Each | 1,780.00 | 445.00 |
| 210-01000 | Reset Fence | 1,759 | Lin Foot | 21,410.67 | 12.17 |
| 210-01005 | Reset Fence Post | 4 | Each | 200.00 | 50.00 |
| 210-01011 | Reset Gate | 12 | Each | 4,814.19 | 401.18 |
| 210-01130 | Reset Guardrail Type 3 | 3,070 | Lin Foot | 27,686.28 | 9.02 |
| 210-01180 | Reset Guardrail (Special) | 14,419 | Lin Foot | 30,279.90 | 2.10 |
| 210-01200 | Reset End Anchorage | 14 | Each | 5,654.84 | 403.92 |
| 210-01720 | Reset Air Vent | 1 | Each | 1,385.00 | 1,385.00 |
| 210-02024 | Relay Pipe (24 Inch) | 20 | Lin Foot | 2,300.00 | 115.00 |
| 210-02510 | Relay Sprinkler System | 2 | Lump Sum | 4,500.00 | 2,250.00 |
| 210-02900 | Relay Riprap | 478 | Cubic Yard | 14,044.48 | 29.38 |
| 210-03100 | Replace Concrete Pavement | 3,944 | Sq Yard | 532,440.00 | 135.00 |
| 210-04006 | Heat Straightening (Special) | 1 | Lump Sum | 31,300.00 | 31,300.00 |
| 210-04010 | Adjust Manhole | 99 | Each | 54,379.12 | 549.28 |
| 210-04015 | Modify Manhole | 20 | Each | 30,779.92 | 1,539.00 |

INDEX AND AVERAGE UNIT BID PRICES FOR 01/01/11 THROUGH 12/31/11

| ITEM NUMBER | ITEM | TOTAL QUANTITY | UNIT | TOTAL COST | AVERAGE PRICE |
|---|---|---|---|---|---|
| 210-04020 | Modify Inlet | 75 | Each | 129,748.44 | 1,729.98 |
| 210-04030 | Modify Guardrail | 12,414 | Lin Foot | 133,173.65 | 10.73 |
| 210-04050 | Adjust Valve Box | 301 | Each | 44,500.32 | 147.84 |
| 210-04060 | Adjust Water Meter | 8 | Each | 1,920.00 | 240.00 |
| 210-04200 | Adjust Guardrail | 30,405 | Lin Foot | 117,697.55 | 3.87 |
| 211-00100 | Drilling Hole | 331 | Lin Foot | 7,282.00 | 22.00 |
| 211-01111 | Rock Reinforcement (Dowels) | 80 | Lin Foot | 8,560.00 | 107.00 |
| 211-01115 | Rock Reinforcement (Number 10) | 1,150 | Lin Foot | 134,657.50 | 117.09 |
| 211-01160 | Trial Pull Test | 18 | Each | 2,160.00 | 120.00 |
| 211-01300 | Rock Anchor | 210 | Each | 49,301.20 | 234.77 |
| 211-02275 | Cement Grout | 10 | Cubic Yard | 3,000.00 | 300.00 |
| 211-03005 | Dewatering | 4 | Lump Sum | 80,802.55 | 20,200.64 |
| 212-00006 | Seeding (Native) | 350 | Acre | 216,649.50 | 619.00 |
| 212-00007 | Seeding (Native) (Hydraulic) | 24 | Acre | 19,387.50 | 807.81 |
| 212-00009 | Seeding (Temporary) | 16 | Acre | 6,793.67 | 424.60 |
| 212-00028 | Seeding (Wetlands) | 3 | Acre | 5,905.35 | 1,968.45 |
| 212-00032 | Soil Conditioning | 251 | Acre | 547,424.07 | 2,180.97 |
| 212-00047 | Soil Preparation (Special) | 2 | Acre | 3,909.31 | 1,954.66 |
| 212-00048 | Soil Preparation (Special) | 7 | Cubic Yard | 210.00 | 30.00 |
| 212-00050 | Sod | 56,520 | Sq Foot | 37,227.75 | 0.66 |
| 212-01200 | Landscape Restoration | 1 | Lump Sum | 3,500.00 | 3,500.00 |
| 213-00002 | Mulching (Weed Free Hay) | 101 | Acre | 54,212.17 | 536.75 |
| 213-00003 | Mulching (Weed Free) | 132 | Acre | 86,783.14 | 657.45 |
| 213-00004 | Mulching (Weed Free Straw) | 99 | Acre | 88,460.76 | 893.54 |
| 213-00005 | Mulching (Decorative) | 47 | Cubic Foot | 314.90 | 6.70 |
| 213-00008 | Mulching (Wood Chip) | 28,821 | Cubic Foot | 66,990.00 | 2.32 |
| 213-00009 | Flexible Growth Medium | 0 | Acre | 2,500.00 | |
| 213-00011 | Mulching (Hydraulic) | 9 | Acre | 16,572.71 | 1,841.41 |
| 213-00012 | Spray-on Mulch Blanket | 72 | Acre | 203,118.91 | 2,821.10 |
| 213-00061 | Mulch Tackifier | 55,361 | Pound | 239,316.23 | 4.32 |
| 213-00065 | Inorganic Mulch | 20 | Cubic Yard | 4,147.20 | 207.36 |
| 213-00100 | Soil Binder | 212 | Acre | 137,426.54 | 648.24 |
| 213-00150 | Bonded Fiber Matrix | 7 | Acre | 32,688.00 | 4,669.71 |
| 213-00460 | Metal Landscape Border (3/16x4 Inch) | 138 | Lin Foot | 448.50 | 3.25 |
| 213-00705 | Landscape Boulder (Special) | 679 | Each | 443,869.09 | 653.71 |
| 214-00000 | Landscape Maintenance | 8 | Lump Sum | 142,093.26 | 17,761.66 |
| 214-00005 | Landscape Maintenance (24 Month) | 2 | Lump Sum | 8,263.57 | 4,131.79 |
| 214-00205 | Deciduous Tree (5 Gallon Container) | 71 | Each | 3,879.14 | 54.64 |

INDEX AND AVERAGE UNIT BID PRICES FOR 01/01/11 THROUGH 12/31/11

| ITEM NUMBER | ITEM | TOTAL QUANTITY | UNIT | TOTAL COST | AVERAGE PRICE |
|---|---|---|---|---|---|
| 214-00215 | Deciduous Tree (1.5 Inch Caliper) | 73 | Each | 23,295.54 | 319.12 |
| 214-00220 | Deciduous Tree (2 Inch Caliper) | 116 | Each | 46,409.24 | 400.08 |
| 214-00222 | Deciduous Tree (2 Inch Caliper) (Furnish Only) | 215 | Each | 50,395.00 | 234.40 |
| 214-00225 | Deciduous Tree (2.5 Inch Caliper) | 19 | Each | 6,303.82 | 331.78 |
| 214-00230 | Deciduous Tree (3 Inch Caliper) | 16 | Each | 8,224.00 | 514.00 |
| 214-00280 | Deciduous Tree (8 Foot) | 20 | Each | 4,322.26 | 216.11 |
| 214-00350 | Deciduous Shrub (5 Gallon Container) | 4,046 | Each | 98,383.36 | 24.32 |
| 214-00450 | Evergreen Tree (5 Gallon Container) | 67 | Each | 3,921.36 | 58.53 |
| 214-00504 | Evergreen Tree (4 Foot) (Ball and Burlap) | 14 | Each | 4,025.00 | 287.50 |
| 214-00506 | Evergreen Tree (6 Foot) (Ball and Burlap) | 98 | Each | 16,489.88 | 168.26 |
| 214-00507 | Evergreen Tree (6 Foot) (Ball and Burlap) (Furnish On | 4 | Each | 1,060.88 | 265.22 |
| 214-00508 | Evergreen Tree (8 Foot) (Ball and Burlap) | 107 | Each | 44,461.38 | 415.53 |
| 214-00511 | Evergreen Tree (10 F00t) (Ball and Burlap) (Furnish O | 8 | Each | 6,800.00 | 850.00 |
| 214-00650 | Evergreen Shrub (5 Gallon Container) | 32 | Each | 1,312.00 | 41.00 |
| 214-00910 | Perennials (1 Gallon Container) | 2,398 | Each | 24,867.26 | 10.37 |
| 214-01010 | Brush Layer Cutting | 990 | Each | 10,237.00 | 10.34 |
| 214-01015 | Willow Cuttings | 746 | Each | 4,987.56 | 6.69 |
| 215-00000 | Transplant Shrub | 20 | Each | 1,400.00 | 70.00 |
| 215-00100 | Transplant Tree (Over 6 Inch) | 5 | Each | 2,125.00 | 425.00 |
| 215-00600 | Transplant Plug | 260 | Each | 12,357.50 | 47.53 |
| 216-00015 | Soil Retention Blanket (Excelsior) | 100 | Sq Yard | 500.00 | 5.00 |
| 216-00021 | Soil Retention Blanket (Class 1) | 12,850 | Sq Yard | 22,852.00 | 1.78 |
| 216-00030 | Soil Retention Blanket (Special) | 11,225 | Sq Yard | 22,753.50 | 2.03 |
| 216-00037 | Soil Retention Blanket (Coconut) | 12,910 | Sq Yard | 33,060.52 | 2.56 |
| 216-00039 | Soil Retention Blanket (Straw) | 277 | Sq Yard | 2,271.40 | 8.20 |
| 216-00041 | Soil Retention Blanket (Straw/Coconut) | 59,537 | Sq Yard | 136,508.24 | 2.29 |
| 216-00042 | Soil Retention Blanket (Biodegradable Straw/Coconut) | 37,751 | Sq Yard | 61,054.07 | 1.62 |
| 216-00201 | Soil Retention Blanket (Straw-Coconut) | 163,826 | Sq Yard | 224,779.00 | 1.37 |
| 216-00211 | Soil Retention Blanket (Excelsior) | 9,046 | Sq Yard | 15,408.36 | 1.70 |
| 216-00303 | Turf Reinforcement Mat (Class 3) | 6,483 | Sq Yard | 60,486.39 | 9.33 |
| 217-00000 | Herbicide Treatment | 286,628 | Sq Yard | 17,723.68 | 0.06 |
| 217-00015 | Noxious Weed Management | 9,793 | Sq Yard | 9,303.35 | 0.95 |
| 217-00020 | Herbicide Treatment | 730 | Hour | 66,793.70 | 91.50 |
| 218-00000 | Noxious Weed Management | 1 | Lump Sum | 5,200.00 | 5,200.00 |
| 240-00000 | Wildlife Biologist | 230 | Hour | 20,629.20 | 89.69 |
| 240-00010 | Removal of Nests | 107 | Hour | 10,693.30 | 99.94 |
| 240-00020 | Netting | 300 | Sq Yard | 4,906.00 | 16.35 |
| 240-00100 | Prairie Dog Management | 3 | Lump Sum | 29,808.25 | 9,936.08 |

INDEX AND AVERAGE UNIT BID PRICES FOR 01/01/11 THROUGH 12/31/11

| ITEM NUMBER | ITEM | TOTAL QUANTITY | UNIT | TOTAL COST | AVERAGE PRICE |
|---|---|---|---|---|---|
| 250-00010 | Environmental Health and Safety Management | 12 | Lump Sum | 47,913.00 | 3,992.75 |
| 250-00050 | Monitoring Technician | 1,766 | Hour | 103,028.00 | 58.34 |
| 250-00100 | Environmental Health and Safety | 1 | Lump Sum | 725.00 | 725.00 |
| 250-00110 | Health and Safety Officer | 988 | Hour | 64,761.00 | 65.55 |
| 250-00120 | Material Sampling and Delivery | 8 | Each | 2,920.00 | 365.00 |
| 250-00200 | Material Handling (Stockpile) | 30 | Cubic Yard | 2,220.00 | 74.00 |
| 250-00210 | Solid Waste Disposal | 10 | Cubic Yard | 800.00 | 80.00 |
| 250-00220 | Hazardous Waste Disposal | 140 | Cubic Yard | 57,958.60 | 413.99 |
| 304-01000 | Aggregate Base Course (Class 1) | 132,942 | Ton | 2,245,125.15 | 16.89 |
| 304-02000 | Aggregate Base Course (Class 2) | 56,613 | Ton | 862,470.52 | 15.23 |
| 304-02005 | Aggregate Base Course (Class 2) | 22,109 | Cubic Yard | 641,161.00 | 29.00 |
| 304-03000 | Aggregate Base Course (Class 3) | 7,318 | Ton | 128,862.40 | 17.61 |
| 304-03005 | Aggregate Base Course (Class 3) | 44 | Cubic Yard | 1,320.00 | 30.00 |
| 304-05000 | Aggregate Base Course (Class 5) | 2,335 | Ton | 46,700.00 | 20.00 |
| 304-06000 | Aggregate Base Course (Class 6) | 200,423 | Ton | 3,319,224.29 | 16.56 |
| 304-06007 | Aggregate Base Course (Class 6) | 82,064 | Cubic Yard | 2,140,819.52 | 26.09 |
| 304-06008 | Aggregate Base Course (Class 6) (Special) | 2,089 | Cubic Yard | 55,324.69 | 26.48 |
| 304-07000 | Aggregate Base Course (Class 7) | 6,599 | Ton | 140,649.44 | 21.31 |
| 304-07005 | Aggregate Base Course (Class 7) | 3,862 | Cubic Yard | 150,393.14 | 38.94 |
| 304-09000 | Aggregate Base Course (Special) | 4,123 | Cubic Yard | 129,246.00 | 31.35 |
| 304-09014 | Aggregate Base Course (Special) | 11,774 | Ton | 194,038.05 | 16.48 |
| 307-00000 | Hydrated Lime | 1,968 | Ton | 310,330.00 | 157.69 |
| 310-00608 | Full Depth Reclamation of Hot Mix Asphalt Pavement (0 | 45,567 | Sq Yard | 108,422.50 | 2.38 |
| 310-00610 | Full Depth Reclamation of Hot Mix Asphalt Pavement (8 | 122,347 | Sq Yard | 323,020.30 | 2.64 |
| 403-00720 | Hot Bituminous Pavement (Patching) (Asphalt) | 18,537 | Ton | 2,041,448.84 | 110.13 |
| 403-00721 | Hot Bituminous Pavement (Patching) (Asphalt) | 1,311 | Sq Yard | 133,683.61 | 101.97 |
| 403-00800 | Emergency Pothole Repair | 330 | Ton | 89,798.50 | 272.12 |
| 403-02000 | Hot Bituminous Pavement (Special) | 4,670 | Ton | 347,890.00 | 74.49 |
| 403-09210 | Stone Matrix Asphalt | 23,332 | Ton | 2,231,705.80 | 95.65 |
| 403-09221 | Stone Matrix Asphalt (Fibers)(Asphalt) | 40,925 | Ton | 3,800,049.76 | 92.85 |
| 403-09500 | Furnish Hot Bituminous Pavement | 14,401 | Ton | 879,000.79 | 61.04 |
| 403-33751 | Hot Bituminous Pavement (Grading S) (75) (PG 64-28) | 43,285 | Ton | 2,463,050.23 | 56.90 |
| 403-33841 | Hot Bituminous Pavement (Grading S) (100) (PG 64-22) | 78,685 | Ton | 4,135,896.99 | 52.56 |
| 403-33851 | Hot Bituminous Pavement (Grading S) (100) (PG 64-28) | 1,649 | Ton | 103,887.00 | 63.00 |
| 403-33871 | Hot Bituminous Pavement (Grading S) (100) (PG 76-28) | 218 | Ton | 13,734.00 | 63.00 |
| 403-34701 | Hot Bituminous Pavement (Grading SX) (75) | 263,040 | Ton | 11,189,266.35 | 42.54 |
| 403-34721 | Hot Bituminous Pavement (Grading SX) (75) (PG 58-28) | 141,283 | Ton | 10,197,844.25 | 72.18 |
| 403-34731 | Hot Bituminous Pavement (Grading SX) (75) (PG 58-34) | 25,829 | Ton | 1,671,116.89 | 64.70 |

INDEX AND AVERAGE UNIT BID PRICES FOR 01/01/11 THROUGH 12/31/11

| ITEM NUMBER | ITEM | TOTAL QUANTITY | UNIT | TOTAL COST | AVERAGE PRICE |
|---|---|---|---|---|---|
| 403-34741 | Hot Bituminous Pavement (Grading SX) (75) (PG 64-22) | 37,671 | Ton | 2,754,411.66 | 73.12 |
| 403-34751 | Hot Bituminous Pavement (Grading SX) (75) (PG 64-28) | 34,128 | Ton | 2,550,479.12 | 74.73 |
| 403-34801 | Hot Bituminous Pavement (Grading SX) (100) | 20,335 | Ton | 932,204.50 | 45.84 |
| 403-34821 | Hot Bituminous Pavement (Grading SX) (100) (PG 58-28) | 2,753 | Ton | 187,286.59 | 68.03 |
| 403-34841 | Hot Bituminous Pavement (Grading SX) (100) (PG 64-22) | 49,719 | Ton | 2,821,792.84 | 56.75 |
| 403-34851 | Hot Bituminous Pavement (Grading SX) (100) (PG 64-28) | 46,864 | Ton | 2,686,937.85 | 57.33 |
| 403-34871 | Hot Bituminous Pavement (Grading SX) (100) (PG 76-28) | 108,646 | Ton | 6,514,334.40 | 59.96 |
| 405-00100 | Heating and Remixing Treatment | 701,120 | Sq Yard | 3,825,649.04 | 5.46 |
| 406-09500 | Cold Bituminous Pavement (Recycle) | 603,453 | Sq Yard | 1,050,591.40 | 1.74 |
| 408-01000 | Hot Poured Joint and Crack Sealant | 90 | Ton | 261,540.00 | 2,906.00 |
| 408-01400 | Crack Sealant (Special) | 5 | Ton | 24,970.00 | 4,994.00 |
| 409-01015 | Cover Coat Material (Type I) | 584,244 | Sq Yard | 233,697.60 | 0.40 |
| 409-02030 | Cover Coat Material (Type I) (Special) | 527,788 | Sq Yard | 839,780.67 | 1.59 |
| 411-03342 | Asphalt Cement Performance Grade (PG 64-28) | 390 | Ton | 276,802.50 | 709.75 |
| 411-03345 | Asphalt Cement Performance Grade (PG 76-28) | 698 | Ton | 591,490.80 | 847.41 |
| 411-03352 | Asphalt Cement Performance Grade (PG 58-28) | 9,346 | Ton | 5,306,771.80 | 567.81 |
| 411-03354 | Asphalt Cement Performance Grade (PG 64-22) | 2,272 | Ton | 1,216,203.00 | 535.30 |
| 411-03355 | Asphalt Cement Performance Grade (PG 58-34) | 5,063 | Ton | 2,069,907.71 | 408.83 |
| 411-10217 | Emulsified Asphalt (CRS-2P) | 2,318 | Ton | 1,086,590.00 | 468.76 |
| 411-10253 | Emulsified Asphalt (CSS-1H) | 14,377 | Gallon | 33,730.75 | 2.35 |
| 411-10255 | Emulsified Asphalt (Slow-Setting) | 485,568 | Gallon | 986,883.68 | 2.03 |
| 411-10300 | Emulsified Asphalt (Prime Coat) | 932 | Gallon | 3,448.40 | 3.70 |
| 411-90010 | Asphalt Rejuvenating Agent | 37,743 | Gallon | 126,552.22 | 3.35 |
| 411-90040 | Recycling Agent | 764,967 | Gallon | 1,925,059.25 | 2.52 |
| 412-00000 | Furnish Concrete Pavement | 4,159 | Cubic Yard | 194,225.30 | 46.70 |
| 412-00600 | Concrete Pavement (6 Inch) | 103,886 | Sq Yard | 1,897,558.17 | 18.27 |
| 412-00605 | Concrete Pavement (6 Inch) (Fast Track) | 8,382 | Sq Yard | 200,059.80 | 23.87 |
| 412-00800 | Concrete Pavement (8 Inch) | 1,425 | Sq Yard | 89,892.20 | 63.08 |
| 412-00850 | Concrete Pavement (8-1/2 Inch) | 14,002 | Sq Yard | 500,431.48 | 35.74 |
| 412-00870 | Concrete Pavement (8-1/2 Inch) (Fast Track) | 1,749 | Sq Yard | 95,722.77 | 54.73 |
| 412-00900 | Concrete Pavement (9 Inch) | 22,293 | Sq Yard | 881,122.65 | 39.52 |
| 412-00920 | Concrete Pavement (9 Inch) (Fast Track) | 5,551 | Sq Yard | 325,344.11 | 58.61 |
| 412-00950 | Concrete Pavement (9-1/2 Inch) | 1,568 | Sq Yard | 99,256.40 | 63.30 |
| 412-01000 | Concrete Pavement (10 Inch) | 28,795 | Sq Yard | 1,415,931.00 | 49.17 |
| 412-01001 | Concrete Pavement (10 Inch) (Special) | 1,022 | Sq Yard | 80,738.00 | 79.00 |
| 412-01050 | Concrete Pavement (10-1/2 Inch) | 69,699 | Sq Yard | 2,195,518.50 | 31.50 |
| 412-01100 | Concrete Pavement (11 Inch) | 94 | Sq Yard | 5,702.98 | 60.67 |
| 412-01120 | Concrete Pavement (11 Inch) (Fast Track) | 498 | Sq Yard | 69,494.88 | 139.55 |

INDEX AND AVERAGE UNIT BID PRICES FOR 01/01/11 THROUGH 12/31/11

| ITEM NUMBER | ITEM | TOTAL QUANTITY | UNIT | TOTAL COST | AVERAGE PRICE |
|---|---|---|---|---|---|
| 412-01200 | Concrete Pavement (12 Inch) | 216 | Sq Yard | 11,448.00 | 53.00 |
| 412-01300 | Concrete Pavement (13 Inch) | 42,460 | Sq Yard | 1,936,176.00 | 45.60 |
| 412-01350 | Concrete Pavement (13-1/2 Inch) | 27,523 | Sq Yard | 1,348,627.00 | 49.00 |
| 412-01352 | Concrete Pavement (13-1/2 In) (Fast Track) | 3,058 | Sq Yard | 201,828.00 | 66.00 |
| 412-14000 | Sawing and Sealing Concrete Pavement Joints | 29,469 | Lin Foot | 51,570.75 | 1.75 |
| 412-15000 | Routing and Sealing Concrete Pavement Cracks | 38,176 | Lin Foot | 129,798.40 | 3.40 |
| 412-15050 | Cross Stitching | 19,090 | Each | 439,070.00 | 23.00 |
| 420-00000 | Geomembrane | 18,505 | Sq Yard | 155,333.96 | 8.39 |
| 420-00102 | Geotextile (Erosion Control) (Class 1) | 12,280 | Sq Yard | 29,239.26 | 2.38 |
| 420-00103 | Geotextile (Erosion Control) (Class 2) | 2,599 | Sq Yard | 16,198.24 | 6.23 |
| 420-00112 | Geotextile (Drainage) (Class 1) | 4,446 | Sq Yard | 10,219.76 | 2.30 |
| 420-00113 | Geotextile (Drainage) (Class 2) | 492 | Sq Yard | 4,345.28 | 8.83 |
| 420-00114 | Geotextile (Drainage) (Class 3) | 27 | Sq Yard | 141.75 | 5.25 |
| 420-00132 | Geotextile (Separator) (Class 1) | 9,758 | Sq Yard | 21,986.00 | 2.25 |
| 420-00133 | Geotextile (Separator) (Class 2) | 36,407 | Sq Yard | 50,969.80 | 1.40 |
| 420-00200 | Geotextile (Weed Barrier) | 4,495 | Sq Yard | 33,678.24 | 7.49 |
| 420-00400 | Media Filter Drain (MFD) mix (Type 1) | 753 | Cubic Yard | 74,590.08 | 99.06 |
| 420-00511 | Asphalt Reinforcement Geogrid | 321 | Sq Yard | 2,889.00 | 9.00 |
| 501-00000 | Steel Sheet Piling (Type I) | 279 | Sq Foot | 16,740.00 | 60.00 |
| 502-00100 | Drilling Hole to Facilitate Pile Driving | 730 | Lin Foot | 95,046.00 | 130.20 |
| 502-00460 | Pile Tip | 92 | Each | 15,424.10 | 167.65 |
| 502-02000 | Dynamic Load Testing | 1 | Lump Sum | 100.00 | 100.00 |
| 502-11253 | Steel Piling (HP 12x53) | 338 | Lin Foot | 14,196.00 | 42.00 |
| 502-11274 | Steel Piling (HP 12x74) | 6,430 | Lin Foot | 377,267.89 | 58.67 |
| 502-11489 | Steel Piling (HP 14x89) | 984 | Lin Foot | 61,500.00 | 62.50 |
| 502-14117 | Steel Piling (HP 14x117) | 3,135 | Lin Foot | 210,045.00 | 67.00 |
| 503-00018 | Drilled Caisson (18 Inch) | 427 | Lin Foot | 31,329.30 | 73.37 |
| 503-00024 | Drilled Caisson (24 Inch) | 3,169 | Lin Foot | 234,221.72 | 73.91 |
| 503-00030 | Drilled Caisson (30 Inch) | 9,833 | Lin Foot | 1,271,959.92 | 129.36 |
| 503-00036 | Drilled Caisson (36 Inch) | 5,899 | Lin Foot | 1,277,921.26 | 216.63 |
| 503-00042 | Drilled Caisson (42 Inch) | 2,460 | Lin Foot | 565,818.40 | 230.01 |
| 503-00048 | Drilled Caisson (48 Inch) | 5,842 | Lin Foot | 1,715,217.53 | 293.60 |
| 503-00054 | Drilled Caisson (54 Inch) | 4,178 | Lin Foot | 1,080,427.29 | 258.60 |
| 503-00060 | Drilled Caisson (60 Inch) | 708 | Lin Foot | 248,634.60 | 351.18 |
| 503-00072 | Drilled Caisson (72 Inch) | 71 | Lin Foot | 42,600.00 | 600.00 |
| 503-00210 | Aggregate Column Ground Improvement | 1 | Lump Sum | 621,024.71 | 621,024.71 |
| 503-00400 | Drilling and Logging Bores | 59 | Lin Foot | 10,920.00 | 185.08 |
| 504-04410 | Block Facing | 19,577 | Sq Foot | 255,631.29 | 13.06 |

INDEX AND AVERAGE UNIT BID PRICES FOR 01/01/11 THROUGH 12/31/11

| ITEM NUMBER | ITEM | TOTAL QUANTITY | UNIT | TOTAL COST | AVERAGE PRICE |
|---|---|---|---|---|---|
| 504-04420 | Precast Panel Facing | 229,434 | Sq Foot | 3,772,812.98 | 16.44 |
| 504-05000 | Wire Mesh Facing | 2,304 | Sq Foot | 25,344.00 | 11.00 |
| 504-06310 | Ground Nail (10 Foot) | 17 | Each | 3,264.00 | 192.00 |
| 504-06315 | Ground Nail (15 Foot) | 50 | Each | 14,050.00 | 281.00 |
| 504-06320 | Ground Nail (20 Foot) | 867 | Each | 353,736.00 | 408.00 |
| 504-06325 | Ground Nail (25 Foot) | 68 | Each | 30,736.00 | 452.00 |
| 504-06330 | Ground Nail (30 Foot) | 149 | Each | 89,400.00 | 600.00 |
| 504-08050 | Stone Landscape Wall | 100 | Sq Foot | 3,655.00 | 36.55 |
| 504-08100 | Timber Retaining Wall | 100 | Sq Foot | 2,000.00 | 20.00 |
| 504-08255 | Masonry Landscape Wall (Dry Stack) | 8,190 | Sq Foot | 365,908.00 | 44.68 |
| 506-00010 | Riprap (Special) | 2,519 | Cubic Yard | 211,377.37 | 83.91 |
| 506-00030 | Grouted Riprap | 377 | Cubic Yard | 76,864.50 | 203.88 |
| 506-00036 | Grouted Riprap (36 Inch) (Special) | 101 | Cubic Yard | 15,958.00 | 158.00 |
| 506-00100 | Riprap (Gabions) | 6 | Cubic Yard | 554.70 | 92.45 |
| 506-00206 | Riprap (6 Inch) | 2,494 | Cubic Yard | 392,860.00 | 157.52 |
| 506-00209 | Riprap (9 Inch) | 2,084 | Cubic Yard | 124,679.78 | 59.83 |
| 506-00212 | Riprap (12 Inch) | 3,249 | Cubic Yard | 173,888.36 | 53.52 |
| 506-00218 | Riprap (18 Inch) | 5,123 | Cubic Yard | 311,399.77 | 60.78 |
| 506-00224 | Riprap (24 Inch) | 6,761 | Cubic Yard | 333,441.11 | 49.32 |
| 506-00237 | Riprap (36 Inch) (Special) | 69 | Cubic Yard | 5,206.74 | 75.46 |
| 506-00409 | Soil Riprap (9 Inch) | 7 | Cubic Yard | 1,022.42 | 146.06 |
| 506-00412 | Soil Riprap (12 Inch) | 29 | Cubic Yard | 1,458.70 | 50.30 |
| 506-00418 | Soil Riprap (18 Inch) | 2,810 | Cubic Yard | 127,630.20 | 45.42 |
| 506-00424 | Soil Riprap (24 Inch) | 308 | Cubic Yard | 20,944.00 | 68.00 |
| 506-01020 | Geogrid Reinforcement | 29,187 | Sq Yard | 217,473.25 | 7.45 |
| 507-00000 | Concrete Slope and Ditch Paving | 457 | Cubic Yard | 194,191.73 | 424.93 |
| 507-00100 | Concrete Slope and Ditch Paving (Reinforced) | 831 | Cubic Yard | 299,044.47 | 359.86 |
| 507-00105 | Concrete Slope and Ditch Paving (Reinforced) (Colored | 19 | Cubic Yard | 5,890.00 | 310.00 |
| 507-00300 | Grouted Rubble Slope and Ditch Paving | 15 | Cubic Yard | 7,740.00 | 516.00 |
| 507-00400 | Bituminous Slope and Ditch Paving (Asphalt) | 18 | Ton | 5,640.74 | 313.37 |
| 508-00100 | Treated Timber | 4 | M Ft Bd Me | 26,840.00 | 6,710.00 |
| 509-00000 | Structural Steel | 958,655 | Pound | 1,679,555.90 | 1.75 |
| 509-00001 | Structural Steel (Galvanized) | 22,960 | Pound | 35,128.80 | 1.53 |
| 509-08100 | Provide Temporary Support | 2 | Lump Sum | 650,000.00 | 325,000.00 |
| 509-08120 | Temporary Bridge Deck | 1,938 | Sq Foot | 1,938.00 | 1.00 |
| 509-60000 | Architectural Steel Refurbishment | 1 | Lump Sum | 36,000.00 | 36,000.00 |
| 509-90000 | Paint Existing Structure(S) | 1 | Lump Sum | 554,700.00 | 554,700.00 |
| 509-90003 | Paint Structural Steel | 1 | Lump Sum | 55,000.00 | 55,000.00 |

INDEX AND AVERAGE UNIT BID PRICES FOR 01/01/11 THROUGH 12/31/11

| ITEM NUMBER | ITEM | TOTAL QUANTITY | UNIT | TOTAL COST | AVERAGE PRICE |
|---|---|---|---|---|---|
| 512-00101 | Bearing Device (Type I) | 85 | Each | 200,954.40 | 2,364.17 |
| 512-00102 | Bearing Device (Type II) | 8 | Each | 18,880.00 | 2,360.00 |
| 512-00103 | Bearing Device (Type III) | 12 | Each | 66,000.00 | 5,500.00 |
| 513-00600 | Bridge Drain | 12 | Each | 110,600.00 | 9,216.67 |
| 513-00606 | Bridge Drain (6 Inch) | 6 | Each | 900.00 | 150.00 |
| 513-00690 | Bridge Drain (Special) | 14 | Each | 73,773.32 | 5,269.52 |
| 514-00000 | Pipe Railing | 1,434 | Lin Foot | 107,256.00 | 74.79 |
| 514-00200 | Pedestrian Railing (Steel) | 1,492 | Lin Foot | 217,825.50 | 146.00 |
| 514-00201 | Pedestrian Railing (Steel)(Special) | 867 | Lin Foot | 150,810.00 | 173.94 |
| 515-00120 | Waterproofing (Membrane) | 69,060 | Sq Yard | 976,960.73 | 14.15 |
| 515-00300 | Waterproof Coating | 510 | Sq Yard | 4,182.00 | 8.20 |
| 515-00400 | Concrete Sealer | 2,523 | Sq Yard | 15,311.50 | 6.07 |
| 518-00010 | Roadway Compression Joint Sealer | 270 | Lin Foot | 16,740.00 | 62.00 |
| 518-00112 | Waterstop (12 Inch) | 214 | Lin Foot | 3,674.00 | 17.17 |
| 518-01002 | Bridge Expansion Device (0-2 Inch) | 894 | Lin Foot | 185,140.80 | 207.09 |
| 518-01004 | Bridge Expansion Device (0-4 Inch) | 3,459 | Lin Foot | 669,743.15 | 193.62 |
| 518-01012 | Bridge Expansion Device (0-12 Inch) | 72 | Lin Foot | 129,600.00 | 1,800.00 |
| 518-02010 | Elastomeric Concrete End Dam | 426 | Cubic Foot | 110,900.00 | 260.33 |
| 518-03000 | Sawing and Sealing Bridge Joint | 614 | Lin Foot | 4,882.55 | 7.95 |
| 519-01000 | Epoxy Resin (Injection) | 4 | Lin Foot | 2,080.00 | 520.00 |
| 519-01300 | Polyurethane Resin | 25,000 | Pound | 228,750.00 | 9.15 |
| 519-03000 | Thin Bonded Epoxy Overlay | 12,798 | Sq Yard | 495,108.75 | 38.69 |
| 601-01000 | Concrete Class B | 192 | Cubic Yard | 87,601.46 | 456.26 |
| 601-01025 | Concrete Class B (Miscellaneous) | 51 | Cubic Yard | 20,288.10 | 397.81 |
| 601-01030 | Concrete Class B (Box Culvert) | 71 | Cubic Yard | 22,609.95 | 318.45 |
| 601-01040 | Concrete Class B (Bridge) | 156 | Cubic Yard | 28,548.00 | 183.00 |
| 601-01050 | Concrete Class B (Wall) | 42 | Cubic Yard | 25,320.83 | 602.88 |
| 601-03000 | Concrete Class D | 2,311 | Cubic Yard | 936,341.44 | 405.17 |
| 601-03020 | Concrete Class D (Miscellaneous) | 9 | Cubic Yard | 14,625.00 | 1,625.00 |
| 601-03027 | Concrete Class D (Special) | 235 | Cubic Yard | 130,521.35 | 555.41 |
| 601-03030 | Concrete Class D (Box Culvert) | 917 | Cubic Yard | 407,655.34 | 444.55 |
| 601-03040 | Concrete Class D (Bridge) | 22,120 | Cubic Yard | 9,088,676.01 | 410.88 |
| 601-03041 | Concrete Class D (Bridge) (Special) | 1,138 | Cubic Yard | 663,121.50 | 582.71 |
| 601-03050 | Concrete Class D (Wall) | 8,807 | Cubic Yard | 3,253,783.41 | 369.45 |
| 601-03540 | Concrete Class DT (Deck Topping) | 455 | Cubic Yard | 239,995.80 | 527.46 |
| 601-04000 | Concrete Class E | 108 | Cubic Yard | 36,828.00 | 341.00 |
| 601-05000 | Concrete Class H | 125 | Cubic Yard | 83,750.00 | 670.00 |
| 601-05001 | Concrete Class H (Bridge) | 477 | Cubic Yard | 258,057.00 | 541.00 |

INDEX AND AVERAGE UNIT BID PRICES FOR 01/01/11 THROUGH 12/31/11

| ITEM NUMBER | ITEM | TOTAL QUANTITY | UNIT | TOTAL COST | AVERAGE PRICE |
|---|---|---|---|---|---|
| 601-05020 | Concrete Class R | 17 | Cubic Yard | 28,050.00 | 1,650.00 |
| 601-05050 | Concrete Class S50 | 150 | Cubic Yard | 45,000.00 | 300.00 |
| 601-06100 | Concrete (Patching) | 7 | Cubic Yard | 15,120.00 | 2,160.00 |
| 601-06150 | Concrete (Patching) | 200 | Sq Foot | 21,000.00 | 105.00 |
| 601-06400 | Grout (Bridge)(Special) | 11,925 | Cubic Foot | 149,778.00 | 12.56 |
| 601-21003 | Precast Wall Segment | 1,704 | Sq Foot | 71,568.00 | 42.00 |
| 601-40005 | Cut Stone Veneer | 30,718 | Sq Foot | 1,331,010.94 | 43.33 |
| 601-40250 | Bridge Deck Finish (Sawed Grooves) | 266 | Sq Yard | 984.20 | 3.70 |
| 601-40300 | Structural Concrete Coating | 35,407 | Sq Yard | 321,625.83 | 9.08 |
| 601-40302 | Structural Concrete Coating (Anti-Graffiti) | 137,671 | Sq Foot | 117,020.35 | 0.85 |
| 601-40400 | Structural Concrete Stain | 50,226 | Sq Yard | 370,231.30 | 7.37 |
| 602-00000 | Reinforcing Steel | 1,023,178 | Pound | 745,263.66 | 0.73 |
| 602-00020 | Reinforcing Steel (Epoxy Coated) | 5,781,962 | Pound | 4,827,398.42 | 0.83 |
| 603-00001 | Annular Space Grouting | 318 | Cubic Yard | 93,299.75 | 293.40 |
| 603-00024 | Prepare Culvert Pipe (24 Inch) | 310 | Lin Foot | 20,150.00 | 65.00 |
| 603-00025 | Culvert Lining (24 Inch)(Special) | 854 | Lin Foot | 206,561.75 | 241.88 |
| 603-00030 | Culvert Lining (30 Inch) | 172 | Lin Foot | 38,614.00 | 224.50 |
| 603-00035 | Prepare Culvert Pipe (36 Inch) | 75 | Lin Foot | 1,875.00 | 25.00 |
| 603-00036 | Culvert Lining (36 Inch) | 120 | Lin Foot | 25,800.00 | 215.00 |
| 603-00040 | Culvert Lining (40 Inch) | 152 | Lin Foot | 37,925.52 | 249.51 |
| 603-00047 | Prepare Culvert Pipe (48 Inch) | 560 | Lin Foot | 18,700.00 | 33.39 |
| 603-00048 | Culvert Lining (48 Inch) | 735 | Lin Foot | 189,425.00 | 257.72 |
| 603-00049 | Culvert Lining (48 Inch)(Special) | 35 | Lin Foot | 16,800.00 | 480.00 |
| 603-00053 | Prepare Culvert Pipe (54 Inch) | 354 | Lin Foot | 14,160.00 | 40.00 |
| 603-00054 | Culvert Lining (54 Inch) | 354 | Lin Foot | 97,350.00 | 275.00 |
| 603-00060 | Culvert Lining (60 Inch) | 333 | Lin Foot | 193,379.76 | 580.72 |
| 603-00072 | Culvert Lining (72 Inch) | 250 | Lin Foot | 202,240.00 | 808.96 |
| 603-01120 | 12 Inch Reinforced Concrete Pipe | 122 | Lin Foot | 5,868.20 | 48.10 |
| 603-01125 | 12 Inch Reinforced Concrete Pipe (Complete In Place) | 18 | Lin Foot | 676.62 | 37.59 |
| 603-01150 | 15 Inch Reinforced Concrete Pipe | 302 | Lin Foot | 17,937.00 | 59.39 |
| 603-01155 | 15 Inch Reinforced Concrete Pipe (Complete In Place) | 282 | Lin Foot | 29,856.00 | 105.87 |
| 603-01180 | 18 Inch Reinforced Concrete Pipe | 3,042 | Lin Foot | 145,735.00 | 47.91 |
| 603-01185 | 18 Inch Reinforced Concrete Pipe (Complete In Place) | 11,958 | Lin Foot | 601,512.27 | 50.30 |
| 603-01240 | 24 Inch Reinforced Concrete Pipe | 2,080 | Lin Foot | 138,074.00 | 66.38 |
| 603-01245 | 24 Inch Reinforced Concrete Pipe (Complete In Place) | 6,772 | Lin Foot | 453,890.20 | 67.02 |
| 603-01300 | 30 Inch Reinforced Concrete Pipe | 1,900 | Lin Foot | 125,000.00 | 65.79 |
| 603-01305 | 30 Inch Reinforced Concrete Pipe (Complete In Place) | 4,745 | Lin Foot | 451,219.40 | 95.09 |
| 603-01360 | 36 Inch Reinforced Concrete Pipe | 788 | Lin Foot | 82,468.00 | 104.65 |

INDEX AND AVERAGE UNIT BID PRICES FOR 01/01/11 THROUGH 12/31/11

| ITEM NUMBER | ITEM | TOTAL QUANTITY | UNIT | TOTAL COST | AVERAGE PRICE |
|---|---|---|---|---|---|
| 603-01365 | 36 Inch Reinforced Concrete Pipe (Complete In Place) | 2,842 | Lin Foot | 294,927.44 | 103.77 |
| 603-01420 | 42 Inch Reinforced Concrete Pipe | 319 | Lin Foot | 30,725.00 | 96.32 |
| 603-01425 | 42 Inch Reinforced Concrete Pipe (Complete In Place) | 13 | Lin Foot | 2,080.00 | 160.00 |
| 603-01480 | 48 Inch Reinforced Concrete Pipe | 176 | Lin Foot | 32,167.52 | 182.77 |
| 603-01485 | 48 Inch Reinforced Concrete Pipe (Complete In Place) | 759 | Lin Foot | 111,140.00 | 146.43 |
| 603-01545 | 54 Inch Reinforced Concrete Pipe (Complete In Place) | 233 | Lin Foot | 41,707.00 | 179.00 |
| 603-01665 | 66 Inch Reinforced Concrete Pipe (Complete In Place) | 422 | Lin Foot | 101,280.00 | 240.00 |
| 603-01725 | 72 Inch Reinforced Concrete Pipe (Complete In Place) | 2,185 | Lin Foot | 589,950.00 | 270.00 |
| 603-02185 | 23x14 Inch Reinforced Concrete Pipe (Complete In Plac | 396 | Lin Foot | 26,550.81 | 67.05 |
| 603-02240 | 30x19 Inch Reinforced Concrete Pipe Elliptical | 86 | Lin Foot | 11,395.00 | 132.50 |
| 603-02245 | 30x19 Inch Reinforced Concrete Pipe Elliptical | 658 | Lin Foot | 72,388.10 | 110.01 |
| 603-02305 | 38x24 Inch Reinforced Concrete Pipe Elliptical | 1,126 | Lin Foot | 149,980.48 | 133.20 |
| 603-02360 | 45x29 Inch Reinforced Concrete Pipe Elliptical | 182 | Lin Foot | 25,116.00 | 138.00 |
| 603-02365 | 45x29 Inch Reinforced Concrete Pipe Elliptical | 198 | Lin Foot | 20,168.28 | 101.86 |
| 603-02485 | 60x38 Inch Reinforced Concrete Pipe Elliptical (CIP) | 100 | Lin Foot | 28,000.00 | 280.00 |
| 603-02665 | 83X53 Inch Reinforced Concrete Pipe Elliptical | 529 | Lin Foot | 111,090.00 | 210.00 |
| 603-05012 | 12 Inch Reinforced Concrete End Section | 2 | Each | 1,600.00 | 800.00 |
| 603-05018 | 18 Inch Reinforced Concrete End Section | 36 | Each | 30,945.96 | 859.61 |
| 603-05024 | 24 Inch Reinforced Concrete End Section | 24 | Each | 25,075.00 | 1,044.79 |
| 603-05030 | 30 Inch Reinforced Concrete End Section | 4 | Each | 8,531.22 | 2,132.81 |
| 603-05036 | 36 Inch Reinforced Concrete End Section | 8 | Each | 11,916.53 | 1,489.57 |
| 603-05042 | 42 Inch Reinforced Concrete End Section | 1 | Each | 2,000.00 | 2,000.00 |
| 603-05048 | 48 Inch Reinforced Concrete End Section | 2 | Each | 3,600.00 | 1,800.00 |
| 603-05124 | 30x19 Inch Reinforced Concrete End Section Elliptical | 2 | Each | 4,436.31 | 2,218.16 |
| 603-05136 | 45x29 Inch Reinforced Concrete End Section Elliptical | 2 | Each | 3,918.34 | 1,959.17 |
| 603-10120 | 12 Inch Corrugated Steel Pipe | 249 | Lin Foot | 9,806.18 | 39.38 |
| 603-10180 | 18 Inch Corrugated Steel Pipe | 1,067 | Lin Foot | 57,705.00 | 54.08 |
| 603-10240 | 24 Inch Corrugated Steel Pipe | 1,137 | Lin Foot | 96,755.44 | 85.10 |
| 603-10300 | 30 Inch Corrugated Steel Pipe | 93 | Lin Foot | 10,943.08 | 117.67 |
| 603-10360 | 36 Inch Corrugated Steel Pipe | 303 | Lin Foot | 25,686.18 | 84.77 |
| 603-10480 | 48 Inch Corrugated Steel Pipe | 350 | Lin Foot | 58,320.24 | 166.63 |
| 603-10900 | 90 Inch Corrugated Steel Pipe | 152 | Lin Foot | 24,040.32 | 158.16 |
| 603-15015 | 15 Inch Equivalent Corrugated Steel Pipe Arch | 30 | Lin Foot | 1,950.00 | 65.00 |
| 603-15018 | 18 Inch Equivalent Corrugated Steel Pipe Arch | 38 | Lin Foot | 6,460.00 | 170.00 |
| 603-15030 | 30 Inch Equivalent Corrugated Steel Pipe Arch | 87 | Lin Foot | 15,579.96 | 179.08 |
| 603-15036 | 36 Inch Equivalent Corrugated Steel Pipe Arch | 50 | Lin Foot | 10,500.00 | 210.00 |
| 603-15042 | 42 Inch Equivalent Corrugated Steel Pipe Arch | 93 | Lin Foot | 21,413.25 | 230.25 |
| 603-15084 | 84 Inch Equivalent Corrugated Steel Pipe Arch | 24 | Lin Foot | 8,520.00 | 355.00 |

INDEX AND AVERAGE UNIT BID PRICES FOR 01/01/11 THROUGH 12/31/11

| ITEM NUMBER | ITEM | TOTAL QUANTITY | UNIT | TOTAL COST | AVERAGE PRICE |
|---|---|---|---|---|---|
| 603-30018 | 18 Inch Steel End Section | 8 | Each | 2,705.02 | 338.13 |
| 603-30024 | 24 Inch Steel End Section | 39 | Each | 14,021.93 | 359.54 |
| 603-30030 | 30 Inch Steel End Section | 3 | Each | 2,342.48 | 780.83 |
| 603-30036 | 36 Inch Steel End Section | 4 | Each | 2,070.84 | 517.71 |
| 603-30048 | 48 Inch Steel End Section | 3 | Each | 5,000.00 | 1,666.67 |
| 603-31318 | 18 Inch Equivalent Arch Steel End Section | 2 | Each | 520.00 | 260.00 |
| 603-31330 | 30 Inch Equivalent Arch Steel End Section | 2 | Each | 2,353.62 | 1,176.81 |
| 603-31336 | 36 Inch Equivalent Arch Steel End Section | 2 | Each | 1,200.00 | 600.00 |
| 603-31342 | 42 Inch Equivalent Arch Steel End Section | 2 | Each | 3,786.26 | 1,893.13 |
| 603-33030 | 30 Inch Pipe Safety End Treatment | 2 | Each | 3,200.00 | 1,600.00 |
| 603-33048 | 48 Inch Pipe Safety End Treatment | 6 | Each | 14,368.52 | 2,394.75 |
| 603-50004 | 4 Inch Plastic Pipe | 831 | Lin Foot | 10,503.20 | 12.64 |
| 603-50012 | 12 Inch Plastic Pipe | 537 | Lin Foot | 29,982.00 | 55.83 |
| 603-50015 | 15 Inch Plastic Pipe | 1,567 | Lin Foot | 83,865.81 | 53.52 |
| 603-50018 | 18 Inch Plastic Pipe | 163 | Lin Foot | 10,279.00 | 63.06 |
| 603-50030 | 30 Inch Plastic Pipe | 278 | Lin Foot | 140,261.00 | 504.54 |
| 603-61120 | 12 Inch Flexible Pipe | 249 | Lin Foot | 22,290.00 | 89.52 |
| 603-61240 | 24 Inch Flexible Pipe | 688 | Lin Foot | 96,320.00 | 140.00 |
| 603-70703 | 7x3 Foot Concrete Box Culvert (Precast) | 268 | Lin Foot | 170,712.00 | 636.99 |
| 603-70704 | 7x4 Foot Concrete Box Culvert (Precast) | 1,107 | Lin Foot | 442,800.00 | 400.00 |
| 603-70804 | 8x4 Foot Concrete Box Culvert (Precast) | 57 | Lin Foot | 39,362.84 | 690.58 |
| 603-70805 | 8x5 Foot Concrete Box Culvert (Precast) | 57 | Lin Foot | 38,735.74 | 679.57 |
| 603-83008 | 8 Inch Sewer Pipe | 1,314 | Lin Foot | 49,275.00 | 37.50 |
| 603-83009 | 8 Inch Sewer Pipe (Special) | 232 | Lin Foot | 14,384.00 | 62.00 |
| 604-00305 | Inlet Type C (5 Foot) | 46 | Each | 103,778.56 | 2,256.06 |
| 604-00310 | Inlet Type C (10 Foot) | 8 | Each | 30,167.37 | 3,770.92 |
| 604-00315 | Inlet Type C (15 Foot) | 4 | Each | 14,838.00 | 3,709.50 |
| 604-00350 | Inlet Type C (Special) | 3 | Each | 17,100.00 | 5,700.00 |
| 604-00505 | Inlet Type D (5 Foot) | 13 | Each | 43,927.94 | 3,379.07 |
| 604-00510 | Inlet Type D (10 Foot) | 6 | Each | 42,543.90 | 7,090.65 |
| 604-00550 | Inlet Type D (Special) | 2 | Each | 16,600.00 | 8,300.00 |
| 604-13005 | Inlet Type 13 (5 Foot) | 2 | Each | 4,885.00 | 2,442.50 |
| 604-13010 | Inlet Type 13 (10 Foot) | 5 | Each | 16,258.55 | 3,251.71 |
| 604-13015 | Inlet Type 13 (15 Foot) | 1 | Each | 3,100.00 | 3,100.00 |
| 604-16005 | Inlet Type 16 (5 Foot) | 12 | Each | 33,046.90 | 2,753.91 |
| 604-16010 | Inlet Type 16 (10 Foot) | 5 | Each | 14,819.16 | 2,963.83 |
| 604-16015 | Inlet Type 16 (15 Foot) | 3 | Each | 11,683.23 | 3,894.41 |
| 604-16050 | Inlet Type 16 (Single) (Special) | 1 | Each | 2,400.00 | 2,400.00 |

INDEX AND AVERAGE UNIT BID PRICES FOR 01/01/11 THROUGH 12/31/11

| ITEM NUMBER | ITEM | TOTAL QUANTITY | UNIT | TOTAL COST | AVERAGE PRICE |
|---|---|---|---|---|---|
| 604-16505 | Inlet Type 16 (Double) (5 Foot) | 3 | Each | 10,800.00 | 3,600.00 |
| 604-16510 | Inlet Type 16 (Double) (10 Foot) | 4 | Each | 18,522.28 | 4,630.57 |
| 604-16515 | Inlet Type 16 (Double) (15 Foot) | 1 | Each | 5,776.77 | 5,776.77 |
| 604-16605 | Inlet Type 16 (Triple) (5 Foot) | 1 | Each | 6,438.86 | 6,438.86 |
| 604-16610 | Inlet Type 16 (Triple) (10 Foot) | 3 | Each | 17,403.84 | 5,801.28 |
| 604-19000 | Inlet Special | 3 | Each | 8,700.00 | 2,900.00 |
| 604-19105 | Inlet Type R L 5 (5 Foot) | 11 | Each | 47,308.36 | 4,300.76 |
| 604-19110 | Inlet Type R L 5 (10 Foot) | 15 | Each | 70,061.60 | 4,670.77 |
| 604-19115 | Inlet Type R L 5 (15 Foot) | 1 | Each | 4,700.00 | 4,700.00 |
| 604-19205 | Inlet Type R L 10 (5 Foot) | 15 | Each | 79,152.67 | 5,276.84 |
| 604-19210 | Inlet Type R L 10 (10 Foot) | 9 | Each | 53,621.80 | 5,957.98 |
| 604-19215 | Inlet Type R L 10 (15 Foot) | 3 | Each | 22,510.43 | 7,503.48 |
| 604-19305 | Inlet Type R L 15 (5 Foot) | 5 | Each | 32,885.52 | 6,577.10 |
| 604-19310 | Inlet Type R L 15 (10 Foot) | 11 | Each | 92,000.00 | 8,363.64 |
| 604-19315 | Inlet Type R L 15 (15 Foot) | 3 | Each | 30,000.00 | 10,000.00 |
| 604-19405 | Inlet Type R Special (5 Foot) | 1 | Each | 3,435.00 | 3,435.00 |
| 604-19410 | Inlet Type R Special (10 Foot) | 2 | Each | 8,060.00 | 4,030.00 |
| 604-19415 | Inlet Type R Special (15 Foot) | 1 | Each | 6,690.00 | 6,690.00 |
| 604-19510 | Inlet Type R L 20 (10 Foot) | 2 | Each | 30,000.00 | 15,000.00 |
| 604-20000 | Outlet Structure | 3 | Each | 35,928.73 | 11,976.24 |
| 604-20010 | Settling Basin | 2 | Each | 155,600.00 | 77,800.00 |
| 604-25000 | Vane Grate Inlet Special | 30 | Each | 80,033.74 | 2,667.79 |
| 604-25005 | Vane Grate Inlet (5 Foot) | 6 | Each | 22,739.84 | 3,789.97 |
| 604-25006 | Vane Grate Inlet Special (5 Foot) | 7 | Each | 39,200.00 | 5,600.00 |
| 604-25010 | Vane Grate Inlet (10 Foot) | 8 | Each | 30,687.48 | 3,835.94 |
| 604-25011 | Vane Grate Inlet Special (10 Foot) | 7 | Each | 38,300.00 | 5,471.43 |
| 604-25015 | Vane Grate Inlet (15 Foot) | 1 | Each | 4,000.00 | 4,000.00 |
| 604-26005 | Vane Grate Inlet (Double) (5 Foot) | 30 | Each | 113,069.94 | 3,769.00 |
| 604-26006 | Vane Grate Inlet Special (Double) (5 Foot) | 1 | Each | 4,528.03 | 4,528.03 |
| 604-26010 | Vane Grate Inlet (Double) (10 Foot) | 27 | Each | 119,215.56 | 4,415.39 |
| 604-26011 | Vane Grate Inlet Special (Double) (10 Foot) | 2 | Each | 13,211.88 | 6,605.94 |
| 604-26015 | Vane Grate Inlet (Double) (15 Foot) | 3 | Each | 16,400.00 | 5,466.67 |
| 604-26020 | Vane Grate Inlet (Double) (20 Foot) | 1 | Each | 5,800.00 | 5,800.00 |
| 604-30000 | Manhole Slab Base (Special) | 2 | Each | 6,000.00 | 3,000.00 |
| 604-30005 | Manhole Slab Base (5 Foot) | 25 | Each | 61,224.13 | 2,448.97 |
| 604-30010 | Manhole Slab Base (10 Foot) | 63 | Each | 187,037.31 | 2,968.85 |
| 604-30015 | Manhole Slab Base (15 Foot) | 16 | Each | 72,976.89 | 4,561.06 |
| 604-30020 | Manhole Slab Base (20 Foot) | 4 | Each | 18,548.72 | 4,637.18 |

INDEX AND AVERAGE UNIT BID PRICES FOR 01/01/11 THROUGH 12/31/11

| ITEM NUMBER | ITEM | TOTAL QUANTITY | UNIT | TOTAL COST | AVERAGE PRICE |
|---|---|---|---|---|---|
| 604-31010 | Manhole Box Base (10 Foot) | 1 | Each | 8,279.05 | 8,279.05 |
| 604-31015 | Manhole Box Base (15 Foot) | 2 | Each | 28,400.00 | 14,200.00 |
| 604-31020 | Manhole Box Base (20 Foot) | 1 | Each | 9,460.71 | 9,460.71 |
| 604-32010 | Manhole T-Base (10 Foot) | 4 | Each | 19,200.00 | 4,800.00 |
| 604-32015 | Manhole T-Base (15 Foot) | 3 | Each | 16,800.00 | 5,600.00 |
| 604-39000 | Manhole Special | 6 | Each | 29,872.22 | 4,978.70 |
| 604-39005 | Manhole Special (5 Foot) | 3 | Each | 10,200.00 | 3,400.00 |
| 604-39010 | Manhole Special (10 Foot) | 5 | Each | 17,490.00 | 3,498.00 |
| 604-39015 | Manhole Special (15 Foot) | 5 | Each | 39,650.00 | 7,930.00 |
| 604-39020 | Manhole Special (20 Foot) | 4 | Each | 52,000.00 | 13,000.00 |
| 604-39025 | Manhole Special (25 Foot) | 2 | Each | 42,325.00 | 21,162.50 |
| 604-39050 | Manhole (Traffic Management System) | 3 | Each | 15,390.72 | 5,130.24 |
| 604-50062 | Grating and Frame | 2 | Each | 6,700.00 | 3,350.00 |
| 604-50700 | Meter Vault | 5 | Each | 17,384.68 | 3,476.94 |
| 605-00004 | 4 Inch Non-Perforated Pipe Underdrain | 282 | Lin Foot | 3,195.06 | 11.33 |
| 605-00040 | 4 Inch Perforated Pipe Underdrain | 2,514 | Lin Foot | 73,175.92 | 29.11 |
| 605-00041 | 4 Inch Perforated Pipe Underdrain (Special) | 411 | Lin Foot | 47,265.00 | 115.00 |
| 605-00060 | 6 Inch Perforated Pipe Underdrain | 2,808 | Lin Foot | 47,389.77 | 16.88 |
| 605-01030 | 3 Inch Horizontal Drain | 2,000 | Lin Foot | 50,000.00 | 25.00 |
| 605-82200 | French Drain | 1,515 | Lin Foot | 50,695.00 | 33.46 |
| 605-83002 | Geocomposite Drain with Pipe | 77 | Sq Yard | 2,772.00 | 36.00 |
| 605-83580 | 8 Inch Pipe Underdrain | 212 | Lin Foot | 4,090.88 | 19.30 |
| 605-84000 | Subsurface Drain Outlet | 238 | Lin Foot | 14,670.00 | 61.64 |
| 606-00301 | Guardrail Type 3 (6-3 Post Spacing) | 91,001 | Lin Foot | 1,411,482.15 | 15.51 |
| 606-00350 | Guardrail Type 3 (Double) (6-3 Post Spacing) | 838 | Lin Foot | 19,036.26 | 22.72 |
| 606-00705 | Guardrail Type 7 (Special) | 9,112 | Lin Foot | 182,832.00 | 20.06 |
| 606-00710 | Guardrail Type 7 (Style CA) | 12,867 | Lin Foot | 574,132.44 | 44.62 |
| 606-00716 | Guardrail Type 7 (Style CA) (Special) | 1,066 | Lin Foot | 96,216.10 | 90.26 |
| 606-00720 | Guardrail Type 7 (Style CC) | 2,169 | Lin Foot | 101,487.12 | 46.79 |
| 606-00721 | Guardrail Type 7 (Style CC) (Special) | 544 | Lin Foot | 58,311.36 | 107.19 |
| 606-00725 | Guardrail Type 7 (Style CC)(Concrete Glare Screen) | 555 | Lin Foot | 50,782.50 | 91.50 |
| 606-00730 | Guardrail Type 7 (Style CD) | 2,717 | Lin Foot | 131,264.00 | 48.31 |
| 606-00731 | Guardrail Type 7 (Style CD) (Special) | 1,914 | Lin Foot | 120,333.18 | 62.87 |
| 606-00740 | Guardrail Type 7 (Style CE) | 5,020 | Lin Foot | 365,315.30 | 72.77 |
| 606-00741 | Guardrail Type 7 (Style CE) (Special) | 75 | Lin Foot | 9,736.00 | 129.81 |
| 606-00745 | Guardrail Type 7 (Style CE)(Concrete Glare Screen) | 4,723 | Lin Foot | 455,654.66 | 96.48 |
| 606-00900 | Guardrail (Special) | 416 | Lin Foot | 66,560.00 | 160.00 |
| 606-01320 | End Anchorage Type 3B | 1 | Each | 350.00 | 350.00 |

INDEX AND AVERAGE UNIT BID PRICES FOR 01/01/11 THROUGH 12/31/11

| ITEM NUMBER | ITEM | TOTAL QUANTITY | UNIT | TOTAL COST | AVERAGE PRICE |
|---|---|---|---|---|---|
| 606-01340 | End Anchorage Type 3D | 67 | Each | 43,614.00 | 650.96 |
| 606-01370 | Transition Type 3G | 166 | Each | 197,787.15 | 1,191.49 |
| 606-01371 | Transition Type 3G (Special) | 3 | Each | 4,260.00 | 1,420.00 |
| 606-01380 | Transition Type 3H | 36 | Each | 26,102.86 | 725.08 |
| 606-01385 | Transition Type 3J | 11 | Each | 7,495.36 | 681.40 |
| 606-01390 | End Anchorage Type 3K | 21 | Each | 19,350.57 | 921.46 |
| 606-01460 | Median Terminal | 63 | Each | 189,715.00 | 3,011.35 |
| 606-02003 | End Anchorage (Nonflared) | 163 | Each | 311,633.22 | 1,911.86 |
| 606-02005 | End Anchorage (Flared) | 169 | Each | 268,723.12 | 1,590.08 |
| 606-10700 | Bridge Rail Type 7 | 17,724 | Lin Foot | 1,282,433.92 | 72.36 |
| 606-10705 | Bridge Rail Type 7 (Special) | 3,563 | Lin Foot | 268,888.37 | 75.47 |
| 606-10742 | Bridge Rail Type 7 (42") | 1,598 | Lin Foot | 191,760.00 | 120.00 |
| 606-11005 | Bridge Rail Type 10 (Special) | 517 | Lin Foot | 80,135.00 | 155.00 |
| 606-11010 | Bridge Rail Type 10R | 4,732 | Lin Foot | 422,651.71 | 89.32 |
| 606-11015 | Bridge Rail Type 10R (Special) | 1,028 | Lin Foot | 162,360.00 | 157.94 |
| 606-11025 | Bridge Rail Type 10H (Special) | 72 | Lin Foot | 13,175.40 | 182.99 |
| 606-11030 | Bridge Rail Type 10M | 2,153 | Lin Foot | 243,718.68 | 113.20 |
| 606-11032 | Bridge Rail Type 10M (Special) | 846 | Lin Foot | 137,862.00 | 162.96 |
| 606-20014 | Tensioned Cable Barrier (TL-4) | 18,629 | Lin Foot | 170,326.50 | 9.14 |
| 606-21010 | End Anchorage (Tensioned Cable Barrier) | 46 | Each | 129,885.94 | 2,823.61 |
| 606-99999 | Guardrail Type 7 (Precast) | 30,365 | Lin Foot | 1,987,791.10 | 65.46 |
| 607-00005 | End Post | 96 | Each | 22,713.60 | 236.60 |
| 607-00010 | Corner and Line Brace Post | 303 | Each | 106,882.51 | 352.75 |
| 607-00015 | End Post (Special) | 48 | Each | 27,360.00 | 570.00 |
| 607-00020 | Corner and Line Brace Post (Special) | 65 | Each | 46,910.00 | 721.69 |
| 607-01000 | Fence Barbed Wire with Metal Posts | 28,047 | Lin Foot | 39,174.86 | 1.40 |
| 607-01010 | Fence Barbed Wire with Metal Posts (Special) | 272 | Lin Foot | 816.00 | 3.00 |
| 607-01050 | Fence Wire With Metal Posts | 1,606 | Lin Foot | 2,730.20 | 1.70 |
| 607-01100 | Fence Barbed Wire With Treated Wooden Posts | 10,850 | Lin Foot | 34,720.00 | 3.20 |
| 607-11300 | Fence Combination Wire With Treated Wooden Posts | 1,338 | Lin Foot | 3,628.50 | 2.71 |
| 607-11350 | Fence Deer | 68,704 | Lin Foot | 475,744.00 | 6.92 |
| 607-11525 | Fence (Plastic) | 41,746 | Lin Foot | 115,313.29 | 2.76 |
| 607-11530 | Fence (Special) | 1,619 | Lin Foot | 567,885.28 | 350.76 |
| 607-11580 | Fence (Temporary) | 3,613 | Lin Foot | 14,777.00 | 4.09 |
| 607-13064 | Fence Masonry (Sound Barrier) (64 Inch) | 510 | Lin Foot | 86,700.00 | 170.00 |
| 607-13088 | Fence Masonry (Sound Barrier)(88 Inch) | 44 | Lin Foot | 7,480.00 | 170.00 |
| 607-13096 | Fence Masonry (Sound Barrier) (96 Inch) | 56 | Lin Foot | 10,640.00 | 190.00 |
| 607-13104 | Fence Masonry (Sound Barrier) (104 Inch) | 112 | Lin Foot | 22,400.00 | 200.00 |

INDEX AND AVERAGE UNIT BID PRICES FOR 01/01/11 THROUGH 12/31/11

| ITEM NUMBER | ITEM | TOTAL QUANTITY | UNIT | TOTAL COST | AVERAGE PRICE |
|---|---|---|---|---|---|
| 607-13112 | Fence Masonry (Sound Barrier) (112 Inch) | 44 | Lin Foot | 9,680.00 | 220.00 |
| 607-13144 | Fence Masonry (Sound Barrier) (144 Inch) | 948 | Lin Foot | 255,960.00 | 270.00 |
| 607-14000 | Fence Composite (Sound Barrier) | 2,615 | Sq Foot | 78,450.00 | 30.00 |
| 607-20124 | Glare Screen (24 Inch) | 9,948 | Lin Foot | 176,577.00 | 17.75 |
| 607-53001 | Fence Chain Link (PVC Coated) | 685 | Lin Foot | 19,865.00 | 29.00 |
| 607-53005 | Fence Chain Link (Special) | 467 | Lin Foot | 102,740.00 | 220.00 |
| 607-53137 | Fence Chain Link (Special) (36 Inch) | 8,073 | Lin Foot | 202,162.47 | 25.04 |
| 607-53142 | Fence Chain Link (42 Inch) | 2,037 | Lin Foot | 48,888.00 | 24.00 |
| 607-53143 | Fence Chain Link (Special) (42 Inch) | 1,967 | Lin Foot | 41,307.00 | 21.00 |
| 607-53160 | Fence Chain Link (60 Inch) | 485 | Lin Foot | 19,799.00 | 40.82 |
| 607-53161 | Fence Chain Link (Special) (60 Inch) | 1,316 | Lin Foot | 29,944.00 | 22.75 |
| 607-53172 | Fence Chain Link (72 Inch) | 1,368 | Lin Foot | 34,035.75 | 24.88 |
| 607-53173 | Fence Chain Link (Special) (72 Inch) | 788 | Lin Foot | 23,130.48 | 29.35 |
| 607-53196 | Fence Chain Link (96 Inch) | 390 | Lin Foot | 21,450.00 | 55.00 |
| 607-55030 | Mesh Post | 52 | Each | 168,215.88 | 3,234.92 |
| 607-55031 | Mesh Post (Special) | 28 | Each | 92,001.84 | 3,285.78 |
| 607-55040 | Mesh Anchor | 38 | Each | 22,550.00 | 593.42 |
| 607-55060 | Mesh Pin | 150 | Each | 18,357.00 | 122.38 |
| 607-55100 | Wire Mesh | 195,500 | Sq Foot | 535,670.00 | 2.74 |
| 607-55101 | Cable Net | 19,200 | Sq Foot | 224,640.00 | 11.70 |
| 607-55102 | Cable Net (5/16 Inch) | 16,000 | Sq Foot | 134,400.00 | 8.40 |
| 607-60001 | Pedestrian Gate (Special) | 11 | Each | 5,500.00 | 500.00 |
| 607-60002 | Game Ramp | 18 | Each | 138,050.00 | 7,669.44 |
| 607-60113 | 12 Foot Gate (Special) | 7 | Each | 4,140.00 | 591.43 |
| 607-60116 | 16 Foot Gate | 6 | Each | 4,404.00 | 734.00 |
| 607-60117 | 16 Foot Gate (Special) | 1 | Each | 1,100.00 | 1,100.00 |
| 607-60121 | 20 Foot Gate (Special) | 2 | Each | 880.00 | 440.00 |
| 607-60212 | 12 Foot Gate Single (Chain Link) | 1 | Each | 510.00 | 510.00 |
| 607-60266 | 16 Foot Gate Double (Chain Link) | 13 | Each | 15,600.00 | 1,200.00 |
| 607-60620 | Road Closure Gate | 1 | Each | 10,200.00 | 10,200.00 |
| 608-00000 | Concrete Sidewalk | 21,250 | Sq Yard | 458,533.04 | 21.58 |
| 608-00006 | Concrete Sidewalk (6 Inch) | 7,022 | Sq Yard | 219,077.92 | 31.20 |
| 608-00010 | Concrete Curb Ramp | 3,047 | Sq Yard | 280,448.65 | 92.04 |
| 608-00011 | Curb Ramp (Fast Track) | 75 | Sq Yard | 6,945.75 | 92.61 |
| 608-00015 | Truncated Domes | 2,024 | Sq Foot | 72,926.54 | 36.03 |
| 608-00026 | Concrete Bikeway (6 Inch) | 1,282 | Sq Yard | 57,818.20 | 45.10 |
| 608-00350 | Concrete Sidewalk (Colored) | 700 | Sq Yard | 44,300.00 | 63.29 |
| 608-01000 | Bituminous Sidewalk | 12 | Ton | 1,980.96 | 165.08 |

INDEX AND AVERAGE UNIT BID PRICES FOR 01/01/11 THROUGH 12/31/11

| ITEM NUMBER | ITEM | TOTAL QUANTITY | UNIT | TOTAL COST | AVERAGE PRICE |
|---|---|---|---|---|---|
| 608-10010 | Sidewalk Drain | 2 | Each | 4,330.00 | 2,165.00 |
| 609-20010 | Curb Type 2 (Section B) | 1,123 | Lin Foot | 28,952.26 | 25.78 |
| 609-21010 | Curb and Gutter Type 2 (Section I-B) | 15,255 | Lin Foot | 195,187.54 | 12.79 |
| 609-21011 | Curb and Gutter Type 2 (Section I-M) | 5,329 | Lin Foot | 61,878.50 | 11.61 |
| 609-21020 | Curb and Gutter Type 2 (Section II-B) | 58,395 | Lin Foot | 769,495.02 | 13.18 |
| 609-21021 | Curb and Gutter Type 2 (Section II-M) | 5,651 | Lin Foot | 92,700.75 | 16.40 |
| 609-21110 | Curb and Gutter Type 2 (Section I-B) (Special) | 1,438 | Lin Foot | 38,420.00 | 26.72 |
| 609-23000 | Gutter (Special) | 323 | Lin Foot | 15,777.04 | 48.85 |
| 609-24002 | Gutter Type 2 (2 Foot) | 7,337 | Lin Foot | 149,862.69 | 20.43 |
| 609-24004 | Gutter Type 2 (4 Foot) | 1,209 | Lin Foot | 27,074.40 | 22.39 |
| 609-24005 | Gutter Type 2 (5 Foot) | 38 | Lin Foot | 760.00 | 20.00 |
| 609-24006 | Gutter Type 2 (6 Foot) | 752 | Lin Foot | 25,440.00 | 33.83 |
| 609-24008 | Gutter Type 2 (8 Foot) | 32 | Lin Foot | 1,952.00 | 61.00 |
| 609-24100 | Gutter Type 2 (Variable) | 217 | Lin Foot | 8,680.00 | 40.00 |
| 609-31010 | Curb and Gutter Type 2 (Section I-B) (Fast Track) | 1,235 | Lin Foot | 19,834.10 | 16.06 |
| 609-31020 | Curb and Gutter Type 2 (Section II-B) (Fast Track) | 250 | Lin Foot | 4,717.50 | 18.87 |
| 609-40010 | Curb Type 4 (Section B) | 287 | Lin Foot | 10,045.00 | 35.00 |
| 609-40011 | Curb Type 4 (Section M) | 296 | Lin Foot | 4,410.00 | 14.90 |
| 609-60011 | Curb Type 6 (Section M) | 17,049 | Lin Foot | 176,868.58 | 10.37 |
| 610-00020 | Median Cover Material (Patterned Concrete) | 57,742 | Sq Foot | 326,031.33 | 5.65 |
| 610-00024 | Median Cover Material (4 Inch Patterned Concrete) | 18,329 | Sq Foot | 94,186.83 | 5.14 |
| 610-00026 | Median Cover Material (6 Inch Patterned Concrete) | 32,999 | Sq Foot | 219,222.00 | 6.64 |
| 610-00030 | Median Cover Material (Concrete) | 11,398 | Sq Foot | 73,604.83 | 6.46 |
| 610-00110 | Median Edging | 2,642 | Lin Foot | 24,279.98 | 9.19 |
| 611-00016 | 16 Foot Cattle Guard | 1 | Each | 9,000.00 | 9,000.00 |
| 611-00017 | 16 Foot Deer Guard | 8 | Each | 192,000.00 | 24,000.00 |
| 611-00019 | 18 Foot Deer Guard | 7 | Each | 210,000.00 | 30,000.00 |
| 611-00025 | 24 Foot Deer Guard | 3 | Each | 127,065.00 | 42,355.00 |
| 611-00026 | 26 Foot Cattle Guard | 2 | Each | 19,500.00 | 9,750.00 |
| 612-00001 | Delineator (Type I) | 3,822 | Each | 80,967.89 | 21.18 |
| 612-00002 | Delineator (Type II) | 1,292 | Each | 27,203.00 | 21.05 |
| 612-00003 | Delineator (Type III) | 850 | Each | 22,826.34 | 26.85 |
| 612-00021 | Delineator (Type I) (Barrier) | 429 | Each | 7,057.22 | 16.45 |
| 612-00022 | Delineator (Type II) (Barrier) | 3,634 | Each | 51,332.87 | 14.13 |
| 612-00031 | Delineator (Type I) (Extra Height) | 333 | Each | 9,394.40 | 28.21 |
| 612-00032 | Delineator (Type II) (Extra Height) | 32 | Each | 977.20 | 30.54 |
| 612-00033 | Delineator (Type III) (Extra Height) | 2 | Each | 83.50 | 41.75 |
| 612-00041 | Delineator (Flexible) (Type I) | 2,165 | Each | 88,112.27 | 40.70 |

INDEX AND AVERAGE UNIT BID PRICES FOR 01/01/11 THROUGH 12/31/11

| ITEM NUMBER | ITEM | TOTAL QUANTITY | UNIT | TOTAL COST | AVERAGE PRICE |
|---|---|---|---|---|---|
| 612-00042 | Delineator (Flexible) (Type II) | 276 | Each | 11,405.23 | 41.32 |
| 612-00043 | Delineator (Flexible) (Type III) | 342 | Each | 14,373.10 | 42.03 |
| 612-00060 | Reflector (Median Barrier) | 19 | Each | 304.00 | 16.00 |
| 612-00065 | Reflector Strip (1-1/2 Inch) | 965 | Each | 27,985.00 | 29.00 |
| 612-00075 | Reflector Strip (6 Inch) | 20,781 | Each | 290,934.00 | 14.00 |
| 612-00081 | Delineator (Post Mounted)(Type I) | 1,314 | Each | 23,652.00 | 18.00 |
| 612-00082 | Delineator (Post Mounted)(Type II) | 172 | Each | 3,440.00 | 20.00 |
| 612-00083 | Delineator (Post Mounted)(Type III) | 24 | Each | 504.00 | 21.00 |
| 612-00101 | Delineator (Drivable Concrete Installation) (Type I) | 920 | Each | 82,800.00 | 90.00 |
| 612-00102 | Delineator (Drivable Concrete Installation) (Type II) | 130 | Each | 11,700.00 | 90.00 |
| 612-00103 | Delineator (Drivable Concrete Installation) (Type III | 40 | Each | 3,600.00 | 90.00 |
| 612-00104 | Delineator (Drivable Concrete Installation) (Type I) | 180 | Each | 7,200.00 | 40.00 |
| 612-00105 | Delineator (Drivable Concrete Installation) (Type II) | 80 | Each | 3,200.00 | 40.00 |
| 612-00106 | Delineator (Drivable Concrete Installation) (Type III | 40 | Each | 1,600.00 | 40.00 |
| 612-00107 | Delineator (Mounted) (Type III) | 57 | Each | 3,420.00 | 60.00 |
| 612-00108 | Delineator (Mounted) (Type III) (Furnish Only) | 20 | Each | 400.00 | 20.00 |
| 612-00260 | Location Marker (Fiber Optic)(Dome) | 94 | Each | 6,177.96 | 65.72 |
| 612-00266 | Location Marker (Electronic)(Ball) | 14 | Each | 280.00 | 20.00 |
| 612-00270 | Location Marker (Utility)(Flat Slat) | 30 | Each | 2,322.00 | 77.40 |
| 613-00075 | 3/4 Inch Electrical Conduit | 419 | Lin Foot | 1,386.60 | 3.31 |
| 613-00100 | 1 Inch Electrical Conduit | 5,595 | Lin Foot | 43,430.74 | 7.76 |
| 613-00125 | 1-1/4 Inch Electrical Conduit | 60 | Lin Foot | 1,560.00 | 26.00 |
| 613-00128 | 1 1/4 Inch Electrical Conduit (Multiduct)(Jacked) | 780 | Lin Foot | 15,600.00 | 20.00 |
| 613-00150 | 1-1/2 Inch Electrical Conduit | 624 | Lin Foot | 3,528.48 | 5.65 |
| 613-00151 | 1-1/2 Inch Electrical Conduit (Jacked) | 200 | Lin Foot | 2,816.00 | 14.08 |
| 613-00200 | 2 Inch Electrical Conduit | 65,910 | Lin Foot | 482,549.94 | 7.32 |
| 613-00201 | 2 Inch Electrical Conduit (Jacked) | 580 | Lin Foot | 5,222.20 | 9.00 |
| 613-00203 | 2 Inch Electrical Conduit (Multiduct)(Jacked) | 390 | Lin Foot | 7,800.00 | 20.00 |
| 613-00206 | 2 Inch Electrical Conduit (Bored) | 45,130 | Lin Foot | 709,280.03 | 15.72 |
| 613-00300 | 3 Inch Electrical Conduit | 7,416 | Lin Foot | 59,737.49 | 8.06 |
| 613-00306 | 3 Inch Electrical Conduit (Bored) | 14,141 | Lin Foot | 229,608.09 | 16.24 |
| 613-00400 | 4 Inch Electrical Conduit | 1,896 | Lin Foot | 30,980.64 | 16.34 |
| 613-00402 | 4 Inch Electrical Conduit (Install Only) | 3,540 | Lin Foot | 4,425.00 | 1.25 |
| 613-00408 | 4 Inch Electrical Conduit (Bored) | 2,700 | Lin Foot | 49,410.00 | 18.30 |
| 613-00602 | 6 Inch Electrical Conduit (Install Only) | 1,180 | Lin Foot | 1,770.00 | 1.50 |
| 613-01100 | 1 Inch Electrical Conduit (Plastic) | 1,300 | Lin Foot | 9,570.00 | 7.36 |
| 613-01150 | 1-1/2 Inch Electrical Conduit (Plastic) | 4,100 | Lin Foot | 26,199.00 | 6.39 |
| 613-01200 | 2 Inch Electrical Conduit (Plastic) | 130,680 | Lin Foot | 831,512.22 | 6.36 |

INDEX AND AVERAGE UNIT BID PRICES FOR 01/01/11 THROUGH 12/31/11

| ITEM NUMBER | ITEM | TOTAL QUANTITY | UNIT | TOTAL COST | AVERAGE PRICE |
|---|---|---|---|---|---|
| 613-01250 | 2-1/2 Inch Electrical Conduit (Plastic) | 2,811 | Lin Foot | 23,612.40 | 8.40 |
| 613-01300 | 3 Inch Electrical Conduit (Plastic) | 27,070 | Lin Foot | 253,551.95 | 9.37 |
| 613-01400 | 4 Inch Electrical Conduit (Plastic) | 1,552 | Lin Foot | 18,322.00 | 11.81 |
| 613-01600 | 6 Inch Electrical Conduit (Plastic) | 30 | Lin Foot | 547.50 | 18.25 |
| 613-04130 | 1-1/2 Inch Electrical Conduit (Liquidtight Flexible M | 50 | Lin Foot | 562.50 | 11.25 |
| 613-05151 | Wildlife Detection System | 2 | Each | 128,000.00 | 64,000.00 |
| 613-06000 | Meter Pole | 9 | Each | 19,831.99 | 2,203.55 |
| 613-07000 | Pull Box (Special) | 124 | Each | 55,420.08 | 446.94 |
| 613-07016 | Pull Box (16"x16"x6") | 2 | Each | 1,390.00 | 695.00 |
| 613-07018 | Pull Box (18"x12"x8") | 6 | Each | 3,780.00 | 630.00 |
| 613-07023 | Pull Box (24"x36"x24") | 240 | Each | 219,264.61 | 913.60 |
| 613-07026 | Pull Box (16"x24"x12") | 20 | Each | 12,584.00 | 629.20 |
| 613-07034 | Pull Box (24"x36"x18") | 99 | Each | 80,031.02 | 808.39 |
| 613-07038 | Pull Box (36"x48"x18") | 10 | Each | 10,249.62 | 1,024.96 |
| 613-07039 | Pull Box (30"x48"x18") | 16 | Each | 19,760.00 | 1,235.00 |
| 613-07040 | Pull Box (30"x48"x24") | 15 | Each | 16,449.60 | 1,096.64 |
| 613-07050 | Pull Box (13"x24"x18") Deep | 16 | Each | 13,440.00 | 840.00 |
| 613-07199 | Pull Box (Install Only) | 9 | Each | 4,680.00 | 520.00 |
| 613-10000 | Wiring | 33 | Lump Sum | 676,079.98 | 20,487.27 |
| 613-10010 | Wiring (Special) | 1 | Lump Sum | 5,200.00 | 5,200.00 |
| 613-16000 | Luminaire (Special) | 69 | Each | 76,553.96 | 1,109.48 |
| 613-30005 | Light Standard and Luminaire (Pedestrian) | 2 | Each | 7,168.00 | 3,584.00 |
| 613-32300 | Light Standard Steel (30 Foot) | 1 | Each | 4,200.00 | 4,200.00 |
| 613-32350 | Light Standard Steel (35 Foot) | 15 | Each | 52,384.59 | 3,492.31 |
| 613-32352 | Light Standard Steel (35 Foot) (2-Arm) | 1 | Each | 3,219.43 | 3,219.43 |
| 613-32400 | Light Standard Steel (40 Foot) | 78 | Each | 276,053.87 | 3,539.15 |
| 613-34180 | Light Standard Metal (18 Foot) | 8 | Each | 26,400.00 | 3,300.00 |
| 613-34250 | Light Standard Metal (25 Foot) | 18 | Each | 25,200.00 | 1,400.00 |
| 613-34300 | Light Standard Metal (30 Foot) | 54 | Each | 81,360.00 | 1,506.67 |
| 613-34350 | Light Standard Metal (35 Foot) | 24 | Each | 78,618.39 | 3,275.77 |
| 613-34400 | Light Standard Metal (40 Foot) | 87 | Each | 230,985.58 | 2,655.01 |
| 613-34700 | Light Standard Metal (70 Foot) | 9 | Each | 74,640.00 | 8,293.33 |
| 613-40000 | Concrete Foundation Pad | 5 | Each | 5,595.50 | 1,119.10 |
| 613-40010 | Light Standard Foundation | 252 | Each | 232,447.80 | 922.41 |
| 613-50010 | Photoelectric Cell | 4 | Each | 1,630.00 | 407.50 |
| 613-50100 | Lighting Control Center | 13 | Each | 85,283.28 | 6,560.25 |
| 613-50105 | Lighting Control Center (Pedestal Only) | 15 | Each | 23,370.22 | 1,558.01 |
| 613-50150 | Secondary Service Pedestal | 4 | Each | 5,368.38 | 1,342.10 |

INDEX AND AVERAGE UNIT BID PRICES FOR 01/01/11 THROUGH 12/31/11

| ITEM NUMBER | ITEM | TOTAL QUANTITY | UNIT | TOTAL COST | AVERAGE PRICE |
|---|---|---|---|---|---|
| 613-50210 | Temporary Lighting | 3 | Lump Sum | 47,208.77 | 15,736.26 |
| 613-70100 | Luminaire High Pressure Sodium (100 Watt) | 4 | Each | 5,272.00 | 1,318.00 |
| 613-70150 | Luminaire High Pressure Sodium (150 Watt) | 36 | Each | 68,256.44 | 1,896.01 |
| 613-70250 | Luminaire High Pressure Sodium (250 Watt) | 245 | Each | 128,076.79 | 522.76 |
| 613-70400 | Luminaire High Pressure Sodium (400 Watt) | 87 | Each | 46,415.57 | 533.51 |
| 613-71000 | Luminaire High Pressure Sodium (1000 Watt) | 16 | Each | 17,280.00 | 1,080.00 |
| 613-72150 | Luminaire High Pressure Sodium (Wall Type) (150 Watt) | 31 | Each | 55,679.95 | 1,796.13 |
| 614-00011 | Sign Panel (Class I) | 4,296 | Sq Foot | 83,210.17 | 19.37 |
| 614-00012 | Sign Panel (Class II) | 7,217 | Sq Foot | 146,717.32 | 20.33 |
| 614-00013 | Sign Panel (Class III) | 11,208 | Sq Foot | 291,275.16 | 25.99 |
| 614-00035 | Sign Panel (Special) | 36 | Sq Foot | 1,830.48 | 50.85 |
| 614-00037 | Sign Panel (Special) | 1 | Each | 56,550.00 | 56,550.00 |
| 614-00040 | Sign Post (Special) | 85 | Lin Foot | 6,279.00 | 73.87 |
| 614-00200 | Steel Sign Post (U-2) | 155 | Lin Foot | 1,557.30 | 10.05 |
| 614-00216 | Steel Sign Post (2x2 Inch Tubing) | 1,568 | Lin Foot | 19,379.98 | 12.36 |
| 614-00612 | Steel Sign Post (W 6x12) | 49 | Lin Foot | 2,614.28 | 53.35 |
| 614-00615 | Steel Sign Post (W 6x15) | 321 | Lin Foot | 13,600.17 | 42.37 |
| 614-00818 | Steel Sign Post (W 8x18) | 282 | Lin Foot | 22,451.18 | 79.61 |
| 614-00821 | Steel Sign Post (W 8x21) | 33 | Lin Foot | 2,324.19 | 70.43 |
| 614-01022 | Steel Sign Post (W 10x22) | 33 | Lin Foot | 2,640.00 | 80.00 |
| 614-01026 | Steel Sign Post (W 10x26) | 85 | Lin Foot | 6,632.60 | 78.03 |
| 614-01226 | Steel Sign Post (W 12x26) | 212 | Lin Foot | 11,236.00 | 53.00 |
| 614-01502 | Steel Sign Support (2-Inch Round)(Post & Socket) | 309 | Lin Foot | 4,236.25 | 13.71 |
| 614-01503 | Steel Sign Support (2-Inch Round)(Post and Socket) | 49 | Each | 5,782.62 | 118.01 |
| 614-01512 | Steel Sign Support (2-Inch Round)(Post) | 1,440 | Lin Foot | 10,168.00 | 7.06 |
| 614-01522 | Steel Sign Support (2-Inch Round)(Socket) | 152 | Each | 9,532.12 | 62.71 |
| 614-01572 | Steel Sign Support (2-1/2 Inch Round NP-40)(Post & Sl | 117 | Lin Foot | 2,925.00 | 25.00 |
| 614-01573 | Steel Sign Support (2-1/2 Inch Round NP-40)(Post & Sl | 203 | Each | 62,860.42 | 309.66 |
| 614-01575 | Steel Sign Support (2-1/2 Inch Round NP-40)(Post) | 1,386 | Lin Foot | 22,719.24 | 16.39 |
| 614-01578 | Steel Sign Support (2-1/2 Inch Round NP-40)(Slipbase) | 116 | Each | 24,306.26 | 209.54 |
| 614-01582 | Steel Sign Support (2-1/2 Inch Round)(Post and Slipba | 94 | Lin Foot | 4,242.00 | 45.13 |
| 614-01583 | Steel Sign Support (2-1/2 Inch Round)(Post & Slipbase | 113 | Each | 44,984.32 | 398.09 |
| 614-01585 | Steel Sign Support (2-1/2 Inch Round Sch 80) (Post) | 1,182 | Lin Foot | 19,806.61 | 16.76 |
| 614-01588 | Steel Sign Support (2-1/2 Inch Round Sch 80)(Slipbase | 134 | Each | 18,187.54 | 135.73 |
| 614-03001 | Concrete Footing (Type 1) | 9 | Each | 10,226.94 | 1,136.33 |
| 614-03002 | Concrete Footing (Type 2) | 10 | Each | 16,756.52 | 1,675.65 |
| 614-03003 | Concrete Footing (Type 3) | 17 | Each | 17,332.00 | 1,019.53 |
| 614-03004 | Concrete Footing (Type 4) | 2 | Each | 4,402.08 | 2,201.04 |

INDEX AND AVERAGE UNIT BID PRICES FOR 01/01/11 THROUGH 12/31/11

| ITEM NUMBER | ITEM | TOTAL QUANTITY | UNIT | TOTAL COST | AVERAGE PRICE |
|---|---|---|---|---|---|
| 614-03005 | Concrete Footing (Type 5) | 2 | Each | 5,000.00 | 2,500.00 |
| 614-03006 | Concrete Footing (Type 6) | 4 | Each | 9,082.50 | 2,270.63 |
| 614-03007 | Concrete Footing (Type 7) | 10 | Each | 12,000.00 | 1,200.00 |
| 614-03100 | Concrete Footing (Traffic Signal Pole) | 4 | Each | 9,924.00 | 2,481.00 |
| 614-07000 | Mask Sign Legend | 3 | Each | 1,410.12 | 470.04 |
| 614-10115 | Dynamic Message Sign (Color LED)(Overhead) | 1 | Each | 275,000.00 | 275,000.00 |
| 614-10120 | Variable Message Sign | 1 | Each | 80,408.00 | 80,408.00 |
| 614-10125 | Variable Message Sign (Ground Mounted) | 8 | Each | 826,273.04 | 103,284.13 |
| 614-10128 | Blankout Sign (Fiber Optic) | 4 | Each | 36,000.00 | 9,000.00 |
| 614-10130 | Illuminated Sign | 2 | Each | 5,400.00 | 2,700.00 |
| 614-10139 | Radar Speed Display Sign (LED) | 2 | Each | 22,000.00 | 11,000.00 |
| 614-10147 | Variable Message Sign LED (Overhead) | 4 | Each | 544,963.00 | 136,240.75 |
| 614-10148 | Variable Message Sign LED (Speed Radar) | 3 | Each | 79,362.00 | 26,454.00 |
| 614-10160 | Signal Head Backplates | 65 | Each | 11,505.00 | 177.00 |
| 614-30110 | Butterfly Structure | 7 | Each | 152,832.56 | 21,833.22 |
| 614-31800 | Monotube Overhead Sign Cantilever (18 Inch Diameter) | 1 | Each | 22,200.00 | 22,200.00 |
| 614-32000 | Monotube Overhead Sign Cantilever (20 Inch Diameter) | 3 | Each | 77,700.00 | 25,900.00 |
| 614-32400 | Monotube Overhead Sign Cantilever (24 Inch Diameter) | 15 | Each | 583,149.17 | 38,876.61 |
| 614-41400 | Monotube Overhead Sign Bridge (14 Inch Diameter) | 1 | Each | 37,300.00 | 37,300.00 |
| 614-41800 | Monotube Overhead Sign Bridge (18 Inch Diameter) | 1 | Each | 45,000.00 | 45,000.00 |
| 614-42000 | Monotube Overhead Sign Bridge (20 Inch Diameter) | 5 | Each | 250,800.00 | 50,160.00 |
| 614-42400 | Monotube Overhead Sign Bridge (24 Inch Diameter) | 4 | Each | 271,910.71 | 67,977.68 |
| 614-70117 | Pedestrian Signal Face (16) | 26 | Each | 12,540.96 | 482.34 |
| 614-70150 | Pedestrian Signal Face (16) (Countdown) | 117 | Each | 61,096.00 | 522.19 |
| 614-70216 | Traffic Signal Face (8-8) | 4 | Each | 2,600.00 | 650.00 |
| 614-70328 | Traffic Signal Face (12-8-8) | 4 | Each | 3,120.00 | 780.00 |
| 614-70336 | Traffic Signal Face (12-12-12) | 322 | Each | 220,542.08 | 684.91 |
| 614-70448 | Traffic Signal Face (12-12-12-12) | 93 | Each | 97,128.00 | 1,044.39 |
| 614-70560 | Traffic Signal Face (12-12-12-12-12) | 46 | Each | 48,619.88 | 1,056.95 |
| 614-72830 | Communications Cabinet | 1 | Each | 11,400.00 | 11,400.00 |
| 614-72831 | Communications Cabinet (Type 1) | 18 | Each | 79,038.00 | 4,391.00 |
| 614-72832 | Communications Cabinet (Type 2) | 3 | Each | 20,306.79 | 6,768.93 |
| 614-72855 | Traffic Signal Controller Cabinet | 15 | Each | 144,235.90 | 9,615.73 |
| 614-72858 | Pedestal Pole (3 Foot 6 Inch) | 1 | Each | 1,000.00 | 1,000.00 |
| 614-72860 | Pedestrian Push Button | 93 | Each | 20,456.88 | 219.97 |
| 614-72866 | Fire Preemption Unit and Timer | 18 | Each | 61,750.08 | 3,430.56 |
| 614-72871 | Loop Detector Wire (Prefab) Special | 15,748 | Lin Foot | 77,882.60 | 4.95 |
| 614-72875 | Loop Detector Wire | 41,082 | Lin Foot | 135,769.02 | 3.30 |

INDEX AND AVERAGE UNIT BID PRICES FOR 01/01/11 THROUGH 12/31/11

| ITEM NUMBER | ITEM | TOTAL QUANTITY | UNIT | TOTAL COST | AVERAGE PRICE |
|---|---|---|---|---|---|
| 614-72876 | Traffic Signal Vehicle Detector Amplifier (Loop Type) | 6 | Each | 3,354.00 | 559.00 |
| 614-72878 | Traffic Signal Vehicle Detector Amplifier (Loop Type) | 4 | Each | 2,860.00 | 715.00 |
| 614-72882 | Traffic Signal Vehicle Detector (Micro Type) | 6 | Each | 3,000.00 | 500.00 |
| 614-72884 | Traffic Signal Vehicle Detector (Micro Wave Type) | 20 | Each | 172,222.08 | 8,611.10 |
| 614-72886 | Intersection Detection System (Camera) | 27 | Each | 181,232.60 | 6,712.32 |
| 614-72887 | Microwave Vehicle Radar Detector | 15 | Each | 114,729.00 | 7,648.60 |
| 614-72889 | Traffic Signal Vehicle Detector (Micro Type) (Non-Inv | 61 | Each | 41,745.90 | 684.36 |
| 614-72900 | Wireless Magnetometer Vehicle Detection system | 3 | Each | 32,240.88 | 10,746.96 |
| 614-80000 | Flashing Beacon | 13 | Each | 36,285.00 | 2,791.15 |
| 614-80001 | Flashing Beacon (Solar Powered) | 6 | Each | 22,882.00 | 3,813.67 |
| 614-80006 | Surface Condition Analyzer | 5 | Each | 28,422.20 | 5,684.44 |
| 614-80010 | Travel Time Indicator | 22 | Each | 140,244.88 | 6,374.77 |
| 614-80321 | Barricade (Type 3 M-A) | 6 | Each | 600.00 | 100.00 |
| 614-80385 | Rumble Strip | 682,734 | Lin Foot | 179,632.81 | 0.26 |
| 614-80387 | Rumble Strip (Grinding) | 3,400 | Lin Foot | 6,392.00 | 1.88 |
| 614-80391 | Rumble Strip (Grinding)(Asphalt) | 146,520 | Lin Foot | 58,608.00 | 0.40 |
| 614-80392 | Rumble Strip (Grinding)(Concrete) | 68,471 | Lin Foot | 30,811.95 | 0.45 |
| 614-81010 | Traffic Signal-Light Pole Steel (1 Mast Arm) | 2 | Each | 28,650.00 | 14,325.00 |
| 614-81125 | Traffic Signal-Light Pole Steel (1-25 Foot Mast Arm) | 2 | Each | 26,000.00 | 13,000.00 |
| 614-81130 | Traffic Signal-Light Pole Steel (1-30 Foot Mast Arm) | 3 | Each | 37,500.00 | 12,500.00 |
| 614-81135 | Traffic Signal-Light Pole Steel (1-35 Foot Mast Arm) | 7 | Each | 106,608.51 | 15,229.79 |
| 614-81140 | Traffic Signal-Light Pole Steel (1-40 Foot Mast Arm) | 7 | Each | 108,177.16 | 15,453.88 |
| 614-81145 | Traffic Signal-Light Pole Steel (1-45 Foot Mast Arm) | 6 | Each | 94,958.00 | 15,826.33 |
| 614-81150 | Traffic Signal-Light Pole Steel (1-50 Foot Mast Arm) | 7 | Each | 105,684.31 | 15,097.76 |
| 614-81155 | Traffic Signal-Light Pole Steel (1-55 Foot Mast Arm) | 8 | Each | 119,473.32 | 14,934.17 |
| 614-81160 | Traffic Signal Light Pole Steel (1-60 Mast Arm Foot) | 5 | Each | 104,859.32 | 20,971.86 |
| 614-81165 | Traffic Signal-Light Pole Steel (1-65 Foot Mast Arm) | 4 | Each | 81,654.44 | 20,413.61 |
| 614-81170 | Traffic Signal-Light Pole Steel (1-70 Foot Mast Arm) | 2 | Each | 43,964.00 | 21,982.00 |
| 614-81175 | Traffic Signal-Light Pole Steel (1-75 Foot Mast Arm) | 3 | Each | 66,756.90 | 22,252.30 |
| 614-81230 | Traffic Signal-Light Pole Steel (2-30 Foot Mast Arm) | 2 | Each | 42,128.00 | 21,064.00 |
| 614-81255 | Traffic Signal Light Pole Steel (2-55 Foot Mast Arm) | 2 | Each | 66,826.42 | 33,413.21 |
| 614-82010 | Traffic Signal Pole Steel (1 Mast Arm) | 9 | Each | 109,964.00 | 12,218.22 |
| 614-82020 | Traffic Signal Pole Steel (2 Mast Arm) | 2 | Each | 38,973.20 | 19,486.60 |
| 614-84000 | Traffic Signal Pedestal Pole Steel | 33 | Each | 43,559.10 | 1,319.97 |
| 614-84100 | Traffic Signal Pedestal Pole Aluminum | 3 | Each | 2,708.87 | 902.96 |
| 614-85001 | Impact Attenuator | 10 | Each | 225,424.25 | 22,542.43 |
| 614-85003 | Impact Attenuator (Low Maintenance) | 9 | Each | 199,675.00 | 22,186.11 |
| 614-85130 | Impact Attenuator (Quadguard II) | 3 | Each | 61,000.90 | 20,333.63 |

INDEX AND AVERAGE UNIT BID PRICES FOR 01/01/11 THROUGH 12/31/11

| ITEM NUMBER | ITEM | TOTAL QUANTITY | UNIT | TOTAL COST | AVERAGE PRICE |
|---|---|---|---|---|---|
| 614-85312 | Traffic Signal Span Wire Pole (12 Inch) | 2 | Each | 11,600.00 | 5,800.00 |
| 614-85362 | Traffic Signal-Light Span Wire Pole (12 Inch) | 3 | Each | 24,900.00 | 8,300.00 |
| 614-85366 | Traffic Signal-Light Span Wire Pole (16 Inch) | 2 | Each | 20,200.00 | 10,100.00 |
| 614-86002 | Spread Spectrum Radio | 1 | Each | 2,500.00 | 2,500.00 |
| 614-86004 | Spread Spectrum Radio (Install Only) | 6 | Each | 2,604.00 | 434.00 |
| 614-86007 | Serial to IP Converter | 6 | Each | 12,943.00 | 2,157.17 |
| 614-86105 | Telemetry (Field) | 19 | Each | 25,331.48 | 1,333.24 |
| 614-86106 | Telemetry (Field)(Install Only) | 4 | Each | 3,375.16 | 843.79 |
| 614-86238 | Traffic Signal Controller (Solid State) (Full-Actuate | 3 | Each | 11,490.00 | 3,830.00 |
| 614-86239 | Traffic Signal Controller (Solid State) (Full-Actuate | 5 | Each | 21,084.52 | 4,216.90 |
| 614-86246 | Controller (Type 170E-HC11) | 8 | Each | 165,067.32 | 20,633.42 |
| 614-86250 | Ramp Metering Controller | 2 | Each | 21,000.00 | 10,500.00 |
| 614-86710 | Traffic Signal Equipment | 1 | Lump Sum | 30,680.00 | 30,680.00 |
| 614-86735 | Weather Sensor | 1 | Lump Sum | 15,000.00 | 15,000.00 |
| 614-86741 | Weather Monitoring System | 1 | Each | 52,824.98 | 52,824.98 |
| 614-86748 | Controller (Type 2070) | 2 | Each | 42,000.00 | 21,000.00 |
| 614-86752 | Fold-Over Tower (ITS) | 1 | Each | 8,804.16 | 8,804.16 |
| 614-86800 | Uninterrupted Power Supply | 6 | Each | 39,845.71 | 6,640.95 |
| 614-87006 | Fiber Optic Termination Panel - 6 Fiber | 3 | Each | 9,228.00 | 3,076.00 |
| 614-87010 | Fiber Optic Cable (Single Mode) (12 Fiber) | 43,977 | Lin Foot | 88,882.60 | 2.02 |
| 614-87020 | Optical Transceiver | 79 | Each | 203,836.69 | 2,580.21 |
| 614-87028 | Video Optical Transceiver | 8 | Each | 22,715.08 | 2,839.39 |
| 614-87310 | Traffic Management System Building Equipment | 1 | Lump Sum | 10,642.00 | 10,642.00 |
| 614-87320 | Closed Circuit Television | 30 | Each | 112,387.58 | 3,746.25 |
| 614-87325 | Closed Circuit Television Pole | 26 | Each | 64,396.00 | 2,476.77 |
| 614-87333 | Closed Circuit Television Camera (Traffic Surveillanc | 3 | Each | 15,200.00 | 5,066.67 |
| 614-87350 | Test Fiber Optic Cable | 4 | Lump Sum | 9,317.27 | 2,329.32 |
| 614-87360 | Control Center Upgrade | 1 | Lump Sum | 523,311.00 | 523,311.00 |
| 614-87406 | Fiber Optic Cable (Single Mode) (6 Strands) | 200 | Lin Foot | 224.00 | 1.12 |
| 614-87412 | Fiber Optic Cable (Single Mode) (12 Strands) (Install | 1,005 | Lin Foot | 3,997.10 | 3.98 |
| 614-87424 | Fiber Optic Cable (Single Mode) (24 Strands) | 1,670 | Lin Foot | 10,330.00 | 6.19 |
| 614-87448 | Fiber Optic Cable (Single Mode) (48 Strands) | 3,350 | Lin Foot | 12,665.00 | 3.78 |
| 614-87496 | Fiber Optic Cable (Single Mode) (96 Strands) | 83,700 | Lin Foot | 141,748.00 | 1.69 |
| 614-87498 | Fiber Optic Cable (Single Mode) (144 Strands) | 5,950 | Lin Foot | 24,009.50 | 4.04 |
| 614-87506 | Splice Fiber Optic Cable (6 Strand) | 8 | Each | 2,520.00 | 315.00 |
| 614-87660 | Video Encoder/Decoder | 11 | Each | 54,741.00 | 4,976.45 |
| 614-87661 | Video Encoder | 7 | Each | 39,514.00 | 5,644.86 |
| 614-87690 | Ethernet Switch | 9 | Each | 77,170.00 | 8,574.44 |

INDEX AND AVERAGE UNIT BID PRICES FOR 01/01/11 THROUGH 12/31/11

| ITEM NUMBER | ITEM | TOTAL QUANTITY | UNIT | TOTAL COST | AVERAGE PRICE |
|---|---|---|---|---|---|
| 615-00030 | Embankment Protector Type 3 | 37 | Each | 42,154.87 | 1,139.32 |
| 615-00050 | Embankment Protector Type 5 | 14 | Each | 14,707.67 | 1,050.55 |
| 615-10024 | 24 Inch Automatic Drain Gate | 1 | Each | 2,206.03 | 2,206.03 |
| 615-10036 | 36 Inch Automatic Drain Gate | 1 | Each | 3,309.05 | 3,309.05 |
| 615-10048 | 48 Inch Automatic Drain Gate | 1 | Each | 11,000.00 | 11,000.00 |
| 615-21899 | 18 Inch Slide Headgate Special | 1 | Each | 5,800.00 | 5,800.00 |
| 616-00150 | 15 Inch Concrete Siphon Pipe | 77 | Lin Foot | 17,402.00 | 226.00 |
| 616-00180 | 18 Inch Concrete Siphon Pipe | 20 | Lin Foot | 5,620.00 | 281.00 |
| 616-30030 | 30 Inch Trash Guard | 1 | Each | 1,725.00 | 1,725.00 |
| 616-30066 | 66 Inch Trash Guard | 1 | Each | 2,175.00 | 2,175.00 |
| 616-30499 | Trash Guard Special | 5 | Each | 52,656.52 | 10,531.30 |
| 618-00002 | Prestressing Steel Wire or Strand | 21,752 | M Kip Foot | 497,242.04 | 22.86 |
| 618-00005 | Prestressing Steel Bar | 16,349 | M Kip Foot | 287,415.42 | 17.58 |
| 618-00142 | Prestressed Concrete I (BT42) | 4,403 | Lin Foot | 634,032.00 | 144.00 |
| 618-00163 | Prestressed Concrete I (BT63) | 9,574 | Lin Foot | 1,648,930.00 | 172.23 |
| 618-00172 | Prestressed Concrete I (BT72) | 903 | Lin Foot | 252,876.12 | 280.04 |
| 618-00184 | Prestressed Concrete I (BT84) | 3,689 | Lin Foot | 932,120.00 | 252.68 |
| 618-01994 | Prestressed Concrete Box (Depth 32" Through 48") | 8,919 | Sq Foot | 560,575.92 | 62.85 |
| 618-06032 | Prestressed Concrete Slab (Depth Less Than 6 Inches) | 43,833 | Sq Foot | 394,497.00 | 9.00 |
| 618-06034 | Prestressed Concrete Slab (Depth 6" Through 13") | 67,602 | Sq Foot | 1,775,904.54 | 26.27 |
| 618-10000 | Precast Concrete U Girder (Pre-Tensioned) | 2,136 | Lin Foot | 779,640.00 | 365.00 |
| 618-10060 | Precast Concrete U Girder (U60)(Pre-Tensioned) | 696 | Lin Foot | 285,360.00 | 410.00 |
| 618-10072 | Precast Concrete U Girder (U72)(Pre-Tensioned) | 6,211 | Lin Foot | 2,946,242.60 | 474.36 |
| 618-10372 | Precast Concrete U Girder (U72)(Curved) | 3,439 | Lin Foot | 2,063,400.00 | 600.00 |
| 619-00000 | Water Meter and Vault | 10 | Each | 49,900.00 | 4,990.00 |
| 619-00002 | Water Service | 3 | Each | 6,000.00 | 2,000.00 |
| 619-00007 | Connect To Existing Waterline | 22 | Each | 23,100.00 | 1,050.00 |
| 619-10000 | Temporary Water Line | 11,000 | Lin Foot | 118,250.00 | 10.75 |
| 619-10120 | 12 Inch Welded Steel Pipe | 91 | Lin Foot | 12,017.46 | 132.06 |
| 619-10200 | 20 Inch Welded Steel Pipe | 175 | Lin Foot | 60,260.00 | 344.34 |
| 619-10240 | 24 Inch Welded Steel Pipe | 74 | Lin Foot | 30,220.00 | 408.38 |
| 619-10300 | 30 Inch Welded Steel Pipe | 22 | Lin Foot | 76,758.00 | 3,489.00 |
| 619-10360 | 36 Inch Welded Steel Pipe | 58 | Lin Foot | 40,020.00 | 690.00 |
| 619-10425 | 42 Inch Welded Steel Pipe (Special) | 133 | Lin Foot | 77,140.00 | 580.00 |
| 619-10600 | 60 Inch Welded Steel Pipe | 686 | Lin Foot | 514,006.08 | 749.28 |
| 619-30000 | 60 Inch Internal Joint Seals | 6 | Each | 12,575.34 | 2,095.89 |
| 619-40060 | 3/4 Inch Copper Pipe | 35 | Lin Foot | 1,190.00 | 34.00 |
| 619-40080 | 1 Inch Copper Pipe | 328 | Lin Foot | 14,116.50 | 43.04 |

INDEX AND AVERAGE UNIT BID PRICES FOR 01/01/11 THROUGH 12/31/11

| ITEM NUMBER | ITEM | TOTAL QUANTITY | UNIT | TOTAL COST | AVERAGE PRICE |
|---|---|---|---|---|---|
| 619-40120 | 1-1/2 Inch Copper Pipe | 44 | Lin Foot | 2,200.00 | 50.00 |
| 619-40160 | 2 Inch Copper Pipe | 851 | Lin Foot | 42,550.00 | 50.00 |
| 619-50080 | 1 Inch Plastic Pipe | 10,520 | Lin Foot | 3,261.20 | 0.31 |
| 619-50100 | 1-1/4 Inch Plastic Pipe | 500 | Lin Foot | 310.00 | 0.62 |
| 619-50120 | 1-1/2 Inch Plastic Pipe | 4,240 | Lin Foot | 4,409.60 | 1.04 |
| 619-50200 | 2-1/2 Inch Plastic Pipe | 280 | Lin Foot | 319.20 | 1.14 |
| 619-50240 | 3 Inch Plastic Pipe | 700 | Lin Foot | 1,379.00 | 1.97 |
| 619-50320 | 4 Inch Plastic Pipe | 1,799 | Lin Foot | 45,977.80 | 25.56 |
| 619-50480 | 6 Inch Plastic Pipe | 659 | Lin Foot | 30,692.00 | 46.57 |
| 619-50640 | 8 Inch Plastic Pipe | 7,916 | Lin Foot | 560,692.20 | 70.83 |
| 619-50800 | 10 Inch Plastic Pipe | 1,944 | Lin Foot | 84,913.92 | 43.68 |
| 619-50960 | 12 Inch Plastic Pipe | 3,086 | Lin Foot | 188,246.00 | 61.00 |
| 619-51280 | 16 Inch Plastic Pipe | 353 | Lin Foot | 39,468.93 | 111.81 |
| 619-71508 | 1 Inch Air and Vacuum Valve | 1 | Each | 5,040.00 | 5,040.00 |
| 619-71516 | 2 Inch Air and Vacuum Valve | 1 | Each | 5,400.00 | 5,400.00 |
| 619-71548 | 6 Inch Air and Vacuum Valve | 1 | Each | 5,826.00 | 5,826.00 |
| 619-71596 | 12 Inch Air and Vacuum Valve | 1 | Each | 6,430.44 | 6,430.44 |
| 619-73050 | 6 Inch Blow Off Valve and Vault | 1 | Each | 13,099.34 | 13,099.34 |
| 619-73051 | 6 Inch Air Valve Access Manhole Assembly | 2 | Each | 40,869.94 | 20,434.97 |
| 619-75000 | Cast Iron Valve Box | 22 | Each | 1,966.80 | 89.40 |
| 619-75032 | 4 Inch Gate Valve | 11 | Each | 5,710.21 | 519.11 |
| 619-75048 | 6 Inch Gate Valve | 4 | Each | 5,621.59 | 1,405.40 |
| 619-75064 | 8 Inch Gate Valve | 34 | Each | 60,604.12 | 1,782.47 |
| 619-75096 | 12 Inch Gate Valve | 12 | Each | 36,000.00 | 3,000.00 |
| 619-76096 | 12 Inch Eccentric Plug Valve | 7 | Each | 21,759.85 | 3,108.55 |
| 619-77210 | Restrained Plug (Special) | 5 | Each | 6,000.00 | 1,200.00 |
| 619-77300 | Corporation Stop | 10 | Each | 4,214.10 | 421.41 |
| 619-78048 | 6 Inch Fire Hydrant | 7 | Each | 40,936.17 | 5,848.02 |
| 619-78049 | 6 Inch Fire Hydrant (Install Only) | 14 | Each | 26,600.00 | 1,900.00 |
| 620-00001 | Field Office (Class 1) | 11 | Each | 134,877.00 | 12,261.55 |
| 620-00002 | Field Office (Class 2) | 38 | Each | 727,779.27 | 19,152.09 |
| 620-00005 | Field Office (Special) | 6 | Each | 473,383.54 | 78,897.26 |
| 620-00011 | Field Laboratory (Class 1) | 2 | Each | 23,090.00 | 11,545.00 |
| 620-00012 | Field Laboratory (Class 2) | 52 | Each | 832,178.05 | 16,003.42 |
| 620-00015 | Field Laboratory (State Furnished) | 1 | Each | 2,664.35 | 2,664.35 |
| 620-00020 | Sanitary Facility | 108 | Each | 148,773.89 | 1,377.54 |
| 621-00202 | Haul Road (Special) | 8,488 | Sq Yard | 101,856.00 | 12.00 |
| 621-00425 | Detour | 1 | Lump Sum | 207,060.62 | 207,060.62 |

INDEX AND AVERAGE UNIT BID PRICES FOR 01/01/11 THROUGH 12/31/11

| ITEM NUMBER | ITEM | TOTAL QUANTITY | UNIT | TOTAL COST | AVERAGE PRICE |
|---|---|---|---|---|---|
| 621-00430 | Detour | 21,581 | Sq Yard | 647,430.00 | 30.00 |
| 621-00450 | Detour Pavement | 31,679 | Sq Yard | 1,080,281.36 | 34.10 |
| 621-00500 | Temporary Bridge | 2 | Lump Sum | 359,510.86 | 179,755.43 |
| 622-00010 | Bicycle Rack | 28 | Each | 16,492.00 | 589.00 |
| 622-00100 | Shade Shelter | 1 | Each | 28,000.00 | 28,000.00 |
| 622-00270 | Bollard | 2 | Each | 1,000.00 | 500.00 |
| 622-01025 | Pond Lining | 7,944 | Sq Yard | 32,570.40 | 4.10 |
| 623-00162 | Drip Emitter Tubing | 65,900 | Lin Foot | 28,337.00 | 0.43 |
| 623-00168 | 1 Inch Emitter Valve Assembly | 27 | Each | 4,982.85 | 184.55 |
| 623-00186 | 3/4 Inch Flush Unit | 163 | Each | 4,479.24 | 27.48 |
| 623-01708 | 1 Inch Backflow Preventer | 2 | Each | 3,574.94 | 1,787.47 |
| 623-03004 | 3/4 In Drip Zone Control Valve | 75 | Each | 4,821.00 | 64.28 |
| 623-03108 | 1 Inch Automatic Control Valve | 2 | Each | 207.38 | 103.69 |
| 623-04000 | Control Wire 24 Volt | 18,500 | Lin Foot | 3,885.00 | 0.21 |
| 623-04008 | 1 Inch Quick-Coupler Valve | 15 | Each | 2,332.80 | 155.52 |
| 623-05012 | 1-1/2 Inch Gate Valve | 8 | Each | 547.44 | 68.43 |
| 623-06900 | Valve Box | 27 | Each | 2,239.38 | 82.94 |
| 623-08118 | 18 Station Automatic Controller | 2 | Each | 5,043.06 | 2,521.53 |
| 623-09900 | Sprinkler System | 2 | Lump Sum | 62,875.00 | 31,437.50 |
| 624-20012 | 12 Inch Drainage Pipe (Class 0) | 112 | Lin Foot | 3,435.04 | 30.67 |
| 624-20013 | 12 Inch Drainage Pipe (Class 0) (Complete In Place) | 4 | Lin Foot | 316.00 | 79.00 |
| 624-20018 | 18 Inch Drainage Pipe (Class 0) | 1,241 | Lin Foot | 42,914.77 | 34.58 |
| 624-20019 | 18 Inch Drainage Pipe (Class 0) (Complete In Place) | 30 | Lin Foot | 1,500.00 | 50.00 |
| 624-20024 | 24 Inch Drainage Pipe (Class 0) | 1,649 | Lin Foot | 84,153.82 | 51.03 |
| 624-20025 | 24 Inch Drainage Pipe (Class 0) (Complete In Place) | 340 | Lin Foot | 16,660.00 | 49.00 |
| 624-20036 | 36 Inch Drainage Pipe (Class 0) | 194 | Lin Foot | 15,714.00 | 81.00 |
| 624-20048 | 48 Inch Drainage Pipe (Class 0) | 107 | Lin Foot | 11,663.00 | 109.00 |
| 624-20072 | 72 Inch Drainage Pipe (Class 0) | 122 | Lin Foot | 16,958.00 | 139.00 |
| 624-20108 | 108 Inch Drainage Pipe (Class 0) | 146 | Lin Foot | 45,990.00 | 315.00 |
| 624-20300 | Detour Drainage Pipe (Class 0) | 1,000 | Lin Foot | 43,000.00 | 43.00 |
| 624-20301 | Detour Drainage Pipe (Class 0) | 2 | Lump Sum | 50,967.48 | 25,483.74 |
| 624-22018 | 18 Inch Drainage Pipe (Class 2) | 158 | Lin Foot | 8,753.20 | 55.40 |
| 624-22024 | 24 Inch Drainage Pipe (Class 2) | 70 | Lin Foot | 5,117.00 | 73.10 |
| 624-22036 | 36 Inch Drainage Pipe (Class 2) | 80 | Lin Foot | 13,196.80 | 164.96 |
| 624-23024 | 24 Inch Drainage Pipe (Class 3) | 238 | Lin Foot | 15,946.00 | 67.00 |
| 624-24018 | 18 Inch Drainage Pipe (Class 4) | 562 | Lin Foot | 38,245.11 | 68.05 |
| 624-24024 | 24 Inch Drainage Pipe (Class 4) | 260 | Lin Foot | 24,960.00 | 96.00 |
| 624-24030 | 30 Inch Drainage Pipe (Class 4) | 338 | Lin Foot | 49,348.00 | 146.00 |

INDEX AND AVERAGE UNIT BID PRICES FOR 01/01/11 THROUGH 12/31/11

| ITEM NUMBER | ITEM | TOTAL QUANTITY | UNIT | TOTAL COST | AVERAGE PRICE |
|---|---|---|---|---|---|
| 624-24036 | 36 Inch Drainage Pipe (Class 4) | 749 | Lin Foot | 123,585.00 | 165.00 |
| 624-24042 | 42 Inch Drainage Pipe (Class 4) | 134 | Lin Foot | 25,862.00 | 193.00 |
| 624-26036 | 36 Inch Drainage Pipe (Class 6) | 152 | Lin Foot | 19,456.00 | 128.00 |
| 624-27018 | 18 Inch Drainage Pipe (Class 7) | 1,470 | Lin Foot | 71,007.00 | 48.30 |
| 624-27024 | 24 Inch Drainage Pipe (Class 7) | 45 | Lin Foot | 3,735.00 | 83.00 |
| 624-27025 | 24 Inch Drainage Pipe (Class 7) (Complete In Place) | 220 | Lin Foot | 31,900.00 | 145.00 |
| 624-27036 | 36 Inch Drainage Pipe (Class 7) | 100 | Lin Foot | 11,000.00 | 110.00 |
| 625-00000 | Construction Surveying | 55 | Lump Sum | 1,613,176.79 | 29,330.49 |
| 625-00001 | Construction Surveying (Hourly) | 1,002 | Hour | 111,251.00 | 111.03 |
| 626-00000 | Mobilization | 94 | Lump Sum | 19,846,130.28 | 211,129.05 |
| 626-01000 | Public Information Services | 56 | Lump Sum | 499,147.90 | 8,913.36 |
| 627-00001 | Pavement Marking Paint | 15,404 | Gallon | 484,276.08 | 31.44 |
| 627-00002 | Thermoplastic Pavement Marking | 2,434 | Sq Foot | 18,255.00 | 7.50 |
| 627-00003 | Thermoplastic Pavement Marking (Inlaid) | 384 | Sq Foot | 7,749.00 | 20.18 |
| 627-00005 | Epoxy Pavement Marking | 22,857 | Gallon | 1,714,922.00 | 75.03 |
| 627-00011 | Pavement Marking Paint (Waterborne) | 11,649 | Gallon | 418,226.64 | 35.90 |
| 627-00012 | Pavement Marking Paint (Low VOC Solvent Base) | 17,611 | Gallon | 560,670.19 | 31.84 |
| 627-00025 | 4 Inch Pavement Marking Tape (Removable) | 22,601 | Lin Foot | 45,428.01 | 2.01 |
| 627-00032 | Raised Flexible Pavement Marker (Temporary) | 354 | Each | 2,301.00 | 6.50 |
| 627-00070 | Preformed Thermoplastic Pavement Marking | 1,116 | Sq Foot | 9,670.00 | 8.66 |
| 627-00090 | Pavement Marking (Special) | 513 | Sq Foot | 25,650.00 | 50.00 |
| 627-01001 | Preformed Plastic Pavement Marking (Type I) | 29,180 | Sq Foot | 303,033.04 | 10.38 |
| 627-01010 | Preformed Plastic Pavement Marking (Type I)(Inlaid) | 35,759 | Sq Foot | 382,106.18 | 10.69 |
| 627-02001 | Preformed Plastic Pavement Marking (Type II) | 22,900 | Sq Foot | 215,590.00 | 9.41 |
| 627-02010 | Preformed Plastic Pavement Marking (Type II) (Inlaid) | 7,899 | Sq Foot | 84,484.80 | 10.70 |
| 627-03003 | Preformed Plastic Pavement Marking (Type C) (Inlaid) | 899 | Sq Foot | 9,043.94 | 10.06 |
| 627-30324 | Preformed Plastic Pavement Marking (Word-Symbol) (Typ | 2,095 | Sq Foot | 48,055.00 | 22.94 |
| 627-30326 | Preformed Plastic Pavement Marking (Word - Symbol) (T | 1,072 | Sq Foot | 16,080.00 | 15.00 |
| 627-30327 | Preformed Plastic Pavement Marking (Word-Symbol) (Typ | 18,024 | Sq Foot | 175,292.92 | 9.73 |
| 627-30329 | Preformed Plastic Pavement Marking (Xwalk-Stop Line) | 390 | Sq Foot | 5,160.00 | 13.23 |
| 627-30332 | Preformed Plastic Pavement Marking (Xwalk-Stop Line) | 26,886 | Sq Foot | 245,789.56 | 9.14 |
| 627-30405 | Preformed Thermoplastic Pavement Marking (Word-Symbol | 8,232 | Sq Foot | 123,837.50 | 15.04 |
| 627-30407 | Preformed Thermoplastic Pavement Marking (Word-Symbol | 1,197 | Sq Foot | 20,630.75 | 17.24 |
| 627-30410 | Preformed Thermoplastic Pavement Marking (Xwalk-Stop | 19,504 | Sq Foot | 204,211.78 | 10.47 |
| 627-30411 | Preformed Thermoplastic Pavement Marking (Xwalk-Stop | 3,758 | Sq Foot | 53,548.00 | 14.25 |
| 627-40003 | Methyl Methacrylate Pavement Marking (Inlaid) | 3,350 | Sq Foot | 55,275.00 | 16.50 |
| 628-50001 | Design Services | 1 | Lump Sum | 25,000.00 | 25,000.00 |
| 629-01001 | Survey Monument (Type 1) | 142 | Each | 13,236.46 | 93.21 |

INDEX AND AVERAGE UNIT BID PRICES FOR 01/01/11 THROUGH 12/31/11

| ITEM NUMBER | ITEM | TOTAL QUANTITY | UNIT | TOTAL COST | AVERAGE PRICE |
|---|---|---|---|---|---|
| 629-01002 | Survey Monument (Type 2) | 7 | Each | 1,250.41 | 178.63 |
| 629-01003 | Survey Monument (Type 3) | 2 | Each | 320.00 | 160.00 |
| 629-01005 | Survey Monument (Type 5) | 4 | Each | 480.12 | 120.03 |
| 629-01031 | Survey Monument (Type 3A) | 3 | Each | 1,172.26 | 390.75 |
| 629-01050 | Monument Box | 1 | Each | 60.00 | 60.00 |
| 629-01065 | Survey Monument (Type 5S) | 3 | Each | 410.16 | 136.72 |
| 629-01110 | Locate Monuments | 16 | Hour | 1,742.48 | 108.91 |
| 629-01210 | Adjust Monument Box | 7 | Each | 3,013.13 | 430.45 |
| 630-00000 | Flagging | 222,754 | Hour | 4,597,905.00 | 20.64 |
| 630-00001 | Pilot Car Operation | 4,542 | Hour | 165,844.00 | 36.51 |
| 630-00003 | Uniformed Traffic Control | 16,166 | Hour | 639,200.10 | 39.54 |
| 630-00004 | Traffic Control Vehicle | 30 | Each | 120,494.04 | 4,016.47 |
| 630-00005 | Uniformed Traffic Control (Vehicle) | 4,008 | Hour | 35,368.00 | 8.82 |
| 630-00007 | Traffic Control Inspection | 5,256 | Day | 388,398.54 | 73.90 |
| 630-00012 | Traffic Control Management | 11,031 | Day | 4,860,312.52 | 440.60 |
| 630-00015 | Uniformed Traffic Control Coordination | 575 | Hour | 27,122.75 | 47.17 |
| 630-00020 | Traffic Control Vehicle | 180 | Day | 17,820.00 | 99.00 |
| 630-00025 | Traffic Control Vehicle | 2,570 | Hour | 21,520.50 | 8.37 |
| 630-80001 | Flashing Beacon (Portable) | 200 | Each | 177,616.68 | 888.08 |
| 630-80305 | Flagging Station Light | 6 | Each | 1,904.00 | 317.33 |
| 630-80335 | Barricade (Type 3 M-A) (Temporary) | 262 | Each | 24,535.64 | 93.65 |
| 630-80336 | Barricade (Type 3 M-B) (Temporary) | 65 | Each | 11,223.42 | 172.67 |
| 630-80337 | Barricade (Type 3 M-C) (Temporary) | 1 | Each | 55.00 | 55.00 |
| 630-80338 | Barricade (Type 3 M-D) (Temporary) | 1 | Each | 105.61 | 105.61 |
| 630-80341 | Construction Traffic Sign (Panel Size A) | 3,062 | Each | 140,442.32 | 45.87 |
| 630-80342 | Construction Traffic Sign (Panel Size B) | 4,828 | Each | 244,548.77 | 50.65 |
| 630-80343 | Construction Traffic Sign (Panel Size C) | 886 | Each | 50,919.09 | 57.47 |
| 630-80344 | Construction Traffic Sign (Special) | 9,693 | Sq Foot | 177,015.05 | 18.26 |
| 630-80348 | Construction Information Sign | 11 | Each | 4,208.00 | 382.55 |
| 630-80350 | Vertical Panel | 376 | Each | 7,045.06 | 18.74 |
| 630-80351 | Vertical Panel (Plastic) | 150 | Each | 165.00 | 1.10 |
| 630-80353 | Vertical Panel (With Light) (Flashing) | 50 | Each | 55.00 | 1.10 |
| 630-80354 | Vertical Panel (With Light) (Steady Burn) | 10 | Each | 180.00 | 18.00 |
| 630-80355 | Portable Message Sign Panel | 208 | Each | 934,118.85 | 4,490.96 |
| 630-80356 | Advance Warning Flashing or Sequencing Arrow Panel (A | 4 | Each | 30,234.74 | 7,558.69 |
| 630-80357 | Advance Warning Flashing or Sequencing Arrow Panel (B | 14 | Each | 10,813.00 | 772.36 |
| 630-80358 | Advance Warning Flashing or Sequencing Arrow Panel (C | 144 | Each | 140,266.62 | 974.07 |
| 630-80359 | Portable Message Sign Panel | 1,878 | Day | 113,511.00 | 60.44 |

INDEX AND AVERAGE UNIT BID PRICES FOR 01/01/11 THROUGH 12/31/11

| ITEM NUMBER | ITEM | TOTAL QUANTITY | UNIT | TOTAL COST | AVERAGE PRICE |
|---|---|---|---|---|---|
| 630-80360 | Drum Channelizing Device | 9,587 | Each | 248,286.40 | 25.90 |
| 630-80363 | Drum Channelizing Device (With Light) (Flashing) | 617 | Each | 22,398.00 | 36.30 |
| 630-80364 | Drum Channelizing Device (With Light) (Steady Burn) | 448 | Each | 16,376.90 | 36.56 |
| 630-80367 | Portable Traffic Speed Monitor | 4 | Each | 14,800.16 | 3,700.04 |
| 630-80370 | Concrete Barrier (Temporary) | 113,781 | Lin Foot | 2,831,012.65 | 24.88 |
| 630-80377 | Portable Water Filled Barrier (Temporary) | 1,000 | Lin Foot | 15,500.00 | 15.50 |
| 630-80378 | Glare Screen (Temporary) | 8,000 | Lin Foot | 76,300.00 | 9.54 |
| 630-80380 | Traffic Cone | 23,880 | Each | 154,296.00 | 6.46 |
| 630-80384 | Tubular Marker | 250 | Each | 5,737.40 | 22.95 |
| 630-80390 | Channelizing Device (Special) | 2,260 | Each | 89,570.00 | 39.63 |
| 630-80393 | Stackable Vertical Panels | 450 | Each | 7,950.00 | 17.67 |
| 630-80430 | Rumble Strip (Portable) | 60 | Each | 52,026.76 | 867.11 |
| 630-80510 | Mobile Pavement Marking Zone | 17 | Lump Sum | 32,353.02 | 1,903.12 |
| 630-80520 | Mobile Pavement Marking Zone | 28 | Day | 17,141.21 | 612.19 |
| 630-80560 | Mobile Profilograph Operation Zone | 1 | Lump Sum | 1,100.00 | 1,100.00 |
| 630-80570 | Mobile Profilograph Operation Zone | 2 | Day | 3,310.86 | 1,655.43 |
| 630-85006 | Impact Attenuator (Sand Filled Plastic Barrel) (Tempo | 32 | Each | 118,904.00 | 3,715.75 |
| 630-85010 | Impact Attenuator (Temporary) | 134 | Each | 325,956.32 | 2,432.51 |
| 630-85020 | Mobile Attenuator | 3 | Each | 5,607.96 | 1,869.32 |
| 630-85040 | Impact Attenuator (Truck Mounted Attenuator) (Tempora | 62 | Each | 767,769.16 | 12,383.37 |
| 630-85041 | Mobile Attenuator | 230 | Day | 86,365.00 | 375.50 |
| 630-86800 | Traffic Signal (Temporary) | 5 | Lump Sum | 32,493.56 | 6,498.71 |
| 630-86810 | Traffic Signal (Temporary) | 10 | Each | 168,236.43 | 16,823.64 |
| 630-86820 | Traffic Signal (Temporary)(State Furnished) | 2 | Each | 3,200.00 | 1,600.00 |
| 631-00100 | Highway Design & Construction | 1 | Lump Sum | 1,116,878.47 | 1,116,878.47 |
| 631-10000 | Alternate Bridge Design and Construction | 1 | Lump Sum | 6,588,686.87 | 6,588,686.87 |
| 631-10002 | Bridge Design and Construction | 1 | Lump Sum | 1,185,461.34 | 1,185,461.34 |
| 641-10000 | Shotcrete | 7,264 | Sq Yard | 620,263.20 | 85.39 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 201-00000 | Clear and Grub | | LUMP SUM | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 1.00 | 4000.00 | 6392.00 | 2500.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 1.00 | 100000.00 | 91190.02 | 100000.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 1.00 | 15000.00 | 38646.07 | 199000.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 1.00 | 50000.00 | 55865.71 | 6040.57 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 4.00 | 67000.00 | 43460.20 | 61708.11 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 1.00 | 5000.00 | 26555.00 | 4665.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 1.00 | 27500.00 | 34379.22 | 60700.00 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 1.00 | 25000.00 | 6377.40 | 5800.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 1.00 | 50000.00 | 78412.70 | 45000.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 1.00 | 25000.00 | 38214.29 | 10200.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 1.00 | 30000.00 | 29899.73 | 12300.00 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 1.00 | 10000.00 | 16040.00 | 15750.00 |
| ITS0703-370 | | EAST OF EJMT ON I-70 EB LANES | 06/16/11 | 1.00 | 2000.00 | 3874.00 | 2915.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 1.00 | 4000.00 | 14074.50 | 4500.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1.00 | 5000.00 | 113913.36 | 25396.67 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 10.00 | 18350.00 | 40281.68 | 16420.31 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 1.00 | 5000.00 | 8322.14 | 2500.00 |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 1.00 | 500.00 | 1747.00 | 970.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 1.00 | 25000.00 | 28187.72 | 12300.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 1.00 | 10000.00 | 18059.93 | 20000.00 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 1.00 | 15000.00 | 41883.00 | 10000.00 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 1.00 | 20000.00 | 40365.19 | 12000.00 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 1.00 | 10000.00 | 13168.40 | 10000.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 7.00 | 12214.29 | 20699.38 | 12586.91 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 1.00 | 20000.00 | 24173.08 | 13540.67 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 1.00 | 200000.00 | 66075.42 | 66858.14 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1.00 | 30000.00 | 129414.29 | 55000.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1.00 | 10000.00 | 50817.99 | 50000.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 201-00000 | Clear and Grub | | LUMP SUM | | | |
| SHE025A-013 | | I 25 BETWEEN MP 122 AND MP 12 | 11/03/11 | 1.00 | 4000.00 | 19118.79 | 2500.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 1.00 | 15000.00 | 17901.74 | 19135.92 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 1.00 | 10000.00 | 15117.51 | 6800.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 1.00 | 7000.00 | 7637.81 | 7500.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 1.00 | 40000.00 | 80189.67 | 98900.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 9.00 | 37333.33 | 49257.28 | 35581.64 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 30.00 | 32545.45 | 37949.89 | 26061.49 |
| ========== | 201-00001 | Clear and Grub | | Acre | | | |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 3.48 | 3000.00 | 4144.46 | 4570.26 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 6.00 | 2000.00 | 5255.48 | 1712.55 |
| C0241-055 | | SH 24 MP 148-152 | 05/26/11 | 0.11 | 10000.00 | 45290.49 | 21000.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 11.00 | 1700.00 | 5523.33 | 1400.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 12.00 | 2000.00 | 2386.16 | 1381.47 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 32.59 | 2032.53 | 4330.94 | 1855.40 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 2.24 | 2000.00 | 6606.14 | 2515.18 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 0.50 | 3000.00 | 3666.67 | 1400.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 2.74 | 2182.48 | 6379.10 | 2311.68 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 35.33 | 2044.16 | 4300.45 | 1825.30 |
| ========== | 201-00002 | Clearing | | LUMP SUM | | | |
| NH5502-070 | | US 550 4 MILES SOUTH OF OURAY | 08/18/11 | 1.00 | 4000.00 | 23995.47 | 16000.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 1.00 | 4000.00 | 23995.47 | 16000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 4000.00 | 23995.47 | 16000.00 |
| ========== | 202-00000 | Rem Str and Obstructions | | LUMP SUM | | | |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 1.00 | 500.00 | 4263.93 | 1494.63 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 1.00 | 500.00 | 25955.81 | 11598.66 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-00000 | Rem Str and Obstructions | | LUMP SUM | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1.00 | 10000.00 | 28014.29 | 20000.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 10000.00 | 28014.29 | 20000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 5250.00 | 26316.04 | 13278.93 |
| ========== | 202-00001 | Rem Structure | | Each | | | |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 2.00 | 4000.00 | 1029.62 | 975.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 19.00 | 1000.00 | 600.34 | 440.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 3.00 | 1000.00 | 986.67 | 800.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 4.00 | 1200.00 | 1667.00 | 1650.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 3.00 | 1000.00 | 1200.83 | 1224.12 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 31.00 | 1219.35 | 495.98 | 432.51 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 2.00 | 1000.00 | 1999.86 | 2095.89 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 1000.00 | 1999.86 | 2095.89 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 33.00 | 1206.06 | 561.22 | 492.70 |
| ========== | 202-00002 | Rem of Structure (Spec) | | Each | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 1.00 | 2000.00 | 6130.47 | 2770.14 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1.00 | 2000.00 | 4873.33 | 1635.07 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 1.00 | 2000.00 | 547.56 | 1700.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 2000.00 | 547.56 | 1700.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 2000.00 | 2926.73 | 1656.71 |
| ========== | 202-00008 | Tree Trimming | | Hour | | | |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 16.00 | 150.00 | 110.27 | 105.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 16.00 | 150.00 | 226.99 | 135.65 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-00008 | Tree Trimming | | Hour | | | |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 1.00 | 150.00 | 236.40 | 200.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1.00 | 150.00 | 236.40 | 200.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 20.00 | 125.00 | 130.31 | 168.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 20.00 | 125.00 | 130.31 | 168.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 37.00 | 136.49 | 181.82 | 150.78 |
| ========== | 202-00010 | Rem Tree | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 412.00 | 210.00 | 217.11 | 160.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 60.00 | 240.00 | 118.05 | 110.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 16.00 | 300.00 | 305.93 | 155.03 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 488.00 | 216.64 | 190.70 | 142.80 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 33.00 | 250.00 | 221.16 | 113.31 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 5.00 | 300.00 | 557.88 | 605.75 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 15.00 | 250.00 | 900.40 | 100.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 1.00 | 300.00 | 1131.92 | 511.66 |
| FSA 0502-064 | | US 50 EAST OF SARGENTS | 06/23/11 | 5.00 | 300.00 | 538.20 | 214.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 59.00 | 259.32 | 547.56 | 328.20 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 6.00 | 1000.00 | 393.93 | 500.00 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 5.00 | 250.00 | 666.07 | 600.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 11.00 | 659.09 | 244.15 | 143.40 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-00010 | Rem Tree | | Each | | | |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 75.00 | 350.00 | 183.40 | 260.28 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 375.00 | 175.00 | 253.29 | 150.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 87.00 | 200.00 | 227.05 | 278.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 27.00 | 200.00 | 392.64 | 307.08 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1.00 | 500.00 | 860.95 | 1006.07 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 565.00 | 203.85 | 252.56 | 193.37 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,123.00 | 216.78 | 302.64 | 198.16 |
| ========== | 202-00011 | Tree Trimming | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 80.00 | 500.00 | 170.62 | 20.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 10.00 | 300.00 | 241.64 | 169.43 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 90.00 | 477.78 | 192.47 | 69.81 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 20.00 | 200.00 | 300.65 | 167.66 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1.00 | 300.00 | 1081.23 | 501.02 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 21.00 | 204.76 | 337.82 | 183.53 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 111.00 | 426.13 | 249.52 | 116.64 |
| ========== | 202-00012 | Rem Tree Stump | | Each | | | |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 1.00 | 500.00 | 392.53 | 500.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 1.00 | 500.00 | 392.53 | 500.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 500.00 | 392.53 | 500.00 |
| ========== | 202-00014 | Brush Clearing | | Hour | | | |
| FSA 0502-064 | | US 50 EAST OF SARGENTS | 06/23/11 | 8.00 | 400.00 | 317.08 | 197.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 8.00 | 400.00 | 317.08 | 197.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 8.00 | 400.00 | 317.08 | 197.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-00015 | Rem Headwall | | Each | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 1.00 | 900.00 | 1250.53 | 200.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 14.00 | 550.00 | 633.47 | 680.00 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 2.00 | 850.00 | 381.27 | 331.54 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 1.00 | 800.00 | 606.17 | 650.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 18.00 | 616.67 | 636.79 | 518.38 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 3.00 | 650.00 | 625.82 | 850.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 3.00 | 650.00 | 625.82 | 850.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 21.00 | 621.43 | 636.12 | 546.80 |
| ========== | 202-00019 | Rem Inlet | | Each | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 1.00 | 2000.00 | 1024.00 | 400.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 152.00 | 750.00 | 552.41 | 310.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 19.00 | 750.00 | 746.16 | 208.74 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 172.00 | 757.27 | 616.16 | 278.38 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 3.00 | 750.00 | 658.93 | 413.38 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 6.00 | 600.00 | 641.08 | 510.00 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 1.00 | 500.00 | 821.80 | 1010.59 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 3.00 | 1200.00 | 743.33 | 850.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 8.00 | 500.00 | 518.73 | 498.79 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 21.00 | 664.29 | 615.75 | 564.34 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 4.00 | 550.00 | 638.10 | 535.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 5.00 | 700.00 | 549.39 | 815.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 1.00 | 1000.00 | 1605.00 | 2000.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 10.00 | 670.00 | 680.30 | 821.50 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-00019 | Rem Inlet | | Each | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 10.00 | 500.00 | 676.00 | 485.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 25.00 | 450.00 | 559.51 | 278.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 2.00 | 700.00 | 614.22 | 382.27 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 10.00 | 500.00 | 604.73 | 774.68 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 47.00 | 481.91 | 602.97 | 432.16 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 250.00 | 694.20 | 616.25 | 415.61 |
| ========== | 202-00020 | Rem CBC | | Each | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 3.00 | 15000.00 | 9385.71 | 6300.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 3.00 | 15000.00 | 9385.71 | 6300.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3.00 | 15000.00 | 9385.71 | 6300.00 |
| ========== | 202-00021 | Rem Manhole | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 40.00 | 1000.00 | 801.63 | 625.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 3.00 | 750.00 | 1292.12 | 456.41 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 43.00 | 982.56 | 904.89 | 586.09 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 1.00 | 1000.00 | 782.48 | 975.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 4.00 | 805.00 | 561.45 | 410.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 2.00 | 200.00 | 523.35 | 498.79 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 7.00 | 660.00 | 582.14 | 516.08 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 3.00 | 1000.00 | 721.26 | 570.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-00021 | Rem Manhole | | Each | | | |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 3.00 | 500.00 | 544.79 | 815.00 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 6.00 | 750.00 | 653.39 | 692.50 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 3.00 | 1000.00 | 612.86 | 480.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 3.00 | 650.00 | 816.92 | 716.39 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 6.00 | 825.00 | 721.69 | 598.20 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 62.00 | 908.39 | 773.19 | 593.00 |
| ========== | 202-00023 | Rem Emb Prot Ty 3 | | Each | | | |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 2.00 | 500.00 | 567.58 | 293.57 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 2.00 | 500.00 | 567.58 | 293.57 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 6.00 | 420.00 | 400.76 | 311.81 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 6.00 | 420.00 | 400.76 | 311.81 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 8.00 | 440.00 | 458.79 | 307.25 |
| ========== | 202-00024 | Rem Emb Prot Ty 5 | | Each | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 2.00 | 400.00 | 594.64 | 750.00 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 2.00 | 400.00 | 594.64 | 750.00 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 3.00 | 200.00 | 343.13 | 159.86 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 3.00 | 200.00 | 343.13 | 159.86 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 5.00 | 280.00 | 426.96 | 395.92 |
| ========== | 202-00025 | Rem Ditch Lining | | Lin Foot | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 2,475.00 | 3.00 | 4.57 | 6.10 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 2,475.00 | 3.00 | 4.57 | 6.10 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-00025 | Rem Ditch Lining | | Lin Foot | | | |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 73.00 | 11.00 | 26.28 | 37.78 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 53.00 | 20.00 | 13.61 | 15.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 126.00 | 14.79 | 20.95 | 28.20 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,601.00 | 3.57 | 5.23 | 7.17 |
| ========== | 202-00026 | Rem S and D Pave | | Sq Yard | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 1,838.00 | 6.00 | 7.92 | 4.97 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1,838.00 | 6.00 | 7.92 | 4.97 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 5.30 | 50.00 | 117.14 | 137.69 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 522.00 | 6.00 | 5.14 | 4.70 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 527.30 | 6.44 | 7.21 | 6.10 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 857.00 | 15.00 | 9.07 | 4.26 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 5.00 | 15.00 | 39.73 | 33.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 54.00 | 10.00 | 12.12 | 11.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 499.00 | 5.00 | 6.64 | 4.89 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 826.00 | 6.00 | 8.17 | 7.04 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 532.00 | 10.00 | 11.66 | 4.80 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2,773.00 | 9.46 | 9.00 | 5.49 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 5,138.30 | 7.91 | 8.48 | 5.27 |
| ========== | 202-00027 | Rem Riprap | | Sq Yard | | | |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 25.00 | 20.00 | 20.63 | 38.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 25.00 | 20.00 | 20.63 | 38.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 25.00 | 20.00 | 20.63 | 38.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-00030 | Rem Water Service | | Each | | | |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 16.00 | 300.00 | 524.29 | 915.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 16.00 | 300.00 | 524.29 | 915.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 16.00 | 300.00 | 524.29 | 915.00 |
| ========== | 202-00031 | Rem of Fire Hydrant | | Each | | | |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 1.00 | 700.00 | 1017.33 | 250.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 1.00 | 700.00 | 1017.33 | 250.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 6.00 | 700.00 | 592.57 | 725.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 6.00 | 700.00 | 592.57 | 725.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 11.00 | 500.00 | 667.43 | 400.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 11.00 | 500.00 | 667.43 | 400.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 18.00 | 577.78 | 666.13 | 500.00 |
| ========== | 202-00032 | Rem Valve | | Each | | | |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 8.00 | 400.00 | 447.85 | 375.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 8.00 | 400.00 | 447.85 | 375.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 8.00 | 400.00 | 447.85 | 375.00 |
| ========== | 202-00033 | Rem Pipe | | Each | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 1.00 | 850.00 | 889.73 | 690.00 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 3.00 | 1000.00 | 1098.78 | 2000.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 4.00 | 962.50 | 1055.74 | 1672.50 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-00033 | Rem Pipe | | Each | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 7.00 | 1500.00 | 4398.26 | 4000.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 17.00 | 400.00 | 1020.73 | 915.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 24.00 | 720.83 | 1480.32 | 1232.18 |
| C0091-038 | | SH 9 MM 81.9 BLUE RIVER EMERG | 08/24/11 | 4.00 | 100.00 | 320.45 | 278.00 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 1.00 | 500.00 | 1796.40 | 1100.00 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 15.00 | 320.00 | 1775.46 | 3405.00 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 5.00 | 150.00 | 2400.00 | 1000.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 25.00 | 258.00 | 1694.11 | 2331.48 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 1.00 | 2000.00 | 2224.86 | 2095.89 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 1.00 | 2000.00 | 1411.18 | 3500.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 2000.00 | 1953.64 | 2797.95 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 55.00 | 574.55 | 1535.61 | 1694.68 |
| ========== | 202-00035 | Rem Pipe | | Lin Foot | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 59.00 | 20.00 | 40.88 | 16.40 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 22,580.00 | 15.00 | 21.55 | 16.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 457.00 | 18.00 | 18.29 | 25.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 1,690.00 | 15.00 | 25.95 | 11.28 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 24,786.00 | 15.07 | 22.38 | 15.51 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 20.00 | 15.00 | 24.34 | 38.00 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 114.00 | 20.00 | 29.13 | 12.43 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-00035 | Rem Pipe | | Lin Foot | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 2,601.00 | 15.00 | 13.57 | 13.00 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 341.50 | 21.00 | 34.00 | 16.00 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 30.00 | 25.00 | 29.23 | 29.00 |
| C0241-055 | | SH 24 MP 148-152 | 05/26/11 | 50.00 | 20.00 | 86.34 | 63.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 130.00 | 25.00 | 14.08 | 14.00 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 162.00 | 50.00 | 26.64 | 19.78 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 758.00 | 22.00 | 17.24 | 10.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 1,309.00 | 15.00 | 21.08 | 14.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 180.00 | 20.00 | 19.77 | 14.33 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 228.00 | 15.00 | 34.50 | 16.50 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 3,696.00 | 12.00 | 11.79 | 10.16 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 9,619.50 | 15.55 | 14.34 | 11.01 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 97.00 | 35.00 | 24.54 | 20.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 343.00 | 12.00 | 19.36 | 19.50 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 1,270.00 | 20.00 | 14.35 | 12.60 |
| C0091-038 | | SH 9 MM 81.9 BLUE RIVER EMERG | 08/24/11 | 180.00 | 15.00 | 83.25 | 44.24 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 119.00 | 20.00 | 37.04 | 10.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 2,009.00 | 18.91 | 22.04 | 16.78 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 459.00 | 20.00 | 19.92 | 13.72 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 4,583.00 | 13.00 | 17.81 | 13.50 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1,223.00 | 15.00 | 28.49 | 34.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 1,452.00 | 15.00 | 57.84 | 40.73 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1,035.00 | 17.00 | 17.29 | 20.12 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 16.00 | 20.00 | 58.08 | 88.00 |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 103.00 | 20.00 | 105.00 | 100.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 8,871.00 | 14.53 | 26.89 | 22.71 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 45,285.50 | 15.23 | 20.94 | 15.59 |
| ========== | 202-00037 | Rem of End Section | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 4.00 | 200.00 | 289.14 | 200.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-00037 | Rem of End Section | | Each | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 2.00 | 250.00 | 236.11 | 220.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 6.00 | 216.67 | 197.35 | 160.56 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 2.00 | 100.00 | 305.60 | 200.01 |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 2.00 | 250.00 | 148.40 | 145.00 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 5.00 | 250.00 | 180.82 | 80.47 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 4.00 | 250.00 | 263.53 | 245.60 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 1.00 | 300.00 | 364.75 | 130.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 14.00 | 232.14 | 216.40 | 157.48 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 4.00 | 300.00 | 242.84 | 245.00 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 3.00 | 110.00 | 248.04 | 135.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 7.00 | 218.57 | 267.39 | 277.36 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 1.00 | 250.00 | 297.35 | 230.77 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1.00 | 200.00 | 277.65 | 251.52 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 225.00 | 287.50 | 241.15 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 29.00 | 225.17 | 224.98 | 185.62 |
| ========== | 202-00038 | Rem Structural Plate Pipe | | Lin Foot | | | |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 5.00 | 30.00 | 525.40 | 130.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 5.00 | 30.00 | 525.40 | 130.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 5.00 | 30.00 | 525.40 | 130.00 |
| ========== | 202-00040 | Rem Elec Conduit | | Lin Foot | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 3,230.00 | 2.00 | 3.34 | 3.20 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 3,230.00 | 2.00 | 3.34 | 3.20 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3,230.00 | 2.00 | 3.34 | 3.20 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-00090 | Rem Delineator | | Each | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 3.00 | 6.00 | 41.76 | 25.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 200.00 | 5.00 | 12.11 | 7.45 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 12.00 | 6.00 | 13.17 | 10.50 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 42.00 | 6.00 | 8.02 | 3.20 |
| C0703-363 | | CLEAR CREEK AND JEFFERSON COU | 02/17/11 | 4,000.00 | 6.00 | 3.78 | 5.00 |
| NH 2852-017 | | US 285 PONCHA PASS SOUTH RESU | 03/03/11 | 181.00 | 5.00 | 8.08 | 10.00 |
| NH 0241-056 | | US 24 BUENA VISTA NORTH | 03/03/11 | 352.00 | 7.00 | 4.69 | 8.00 |
| STA0504-061 | | US 50 M.P.369.9 -M.P.373.2 | 03/03/11 | 134.00 | 65.00 | 3.57 | 4.26 |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 130.00 | 6.00 | 3.87 | 4.15 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 40.00 | 7.00 | 8.69 | 8.80 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 5,094.00 | 7.55 | 4.35 | 5.43 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 290.00 | 7.00 | 5.71 | 7.50 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 200.00 | 8.00 | 8.33 | 7.00 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 16.00 | 5.00 | 8.59 | 6.00 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 12.00 | 6.00 | 9.73 | 5.90 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 22.00 | 6.00 | 6.93 | 5.97 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 350.00 | 4.00 | 9.34 | 8.70 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 300.00 | 7.00 | 3.10 | 3.20 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 25.00 | 8.00 | 5.21 | 5.39 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 44.00 | 8.00 | 5.68 | 6.25 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 18.00 | 9.00 | 6.52 | 13.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 39.00 | 8.00 | 9.52 | 7.50 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 60.00 | 6.00 | 9.33 | 10.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 652.00 | 5.00 | 6.51 | 6.14 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 6.00 | 6.00 | 25.50 | 12.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2,034.00 | 5.95 | 6.87 | 6.24 |
| C006A-051 | | US 6 (LOVELAND PASS), CLEAR C | 07/14/11 | 10.00 | 13.25 | 13.38 | 12.50 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 217.00 | 6.00 | 5.48 | 5.40 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 150.00 | 6.00 | 7.35 | 8.85 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 200.00 | 8.00 | 5.43 | 3.00 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 50.00 | 5.00 | 9.50 | 11.00 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 1,110.00 | 7.00 | 3.71 | 2.10 |
| STR096A-040 | | SH 96 MP 193 TO MP 201 | 09/01/11 | 120.00 | 5.40 | 10.34 | 16.27 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-00090 | Rem Delineator | | Each | | | |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 44.00 | 6.00 | 11.04 | 11.40 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 2.00 | 15.00 | 64.51 | 25.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1,903.00 | 6.78 | 6.42 | 6.48 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 7.00 | 7.00 | 11.98 | 3.97 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 27.00 | 6.00 | 8.40 | 17.65 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 90.00 | 7.50 | 8.39 | 11.50 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 10.00 | 9.00 | 9.84 | 8.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 7.00 | 6.00 | 9.55 | 11.03 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 50.00 | 7.00 | 7.72 | 5.03 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 19.00 | 15.00 | 11.73 | 11.00 |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 650.00 | 5.00 | 3.70 | 2.85 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 860.00 | 5.70 | 5.16 | 4.66 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 9,891.00 | 6.91 | 5.24 | 5.77 |
| ========== | 202-00150 | Rem Wall | | Each | | | |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 2.00 | 2500.00 | 8500.00 | 9500.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 2500.00 | 8500.00 | 9500.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 2500.00 | 8500.00 | 9500.00 |
| ========== | 202-00155 | Rem Wall | | Lin Foot | | | |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 276.00 | 25.00 | 26.82 | 33.95 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 280.00 | 33.00 | 25.16 | 18.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 556.00 | 29.03 | 26.04 | 25.92 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 208.00 | 20.00 | 18.59 | 10.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1,703.00 | 38.00 | 76.94 | 68.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 92.00 | 40.00 | 28.57 | 5.02 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 472.00 | 35.00 | 23.46 | 25.15 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2,475.00 | 35.99 | 54.67 | 52.61 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3,031.00 | 34.71 | 48.27 | 47.72 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-00160 | Rem Wall | | Sq Foot | | | |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 265.00 | 15.00 | 17.94 | 5.00 |
| NH0403-053 | | US 40 RETAINING WALL REPAIR | 07/28/11 | 516.00 | 40.00 | 38.06 | 14.17 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 781.00 | 31.52 | 27.09 | 11.06 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 781.00 | 31.52 | 27.09 | 11.06 |
| ========== | 202-00165 | Rem Wall | | LUMP SUM | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 1.00 | 30000.00 | 25233.62 | 10000.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 1.00 | 30000.00 | 25233.62 | 10000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 30000.00 | 25233.62 | 10000.00 |
| ========== | 202-00170 | Grinding And Texturing Conc Pvmt | | Sq Yard | | | |
| NH2872-018 | | US 287 RUSH CREEK NORTH | 07/21/11 | 31,300.00 | 6.25 | 3.42 | 3.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 31,300.00 | 6.25 | 3.42 | 3.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 31,300.00 | 6.25 | 3.95 | 3.42 |
| ========== | 202-00190 | Rem of Conc Median Cover Matl | | Sq Yard | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 3,080.00 | 6.00 | 5.54 | 3.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 765.00 | 10.00 | 5.97 | 3.20 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 3,845.00 | 6.80 | 5.74 | 3.10 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 937.00 | 5.00 | 9.83 | 12.39 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 937.00 | 5.00 | 9.83 | 12.39 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-00190 | Rem of Conc Median Cover Matl | | Sq Yard | | | |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 554.00 | 18.00 | 10.30 | 12.90 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 100.00 | 10.00 | 16.31 | 14.45 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 666.00 | 5.00 | 6.91 | 8.00 |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 473.00 | 20.00 | 15.50 | 14.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 1,793.00 | 13.25 | 9.01 | 11.46 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 653.00 | 15.00 | 5.57 | 9.50 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 653.00 | 15.00 | 5.57 | 9.50 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 7,228.00 | 8.91 | 7.31 | 8.77 |
| ========== | 202-00195 | Rem of Median Cover | | Sq Yard | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 10,520.00 | 7.00 | 5.37 | 3.50 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 10,520.00 | 7.00 | 5.76 | 3.97 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 18.00 | 18.00 | 18.54 | 40.00 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 425.00 | 8.00 | 5.66 | 2.71 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 70.00 | 11.00 | 13.15 | 13.40 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 440.00 | 7.00 | 8.77 | 9.60 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 953.00 | 7.95 | 8.06 | 8.18 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 88.00 | 7.50 | 17.12 | 13.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 205.00 | 10.00 | 7.94 | 5.50 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 293.00 | 9.25 | 10.70 | 7.75 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-00195 | Rem of Median Cover | | Sq Yard | | | |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 449.50 | 5.00 | 7.09 | 5.03 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 449.50 | 5.00 | 7.09 | 5.03 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 12,215.50 | 7.05 | 6.52 | 5.35 |
| ========== | 202-00200 | Rem Sidewalk | | Sq Yard | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 230.00 | 15.00 | 10.44 | 5.20 |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 193.00 | 9.00 | 10.69 | 11.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 220.00 | 10.00 | 8.21 | 7.50 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 1,041.00 | 9.00 | 6.24 | 3.55 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1,684.00 | 9.95 | 7.99 | 6.04 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 28.00 | 12.50 | 13.51 | 16.00 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 1,454.00 | 6.00 | 8.94 | 12.39 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 433.00 | 8.00 | 5.49 | 6.50 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 7.00 | 10.00 | 26.63 | 41.30 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 805.00 | 7.00 | 5.72 | 4.90 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 113.00 | 10.00 | 11.02 | 10.50 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 82.00 | 18.00 | 18.05 | 17.60 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2,922.00 | 7.14 | 8.59 | 11.20 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 16.00 | 7.00 | 25.71 | 43.50 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 5.00 | 50.00 | 56.00 | 33.00 |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 139.00 | 15.00 | 16.40 | 24.75 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 1,346.00 | 7.00 | 6.08 | 7.25 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 79.00 | 10.00 | 8.46 | 6.00 |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 44.00 | 35.00 | 44.50 | 39.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1,629.00 | 8.72 | 7.44 | 10.77 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-00200 | Rem Sidewalk | | Sq Yard | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 380.00 | 15.00 | 6.18 | 5.25 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 209.00 | 10.00 | 11.07 | 8.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 718.00 | 8.00 | 6.15 | 5.87 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 65.00 | 10.00 | 9.60 | 5.03 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 135.00 | 20.00 | 25.21 | 25.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 1,507.00 | 11.20 | 7.34 | 7.69 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 7,742.00 | 8.87 | 7.96 | 9.33 |
| ========== | 202-00201 | Rem Curb | | Lin Foot | | | |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 118.00 | 10.00 | 3.87 | 2.50 |
| NH 0241-056 | | US 24 BUENA VISTA NORTH | 03/03/11 | 1,110.00 | 3.50 | 3.65 | 7.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 1,228.00 | 4.12 | 3.92 | 4.70 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 1,560.00 | 4.50 | 3.12 | 2.12 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 9,670.00 | 3.50 | 2.84 | 2.50 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 222.00 | 5.00 | 12.83 | 11.00 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 12.00 | 5.00 | 17.40 | 17.55 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 512.00 | 4.00 | 4.48 | 4.20 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 11,976.00 | 3.68 | 3.11 | 2.70 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 302.00 | 6.60 | 7.29 | 10.80 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 248.00 | 10.00 | 21.65 | 13.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 550.00 | 8.13 | 13.76 | 11.79 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 13,754.00 | 3.90 | 3.59 | 3.39 |
| ========== | 202-00202 | Rem Gutter | | Lin Foot | | | |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 10.00 | 10.00 | 5.96 | 4.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-00202 | Rem Gutter | | Lin Foot | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 1,689.00 | 3.00 | 4.73 | 2.39 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1,699.00 | 3.04 | 4.73 | 2.40 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 15.00 | 12.00 | 16.28 | 31.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 15.00 | 12.00 | 16.28 | 31.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 315.00 | 4.00 | 5.52 | 7.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 315.00 | 4.00 | 5.52 | 7.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,029.00 | 3.26 | 4.88 | 3.33 |
| ========== | 202-00203 | Rem Curb and Gutter | | Lin Foot | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 1,501.00 | 6.00 | 4.95 | 2.40 |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 2,312.00 | 5.00 | 4.60 | 3.50 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 41,792.00 | 4.00 | 3.85 | 2.50 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 4,194.00 | 6.00 | 4.36 | 1.75 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 49,799.00 | 4.28 | 4.18 | 2.59 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 351.00 | 5.00 | 4.27 | 5.00 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 5,975.00 | 4.00 | 4.48 | 5.12 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 2,108.00 | 5.00 | 4.00 | 1.96 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 528.00 | 4.00 | 4.01 | 2.80 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 230.00 | 4.00 | 8.26 | 8.25 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 1,304.00 | 4.00 | 4.33 | 4.96 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 180.00 | 8.00 | 4.83 | 4.75 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 170.00 | 5.00 | 10.03 | 4.00 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 117.00 | 10.00 | 9.40 | 8.80 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 10,963.00 | 4.37 | 4.66 | 4.51 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-00203 | Rem Curb and Gutter | | Lin Foot | | | |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 939.00 | 4.00 | 8.30 | 6.35 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 376.00 | 15.00 | 8.15 | 6.45 |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 240.00 | 5.00 | 12.97 | 12.00 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 457.00 | 7.00 | 8.45 | 7.76 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 4,377.00 | 4.00 | 3.33 | 4.50 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 11,528.00 | 6.00 | 3.49 | 3.20 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 18.00 | 25.00 | 20.70 | 14.00 |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 343.00 | 7.00 | 7.50 | 8.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 18,278.00 | 5.65 | 3.98 | 4.11 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 7,412.00 | 5.00 | 3.10 | 3.40 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 2,039.00 | 5.00 | 4.00 | 3.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 1,631.00 | 5.00 | 3.77 | 2.58 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1,823.00 | 4.00 | 3.94 | 5.03 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 170.00 | 20.00 | 10.70 | 11.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 13,075.00 | 5.06 | 3.46 | 3.56 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 92,115.00 | 4.67 | 4.06 | 3.61 |
| ========== | 202-00206 | Rem Conc Curb Ramp | | Sq Yard | | | |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 157.00 | 10.00 | 13.47 | 15.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 80.00 | 15.00 | 23.04 | 50.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 237.00 | 11.69 | 15.00 | 18.95 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 83.00 | 12.00 | 13.20 | 14.00 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 656.00 | 10.00 | 11.99 | 12.39 |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 12.00 | 17.00 | 37.18 | 42.25 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 60.00 | 10.00 | 19.96 | 15.50 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 117.00 | 10.00 | 15.40 | 19.95 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-00206 | Rem Conc Curb Ramp | | Sq Yard | | | |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 40.00 | 10.00 | 20.05 | 17.60 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 968.00 | 10.26 | 13.38 | 14.22 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 216.00 | 12.00 | 36.79 | 115.00 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 19.00 | 35.00 | 42.40 | 32.20 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 124.00 | 10.00 | 21.02 | 20.33 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 78.00 | 25.00 | 12.14 | 11.50 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 437.00 | 14.75 | 26.74 | 65.28 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 32.00 | 19.50 | 21.79 | 8.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 55.00 | 16.00 | 17.04 | 19.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 26.20 | 10.00 | 21.12 | 7.04 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 113.20 | 15.60 | 19.75 | 13.12 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,755.20 | 11.91 | 17.30 | 28.00 |
| ========== | 202-00207 | Rem of Brick Pavers | | Sq Yard | | | |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 8.00 | 10.00 | 14.75 | 21.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 8.00 | 10.00 | 14.75 | 21.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 8.00 | 10.00 | 14.75 | 21.00 |
| ========== | 202-00210 | Rem Conc Pavement | | Sq Yard | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 400.00 | 15.00 | 24.90 | 100.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 400.00 | 15.00 | 50.23 | 81.51 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 60.00 | 18.00 | 19.33 | 40.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-00210 | Rem Conc Pavement | | Sq Yard | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 10,173.00 | 6.00 | 6.94 | 5.00 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 54.00 | 15.00 | 21.38 | 20.60 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 189.00 | 20.00 | 16.67 | 15.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 10,335.00 | 12.00 | 5.88 | 4.88 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 20,811.00 | 9.16 | 8.06 | 7.73 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 169.00 | 35.00 | 18.80 | 5.35 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 169.00 | 35.00 | 18.80 | 5.35 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1,717.00 | 20.00 | 7.73 | 8.80 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 69.00 | 30.00 | 46.85 | 100.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 195.00 | 10.00 | 16.31 | 12.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 13,062.00 | 6.00 | 7.66 | 5.53 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 15,043.00 | 7.76 | 7.89 | 6.42 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 36,423.00 | 8.77 | 8.24 | 7.56 |
| ========== | 202-00212 | Rem Conc Pavement (Spec) | | Sq Yard | | | |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 3,557.00 | 8.00 | 8.61 | 2.97 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 3,557.00 | 8.00 | 8.61 | 2.97 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3,557.00 | 8.00 | 8.61 | 2.97 |
| ========== | 202-00220 | Rem Asphalt Mat | | Sq Yard | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 156.00 | 9.00 | 9.49 | 7.15 |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 508.00 | 10.00 | 13.21 | 8.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 255,688.00 | 4.00 | 4.25 | 6.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 659.00 | 10.00 | 4.54 | 2.45 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 971.00 | 6.50 | 8.26 | 7.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-00220 | Rem Asphalt Mat | | Sq Yard | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 9,786.00 | 5.00 | 8.33 | 4.81 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 267,768.00 | 4.07 | 4.96 | 5.78 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 18.00 | 4.50 | 32.69 | 21.00 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 2,404.00 | 5.00 | 10.96 | 6.71 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 9,006.00 | 5.00 | 8.25 | 7.75 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 6,806.00 | 3.00 | 4.99 | 4.34 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 167.00 | 10.00 | 13.89 | 33.00 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 12.00 | 25.00 | 84.97 | 12.40 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 444.00 | 6.00 | 16.31 | 6.94 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 3,390.00 | 5.00 | 4.24 | 3.50 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 111.00 | 30.00 | 18.21 | 7.12 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 29,388.00 | 3.00 | 3.63 | 2.60 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 27,672.00 | 4.00 | 5.58 | 1.58 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 133.00 | 15.00 | 7.58 | 7.35 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 3,898.00 | 4.00 | 5.93 | 6.50 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 27,994.00 | 3.00 | 2.99 | 3.05 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 111,443.00 | 3.62 | 4.47 | 3.26 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 1,770.00 | 6.00 | 7.50 | 9.15 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 416.00 | 20.00 | 17.07 | 10.50 |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 98.00 | 12.00 | 12.94 | 18.00 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 122.00 | 30.00 | 26.26 | 10.70 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 9,952.00 | 5.00 | 4.28 | 4.00 |
| NH0403-053 | | US 40 RETAINING WALL REPAIR | 07/28/11 | 58.00 | 20.00 | 27.44 | 40.83 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 34,565.00 | 3.00 | 3.23 | 1.75 |
| C0091-038 | | SH 9 MM 81.9 BLUE RIVER EMERG | 08/24/11 | 233.00 | 20.00 | 9.09 | 7.10 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 929.00 | 7.00 | 21.80 | 24.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 92.00 | 15.00 | 23.40 | 22.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 48,235.00 | 3.96 | 4.28 | 3.16 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 6,703.00 | 4.00 | 3.51 | 2.28 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 44,963.00 | 1.90 | 3.21 | 2.10 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 58,199.00 | 3.00 | 3.18 | 3.10 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 7,231.00 | 6.00 | 5.76 | 4.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 6,031.00 | 5.00 | 4.94 | 2.97 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-00220 | Rem Asphalt Mat | | Sq Yard | | | |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 13,062.00 | 4.00 | 4.39 | 3.90 |
| MC0504-065 | | US50B FROM MP 318 TO MP 359 | 12/01/11 | 120.00 | 5.50 | 44.00 | 10.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 136,309.00 | 3.03 | 3.57 | 2.85 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 563,755.00 | 3.72 | 4.30 | 3.68 |
| ========== | 202-00240 | Rem Asphalt Mat (Planing) | | Sq Yard | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 6,718.00 | 5.00 | 3.36 | 1.55 |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 28,645.00 | 1.50 | 1.42 | 1.40 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 18,684.00 | 3.00 | 4.07 | 4.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 4,230.00 | 5.00 | 2.35 | 1.55 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 8,147.00 | 1.40 | 2.96 | 1.80 |
| NH 2852-017 | | US 285 PONCHA PASS SOUTH RESU | 03/03/11 | 1,697.00 | 3.50 | 5.67 | 7.00 |
| NH 0241-056 | | US 24 BUENA VISTA NORTH | 03/03/11 | 1,124.00 | 5.00 | 6.98 | 6.00 |
| STA0504-061 | | US 50 M.P.369.9 -M.P.373.2 | 03/03/11 | 134,188.00 | 1.00 | 1.29 | 1.21 |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 1,000.00 | 3.00 | 6.68 | 5.70 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 259,224.00 | 1.00 | 1.98 | 1.50 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 67,510.00 | 1.50 | 1.87 | 1.72 |
| NH 0402-079 | | US40 MP 165.0 - 179.0 GRAND C | 03/31/11 | 1,390.00 | 7.00 | 8.19 | 7.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 532,557.00 | 1.28 | 1.93 | 1.58 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 1,901.00 | 6.00 | 4.60 | 3.99 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 200,805.00 | 1.40 | 1.17 | 0.80 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 121,990.00 | 0.50 | 1.14 | 1.55 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 4,131.00 | 4.00 | 6.01 | 7.15 |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 50,656.00 | 2.00 | 1.63 | 1.70 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 5,367.00 | 2.25 | 2.83 | 1.70 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 16,430.00 | 1.50 | 2.30 | 2.18 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 788.00 | 2.00 | 7.79 | 2.50 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 65,938.00 | 1.50 | 1.99 | 1.60 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 65,446.00 | 1.50 | 1.63 | 1.00 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 33,957.00 | 2.00 | 1.71 | 2.20 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 176,492.00 | 2.00 | 1.73 | 1.90 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 273,802.00 | 1.60 | 1.75 | 1.20 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 800.00 | 7.00 | 5.66 | 7.65 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 1,581.00 | 6.00 | 3.74 | 2.25 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 30,673.00 | 1.50 | 1.41 | 0.90 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-00240 | Rem Asphalt Mat (Planing) | | Sq Yard | | | |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 1,025.00 | 6.00 | 10.00 | 8.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 244,708.00 | 1.50 | 1.37 | 1.03 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 630.00 | 2.25 | 6.30 | 7.20 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 870.00 | 2.00 | 6.63 | 6.43 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1,297,990.00 | 1.54 | 1.58 | 1.37 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 283.00 | 10.00 | 16.41 | 15.00 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 136,570.00 | 1.35 | 1.59 | 1.66 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 105,332.00 | 1.50 | 3.29 | 2.90 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 15,213.00 | 1.50 | 2.36 | 2.60 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 1,001.00 | 8.00 | 6.38 | 9.00 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 866.00 | 8.00 | 7.78 | 9.00 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 700.00 | 6.00 | 9.38 | 10.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 259,965.00 | 1.49 | 2.42 | 2.31 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 2,268.00 | 3.00 | 3.83 | 3.30 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 6,805.00 | 2.00 | 2.11 | 1.50 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 7,616.00 | 1.50 | 1.97 | 3.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 5,985.00 | 2.00 | 2.17 | 1.29 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 27,116.40 | 2.00 | 2.22 | 1.61 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 55,101.00 | 2.00 | 2.10 | 1.70 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 759.00 | 8.00 | 9.87 | 10.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 2,513.00 | 4.10 | 3.81 | 4.00 |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 2,000.00 | 3.75 | 4.14 | 4.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 18,463.00 | 6.00 | 2.54 | 2.00 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 7,813.00 | 7.00 | 3.47 | 2.40 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 136,439.40 | 2.91 | 2.40 | 1.96 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,226,951.40 | 1.56 | 1.83 | 1.56 |
| ========== | 202-00246 | Rem Asphalt Mat (Planing)(Special) | | Sq Yard | | | |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 3,641.00 | 10.00 | 16.05 | 22.50 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 8,521.00 | 6.00 | 5.33 | 8.00 |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 1,055.00 | 8.00 | 8.33 | 8.15 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 8,385.00 | 6.00 | 10.09 | 3.90 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 194.00 | 25.00 | 19.24 | 17.30 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-00246 | Rem Asphalt Mat (Planing)(Special) | | Sq Yard | | | |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 350.00 | 25.00 | 6.32 | 3.71 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 22,146.00 | 7.22 | 9.74 | 8.64 |
| BR2706-036 | | I-270 BRIDGE DECK REHABILITAT | 08/11/11 | 6,413.00 | 6.00 | 9.25 | 10.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 6,413.00 | 6.00 | 9.25 | 10.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 28,559.00 | 6.95 | 9.65 | 8.93 |
| ========== | 202-00250 | Rem Pavement Marking | | Sq Foot | | | |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 3,000.00 | 1.00 | 1.98 | 1.90 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 132,956.00 | 1.00 | 1.26 | 0.90 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 10,500.00 | 2.00 | 1.00 | 1.05 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 146,456.00 | 1.07 | 1.21 | 0.92 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 3,000.00 | 1.00 | 1.62 | 2.40 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 3,893.00 | 2.00 | 2.01 | 2.01 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 3,910.00 | 2.00 | 1.27 | 1.30 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 400.00 | 3.00 | 4.00 | 3.15 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 8,264.00 | 1.00 | 1.31 | 1.30 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 9,000.00 | 2.00 | 2.03 | 2.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 500.00 | 2.00 | 2.97 | 2.81 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 600.00 | 1.00 | 2.56 | 2.25 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 100.00 | 3.50 | 2.38 | 2.30 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 26,945.00 | 0.20 | 1.02 | 0.91 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 752.00 | 2.00 | 2.50 | 2.50 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 57,364.00 | 0.96 | 1.41 | 1.44 |
| NH2872-018 | | US 287 RUSH CREEK NORTH | 07/21/11 | 1,580.00 | 1.00 | 2.79 | 3.00 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 226.00 | 3.00 | 3.15 | 3.20 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-00250 | Rem Pavement Marking | | Sq Foot | | | |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 620.00 | 3.00 | 3.15 | 3.21 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 2,674.00 | 2.00 | 1.71 | 1.65 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 500.00 | 2.00 | 5.52 | 7.00 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 1,528.00 | 1.00 | 2.16 | 2.20 |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 2,731.00 | 3.00 | 2.25 | 2.50 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 9,859.00 | 2.05 | 2.25 | 2.47 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 195.00 | 2.00 | 4.41 | 4.41 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 4,000.00 | 1.50 | 1.25 | 1.17 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 20,050.00 | 0.70 | 1.43 | 1.50 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 8,771.00 | 1.50 | 2.25 | 2.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 3,103.00 | 2.00 | 2.41 | 2.76 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1,500.00 | 1.50 | 2.92 | 3.17 |
| MC0504-065 | | US50B FROM MP 318 TO MP 359 | 12/01/11 | 1,000.00 | 1.25 | 2.25 | 2.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 38,619.00 | 1.12 | 1.76 | 1.77 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 252,298.00 | 1.09 | 1.46 | 1.43 |
| ========== | 202-00400 | Rem Bridge | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 8.00 | 150000.00 | 100201.02 | 150000.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 1.00 | 80000.00 | 23269.82 | 10000.00 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 1.00 | 40000.00 | 107295.31 | 115600.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 1.00 | 750000.00 | 574492.62 | 482229.94 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 11.00 | 188181.82 | 179240.61 | 181565.99 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 2.00 | 120000.00 | 95396.76 | 51979.10 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 1.00 | 70000.00 | 235574.35 | 151000.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 2.00 | 80000.00 | 128129.02 | 109400.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1.00 | 75000.00 | 82974.47 | 70000.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 6.00 | 90833.33 | 104734.32 | 79536.89 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 1.00 | 150000.00 | 134892.68 | 140000.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1.00 | 150000.00 | 86601.93 | 82250.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-00400 | Rem Bridge | | Each | | | |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 1.00 | 300000.00 | 100308.53 | 28814.31 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1.00 | 70000.00 | 46057.14 | 76000.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1.00 | 80000.00 | 172512.16 | 120000.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 1.00 | 80000.00 | 112508.34 | 129492.70 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1.00 | 127000.00 | 147332.90 | 142963.21 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 5.00 | 131400.00 | 112948.86 | 99454.04 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 23.00 | 148782.61 | 125773.71 | 111913.60 |
| ========== | 202-00420 | Rem Ped Rail | | Lin Foot | | | |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 197.00 | 10.00 | 6.66 | 3.10 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 197.00 | 10.00 | 6.66 | 3.10 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 91.00 | 10.00 | 7.04 | 5.07 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 91.00 | 10.00 | 7.04 | 5.07 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 288.00 | 10.00 | 6.79 | 3.72 |
| ========== | 202-00425 | Rem Bridge Railing | | Lin Foot | | | |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 810.00 | 14.00 | 8.01 | 4.00 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 1,598.00 | 20.00 | 58.08 | 26.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 184.00 | 15.00 | 42.36 | 36.33 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 2,592.00 | 17.77 | 36.08 | 18.91 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 1,169.00 | 8.00 | 24.83 | 45.25 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 2,860.00 | 10.00 | 7.72 | 7.50 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 99.00 | 15.00 | 19.52 | 15.30 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 34.00 | 50.00 | 9.17 | 9.22 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-00425 | Rem Bridge Railing | | Lin Foot | | | |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 939.00 | 6.00 | 17.46 | 8.23 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 5,101.00 | 9.17 | 11.21 | 15.23 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 248.00 | 5.00 | 16.46 | 5.20 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 248.00 | 5.00 | 16.46 | 5.20 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 106.00 | 50.00 | 13.89 | 10.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 744.00 | 8.00 | 43.04 | 29.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 850.00 | 13.24 | 40.91 | 26.63 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 8,791.00 | 11.98 | 24.09 | 17.03 |
| ========== | 202-00450 | Rem Port Present Str (1) | | Sq Yard | | | |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 99.00 | 100.00 | 190.58 | 128.75 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 7,343.00 | 100.00 | 47.13 | 56.25 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 125.00 | 180.00 | 149.33 | 153.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 7,567.00 | 101.32 | 50.53 | 60.32 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 72.60 | 150.00 | 117.58 | 84.00 |
| BR2706-036 | | I-270 BRIDGE DECK REHABILITAT | 08/11/11 | 5,260.00 | 30.00 | 15.05 | 11.75 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 5,332.60 | 31.63 | 16.79 | 12.73 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 12,899.60 | 72.51 | 39.68 | 40.80 |
| ========== | 202-00453 | Rem Port Present Str (2) | | Sq Yard | | | |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 99.00 | 150.00 | 226.33 | 142.00 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 368.00 | 200.00 | 145.50 | 109.00 |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 465.00 | 160.00 | 191.75 | 200.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-00453 | Rem Port Present Str (2) | | Sq Yard | | | |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 2,081.00 | 150.00 | 287.65 | 273.00 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 75.00 | 200.00 | 213.33 | 195.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 3,088.00 | 158.68 | 253.99 | 235.97 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 72.60 | 200.00 | 177.47 | 107.00 |
| BR2706-036 | | I-270 BRIDGE DECK REHABILITAT | 08/11/11 | 2,567.00 | 275.00 | 131.25 | 175.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 31.00 | 200.00 | 526.80 | 358.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 2,670.60 | 272.09 | 138.49 | 175.28 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 5,758.60 | 211.27 | 211.04 | 208.15 |
| ========== | 202-00460 | Rem Port Present Str (3) | | Sq Yard | | | |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 35.00 | 250.00 | 304.67 | 262.00 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 144.00 | 300.00 | 279.33 | 194.00 |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 47.00 | 350.00 | 362.89 | 342.00 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 116.00 | 300.00 | 436.40 | 491.00 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 50.00 | 200.00 | 486.00 | 543.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 392.00 | 288.78 | 358.75 | 350.22 |
| BR2706-036 | | I-270 BRIDGE DECK REHABILITAT | 08/11/11 | 210.00 | 500.00 | 423.50 | 204.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 210.00 | 500.00 | 423.50 | 204.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 602.00 | 362.46 | 375.15 | 309.13 |
| ========== | 202-00495 | Rem Port Present Str | | LUMP SUM | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 1.00 | 50000.00 | 35708.40 | 15000.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 1.00 | 20000.00 | 14120.54 | 3700.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 2.00 | 44000.00 | 27073.25 | 9350.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-00495 | Rem Port Present Str | | LUMP SUM | | | |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 1.00 | 2000.00 | 15180.00 | 16925.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 1.00 | 50000.00 | 50292.93 | 35300.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 1.00 | 20000.00 | 24484.56 | 17400.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 3.00 | 24000.00 | 26259.65 | 17823.75 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 5.00 | 36500.00 | 26608.34 | 14999.17 |
| ========== | 202-00500 | Rem Port Present Str | | Each | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 2.00 | 18000.00 | 9183.12 | 5058.04 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 2.00 | 18000.00 | 9183.12 | 5058.04 |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 2.00 | 50000.00 | 68387.39 | 108300.00 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 2.00 | 2100.00 | 2057.90 | 1079.50 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 4.00 | 26050.00 | 38237.62 | 54689.75 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 2.00 | 5000.00 | 5708.29 | 7500.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 5000.00 | 5708.29 | 7500.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 8.00 | 18775.00 | 21775.84 | 30484.39 |
| ========== | 202-00502 | Rem Port Present Str | | Cubic Yard | | | |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 2.00 | 1000.00 | 6318.33 | 5925.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 2.00 | 1000.00 | 6318.33 | 5925.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 1000.00 | 6318.33 | 5925.00 |
| ========== | 202-00504 | Rem Exp Device | | Lin Foot | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 684.00 | 60.00 | 257.61 | 125.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 684.00 | 60.00 | 214.63 | 110.82 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-00504 | Rem Exp Device | | Lin Foot | | | |
| BR2706-036 | | I-270 BRIDGE DECK REHABILITAT | 08/11/11 | 40.00 | 100.00 | 160.00 | 140.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 40.00 | 100.00 | 160.00 | 140.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 724.00 | 62.21 | 208.05 | 108.29 |
| ========== | 202-00700 | Rem Light Standard | | Each | | | |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 6.00 | 250.00 | 404.67 | 420.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 16.00 | 250.00 | 134.38 | 124.71 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 22.00 | 250.00 | 216.64 | 205.24 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 1.00 | 500.00 | 398.75 | 276.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 1.00 | 250.00 | 145.02 | 210.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 2.00 | 375.00 | 257.79 | 243.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 24.00 | 260.42 | 219.16 | 208.39 |
| ========== | 202-00705 | Rem Light Standard Foundation | | Each | | | |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 18.00 | 225.00 | 163.83 | 85.03 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 18.00 | 225.00 | 163.83 | 85.03 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 2.00 | 225.00 | 332.59 | 330.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 2.00 | 225.00 | 332.59 | 330.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 12.00 | 200.00 | 272.51 | 248.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 12.00 | 200.00 | 272.51 | 248.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 32.00 | 215.63 | 205.74 | 161.45 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-00750 | Rem Luminaire | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 8.00 | 60.00 | 291.03 | 275.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 8.00 | 60.00 | 291.03 | 275.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 14.00 | 50.00 | 52.60 | 50.29 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 14.00 | 50.00 | 52.60 | 50.29 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 22.00 | 53.64 | 94.68 | 78.38 |
| ========== | 202-00800 | Rem Overpass Mtd Sign Brkt | | Each | | | |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 2.00 | 2500.00 | 1296.76 | 1290.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 2.00 | 2500.00 | 1296.76 | 1290.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 2500.00 | 1296.76 | 1290.00 |
| ========== | 202-00805 | Rem Overhead Sign Str | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 12.00 | 6500.00 | 5787.07 | 7500.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 4.00 | 5000.00 | 3643.70 | 2619.40 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 16.00 | 6125.00 | 4624.56 | 4711.09 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 1.00 | 5000.00 | 5338.38 | 3266.14 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 3.00 | 6500.00 | 4013.47 | 6700.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 3.00 | 6000.00 | 3614.59 | 3900.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 7.00 | 6071.43 | 4060.76 | 5009.45 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-00805 | Rem Overhead Sign Str | | Each | | | |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1.00 | 5000.00 | 4965.08 | 3560.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 5000.00 | 4965.08 | 3560.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 24.00 | 6062.50 | 4401.18 | 4773.58 |
| ========== | 202-00810 | Rem Ground Sign | | Each | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 8.00 | 150.00 | 97.78 | 60.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 228.00 | 90.00 | 104.98 | 165.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 10.00 | 54.00 | 46.84 | 39.00 |
| STA0504-061 | | US 50 M.P.369.9 -M.P.373.2 | 03/03/11 | 31.00 | 50.00 | 67.35 | 53.24 |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 1.00 | 100.00 | 25.65 | 20.65 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 18.00 | 80.00 | 93.04 | 93.54 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 296.00 | 85.64 | 69.11 | 87.43 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 3.00 | 50.00 | 132.70 | 150.00 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 1.00 | 46.00 | 48.84 | 55.00 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 4.00 | 75.00 | 96.42 | 85.00 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 3.00 | 100.00 | 83.53 | 94.10 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 1.00 | 75.00 | 131.07 | 81.70 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 8.00 | 150.00 | 72.08 | 71.00 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 2.00 | 100.00 | 154.00 | 158.00 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 7.00 | 90.00 | 33.08 | 37.73 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 26.00 | 14.00 | 79.67 | 132.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 6.00 | 80.00 | 61.49 | 62.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 2.00 | 150.00 | 53.83 | 53.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 2.00 | 100.00 | 84.86 | 91.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 1.00 | 100.00 | 166.67 | 150.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 11.00 | 75.00 | 87.75 | 135.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 14.00 | 25.00 | 169.06 | 125.71 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 91.00 | 60.66 | 96.35 | 103.04 |
| C006A-051 | | US 6 (LOVELAND PASS), CLEAR C | 07/14/11 | 13.00 | 69.25 | 89.50 | 69.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-00810 | Rem Ground Sign | | Each | | | |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 4.00 | 100.00 | 74.70 | 22.50 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 2.00 | 100.00 | 95.67 | 74.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 7.00 | 75.00 | 131.92 | 90.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 63.00 | 100.00 | 36.37 | 26.15 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 9.00 | 130.00 | 117.77 | 138.00 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 16.00 | 80.00 | 87.93 | 90.00 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 9.00 | 40.00 | 170.49 | 200.00 |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 2.00 | 50.00 | 171.00 | 177.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 125.00 | 89.88 | 72.32 | 64.03 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 19.00 | 75.00 | 101.21 | 52.96 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 59.00 | 75.00 | 32.64 | 24.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 6.00 | 95.00 | 58.66 | 75.00 |
| SHE025A-013 | | I 25 BETWEEN MP 122 AND MP 12 | 11/03/11 | 2.00 | 110.00 | 206.76 | 150.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 2.00 | 100.00 | 79.66 | 110.30 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 20.00 | 150.00 | 81.87 | 85.52 |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 11.00 | 600.00 | 1238.39 | 893.55 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 4.00 | 100.00 | 169.17 | 170.00 |
| C2854-125 | | US 285, ASPEN PARK TO MORRISO | 12/08/11 | 2.00 | 250.00 | 416.67 | 300.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 6.00 | 85.00 | 85.31 | 54.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 131.00 | 136.26 | 125.30 | 126.23 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 643.00 | 93.24 | 83.86 | 85.42 |
| ========== | 202-00815 | Rem of Sign (Special) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 24.00 | 500.00 | 970.12 | 1467.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 24.00 | 500.00 | 970.12 | 1467.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 24.00 | 500.00 | 970.12 | 1467.00 |
| ========== | 202-00821 | Rem Sign Panel | | Each | | | |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 8.00 | 75.00 | 64.75 | 16.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 76.00 | 90.00 | 146.02 | 268.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-00821 | Rem Sign Panel | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| STA0504-061 | | US 50 M.P.369.9 -M.P.373.2 | 03/03/11 | 3.00 | 15.00 | 28.98 | 31.95 |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 41.00 | 25.00 | 10.10 | 10.30 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 5.00 | 60.00 | 57.89 | 60.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 6.00 | 70.00 | 218.53 | 55.02 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 139.00 | 66.40 | 67.91 | 57.58 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 3.00 | 50.00 | 94.27 | 85.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 9.00 | 90.00 | 81.75 | 62.00 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 5.00 | 90.00 | 51.17 | 26.00 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 17.00 | 75.00 | 31.37 | 10.78 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 2.00 | 2.00 | 170.00 | 84.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 5.00 | 55.00 | 25.48 | 12.50 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 1.00 | 60.00 | 176.75 | 28.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 4.00 | 15.00 | 229.72 | 266.51 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 46.00 | 67.04 | 73.93 | 53.28 |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 2.00 | 60.00 | 39.20 | 18.00 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 2.00 | 75.00 | 53.08 | 30.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 3.00 | 100.00 | 93.79 | 90.00 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 3.00 | 150.00 | 36.69 | 61.00 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 1.00 | 80.00 | 92.95 | 110.00 |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 4.00 | 40.00 | 57.00 | 59.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 15.00 | 84.00 | 64.79 | 57.69 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 15.00 | 50.00 | 36.11 | 49.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 9.00 | 55.00 | 66.22 | 250.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 24.00 | 51.88 | 45.14 | 124.38 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 224.00 | 66.16 | 66.18 | 63.70 |
| ========== | 202-00825 | Rem Flashing Beacon | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 8.00 | 300.00 | 310.24 | 300.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-00825 | Rem Flashing Beacon | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 8.00 | 300.00 | 310.24 | 300.00 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 2.00 | 200.00 | 75.07 | 65.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 2.00 | 300.00 | 143.93 | 140.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 4.00 | 250.00 | 109.50 | 102.50 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 1.00 | 200.00 | 209.93 | 218.97 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 2.00 | 200.00 | 264.29 | 565.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 3.00 | 200.00 | 249.98 | 449.66 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 15.00 | 266.67 | 212.49 | 262.11 |
| ========== | 202-00827 | Rem of Pull Box | | Each | | | |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 12.00 | 50.00 | 98.45 | 52.81 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 2.00 | 100.00 | 289.52 | 290.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 14.00 | 57.14 | 126.90 | 142.87 |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 5.00 | 100.00 | 148.20 | 50.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 5.00 | 100.00 | 149.02 | 82.08 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 2.00 | 200.00 | 308.33 | 275.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 200.00 | 308.33 | 275.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 21.00 | 80.95 | 139.36 | 127.86 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-00828 | Rem Traf Sig Equipment | | LUMP SUM | | | |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 1.00 | 4000.00 | 3457.77 | 4700.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 1.00 | 4000.00 | 5632.74 | 5615.94 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1.00 | 8000.00 | 6896.40 | 6509.95 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 1.00 | 3000.00 | 23635.00 | 8270.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 4.00 | 4750.00 | 7329.22 | 6273.97 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 1.00 | 5000.00 | 4316.67 | 3700.00 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 1.00 | 20000.00 | 21504.16 | 13606.00 |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 1.00 | 15000.00 | 3815.00 | 4130.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 3.00 | 13333.33 | 11844.07 | 7145.33 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1.00 | 5000.00 | 3608.89 | 3474.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1.00 | 5000.00 | 8162.95 | 3018.22 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 5000.00 | 6411.39 | 3246.11 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 9.00 | 7666.67 | 7933.80 | 5652.71 |
| ========== | 202-00831 | Rem Traf Sig Head | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 28.00 | 60.00 | 82.22 | 80.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 28.00 | 60.00 | 126.32 | 127.50 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 2.00 | 60.00 | 101.00 | 100.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2.00 | 60.00 | 101.00 | 100.00 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 4.00 | 500.00 | 32.67 | 33.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 4.00 | 500.00 | 32.67 | 33.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 34.00 | 111.76 | 119.11 | 105.85 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-00840 | Rem Traf Sig Pole | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 8.00 | 1500.00 | 573.00 | 580.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 8.00 | 1500.00 | 573.00 | 580.00 |
| SHE074A-001 | | SH 74 - EVERGREEN - JEFFERSON | 04/28/11 | 4.00 | 500.00 | 983.33 | 1140.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 4.00 | 500.00 | 983.33 | 1140.00 |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 4.00 | 1300.00 | 923.00 | 300.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 1.00 | 2000.00 | 310.84 | 525.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 5.00 | 1440.00 | 800.57 | 345.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 7.00 | 600.00 | 766.86 | 755.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 7.00 | 600.00 | 766.86 | 755.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 24.00 | 1058.33 | 766.39 | 707.22 |
| ========== | 202-00848 | Rem Traf Sig Control+Cab | | Each | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 1.00 | 554.00 | 805.44 | 810.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 1.00 | 554.00 | 805.44 | 810.00 |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 1.00 | 500.00 | 427.00 | 200.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 1.00 | 1000.00 | 208.02 | 525.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 2.00 | 750.00 | 317.51 | 362.50 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-00848 | Rem Traf Sig Control+Cab | | Each | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 2.00 | 750.00 | 582.71 | 1135.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 750.00 | 582.71 | 1135.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 5.00 | 710.80 | 538.86 | 761.00 |
| ========== | 202-00858 | Rem Pedestal Pole | | Each | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 2.00 | 250.00 | 309.72 | 310.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2.00 | 250.00 | 309.72 | 310.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 250.00 | 309.72 | 310.00 |
| ========== | 202-00860 | Rem Ped Push Button | | Each | | | |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 4.00 | 500.00 | 23.05 | 23.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 4.00 | 500.00 | 23.05 | 23.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4.00 | 500.00 | 23.05 | 23.00 |
| ========== | 202-00895 | Rem of Impact Attenuator | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 16.00 | 2000.00 | 951.89 | 1200.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 1.00 | 1500.00 | 1854.33 | 1612.26 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 17.00 | 1970.59 | 1115.97 | 1282.45 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 1.00 | 1000.00 | 1560.54 | 520.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1.00 | 1000.00 | 1560.54 | 520.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-00895 | Rem of Impact Attenuator | | Each | | | |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 1.00 | 1500.00 | 1277.65 | 1315.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1.00 | 1500.00 | 1277.65 | 1315.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 2.00 | 1000.00 | 1469.81 | 3826.80 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 1000.00 | 1469.81 | 3826.80 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 21.00 | 1809.52 | 1246.00 | 1766.76 |
| ========== | 202-00900 | Rem Conc Footing | | Each | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 1.00 | 300.00 | 871.00 | 495.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 240.00 | 300.00 | 259.01 | 120.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 30.00 | 400.00 | 283.57 | 132.08 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 271.00 | 311.07 | 270.42 | 128.10 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 1.00 | 500.00 | 7583.33 | 7350.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1.00 | 500.00 | 7583.33 | 7350.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 1.00 | 500.00 | 553.56 | 475.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1.00 | 500.00 | 553.56 | 475.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 7.00 | 400.00 | 383.60 | 201.21 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 7.00 | 400.00 | 383.60 | 201.21 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 280.00 | 314.64 | 305.39 | 208.91 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-01000 | Rem Fence | | Lin Foot | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 555.00 | 1.00 | 1.71 | 1.35 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 6,725.00 | 0.50 | 0.66 | 0.65 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 729.00 | 2.00 | 1.81 | 1.96 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 8,009.00 | 0.67 | 0.54 | 0.43 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 50.00 | 2.00 | 4.09 | 1.88 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 11,389.00 | 0.60 | 0.85 | 0.55 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 635.00 | 7.00 | 2.71 | 3.20 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 620.00 | 1.00 | 2.14 | 1.10 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 15,524.00 | 0.60 | 0.58 | 0.60 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 390.00 | 2.00 | 3.65 | 4.20 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 3,049.00 | 1.00 | 1.03 | 0.96 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 31,657.00 | 0.79 | 0.87 | 0.65 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 12,820.00 | 0.50 | 0.48 | 0.50 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 12,820.00 | 0.50 | 0.52 | 0.52 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 1,896.00 | 3.00 | 0.91 | 0.88 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 856.00 | 2.50 | 1.75 | 1.22 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 4,147.00 | 1.00 | 0.96 | 0.90 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1,872.00 | 2.00 | 2.66 | 2.50 |
| SHE025A-013 | | I 25 BETWEEN MP 122 AND MP 12 | 11/03/11 | 19,400.00 | 0.82 | 0.57 | 0.45 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 34.00 | 10.00 | 5.13 | 4.69 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 776.00 | 1.00 | 1.11 | 1.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 3,801.00 | 3.00 | 1.71 | 1.70 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 32,782.00 | 1.35 | 0.93 | 0.83 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 85,268.00 | 0.95 | 0.77 | 0.60 |
| ========== | 202-01015 | Rem Rockfall Fence | | Lin Foot | | | |
| IM0703-368 | | GEORGETOWN HILL CHUTES 6,7,9, | 12/01/11 | 210.00 | 300.00 | 99.15 | 40.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 210.00 | 300.00 | 99.15 | 40.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 210.00 | 300.00 | 99.15 | 40.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-01020 | Rem Sound Barrier Fence | | Lin Foot | ========== | ========== | ========== |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 2,097.00 | 12.00 | 19.08 | 15.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2,097.00 | 12.00 | 19.08 | 15.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,097.00 | 12.00 | 19.08 | 15.00 |
| ========== | 202-01130 | Rem Gdrail Ty 3 | | Lin Foot | ========== | ========== | ========== |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 53.00 | 4.00 | 15.48 | 17.75 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 14,364.00 | 3.00 | 2.32 | 1.90 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 427.00 | 4.00 | 5.32 | 2.10 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 1,615.00 | 2.00 | 3.21 | 1.80 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 2,941.00 | 3.00 | 2.47 | 1.93 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 19,400.00 | 2.94 | 2.55 | 2.40 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 540.00 | 3.00 | 1.91 | 2.50 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 357.00 | 3.00 | 2.56 | 3.00 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 50.00 | 2.00 | 6.60 | 6.00 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 5,762.00 | 3.00 | 2.54 | 2.00 |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 375.00 | 3.00 | 3.51 | 3.40 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 1,608.00 | 2.50 | 2.10 | 2.11 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 919.00 | 3.00 | 2.82 | 2.80 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 80.00 | 6.00 | 10.15 | 7.50 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 3,758.00 | 4.00 | 2.41 | 2.30 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 196.00 | 3.00 | 5.09 | 11.40 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 5,696.00 | 2.50 | 1.96 | 2.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 478.00 | 2.00 | 2.25 | 2.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 532.00 | 3.00 | 2.56 | 3.79 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 23,239.00 | 2.25 | 2.15 | 2.15 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 65.00 | 8.00 | 15.77 | 52.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 3,369.00 | 2.00 | 2.13 | 2.01 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 47,024.00 | 2.56 | 2.33 | 2.27 |
| C006A-051 | | US 6 (LOVELAND PASS), CLEAR C | 07/14/11 | 1,200.00 | 3.50 | 5.00 | 2.65 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-01130 | Rem Gdrail Ty 3 | | Lin Foot | ========== | ========== | ========== |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 130.00 | 4.00 | 3.45 | 3.00 |
| C0091-038 | | SH 9 MM 81.9 BLUE RIVER EMERG | 08/24/11 | 75.00 | 10.00 | 19.02 | 42.50 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 181.00 | 3.00 | 3.03 | 2.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1,586.00 | 3.79 | 4.97 | 4.25 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 429.00 | 3.00 | 2.81 | 2.92 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 3,170.00 | 2.50 | 2.46 | 2.56 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 368.00 | 3.50 | 2.67 | 2.50 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 211.00 | 3.00 | 4.53 | 3.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 131.00 | 4.00 | 5.06 | 6.29 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1,788.00 | 2.00 | 2.59 | 4.02 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 250.00 | 3.50 | 5.70 | 4.00 |
| MC0504-065 | | US50B FROM MP 318 TO MP 359 | 12/01/11 | 50.00 | 2.25 | 3.68 | 3.05 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 4,506.00 | 6.00 | 2.19 | 2.40 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 74.00 | 2.00 | 2.61 | 2.40 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 10,977.00 | 3.95 | 2.45 | 2.83 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 78,987.00 | 2.87 | 2.46 | 2.42 |
| ========== | 202-01140 | Rem Gdrail Ty 4 | | Lin Foot | ========== | ========== | ========== |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 29,820.00 | 15.47 | 14.72 | 9.61 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 29,820.00 | 15.47 | 14.72 | 9.61 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 1,976.00 | 18.00 | 10.25 | 10.00 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 436.00 | 10.00 | 13.69 | 4.27 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2,412.00 | 16.55 | 12.49 | 11.11 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 61.00 | 6.00 | 24.96 | 8.50 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 788.00 | 12.00 | 14.61 | 19.00 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 14.00 | 20.00 | 151.08 | 152.00 |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 530.00 | 20.00 | 24.87 | 24.46 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 300.00 | 24.00 | 18.63 | 5.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-01140 | Rem Gdrail Ty 4 | | Lin Foot | ========== | ========== | ========== |
| MC0504-065 | | US50B FROM MP 318 TO MP 359 | 12/01/11 | 980.00 | 25.00 | 32.33 | 17.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2,673.00 | 19.60 | 22.77 | 18.24 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 34,905.00 | 15.86 | 14.99 | 10.38 |
| ========== | 202-01170 | Rem Gdrail Ty 7 | | Lin Foot | ========== | ========== | ========== |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 19,932.00 | 6.00 | 10.43 | 15.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 460.00 | 15.00 | 19.92 | 8.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 3,822.00 | 10.00 | 15.67 | 6.01 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 24,214.00 | 6.80 | 13.53 | 12.16 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 1,882.00 | 11.00 | 11.45 | 4.98 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 1,230.00 | 8.00 | 10.93 | 8.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 300.00 | 48.00 | 23.64 | 17.15 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 1,391.00 | 10.00 | 10.25 | 5.50 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 240.00 | 16.00 | 21.25 | 6.36 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 5,043.00 | 12.43 | 12.04 | 6.65 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 13.00 | 125.00 | 47.70 | 60.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 13.00 | 125.00 | 20.64 | 18.38 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 699.00 | 9.00 | 15.92 | 20.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 2,118.50 | 8.00 | 14.03 | 15.09 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2,817.50 | 8.25 | 14.35 | 16.31 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 32,087.50 | 7.86 | 13.30 | 11.34 |
| ========== | 202-01180 | Rem Median Barrier | | Lin Foot | ========== | ========== | ========== |
| ITS0703-370 | | EAST OF EJMT ON I-70 EB LANES | 06/16/11 | 267.50 | 27.00 | 9.35 | 10.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 267.50 | 27.00 | 9.35 | 10.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-01180 | Rem Median Barrier | | Lin Foot | | | |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 168.00 | 30.00 | 18.16 | 29.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 168.00 | 30.00 | 18.16 | 29.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 435.50 | 28.16 | 14.87 | 17.33 |
| ========== | 202-01200 | Rem Tensioned Cable Barrier | | Lin Foot | | | |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 1,175.00 | 2.00 | 2.29 | 3.17 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 653.00 | 2.00 | 2.80 | 2.61 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1,828.00 | 2.00 | 2.52 | 2.97 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,828.00 | 2.00 | 1.41 | 1.63 |
| ========== | 202-01300 | Rem End Anchorage | | Each | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 2.00 | 120.00 | 372.88 | 225.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 56.00 | 175.00 | 149.38 | 144.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 8.00 | 150.00 | 171.99 | 151.00 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 8.00 | 110.00 | 172.23 | 130.00 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 19.00 | 150.00 | 222.30 | 330.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 93.00 | 160.97 | 170.91 | 183.83 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 7.00 | 150.00 | 107.05 | 108.50 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 2.00 | 120.00 | 145.96 | 120.00 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 6.00 | 150.00 | 157.15 | 144.80 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 3.00 | 150.00 | 163.25 | 168.98 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 1.00 | 175.00 | 154.83 | 156.33 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 6.00 | 140.00 | 196.33 | 195.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 1.00 | 10.00 | 170.14 | 127.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 22.00 | 150.00 | 159.67 | 170.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 2.00 | 125.00 | 159.00 | 150.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-01300 | Rem End Anchorage | | Each | | | |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 6.00 | 200.00 | 220.41 | 301.88 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 110.00 | 110.00 | 184.88 | 280.00 |
| ITS0703-370 | | EAST OF EJMT ON I-70 EB LANES | 06/16/11 | 1.00 | 125.00 | 609.00 | 765.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 167.00 | 123.59 | 172.24 | 240.04 |
| C006A-051 | | US 6 (LOVELAND PASS), CLEAR C | 07/14/11 | 4.00 | 171.00 | 190.00 | 161.00 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 1.00 | 200.00 | 151.57 | 156.37 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 1.00 | 150.00 | 172.84 | 160.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 6.00 | 172.33 | 171.35 | 157.55 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 4.00 | 160.00 | 127.61 | 115.88 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 14.00 | 120.00 | 157.02 | 178.33 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 4.00 | 112.00 | 168.43 | 180.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1.00 | 300.00 | 292.42 | 145.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 2.00 | 150.00 | 144.41 | 143.39 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 11.00 | 160.00 | 633.28 | 562.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 6.00 | 135.00 | 164.18 | 160.00 |
| MC0504-065 | | US50B FROM MP 318 TO MP 359 | 12/01/11 | 1.00 | 250.00 | 224.67 | 200.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 10.00 | 250.00 | 187.68 | 160.00 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 16.00 | 110.00 | 167.33 | 157.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 69.00 | 151.42 | 198.32 | 225.59 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 335.00 | 140.57 | 176.98 | 220.34 |
| ========== | 202-01400 | Removal of Cattle Guard | | Each | | | |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 2.00 | 1000.00 | 3024.67 | 2550.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2.00 | 1000.00 | 2495.20 | 2108.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 1000.00 | 2495.20 | 2108.00 |
| ========== | 202-04000 | Plug Structure | | Each | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 2.00 | 150.00 | 432.90 | 379.94 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2.00 | 150.00 | 432.90 | 379.94 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-04000 | Plug Structure | | Each | | | |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 16.00 | 500.00 | 409.10 | 500.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 16.00 | 500.00 | 409.10 | 500.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 18.00 | 461.11 | 412.21 | 486.66 |
| ========== | 202-04001 | Plug Culvert | | Each | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 1.00 | 900.00 | 480.65 | 265.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 12.00 | 800.00 | 1054.62 | 750.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 1.00 | 1500.00 | 2036.94 | 5200.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 6.00 | 3000.00 | 1283.57 | 665.88 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 20.00 | 1500.00 | 1217.57 | 1064.57 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 2.00 | 3000.00 | 12915.18 | 12315.36 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 2.00 | 200.00 | 367.47 | 379.94 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 4.00 | 1600.00 | 3504.40 | 6347.65 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 2.00 | 1000.00 | 3679.81 | 3755.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 2.00 | 1000.00 | 3679.81 | 3755.00 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 4.00 | 850.00 | 2253.67 | 1297.46 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 15.00 | 400.00 | 968.86 | 660.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 2.00 | 800.00 | 1835.56 | 1262.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 21.00 | 523.81 | 1223.40 | 838.75 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 47.00 | 1051.06 | 1521.02 | 1637.49 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-04002 | Clean Culvert | | Each | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 3.00 | 1800.00 | 6128.34 | 7000.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 3.00 | 1800.00 | 1924.80 | 2563.64 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 20.00 | 1100.00 | 804.02 | 1280.00 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 6.00 | 1800.00 | 1850.00 | 1200.00 |
| C0241-055 | | SH 24 MP 148-152 | 05/26/11 | 2.00 | 3000.00 | 12335.97 | 10500.00 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 3.00 | 3500.00 | 1694.56 | 1904.11 |
| FSA 0502-064 | | US 50 EAST OF SARGENTS | 06/23/11 | 1.00 | 2000.00 | 11630.94 | 4777.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 32.00 | 1603.13 | 1861.70 | 2103.41 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 2.00 | 2100.00 | 1758.75 | 1619.26 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 4.00 | 1500.00 | 1266.93 | 1370.00 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 4.00 | 1500.00 | 2087.50 | 1350.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 1.00 | 1500.00 | 2574.00 | 2700.00 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 2.00 | 1500.00 | 3061.67 | 2875.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 13.00 | 1592.31 | 1757.04 | 1789.73 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 4.00 | 5000.00 | 1863.96 | 926.43 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 4.00 | 1500.00 | 2927.50 | 4500.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 3.00 | 1200.00 | 1659.76 | 2600.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 11.00 | 2690.91 | 2225.89 | 2682.34 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 59.00 | 1813.56 | 1879.66 | 2082.84 |
| ========== | 202-04003 | Clean Culvert (Spec) | | Each | | | |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 3.00 | 1000.00 | 903.02 | 1020.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 3.00 | 1000.00 | 903.02 | 1020.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3.00 | 1000.00 | 903.02 | 1020.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-04004 | Plug Culvert (Spec) | | Each | | | |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 2.00 | 4000.00 | 4540.26 | 4000.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2.00 | 4000.00 | 4540.26 | 4000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 4000.00 | 4540.26 | 4000.00 |
| ========== | 202-04005 | Clean Valve Box | | Each | | | |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 46.00 | 150.00 | 109.16 | 120.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 46.00 | 150.00 | 109.16 | 120.00 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 8.00 | 150.00 | 196.63 | 200.00 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 4.00 | 150.00 | 190.49 | 275.00 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 29.00 | 150.00 | 112.26 | 117.52 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 41.00 | 150.00 | 132.06 | 136.43 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 87.00 | 150.00 | 121.66 | 129.62 |
| ========== | 202-04010 | Clean Inlet | | Each | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 1.00 | 750.00 | 2021.24 | 1700.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1.00 | 750.00 | 691.56 | 637.50 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 2.00 | 1000.00 | 3332.50 | 1165.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 1000.00 | 3332.50 | 1165.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3.00 | 916.67 | 883.63 | 769.38 |
| ========== | 202-04100 | Abandon Well | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 32.00 | 1250.00 | 1068.37 | 685.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-04100 | Abandon Well | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 32.00 | 1250.00 | 1096.17 | 858.89 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 32.00 | 1250.00 | 1096.17 | 858.89 |
| ========== | 202-05006 | Sawing Concrete (6 In) | | Lin Foot | | | |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 407.00 | 3.00 | 5.00 | 7.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 407.00 | 3.00 | 5.00 | 7.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 407.00 | 3.00 | 5.00 | 7.00 |
| ========== | 202-05026 | Sawing Asphalt Mat (6 In) | | Lin Foot | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 1,329.00 | 1.00 | 1.25 | 2.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1,329.00 | 1.00 | 1.25 | 2.00 |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 88.00 | 5.00 | 4.71 | 1.30 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 579.00 | 3.00 | 2.89 | 1.00 |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 355.00 | 3.00 | 5.00 | 7.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1,022.00 | 3.17 | 2.81 | 2.39 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,351.00 | 1.94 | 2.22 | 2.23 |
| ========== | 202-05030 | Sawing Asphalt Mat (10 In) | | Lin Foot | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 43,500.00 | 1.50 | 1.68 | 2.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 43,500.00 | 1.50 | 1.68 | 2.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 530.00 | 5.00 | 4.10 | 5.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 530.00 | 5.00 | 4.94 | 4.63 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 44,030.00 | 1.54 | 1.73 | 2.04 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 202-05100 | Sandblasting Reinf Steel | | Sq Yard | | | |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 125.00 | 20.00 | 34.00 | 37.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 125.00 | 20.00 | 16.91 | 17.22 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 125.00 | 20.00 | 16.91 | 17.22 |
| ========== | 202-05150 | Sandblasting | | Sq Foot | | | |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 4,034.00 | 1.00 | 0.93 | 1.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 4,388.00 | 1.50 | 2.94 | 2.05 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 20,000.00 | 0.75 | 0.61 | 0.91 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 28,422.00 | 0.90 | 0.91 | 1.10 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 20,000.00 | 0.45 | 0.83 | 0.85 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 1,329.00 | 2.20 | 2.70 | 2.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 21,329.00 | 0.56 | 0.95 | 0.92 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1,716.00 | 1.50 | 0.63 | 0.13 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1,716.00 | 1.50 | 0.63 | 0.13 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 51,467.00 | 0.78 | 0.85 | 0.86 |
| ========== | 202-05300 | Rem and Disposal of Paint | | LUMP SUM | | | |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 1.00 | 250000.00 | 308729.97 | 170800.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1.00 | 250000.00 | 308729.97 | 170800.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 250000.00 | 308729.97 | 170800.00 |
| ========== | 203-00000 | Uncl Excav | | Cubic Yard | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 115.00 | 24.27 | 13.16 | 12.75 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 115.00 | 24.27 | 13.16 | 12.75 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 203-00000 | Uncl Excav | | Cubic Yard | | | |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 38.00 | 30.00 | 52.35 | 27.76 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 60.00 | 30.00 | 34.87 | 32.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 27,948.00 | 15.00 | 11.07 | 11.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 86,470.00 | 7.00 | 6.75 | 5.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 114,516.00 | 8.97 | 7.75 | 6.11 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 10.00 | 17.00 | 60.21 | 118.75 |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 340.00 | 15.00 | 28.25 | 21.50 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 350.00 | 15.06 | 30.44 | 24.28 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 114,981.00 | 9.01 | 7.78 | 6.15 |
| ========== | 203-00010 | Uncl Excav (CIP) | | Cubic Yard | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 4,182.00 | 15.00 | 18.15 | 7.70 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 591,404.00 | 6.00 | 7.62 | 5.50 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 20,777.00 | 15.00 | 9.73 | 7.44 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 616,363.00 | 6.36 | 8.06 | 5.92 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 10,645.00 | 8.00 | 15.50 | 3.50 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 1,488.00 | 11.00 | 36.56 | 43.50 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 2,729.00 | 11.00 | 21.83 | 11.30 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 6,321.00 | 10.00 | 11.37 | 11.00 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 4,453.00 | 11.00 | 15.45 | 13.00 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 321.00 | 25.00 | 27.13 | 27.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 121,499.00 | 12.00 | 10.74 | 8.25 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 1,201.00 | 17.00 | 25.75 | 31.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 148,657.00 | 11.64 | 11.17 | 9.06 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 455.00 | 20.00 | 52.78 | 43.90 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 203-00010 | Uncl Excav (CIP) | | Cubic Yard | | | |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 2,000.00 | 20.00 | 17.67 | 15.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 2,455.00 | 20.00 | 11.48 | 9.03 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 4,261.00 | 6.00 | 10.01 | 7.32 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 304,987.00 | 6.50 | 5.43 | 4.53 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 167,641.00 | 7.00 | 8.41 | 7.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 41,200.00 | 12.00 | 11.37 | 9.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 5,786.00 | 25.00 | 20.77 | 16.50 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 523,875.00 | 7.29 | 7.20 | 5.83 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,291,350.00 | 7.37 | 8.38 | 6.59 |
| ========== | 203-00040 | Uncl Excav (Spec) | | Cubic Yard | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 3,307.00 | 20.00 | 18.58 | 8.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 3,307.00 | 20.00 | 18.58 | 8.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 475.00 | 30.00 | 24.46 | 16.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 475.00 | 30.00 | 24.46 | 16.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3,782.00 | 21.26 | 19.32 | 9.00 |
| ========== | 203-00060 | Emb Matl (CIP) | | Cubic Yard | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 1,414.00 | 25.00 | 18.87 | 14.75 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 90,823.00 | 4.00 | 7.95 | 6.50 |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 140.00 | 30.00 | 31.13 | 20.40 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 2,985.00 | 15.00 | 24.67 | 16.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 95,362.00 | 4.69 | 8.95 | 7.80 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 2.00 | 100.00 | 311.80 | 357.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 203-00060 | Emb Matl (CIP) | | Cubic Yard | | | |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 3.00 | 100.00 | 160.48 | 112.50 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 28,644.00 | 9.00 | 8.62 | 9.40 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 3,003.00 | 18.00 | 9.22 | 15.00 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 122.00 | 20.00 | 21.75 | 22.00 |
| C0241-055 | | SH 24 MP 148-152 | 05/26/11 | 74.00 | 35.00 | 153.32 | 73.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 12,725.00 | 18.00 | 26.50 | 17.75 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 54,448.00 | 6.00 | 11.34 | 6.50 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 34,398.00 | 7.00 | 14.25 | 11.00 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 5,819.00 | 18.00 | 18.12 | 17.85 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 2,242.00 | 22.00 | 23.42 | 20.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 182,304.00 | 8.00 | 7.20 | 4.83 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 323,784.00 | 8.42 | 9.89 | 7.25 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 1,893.00 | 15.00 | 18.56 | 15.00 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 123.00 | 25.00 | 32.77 | 28.07 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 8,545.00 | 15.00 | 11.24 | 10.75 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 31,875.00 | 8.00 | 7.80 | 7.80 |
| C0091-038 | | SH 9 MM 81.9 BLUE RIVER EMERG | 08/24/11 | 80.00 | 100.00 | 70.30 | 41.38 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 8,080.00 | 16.00 | 28.96 | 21.00 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 89,235.00 | 9.00 | 8.55 | 4.50 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 50.00 | 20.00 | 43.67 | 40.00 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 198.00 | 33.00 | 30.59 | 20.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 140,079.00 | 9.73 | 10.06 | 7.70 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 162.00 | 25.00 | 16.61 | 23.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 5,732.00 | 15.00 | 11.93 | 8.55 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 16,706.00 | 8.00 | 11.70 | 12.07 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 7,442.00 | 20.00 | 15.87 | 14.00 |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 4,410.00 | 15.00 | 15.73 | 17.50 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 298,661.00 | 11.00 | 9.15 | 5.55 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 630.00 | 25.00 | 30.00 | 33.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 333,743.00 | 11.21 | 9.42 | 6.33 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 892,968.00 | 9.27 | 9.59 | 7.11 |
| ========== | 203-00061 | Emb Matl (CIP) | | Ton | | | |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 323.00 | 30.00 | 22.75 | 7.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 323.00 | 30.00 | 22.75 | 7.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 323.00 | 30.00 | 22.75 | 7.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 203-00062 | Emb Matl (CIP) (Spec) | | Cubic Yard | | | |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 6,300.00 | 7.00 | 10.76 | 10.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 12,095.00 | 15.00 | 13.90 | 10.41 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 18,395.00 | 12.26 | 12.74 | 10.27 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 65,630.00 | 10.00 | 8.67 | 5.59 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 65,630.00 | 10.00 | 8.67 | 5.59 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 11,700.00 | 34.00 | 34.57 | 20.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 11,700.00 | 34.00 | 33.16 | 20.15 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 49,239.00 | 12.00 | 12.40 | 8.38 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 59,251.00 | 8.00 | 14.50 | 14.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 108,490.00 | 9.82 | 13.72 | 11.45 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 204,215.00 | 11.48 | 13.02 | 10.06 |
| ========== | 203-00100 | Muck Excav | | Cubic Yard | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 50.00 | 20.00 | 41.75 | 34.75 |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 200.00 | 15.00 | 44.30 | 40.00 |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 100.00 | 25.00 | 19.85 | 15.75 |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 500.00 | 25.00 | 46.98 | 7.50 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 500.00 | 18.00 | 20.15 | 10.18 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1,350.00 | 20.74 | 25.61 | 12.23 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 1,000.00 | 15.00 | 14.98 | 6.31 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 200.00 | 15.00 | 19.69 | 12.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 203-00100 | Muck Excav | | Cubic Yard | | | |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 500.00 | 30.00 | 23.59 | 16.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 3,378.00 | 15.00 | 11.56 | 9.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 100.00 | 20.00 | 15.94 | 15.00 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 5.00 | 50.00 | 72.97 | 55.93 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 100.00 | 18.00 | 18.22 | 12.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 8.00 | 30.00 | 58.67 | 53.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1,000.00 | 20.00 | 17.69 | 20.32 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 6,291.00 | 17.16 | 14.21 | 12.27 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 44.00 | 40.00 | 43.39 | 50.00 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 100.00 | 45.00 | 46.74 | 39.45 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 1,000.00 | 10.00 | 13.82 | 8.20 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 2,000.00 | 12.00 | 9.32 | 9.00 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 2,420.00 | 35.00 | 18.46 | 22.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 27.00 | 50.00 | 43.30 | 65.00 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 9,000.00 | 8.00 | 9.88 | 13.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 14,591.00 | 13.59 | 11.19 | 14.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 2,000.00 | 15.00 | 11.51 | 8.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 1,000.00 | 10.00 | 15.71 | 12.66 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1,000.00 | 15.00 | 15.08 | 20.12 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 500.00 | 30.00 | 13.71 | 18.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 100.00 | 20.00 | 23.09 | 16.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 4,600.00 | 15.65 | 13.85 | 12.91 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 26,832.00 | 15.14 | 13.20 | 13.23 |
| ========== | 203-00400 | Rock Excav | | Cubic Yard | | | |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 13,775.00 | 12.00 | 19.76 | 11.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 13,775.00 | 12.00 | 19.76 | 11.00 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 2,785.00 | 25.00 | 22.30 | 16.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 2,785.00 | 25.00 | 22.44 | 16.27 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 203-00400 | Rock Excav | | Cubic Yard | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 240.00 | 75.00 | 42.07 | 20.00 |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 45.00 | 150.00 | 236.50 | 123.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 285.00 | 86.84 | 51.96 | 36.26 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 16,845.00 | 15.42 | 20.52 | 12.34 |
| ========== | 203-00500 | Rock Fill | | Cubic Yard | | | |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 2,420.00 | 25.00 | 49.44 | 44.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 2,420.00 | 25.00 | 49.44 | 44.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,420.00 | 25.00 | 49.44 | 44.00 |
| ========== | 203-00710 | Clay Plating (CIP) | | Cubic Yard | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 4,760.00 | 28.00 | 22.69 | 28.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 4,760.00 | 28.00 | 22.69 | 28.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 326.00 | 10.00 | 29.36 | 31.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 326.00 | 10.00 | 29.36 | 31.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 5,086.00 | 26.85 | 23.86 | 28.65 |
| ========== | 203-00910 | Contam Soil Excav & Disposal (Off-Site) | | Cubic Yard | | | |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 100.00 | 60.00 | 80.95 | 150.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 100.00 | 60.00 | 80.95 | 150.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 100.00 | 60.00 | 80.95 | 150.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 203-01100 | Proof Rolling | | Hour | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 10.00 | 100.00 | 104.80 | 95.00 |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 32.00 | 125.00 | 88.16 | 78.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 42.00 | 119.05 | 91.60 | 82.05 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 400.00 | 98.00 | 79.24 | 76.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 30.00 | 90.00 | 111.06 | 102.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 80.00 | 90.00 | 130.67 | 90.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 25.00 | 100.00 | 93.19 | 81.27 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 535.00 | 96.45 | 87.35 | 81.34 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 20.00 | 100.00 | 111.08 | 140.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 16.00 | 100.00 | 86.16 | 85.00 |
| STR096A-040 | | SH 96 MP 193 TO MP 201 | 09/01/11 | 50.00 | 80.00 | 85.04 | 87.12 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 90.00 | 110.00 | 96.78 | 85.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 176.00 | 99.43 | 96.51 | 91.85 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 10.00 | 125.00 | 140.43 | 88.69 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 40.00 | 100.00 | 96.49 | 73.44 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 40.00 | 120.00 | 104.00 | 130.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 25.00 | 80.00 | 112.66 | 120.00 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 20.00 | 120.00 | 100.65 | 93.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 135.00 | 107.04 | 107.08 | 102.85 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 888.00 | 99.72 | 92.14 | 86.33 |
| ========== | 203-01140 | Rolling | | Hour | | | |
| NH 2852-017 | | US 285 PONCHA PASS SOUTH RESU | 03/03/11 | 30.00 | 90.00 | 98.29 | 70.00 |
| NH 0241-056 | | US 24 BUENA VISTA NORTH | 03/03/11 | 30.00 | 100.00 | 87.42 | 110.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 60.00 | 95.00 | 92.85 | 90.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 203-01140 | Rolling | | Hour | | | |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 10.00 | 100.00 | 98.62 | 108.11 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 20.00 | 125.00 | 101.00 | 159.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 50.00 | 110.00 | 123.67 | 90.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 80.00 | 112.50 | 109.49 | 104.73 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 5.00 | 110.00 | 129.36 | 85.00 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 30.00 | 120.00 | 95.20 | 97.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 35.00 | 118.57 | 102.91 | 95.29 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 20.00 | 115.00 | 80.52 | 87.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 20.00 | 115.00 | 80.52 | 87.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 195.00 | 108.46 | 101.36 | 98.05 |
| ========== | 203-01500 | Blading | | Hour | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 20.00 | 110.00 | 124.00 | 95.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 960.00 | 125.00 | 129.62 | 100.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 40.00 | 135.00 | 140.55 | 175.00 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 50.00 | 100.00 | 136.71 | 110.00 |
| NH 2852-017 | | US 285 PONCHA PASS SOUTH RESU | 03/03/11 | 30.00 | 100.00 | 113.67 | 70.00 |
| NH 0241-056 | | US 24 BUENA VISTA NORTH | 03/03/11 | 30.00 | 120.00 | 99.90 | 130.00 |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 18.00 | 120.00 | 135.16 | 120.00 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 10.00 | 120.00 | 118.15 | 108.00 |
| NH 0402-079 | | US40 MP 165.0 - 179.0 GRAND C | 03/31/11 | 40.00 | 120.00 | 117.29 | 100.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 1,198.00 | 123.01 | 127.34 | 104.92 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 25.00 | 125.00 | 118.48 | 140.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 203-01500 | Blading | | Hour | | | |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 150.00 | 120.00 | 107.50 | 89.50 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 20.00 | 100.00 | 150.00 | 127.00 |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 30.00 | 120.00 | 126.76 | 125.65 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 45.00 | 110.00 | 147.38 | 139.50 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 160.00 | 110.00 | 107.51 | 118.10 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 240.00 | 98.00 | 109.65 | 93.00 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 40.00 | 130.00 | 114.46 | 120.00 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 32.00 | 100.00 | 128.67 | 151.00 |
| C0241-055 | | SH 24 MP 148-152 | 05/26/11 | 10.00 | 150.00 | 166.18 | 135.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 40.00 | 120.00 | 135.36 | 155.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 70.00 | 160.00 | 119.14 | 127.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 120.00 | 110.00 | 111.68 | 93.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 50.00 | 120.00 | 164.33 | 120.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 20.00 | 120.00 | 124.18 | 100.20 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 130.00 | 120.00 | 139.18 | 140.00 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 45.00 | 125.00 | 143.75 | 130.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 10.00 | 100.00 | 141.50 | 115.00 |
| FSA 0502-064 | | US 50 EAST OF SARGENTS | 06/23/11 | 10.00 | 180.00 | 156.89 | 150.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 400.00 | 120.00 | 103.04 | 86.35 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 1,647.00 | 116.77 | 115.06 | 110.28 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 5.00 | 115.00 | 139.54 | 118.00 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 6.00 | 105.00 | 139.91 | 123.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 80.00 | 120.00 | 123.38 | 180.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 120.00 | 105.00 | 112.69 | 140.00 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 30.00 | 130.00 | 115.41 | 120.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 10.00 | 125.00 | 159.40 | 185.00 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 10.00 | 150.00 | 162.03 | 100.00 |
| STR096A-040 | | SH 96 MP 193 TO MP 201 | 09/01/11 | 50.00 | 110.00 | 92.20 | 86.59 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 215.00 | 120.00 | 115.11 | 85.00 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 20.00 | 150.00 | 138.33 | 165.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 546.00 | 117.87 | 127.69 | 119.97 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 120.00 | 115.00 | 121.94 | 152.50 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 100.00 | 125.00 | 129.00 | 120.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 60.00 | 100.00 | 112.05 | 115.93 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 20.00 | 130.00 | 118.00 | 116.00 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 20.00 | 130.00 | 99.88 | 110.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 20.00 | 100.00 | 120.06 | 120.00 |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 60.00 | 130.00 | 116.90 | 105.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 203-01500 | Blading | | Hour | | | |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 40.00 | 110.00 | 123.67 | 119.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 440.00 | 117.50 | 120.79 | 125.54 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3,831.00 | 118.96 | 120.53 | 113.01 |
| ========== | 203-01510 | Backhoe | | Hour | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 960.00 | 125.00 | 130.64 | 80.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 300.00 | 125.00 | 122.87 | 92.26 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1,260.00 | 125.00 | 126.55 | 86.81 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 20.00 | 110.00 | 90.10 | 87.52 |
| C0241-055 | | SH 24 MP 148-152 | 05/26/11 | 10.00 | 150.00 | 131.82 | 95.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 25.00 | 120.00 | 104.92 | 110.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 70.00 | 160.00 | 109.57 | 134.00 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 10.00 | 200.00 | 116.54 | 148.07 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 60.00 | 110.00 | 116.52 | 150.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 20.00 | 100.00 | 108.94 | 115.24 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 130.00 | 130.00 | 127.98 | 127.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 400.00 | 120.00 | 107.38 | 86.35 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 745.00 | 125.37 | 110.53 | 106.30 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 32.00 | 120.00 | 105.09 | 130.28 |
| NH0403-053 | | US 40 RETAINING WALL REPAIR | 07/28/11 | 10.00 | 100.00 | 125.24 | 105.73 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 75.00 | 100.00 | 104.09 | 120.00 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 90.00 | 130.00 | 128.00 | 90.00 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 10.00 | 150.00 | 86.67 | 85.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 217.00 | 117.70 | 113.30 | 97.71 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 160.00 | 100.00 | 112.82 | 90.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 203-01510 | Backhoe | | Hour | | | |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 110.00 | 110.00 | 115.08 | 104.61 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 300.00 | 120.00 | 126.19 | 100.61 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 40.00 | 120.00 | 129.70 | 150.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 610.00 | 112.95 | 121.86 | 101.79 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,832.00 | 121.94 | 118.66 | 99.29 |
| ========== | 203-01550 | Dozing | | Hour | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 20.00 | 175.00 | 132.60 | 135.00 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 10.00 | 130.00 | 151.18 | 120.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 30.00 | 160.00 | 139.57 | 130.00 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 160.00 | 125.00 | 108.45 | 139.10 |
| C0241-055 | | SH 24 MP 148-152 | 05/26/11 | 10.00 | 160.00 | 175.07 | 200.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 50.00 | 150.00 | 138.71 | 128.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 110.00 | 110.00 | 139.37 | 110.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 20.00 | 125.00 | 149.82 | 120.26 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 400.00 | 150.00 | 123.53 | 101.59 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 750.00 | 138.27 | 125.14 | 113.51 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 30.00 | 140.00 | 150.41 | 250.00 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 125.00 | 130.00 | 142.44 | 190.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 155.00 | 131.94 | 144.12 | 184.46 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 50.00 | 110.00 | 142.11 | 143.53 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 50.00 | 140.00 | 138.86 | 130.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 160.00 | 120.00 | 136.51 | 165.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 90.00 | 110.00 | 123.71 | 136.14 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 20.00 | 170.00 | 161.56 | 250.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 370.00 | 121.62 | 134.74 | 154.94 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,305.00 | 133.30 | 130.64 | 134.56 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 203-01565 | Hydraulic Excavator | | Hour | | | |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 25.00 | 150.00 | 158.73 | 178.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 60.00 | 150.00 | 202.33 | 140.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 85.00 | 150.00 | 175.70 | 157.96 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 20.00 | 150.00 | 143.33 | 155.00 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 20.00 | 150.00 | 140.84 | 105.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 40.00 | 150.00 | 141.78 | 130.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 125.00 | 150.00 | 166.95 | 150.25 |
| ========== | 203-01582 | Truck (Dump) | | Hour | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 24.00 | 100.00 | 95.43 | 95.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 24.00 | 100.00 | 93.35 | 92.06 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 32.00 | 100.00 | 105.00 | 111.00 |
| C0241-055 | | SH 24 MP 148-152 | 05/26/11 | 10.00 | 120.00 | 101.79 | 92.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 20.00 | 110.00 | 88.93 | 84.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 62.00 | 106.45 | 96.18 | 99.23 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 10.00 | 90.00 | 90.07 | 97.00 |
| NH5502-070 | | US 550 4 MILES SOUTH OF OURAY | 08/18/11 | 100.00 | 115.00 | 126.45 | 130.00 |
| C0091-038 | | SH 9 MM 81.9 BLUE RIVER EMERG | 08/24/11 | 40.00 | 65.00 | 102.04 | 84.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 150.00 | 100.00 | 114.27 | 115.53 |
| SHE0402-081 | | US 40 - MP 113 TO 120 ROUTT C | 10/27/11 | 40.00 | 100.00 | 120.57 | 88.40 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 20.00 | 125.00 | 88.00 | 96.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 203-01582 | Truck (Dump) | | Hour | | | |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 20.00 | 90.00 | 93.00 | 98.00 |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 10.00 | 115.00 | 118.00 | 136.00 |
| IM0703-368 | | GEORGETOWN HILL CHUTES 6,7,9, | 12/01/11 | 50.00 | 107.45 | 105.07 | 120.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 140.00 | 105.88 | 109.46 | 105.54 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 376.00 | 103.25 | 106.94 | 107.22 |
| ========== | 203-01590 | Front End Loader (Rubber) | | Hour | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 10.00 | 140.00 | 123.15 | 110.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 10.00 | 140.00 | 112.99 | 79.12 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 20.00 | 130.00 | 103.71 | 131.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 20.00 | 130.00 | 103.71 | 131.00 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 5.00 | 120.00 | 106.23 | 90.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 75.00 | 110.00 | 99.85 | 140.00 |
| NH5502-070 | | US 550 4 MILES SOUTH OF OURAY | 08/18/11 | 100.00 | 125.00 | 141.79 | 165.00 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 10.00 | 150.00 | 114.30 | 105.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 190.00 | 120.26 | 118.19 | 131.03 |
| SHE0402-081 | | US 40 - MP 113 TO 120 ROUTT C | 10/27/11 | 60.00 | 125.00 | 134.07 | 94.39 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 20.00 | 100.00 | 104.18 | 118.00 |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 40.00 | 125.00 | 148.00 | 156.00 |
| IM0703-368 | | GEORGETOWN HILL CHUTES 6,7,9, | 12/01/11 | 40.00 | 108.10 | 116.53 | 140.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 160.00 | 117.65 | 128.78 | 124.15 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 380.00 | 120.19 | 119.59 | 121.10 |
| ========== | 203-01591 | Front End Loader (Crawler) | | Hour | | | |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 100.00 | 125.00 | 131.68 | 140.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 100.00 | 125.00 | 131.68 | 140.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 203-01591 | Front End Loader (Crawler) | | Hour | | | |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 100.00 | 125.00 | 123.53 | 128.24 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 100.00 | 125.00 | 123.53 | 128.24 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 200.00 | 125.00 | 127.33 | 134.12 |
| ========== | 203-01594 | Combination Loader | | Hour | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 300.00 | 125.00 | 99.15 | 92.26 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 300.00 | 125.00 | 98.91 | 92.19 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 40.00 | 110.00 | 106.65 | 85.00 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 32.00 | 100.00 | 117.67 | 100.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 25.00 | 150.00 | 122.44 | 127.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 50.00 | 110.00 | 97.00 | 131.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 50.00 | 100.00 | 113.67 | 75.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 20.00 | 110.00 | 112.92 | 90.17 |
| FSA 0502-064 | | US 50 EAST OF SARGENTS | 06/23/11 | 10.00 | 90.00 | 124.74 | 105.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 400.00 | 200.00 | 89.51 | 81.27 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 627.00 | 167.38 | 95.60 | 91.43 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 5.00 | 80.00 | 85.77 | 70.00 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 30.00 | 105.00 | 97.91 | 85.00 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 90.00 | 130.00 | 86.89 | 112.00 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 10.00 | 140.00 | 92.22 | 105.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 135.00 | 123.33 | 88.25 | 101.92 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 120.00 | 80.00 | 80.88 | 69.55 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 50.00 | 100.00 | 101.64 | 135.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 400.00 | 100.00 | 89.42 | 100.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 203-01594 | Combination Loader | | Hour | | | |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 110.00 | 125.00 | 90.10 | 87.78 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 300.00 | 110.00 | 108.87 | 100.61 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 20.00 | 125.00 | 88.50 | 77.00 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 20.00 | 110.00 | 80.64 | 75.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 40.00 | 120.00 | 87.45 | 76.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 1,060.00 | 104.58 | 96.17 | 95.30 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,122.00 | 127.21 | 95.85 | 94.09 |
| ========== | 203-01597 | Potholing | | Hour | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 20.00 | 120.00 | 172.60 | 100.00 |
| C0704-225 | | I-70 EAST OF BENNETT | 01/06/11 | 10.00 | 150.00 | 145.25 | 84.00 |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 10.00 | 175.00 | 173.04 | 160.00 |
| ITS4701-121 | | C470 (SANTA FE TO I-25) AND R | 01/20/11 | 300.00 | 90.00 | 122.25 | 80.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 800.00 | 180.00 | 227.77 | 250.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 10.00 | 210.00 | 169.63 | 200.00 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 40.00 | 180.00 | 171.58 | 200.00 |
| NH 2852-017 | | US 285 PONCHA PASS SOUTH RESU | 03/03/11 | 8.00 | 200.00 | 162.33 | 150.00 |
| NH 0241-056 | | US 24 BUENA VISTA NORTH | 03/03/11 | 10.00 | 250.00 | 120.08 | 162.00 |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 10.00 | 200.00 | 183.20 | 140.00 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 40.00 | 200.00 | 201.32 | 155.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 300.00 | 180.00 | 207.01 | 252.50 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 1,558.00 | 163.06 | 192.25 | 185.22 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 10.00 | 180.00 | 151.00 | 150.00 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 30.00 | 180.00 | 168.16 | 165.00 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 10.00 | 150.00 | 198.00 | 116.00 |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 20.00 | 200.00 | 168.60 | 150.75 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 24.00 | 175.00 | 208.06 | 164.50 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 40.00 | 180.00 | 186.27 | 250.60 |
| SHE074A-001 | | SH 74 - EVERGREEN - JEFFERSON | 04/28/11 | 20.00 | 175.00 | 161.67 | 110.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 200.00 | 200.00 | 165.35 | 140.00 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 30.00 | 180.00 | 226.88 | 151.00 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 20.00 | 180.00 | 168.61 | 180.00 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 40.00 | 250.00 | 217.50 | 210.00 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 20.00 | 180.00 | 145.54 | 177.89 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 20.00 | 150.00 | 248.00 | 264.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 203-01597 | Potholing | | Hour | | | |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 16.00 | 110.00 | 248.16 | 170.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 20.00 | 250.00 | 173.13 | 225.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 150.00 | 180.00 | 170.05 | 170.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 150.00 | 200.00 | 166.67 | 150.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 140.00 | 180.00 | 188.73 | 127.91 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 20.00 | 200.00 | 107.75 | 145.00 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 40.00 | 190.00 | 203.25 | 150.00 |
| ITS0703-370 | | EAST OF EJMT ON I-70 EB LANES | 06/16/11 | 50.00 | 170.00 | 173.00 | 245.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 16.00 | 200.00 | 227.17 | 215.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 100.00 | 300.00 | 197.82 | 165.94 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 300.00 | 150.00 | 83.75 | 115.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1,486.00 | 188.73 | 176.76 | 157.06 |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 10.00 | 200.00 | 210.59 | 180.00 |
| C006A-051 | | US 6 (LOVELAND PASS), CLEAR C | 07/14/11 | 20.00 | 172.60 | 213.00 | 242.00 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 10.00 | 150.00 | 178.64 | 200.00 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 10.00 | 200.00 | 178.90 | 175.00 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 20.00 | 175.00 | 237.00 | 141.00 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 100.00 | 200.00 | 152.76 | 142.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 150.00 | 180.00 | 193.46 | 190.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 62.00 | 200.00 | 248.08 | 305.00 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 50.00 | 100.00 | 255.45 | 250.00 |
| STR096A-040 | | SH 96 MP 193 TO MP 201 | 09/01/11 | 25.00 | 180.00 | 128.77 | 171.32 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 25.00 | 130.00 | 178.89 | 113.00 |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 8.00 | 175.00 | 245.00 | 240.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 490.00 | 175.51 | 197.02 | 188.54 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 50.00 | 150.00 | 210.63 | 190.61 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 50.00 | 185.00 | 163.26 | 130.28 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 200.00 | 180.00 | 211.57 | 240.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 20.00 | 180.00 | 189.22 | 180.00 |
| SHE025A-013 | | I 25 BETWEEN MP 122 AND MP 12 | 11/03/11 | 40.00 | 182.00 | 216.95 | 135.00 |
| ITSSW00-928 | | NB I-225 AT MM 2.28 | 11/03/11 | 40.00 | 180.00 | 122.37 | 120.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 100.00 | 180.00 | 196.92 | 261.83 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 160.00 | 180.00 | 198.42 | 147.44 |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 100.00 | 150.00 | 185.94 | 188.76 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 16.00 | 300.00 | 252.17 | 340.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 30.00 | 150.00 | 184.26 | 320.00 |
| C2854-125 | | US 285, ASPEN PARK TO MORRISO | 12/08/11 | 10.00 | 200.00 | 172.67 | 225.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 40.00 | 150.00 | 193.98 | 210.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 203-01597 | Potholing | | Hour | | | |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 25.00 | 110.00 | 218.67 | 275.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 881.00 | 173.30 | 197.44 | 203.25 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4,415.00 | 175.13 | 189.04 | 178.34 |
| ========== | 203-01620 | Sweeping | | Hour | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 960.00 | 135.00 | 170.83 | 300.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 960.00 | 135.00 | 170.83 | 300.00 |
| ITS0703-370 | | EAST OF EJMT ON I-70 EB LANES | 06/16/11 | 5.00 | 144.00 | 196.00 | 300.00 |
| FSA 0502-064 | | US 50 EAST OF SARGENTS | 06/23/11 | 20.00 | 120.00 | 128.27 | 102.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 25.00 | 124.80 | 135.91 | 107.20 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 985.00 | 134.74 | 162.14 | 254.10 |
| ========== | 203-01622 | Sweeping (With Pickup Broom) | | Hour | | | |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 25.00 | 135.00 | 140.59 | 130.00 |
| ITS4701-121 | | C470 (SANTA FE TO I-25) AND R | 01/20/11 | 20.00 | 130.00 | 128.50 | 160.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 400.00 | 150.00 | 164.17 | 165.03 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 445.00 | 148.26 | 162.31 | 162.84 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 40.00 | 135.00 | 138.47 | 50.00 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 300.00 | 135.00 | 140.77 | 158.42 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 120.00 | 150.00 | 173.62 | 170.00 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 40.00 | 80.00 | 155.50 | 240.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 40.00 | 175.00 | 146.43 | 166.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 75.00 | 135.00 | 148.90 | 170.00 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 120.00 | 150.00 | 109.75 | 89.25 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 20.00 | 140.00 | 183.50 | 157.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 755.00 | 139.11 | 145.22 | 149.36 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 203-01622 | Sweeping (With Pickup Broom) | | Hour | | | |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 300.00 | 200.00 | 149.36 | 135.00 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 40.00 | 140.00 | 197.50 | 200.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 340.00 | 192.94 | 152.37 | 142.65 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 160.00 | 150.00 | 150.15 | 200.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 100.00 | 135.00 | 150.82 | 156.06 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 500.00 | 150.00 | 141.55 | 130.79 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 20.00 | 80.00 | 142.01 | 230.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 780.00 | 146.28 | 144.08 | 150.77 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,320.00 | 151.16 | 149.55 | 151.43 |
| ========== | 203-02300 | Rock Scaler | | Hour | | | |
| NH5502-070 | | US 550 4 MILES SOUTH OF OURAY | 08/18/11 | 300.00 | 100.00 | 144.16 | 116.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 300.00 | 100.00 | 144.16 | 116.00 |
| SHE0402-081 | | US 40 - MP 113 TO 120 ROUTT C | 10/27/11 | 240.00 | 100.00 | 122.49 | 90.94 |
| IM0703-368 | | GEORGETOWN HILL CHUTES 6,7,9, | 12/01/11 | 96.00 | 81.98 | 95.73 | 60.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 336.00 | 94.85 | 118.03 | 82.10 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 636.00 | 97.28 | 126.98 | 98.09 |
| ========== | 203-02330 | Laborer | | Hour | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 40.00 | 50.00 | 39.29 | 25.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 40.00 | 50.00 | 38.59 | 26.80 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 40.00 | 40.00 | 43.90 | 47.52 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 203-02330 | Laborer | | Hour | | | |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 40.00 | 35.00 | 45.82 | 54.00 |
| C0241-055 | | SH 24 MP 148-152 | 05/26/11 | 50.00 | 40.00 | 38.39 | 32.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 80.00 | 40.00 | 61.67 | 33.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 20.00 | 40.00 | 39.52 | 38.59 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 230.00 | 39.13 | 47.73 | 39.41 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 10.00 | 35.00 | 31.74 | 30.00 |
| NH5502-070 | | US 550 4 MILES SOUTH OF OURAY | 08/18/11 | 80.00 | 30.00 | 54.02 | 45.00 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 20.00 | 50.00 | 43.00 | 55.00 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 20.00 | 50.00 | 35.77 | 25.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 130.00 | 36.54 | 45.41 | 42.31 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 20.00 | 50.00 | 50.00 | 45.00 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 40.00 | 35.00 | 35.76 | 43.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 90.00 | 35.00 | 35.44 | 50.00 |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 40.00 | 30.00 | 47.50 | 60.00 |
| IM0703-368 | | GEORGETOWN HILL CHUTES 6,7,9, | 12/01/11 | 25.00 | 37.31 | 41.21 | 40.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 40.00 | 40.00 | 33.50 | 32.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 255.00 | 36.40 | 36.71 | 46.27 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 655.00 | 38.22 | 42.47 | 41.42 |
| ========== | 206-00000 | Str Excav | | Cubic Yard | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 387.00 | 15.00 | 19.35 | 9.75 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 151,168.00 | 6.00 | 8.29 | 6.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 2,402.00 | 10.00 | 9.19 | 6.50 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 1,064.00 | 7.00 | 35.80 | 15.00 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 1,338.00 | 25.00 | 15.94 | 17.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 13,461.00 | 10.00 | 11.27 | 8.34 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 169,820.00 | 6.55 | 9.68 | 7.01 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 3.00 | 25.00 | 102.93 | 14.50 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 206-00000 | Str Excav | | Cubic Yard | ========== | ========== | ========== |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 4,503.00 | 9.00 | 7.11 | 11.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 25,198.00 | 8.00 | 7.14 | 4.50 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 122.00 | 45.00 | 28.87 | 29.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 1,728.00 | 15.00 | 13.96 | 7.50 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 143.00 | 35.00 | 37.58 | 41.96 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 14,145.00 | 8.00 | 5.00 | 5.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 2,434.00 | 15.00 | 12.00 | 13.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 83.00 | 20.00 | 17.46 | 24.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 6,096.00 | 10.00 | 8.47 | 3.56 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 54,455.00 | 9.01 | 7.55 | 6.18 |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 970.00 | 30.00 | 27.11 | 39.00 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 1,457.00 | 17.00 | 14.27 | 10.00 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 117.00 | 9.00 | 28.37 | 21.59 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 7,194.00 | 11.00 | 6.77 | 4.00 |
| C0091-038 | | SH 9 MM 81.9 BLUE RIVER EMERG | 08/24/11 | 80.00 | 100.00 | 94.30 | 91.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 47.00 | 40.00 | 39.40 | 56.00 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 189.00 | 30.00 | 12.36 | 5.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 10,054.00 | 14.88 | 10.11 | 9.02 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 600.00 | 14.00 | 10.57 | 4.34 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 1,278.00 | 7.00 | 7.73 | 5.88 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 6,658.00 | 10.00 | 12.36 | 7.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 10,714.00 | 10.00 | 12.35 | 11.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 7,810.00 | 8.00 | 9.42 | 8.78 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 14,545.00 | 5.00 | 11.56 | 9.05 |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 575.00 | 20.00 | 53.00 | 46.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 42,180.00 | 8.01 | 11.44 | 9.51 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 276,509.00 | 7.56 | 9.45 | 7.48 |
| ========== | 206-00050 | Str Bkfl (Spec) | | Cubic Yard | ========== | ========== | ========== |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 72.00 | 50.00 | 63.33 | 160.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 72.00 | 50.00 | 63.33 | 160.00 |
| NH0403-053 | | US 40 RETAINING WALL REPAIR | 07/28/11 | 10.00 | 1000.00 | 1569.17 | 1782.50 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 10.00 | 1000.00 | 1569.17 | 1782.50 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 82.00 | 165.85 | 161.11 | 357.87 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 206-00065 | Str Bkfl (Flow-Fill) | | Cubic Yard | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 172.00 | 90.00 | 139.97 | 138.50 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 88.00 | 95.00 | 135.22 | 200.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 660.00 | 110.00 | 78.05 | 69.00 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 18.00 | 100.00 | 195.38 | 245.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 4,500.00 | 50.00 | 64.25 | 50.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 5,438.00 | 59.44 | 68.36 | 56.49 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 69.00 | 150.00 | 147.00 | 176.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 106.00 | 83.00 | 81.89 | 80.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 26.10 | 82.00 | 213.90 | 220.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 368.00 | 35.00 | 128.40 | 106.00 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 447.00 | 225.00 | 144.14 | 142.03 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 230.00 | 110.00 | 108.07 | 68.76 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 18.00 | 100.00 | 76.94 | 75.17 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1,264.10 | 128.03 | 128.20 | 118.92 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 14.00 | 120.00 | 216.30 | 120.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 14.00 | 120.00 | 216.30 | 120.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 6.00 | 140.00 | 211.43 | 90.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 48.00 | 150.00 | 223.77 | 91.18 |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 50.00 | 160.00 | 188.74 | 196.96 |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 75.00 | 175.00 | 197.50 | 205.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 10.00 | 200.00 | 163.22 | 160.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 189.00 | 164.89 | 204.24 | 167.93 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 6,905.10 | 75.01 | 77.62 | 71.29 |
| ========== | 206-00066 | Str Bkfl (FF Ash) | | Cubic Yard | | | |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 200.00 | 100.00 | 81.28 | 35.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 200.00 | 100.00 | 81.28 | 35.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 200.00 | 100.00 | 81.28 | 35.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 206-00100 | Str Bkfl (CL 1) | | Cubic Yard | ========== | ========== | ========== |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 50.00 | 50.00 | 49.62 | 38.50 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 447,724.00 | 13.00 | 11.06 | 12.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 1,630.00 | 25.00 | 30.44 | 22.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 14,845.00 | 25.00 | 21.55 | 20.20 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 464,249.00 | 13.43 | 12.36 | 13.08 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 2,788.00 | 20.00 | 19.71 | 21.89 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 53,928.00 | 15.00 | 15.51 | 11.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 2,652.00 | 20.00 | 28.92 | 32.30 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 10,538.00 | 16.00 | 19.42 | 10.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 1,760.00 | 35.00 | 44.67 | 43.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 33,170.00 | 15.00 | 17.22 | 16.20 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 104,836.00 | 15.70 | 17.79 | 14.21 |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 70.00 | 30.00 | 71.43 | 130.00 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 117.00 | 17.50 | 37.87 | 32.39 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 2,421.00 | 25.00 | 18.59 | 16.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 25.00 | 65.00 | 65.00 | 60.00 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 5.00 | 50.00 | 80.08 | 100.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 2,638.00 | 25.23 | 20.78 | 17.26 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 700.00 | 20.00 | 30.42 | 22.82 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 371.00 | 25.00 | 22.46 | 24.04 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 5,542.00 | 17.00 | 25.00 | 15.50 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 5,382.00 | 22.00 | 19.56 | 21.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 787.00 | 25.00 | 24.84 | 21.28 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 14,421.00 | 15.00 | 16.28 | 15.00 |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 506.00 | 55.00 | 77.00 | 52.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 27,709.00 | 18.03 | 19.51 | 17.44 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 599,432.00 | 14.09 | 14.98 | 14.09 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 206-00200 | Str Bkfl (CL 2) | | Cubic Yard | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 4,718.00 | 12.04 | 14.20 | 13.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 274.00 | 18.00 | 19.19 | 9.50 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 1,440.00 | 18.00 | 10.96 | 4.40 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 6,432.00 | 13.63 | 13.32 | 9.91 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 1,355.00 | 18.00 | 8.10 | 8.65 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 531.00 | 12.00 | 13.61 | 11.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 65.00 | 25.00 | 22.91 | 10.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 361.00 | 18.00 | 13.08 | 18.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 23.00 | 20.00 | 47.06 | 12.19 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2,335.00 | 16.85 | 10.56 | 10.70 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 224.00 | 15.00 | 12.39 | 12.75 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 224.00 | 15.00 | 14.71 | 10.59 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 166.00 | 10.00 | 23.41 | 17.20 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 176.00 | 16.00 | 19.12 | 31.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 1,162.00 | 16.00 | 8.19 | 9.18 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 251.00 | 13.00 | 15.94 | 10.06 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1,755.00 | 15.00 | 11.40 | 12.25 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 10,746.00 | 14.58 | 12.30 | 10.64 |
| ========== | 206-00360 | Mechanical Reinforcement of Soil | | Cubic Yard | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 281,516.00 | 25.00 | 14.72 | 20.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 206-00360 | Mechanical Reinforcement of Soil | | Cubic Yard | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 1,630.00 | 20.00 | 18.83 | 15.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 8,171.00 | 30.00 | 17.36 | 17.44 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 291,317.00 | 25.11 | 15.03 | 19.64 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 2,579.00 | 20.00 | 16.99 | 14.40 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 36,258.00 | 13.00 | 13.36 | 6.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 2,652.00 | 35.00 | 19.52 | 13.15 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 1,714.00 | 25.00 | 21.79 | 18.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 17,804.00 | 15.00 | 28.01 | 29.74 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 61,007.00 | 15.17 | 18.30 | 13.93 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 1,254.00 | 25.00 | 25.11 | 21.75 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1,254.00 | 25.00 | 22.94 | 19.02 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 710.00 | 32.00 | 15.96 | 19.30 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1,471.00 | 22.00 | 18.47 | 20.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 561.00 | 20.00 | 27.16 | 28.39 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 9,304.00 | 16.00 | 13.80 | 21.13 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 12,046.00 | 17.86 | 14.95 | 21.22 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 365,624.00 | 23.21 | 16.17 | 17.53 |
| ========== | 206-00505 | Filter Matl (Spec) | | Cubic Yard | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 2,848.00 | 45.00 | 44.25 | 38.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 2,848.00 | 45.00 | 44.25 | 38.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,848.00 | 45.00 | 44.25 | 38.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 206-00510 | Filter Matl (CL A) | | Cubic Yard | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 751.00 | 50.00 | 35.92 | 35.71 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 751.00 | 50.00 | 35.92 | 35.71 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 384.00 | 40.00 | 36.10 | 38.45 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 384.00 | 40.00 | 41.12 | 39.38 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 32.00 | 30.00 | 60.36 | 31.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 5.00 | 50.00 | 66.59 | 60.36 |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 50.00 | 25.00 | 167.50 | 210.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 87.00 | 28.28 | 90.48 | 135.56 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,222.00 | 45.31 | 41.03 | 42.80 |
| ========== | 206-00520 | Filter Matl (CL B) | | Cubic Yard | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 81.00 | 65.00 | 67.15 | 55.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 81.00 | 65.00 | 67.15 | 55.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 151.00 | 40.00 | 39.41 | 42.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 180.00 | 70.00 | 63.33 | 57.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 331.00 | 56.31 | 47.50 | 50.16 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 5.00 | 70.00 | 86.28 | 67.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 694.00 | 30.00 | 34.95 | 26.77 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 699.00 | 30.29 | 35.18 | 27.06 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,111.00 | 40.57 | 51.03 | 41.49 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 206-00530 | Filter Matl (CL C) | | Cubic Yard | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 1,268.00 | 50.00 | 37.25 | 31.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1,268.00 | 50.00 | 37.25 | 31.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 28.00 | 50.00 | 66.70 | 40.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 52.00 | 40.00 | 45.13 | 48.18 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 80.00 | 43.50 | 50.56 | 45.32 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,348.00 | 49.61 | 39.42 | 33.89 |
| ========== | 206-01500 | Cofferdam | | LUMP SUM | | | |
| C0091-038 | | SH 9 MM 81.9 BLUE RIVER EMERG | 08/24/11 | 1.00 | 25000.00 | 46164.40 | 25350.30 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1.00 | 25000.00 | 46164.40 | 25350.30 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 25000.00 | 34578.80 | 15116.77 |
| ========== | 206-01750 | Shoring | | LUMP SUM | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 1.00 | 5000.00 | 12428.29 | 10000.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1.00 | 5000.00 | 12428.29 | 10000.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1.00 | 40000.00 | 55428.57 | 51000.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 40000.00 | 55428.57 | 51000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 22500.00 | 35582.29 | 30500.00 |
| ========== | 206-01781 | Shoring (A 1) | | LUMP SUM | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 1.00 | 105000.00 | 157142.06 | 110000.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 206-01781 | Shoring (A 1) | | LUMP SUM | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 1.00 | 105000.00 | 157142.06 | 110000.00 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 1.00 | 50000.00 | 26310.78 | 9026.16 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 1.00 | 20000.00 | 20054.74 | 24100.00 |
| C0241-055 | | SH 24 MP 148-152 | 05/26/11 | 1.00 | 20000.00 | 15908.33 | 3300.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 1.00 | 10000.00 | 31887.14 | 12700.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 1.00 | 15000.00 | 14953.17 | 23800.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1.00 | 15000.00 | 77267.79 | 69015.93 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 6.00 | 21666.67 | 26448.18 | 21027.44 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 1.00 | 5000.00 | 6925.57 | 10039.36 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 1.00 | 9000.00 | 10027.58 | 9400.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 1.00 | 5000.00 | 3014.00 | 4600.00 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 3.00 | 6333.33 | 7217.70 | 8013.12 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 1.00 | 5000.00 | 11003.81 | 5746.16 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1.00 | 18000.00 | 22999.52 | 10000.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 1.00 | 13000.00 | 16834.20 | 5815.61 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1.00 | 12000.00 | 21060.96 | 22375.06 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 4.00 | 12000.00 | 18199.15 | 10984.21 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 14.00 | 36294.12 | 32483.68 | 21677.89 |
| ========== | 206-01782 | Shoring (A 2) | | LUMP SUM | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 1.00 | 84000.00 | 19604.02 | 15000.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 1.00 | 84000.00 | 19604.02 | 15000.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 206-01782 | Shoring (A 2) | | LUMP SUM | | | |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 1.00 | 50000.00 | 28704.53 | 9026.16 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 1.00 | 10000.00 | 33722.86 | 12700.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 1.00 | 17000.00 | 30242.02 | 44000.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1.00 | 15000.00 | 34167.02 | 1000.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 4.00 | 23000.00 | 29089.17 | 18545.23 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 1.00 | 5000.00 | 6925.57 | 10039.36 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 1.00 | 9000.00 | 10115.08 | 9400.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 1.00 | 5000.00 | 3368.00 | 4600.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 3.00 | 6333.33 | 7354.92 | 8013.12 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 1.00 | 4000.00 | 11204.16 | 5264.34 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1.00 | 13500.00 | 10151.94 | 10000.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 1.00 | 13000.00 | 16224.95 | 4541.62 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1.00 | 12000.00 | 21560.96 | 22375.06 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 4.00 | 10625.00 | 15733.38 | 10545.26 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 12.00 | 32633.33 | 20230.74 | 13380.50 |
| ========== | 206-01783 | Shoring (A 3) | | LUMP SUM | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 1.00 | 80000.00 | 17874.14 | 15000.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1.00 | 80000.00 | 17874.14 | 15000.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 1.00 | 15000.00 | 35738.97 | 23800.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1.00 | 15000.00 | 99484.56 | 10142.44 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2.00 | 15000.00 | 47318.85 | 19980.81 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 206-01783 | Shoring (A 3) | | LUMP SUM | ========== | ========== | ========== |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 1.00 | 9000.00 | 9399.21 | 9400.00 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 1.00 | 9000.00 | 9399.21 | 9400.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1.00 | 30000.00 | 25472.21 | 16000.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 1.00 | 13000.00 | 15946.83 | 5815.61 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1.00 | 12000.00 | 18079.82 | 23625.97 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 3.00 | 18333.33 | 19027.34 | 15147.19 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 7.00 | 41400.00 | 28866.77 | 16223.00 |
| ========== | 206-01784 | Shoring (A 4) | | LUMP SUM | ========== | ========== | ========== |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 1.00 | 30000.00 | 23931.43 | 35000.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 1.00 | 30000.00 | 23931.43 | 35000.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 1.00 | 17000.00 | 43432.41 | 44000.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1.00 | 22000.00 | 39133.21 | 1000.00 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 2.00 | 19500.00 | 41448.16 | 22500.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 1.00 | 9000.00 | 9486.71 | 9400.00 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 1.00 | 9000.00 | 9486.71 | 9400.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1.00 | 48000.00 | 6215.31 | 11000.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 206-01784 | Shoring (A 4) | | LUMP SUM | ========== | ========== | ========== |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 1.00 | 13000.00 | 15545.33 | 4723.62 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1.00 | 12000.00 | 18579.82 | 23625.97 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 3.00 | 24333.33 | 14479.89 | 13116.53 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 7.00 | 24100.00 | 22238.83 | 18392.80 |
| ========== | 206-01785 | Shoring (A 5) | | LUMP SUM | ========== | ========== | ========== |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | . | 1.00 | 90000.00 | 8689.91 | . |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1.00 | 90000.00 | 8689.91 | . |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1.00 | 21000.00 | 33006.45 | 1000.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1.00 | 21000.00 | 33006.45 | 1000.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1.00 | 11250.00 | 9987.40 | 16000.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 11250.00 | 9987.40 | 16000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3.00 | 53062.50 | 18849.02 | 8500.00 |
| ========== | 206-01786 | Shoring (A 6) | | LUMP SUM | ========== | ========== | ========== |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 1.00 | 80000.00 | 81057.22 | 100000.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1.00 | 80000.00 | 81057.22 | 100000.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1.00 | 11250.00 | 9987.40 | 16000.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 11250.00 | 9987.40 | 16000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 57083.33 | 51444.80 | 58000.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 206-01787 | Shoring (A 7) | | LUMP SUM | ========== | ========== | ========== |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 1.00 | 80000.00 | 48161.78 | 35000.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1.00 | 80000.00 | 48161.78 | 35000.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1.00 | 48000.00 | 88621.69 | 54000.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 48000.00 | 88621.69 | 54000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 73600.00 | 62611.75 | 44500.00 |
| ========== | 206-01788 | Shoring (A 8) | | LUMP SUM | ========== | ========== | ========== |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1.00 | 20000.00 | 22390.98 | 19000.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 20000.00 | 22390.98 | 19000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 20000.00 | 22390.98 | 19000.00 |
| ========== | 206-01789 | Shoring (A 9) | | LUMP SUM | ========== | ========== | ========== |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1.00 | 6750.00 | 8407.22 | 12500.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 6750.00 | 8407.22 | 12500.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 6750.00 | 8407.22 | 12500.00 |
| ========== | 207-00205 | Topsoil | | Cubic Yard | ========== | ========== | ========== |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 3,592.00 | 11.00 | 6.42 | 7.50 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 3,115.00 | 25.00 | 12.80 | 6.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 970.00 | 50.00 | 19.95 | 15.41 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 7,677.00 | 21.61 | 13.19 | 13.03 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 622.00 | 10.00 | 30.35 | 42.67 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 207-00205 | Topsoil | | Cubic Yard | | | |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 2,300.00 | 8.00 | 16.12 | 12.52 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 1,300.00 | 40.00 | 13.26 | 17.00 |
| C0241-055 | | SH 24 MP 148-152 | 05/26/11 | 58.00 | 30.00 | 41.42 | 25.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 7,529.00 | 7.00 | 10.64 | 14.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 800.00 | 20.00 | 9.96 | 5.60 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 2,360.00 | 10.00 | 18.01 | 10.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 3,360.00 | 10.00 | 10.67 | 14.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 65.00 | 35.00 | 39.16 | 49.12 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 48.00 | 30.00 | 43.83 | 32.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 10,900.00 | 3.00 | 5.42 | 3.56 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 29,342.00 | 8.20 | 11.16 | 9.77 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 1,199.00 | 12.00 | 12.85 | 11.50 |
| STR096A-040 | | SH 96 MP 193 TO MP 201 | 09/01/11 | 6,504.00 | 8.00 | 8.68 | 4.05 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 375.00 | 20.00 | 14.28 | 8.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 8,078.00 | 9.15 | 10.50 | 8.67 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 425.00 | 9.00 | 18.09 | 11.16 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 24,000.00 | 6.00 | 6.23 | 6.30 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 13,500.00 | 10.00 | 7.50 | 4.20 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1,046.00 | 15.00 | 20.09 | 22.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 6,634.00 | 15.00 | 13.53 | 3.68 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1,290.00 | 40.00 | 17.92 | 17.10 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 1,131.00 | 10.00 | 7.20 | 6.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 592.00 | 10.00 | 8.15 | 9.00 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 270.00 | 10.00 | 39.33 | 33.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 48,888.00 | 9.60 | 8.88 | 6.20 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 93,985.00 | 10.11 | 10.43 | 8.47 |
| ========== | 207-00210 | Stockpile Topsoil | | Cubic Yard | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 3,115.00 | 4.00 | 8.28 | 4.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 3,115.00 | 4.00 | 8.28 | 4.00 |
| C0241-055 | | SH 24 MP 148-152 | 05/26/11 | 58.00 | 3.00 | 37.70 | 20.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 207-00210 | Stockpile Topsoil | | Cubic Yard | | | |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 800.00 | 3.00 | 8.71 | 5.25 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 3,360.00 | 5.00 | 8.33 | 6.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 4,218.00 | 4.59 | 6.17 | 4.46 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 1,199.00 | 3.00 | 4.49 | 5.00 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 375.00 | 20.00 | 10.22 | 4.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1,574.00 | 7.05 | 4.61 | 3.27 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 1,131.00 | 4.00 | 4.58 | 4.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 592.00 | 11.00 | 5.28 | 6.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1,723.00 | 6.41 | 4.87 | 4.69 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 10,630.00 | 5.08 | 6.06 | 4.19 |
| ========== | 207-00305 | Wetland Topsoil | | Cubic Yard | | | |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 67.00 | 25.00 | 29.33 | 40.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 67.00 | 25.00 | 29.33 | 40.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 67.00 | 25.00 | 29.33 | 40.00 |
| ========== | 207-00310 | Stockpile Wetland Topsoil | | Cubic Yard | | | |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 67.00 | 12.00 | 18.17 | 10.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 5,200.00 | 2.00 | 8.76 | 7.62 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 5,267.00 | 2.13 | 8.82 | 7.65 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 5,267.00 | 2.13 | 8.82 | 7.65 |
| ========== | 208-00001 | Silt Dike | | Lin Foot | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 110.00 | 5.00 | 10.46 | 9.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 110.00 | 5.00 | 10.46 | 9.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 110.00 | 5.00 | 10.46 | 9.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 208-00002 | Erosion Log (12 In) | | Lin Foot | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 50.00 | 8.00 | 8.11 | 7.95 |
| C0704-225 | | I-70 EAST OF BENNETT | 01/06/11 | 500.00 | 4.00 | 3.62 | 3.13 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 108,600.00 | 4.00 | 3.56 | 2.50 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 200.00 | 10.00 | 4.23 | 6.15 |
| NH 0241-056 | | US 24 BUENA VISTA NORTH | 03/03/11 | 200.00 | 5.00 | 4.38 | 6.00 |
| STA0504-061 | | US 50 M.P.369.9 -M.P.373.2 | 03/03/11 | 100.00 | 4.00 | 4.73 | 5.27 |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 200.00 | 5.00 | 5.01 | 3.75 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 16,396.00 | 3.50 | 4.10 | 4.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 1,056.00 | 4.00 | 4.73 | 3.99 |
| NH 0402-079 | | US40 MP 165.0 - 179.0 GRAND C | 03/31/11 | 200.00 | 7.00 | 5.33 | 4.12 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 127,502.00 | 3.95 | 3.76 | 3.17 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 200.00 | 4.00 | 5.02 | 3.50 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 200.00 | 6.00 | 4.05 | 4.00 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 160.00 | 5.00 | 5.23 | 3.25 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 2,000.00 | 7.00 | 6.93 | 3.80 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 500.00 | 4.00 | 5.10 | 4.00 |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 2,000.00 | 4.00 | 3.52 | 3.10 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 200.00 | 4.00 | 4.80 | 4.20 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 4,800.00 | 4.00 | 4.40 | 4.75 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 7,430.00 | 7.00 | 3.70 | 3.00 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 150.00 | 7.00 | 6.46 | 4.90 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 650.00 | 5.50 | 4.19 | 4.30 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 1,000.00 | 4.00 | 4.02 | 3.23 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 4,500.00 | 4.00 | 4.17 | 4.10 |
| C0241-055 | | SH 24 MP 148-152 | 05/26/11 | 670.00 | 4.00 | 5.42 | 4.30 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 838.00 | 20.00 | 4.32 | 5.00 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 557.00 | 7.00 | 4.02 | 4.04 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 9,071.00 | 3.00 | 3.48 | 3.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 5,600.00 | 5.00 | 4.12 | 5.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 71,300.00 | 2.50 | 3.09 | 2.92 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 9,530.00 | 5.00 | 3.29 | 3.36 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 720.00 | 4.00 | 5.00 | 4.00 |
| ITS0703-370 | | EAST OF EJMT ON I-70 EB LANES | 06/16/11 | 500.00 | 4.00 | 4.21 | 4.35 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 600.00 | 4.00 | 4.10 | 5.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 4,960.00 | 3.00 | 4.56 | 5.08 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 60.00 | 7.00 | 8.40 | 6.30 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 128,196.00 | 3.53 | 3.63 | 3.40 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 208-00002 | Erosion Log (12 In) | | Lin Foot | | | |
| C006A-051 | | US 6 (LOVELAND PASS), CLEAR C | 07/14/11 | 1,000.00 | 3.80 | 3.74 | 3.65 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 650.00 | 6.00 | 3.61 | 3.24 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 750.00 | 4.00 | 3.89 | 3.55 |
| NH2872-018 | | US 287 RUSH CREEK NORTH | 07/21/11 | 100.00 | 3.00 | 5.75 | 5.00 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 600.00 | 3.50 | 4.25 | 4.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 1,596.00 | 4.00 | 4.05 | 4.50 |
| NH0403-053 | | US 40 RETAINING WALL REPAIR | 07/28/11 | 800.00 | 10.00 | 4.68 | 3.54 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 1,000.00 | 4.00 | 4.21 | 4.45 |
| NH5502-070 | | US 550 4 MILES SOUTH OF OURAY | 08/18/11 | 200.00 | 8.00 | 9.91 | 8.00 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 772.00 | 18.00 | 5.22 | 4.50 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 500.00 | 5.00 | 5.27 | 5.00 |
| STR096A-040 | | SH 96 MP 193 TO MP 201 | 09/01/11 | 100.00 | 3.00 | 5.06 | 5.33 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 14,550.00 | 3.00 | 3.56 | 4.00 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 1,200.00 | 5.00 | 4.50 | 3.50 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 800.00 | 6.00 | 5.30 | 5.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 24,618.00 | 4.23 | 3.87 | 4.12 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 440.00 | 7.00 | 4.03 | 3.51 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 3,000.00 | 4.00 | 4.41 | 2.93 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 33,962.00 | 3.50 | 3.79 | 4.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 6,960.00 | 3.00 | 4.09 | 4.00 |
| SHE0402-081 | | US 40 - MP 113 TO 120 ROUTT C | 10/27/11 | 200.00 | 4.00 | 11.51 | 3.53 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 4,600.00 | 3.00 | 4.48 | 4.19 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 820.00 | 5.00 | 4.78 | 5.03 |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 500.00 | 5.00 | 12.05 | 9.94 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 600.00 | 5.50 | 4.19 | 4.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 7,035.00 | 3.25 | 3.96 | 3.40 |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 130.00 | 8.00 | 8.00 | 11.00 |
| MC0504-065 | | US50B FROM MP 318 TO MP 359 | 12/01/11 | 110.00 | 3.50 | 8.00 | 4.00 |
| IM0703-368 | | GEORGETOWN HILL CHUTES 6,7,9, | 12/01/11 | 600.00 | 3.79 | 8.35 | 6.00 |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 2,000.00 | 4.00 | 4.37 | 4.00 |
| C2854-125 | | US 285, ASPEN PARK TO MORRISO | 12/08/11 | 800.00 | 5.00 | 3.53 | 3.50 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 2,800.00 | 5.00 | 4.18 | 4.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 64,557.00 | 3.59 | 4.05 | 3.98 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 344,873.00 | 3.75 | 3.79 | 3.56 |
| ========== | 208-00003 | Erosion Log (18 In) | | Lin Foot | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 300.00 | 25.00 | 5.05 | 6.25 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 208-00003 | Erosion Log (18 In) | | Lin Foot | ========== | ========== | ========== |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 5,505.00 | 4.50 | 5.18 | 5.50 |
| NH 2852-017 | | US 285 PONCHA PASS SOUTH RESU | 03/03/11 | 500.00 | 7.00 | 6.63 | 8.10 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 1,000.00 | 6.00 | 7.49 | 7.37 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 7,305.00 | 5.72 | 5.54 | 5.96 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 400.00 | 5.00 | 6.83 | 6.00 |
| FSA 0502-064 | | US 50 EAST OF SARGENTS | 06/23/11 | 900.00 | 5.00 | 8.04 | 8.14 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 1,300.00 | 5.00 | 7.79 | 7.48 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 400.00 | 4.50 | 5.88 | 5.60 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 400.00 | 4.50 | 5.88 | 5.60 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 9,005.00 | 5.56 | 5.74 | 6.17 |
| ========== | 208-00005 | Erosion Log | | Lin Foot | ========== | ========== | ========== |
| ITS4701-121 | | C470 (SANTA FE TO I-25) AND R | 01/20/11 | 300.00 | 5.00 | 3.53 | 3.35 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 300.00 | 5.00 | 3.53 | 3.35 |
| SHE074A-001 | | SH 74 - EVERGREEN - JEFFERSON | 04/28/11 | 160.00 | 4.00 | 5.08 | 7.00 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 160.00 | 4.00 | 5.08 | 7.00 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 1,000.00 | 4.00 | 4.19 | 6.00 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 1,000.00 | 4.00 | 4.19 | 6.00 |
| ITSSW00-928 | | NB I-225 AT MM 2.28 | 11/03/11 | 200.00 | 7.00 | 4.20 | 3.00 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 200.00 | 7.00 | 4.20 | 3.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 1,660.00 | 4.54 | 4.14 | 5.26 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 208-00007 | Erosion Log (8 In) | | Lin Foot | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 360.00 | 6.00 | 4.41 | 1.65 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 360.00 | 6.00 | 4.55 | 1.94 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 17,070.00 | 4.00 | 3.63 | 3.00 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 17,070.00 | 4.00 | 3.63 | 3.00 |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 590.00 | 5.00 | 4.63 | 2.50 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 195.00 | 4.00 | 3.36 | 4.00 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 785.00 | 4.75 | 4.28 | 2.87 |
| NH0501-060 | | US50 MP 74.0 TO 81, 94.2 TO 1 | 10/20/11 | 200.00 | 6.00 | 4.52 | 1.00 |
| SHE025A-013 | | I 25 BETWEEN MP 122 AND MP 12 | 11/03/11 | 1,500.00 | 3.50 | 2.96 | 3.00 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 1,700.00 | 3.79 | 3.10 | 2.76 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 19,915.00 | 4.05 | 3.62 | 2.95 |
| ========== | 208-00009 | Erosion Log (20 In) | | Lin Foot | | | |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 600.00 | 6.00 | 6.35 | 5.60 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 770.00 | 6.00 | 6.68 | 6.86 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 200.00 | 6.00 | 6.60 | 7.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 2,633.00 | 5.00 | 5.34 | 5.00 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 4,203.00 | 5.37 | 5.77 | 5.52 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 532.00 | 6.00 | 6.60 | 6.80 |
| NH0403-053 | | US 40 RETAINING WALL REPAIR | 07/28/11 | 400.00 | 12.00 | 7.78 | 5.99 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 350.00 | 5.50 | 5.97 | 5.60 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 1,282.00 | 7.74 | 6.64 | 6.22 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 208-00009 | Erosion Log (20 In) | | Lin Foot | | | |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 7,016.00 | 5.00 | 5.86 | 5.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 2,000.00 | 5.00 | 6.85 | 6.84 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 2,460.00 | 6.00 | 6.14 | 7.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 11,476.00 | 5.21 | 6.16 | 5.75 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 16,961.00 | 5.44 | 6.08 | 5.73 |
| ========== | 208-00011 | Erosion Bales (Weed Free) | | Each | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 38.00 | 20.00 | 23.15 | 26.00 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 44.00 | 15.00 | 16.05 | 16.00 |
| STA0504-061 | | US 50 M.P.369.9 -M.P.373.2 | 03/03/11 | 40.00 | 17.00 | 15.71 | 15.92 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 122.00 | 17.21 | 17.26 | 18.06 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 100.00 | 10.00 | 11.75 | 10.50 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 12.00 | 20.00 | 15.57 | 13.00 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 12.00 | 23.00 | 13.43 | 12.60 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 400.00 | 15.00 | 15.00 | 17.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 1,560.00 | 8.00 | 10.64 | 10.74 |
| FSA 0502-064 | | US 50 EAST OF SARGENTS | 06/23/11 | 10.00 | 17.00 | 17.57 | 23.55 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 2,094.00 | 9.63 | 12.05 | 12.09 |
| NH5502-070 | | US 550 4 MILES SOUTH OF OURAY | 08/18/11 | 75.00 | 20.00 | 22.68 | 25.00 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 168.00 | 20.00 | 18.91 | 18.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 243.00 | 20.00 | 18.64 | 19.25 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 60.00 | 15.00 | 12.95 | 14.34 |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 180.00 | 20.00 | 16.50 | 16.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 240.00 | 18.75 | 14.47 | 15.59 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,699.00 | 11.72 | 13.23 | 13.35 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 208-00015 | Sand Bag | | Each | ========== | ========== | ========== |
| FSA 0502-064 | | US 50 EAST OF SARGENTS | 06/23/11 | 100.00 | 15.00 | 9.13 | 21.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 100.00 | 15.00 | 9.13 | 21.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 100.00 | 15.00 | 9.13 | 21.00 |
| ========== | 208-00020 | Silt Fence | | Lin Foot | ========== | ========== | ========== |
| ITS4701-121 | | C470 (SANTA FE TO I-25) AND R | 01/20/11 | 200.00 | 3.00 | 2.05 | 0.70 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 32,672.00 | 1.50 | 1.40 | 0.82 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| NH 2852-017 | | US 285 PONCHA PASS SOUTH RESU | 03/03/11 | 500.00 | 1.50 | 1.58 | 1.87 |
| NH 0241-056 | | US 24 BUENA VISTA NORTH | 03/03/11 | 500.00 | 2.00 | 1.28 | 1.50 |
| STA0504-061 | | US 50 M.P.369.9 -M.P.373.2 | 03/03/11 | 500.00 | 1.80 | 1.25 | 1.43 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 1,500.00 | 2.00 | 1.66 | 2.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 4,453.00 | 2.00 | 1.78 | 0.88 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 40,325.00 | 1.59 | 1.52 | 1.02 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 4,000.00 | 1.00 | 1.01 | 0.88 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 4,200.00 | 1.00 | 1.42 | 0.95 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 2,000.00 | 2.00 | 1.47 | 0.95 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 1,332.00 | 1.50 | 1.22 | 1.25 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 475.00 | 4.00 | 1.20 | 1.10 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 10,491.00 | 1.00 | 1.20 | 0.90 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 14,000.00 | 1.25 | 1.33 | 1.70 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 209.00 | 2.00 | 1.55 | 1.60 |
| FSA 0502-064 | | US 50 EAST OF SARGENTS | 06/23/11 | 550.00 | 3.00 | 2.01 | 1.50 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 4,638.00 | 1.00 | 1.23 | 0.98 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 41,895.00 | 1.21 | 1.26 | 1.17 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 2,272.00 | 1.00 | 1.34 | 2.40 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 2,921.00 | 9.00 | 1.73 | 1.50 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 150.00 | 2.10 | 1.76 | 1.20 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 1,500.00 | 2.50 | 1.69 | 1.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 6,843.00 | 4.77 | 1.51 | 1.60 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 208-00020 | Silt Fence | | Lin Foot | | | |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 800.00 | 2.00 | 1.21 | 1.24 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 9,000.00 | 1.10 | 1.41 | 1.12 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 290.00 | 1.50 | 2.74 | 2.60 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 14,288.00 | 1.00 | 1.06 | 1.00 |
| SHE025A-013 | | I 25 BETWEEN MP 122 AND MP 12 | 11/03/11 | 1,650.00 | 1.25 | 1.59 | 1.15 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 30,600.00 | 1.00 | 1.01 | 0.99 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 3,482.00 | 1.00 | 1.62 | 1.01 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 1,351.00 | 1.50 | 2.19 | 2.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 1,900.00 | 2.00 | 1.53 | 2.20 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 63,361.00 | 1.08 | 1.16 | 1.08 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 152,424.00 | 1.42 | 1.27 | 1.17 |
| ========== | 208-00021 | Silt Fence (Reinf) | | Lin Foot | | | |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 5,580.00 | 2.60 | 1.36 | 1.10 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 781.00 | 4.00 | 3.45 | 2.37 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 6,361.00 | 2.77 | 1.59 | 1.26 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 1,120.00 | 3.00 | 2.90 | 1.85 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 770.00 | 3.00 | 13.67 | 13.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 1,890.00 | 3.00 | 6.95 | 6.39 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 2,504.00 | 3.00 | 8.42 | 2.10 |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 440.00 | 6.00 | 4.00 | 5.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 2,944.00 | 3.45 | 8.24 | 2.53 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 11,195.00 | 2.99 | 3.95 | 2.46 |
| ========== | 208-00030 | Sediment Basin | | Each | | | |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 2.00 | 2500.00 | 5700.00 | 1800.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 208-00030 | Sediment Basin | | Each | | | |
| FSA 0502-064 | | US 50 EAST OF SARGENTS | 06/23/11 | 2.00 | 2400.00 | 891.18 | 725.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 4.00 | 2450.00 | 2694.49 | 1262.50 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 1.00 | 1200.00 | 2073.55 | 2652.04 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 2.00 | 2000.00 | 4486.23 | 9000.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 3.00 | 3000.00 | 1851.94 | 1654.52 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 6.00 | 2366.67 | 2521.36 | 4269.27 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 10.00 | 2400.00 | 2569.12 | 3066.56 |
| ========== | 208-00033 | Sediment Trap | | Each | | | |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 6.00 | 1500.00 | 1266.64 | 450.00 |
| FSA 0502-064 | | US 50 EAST OF SARGENTS | 06/23/11 | 2.00 | 1100.00 | 1636.04 | 2745.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 8.00 | 1400.00 | 1295.07 | 861.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 3.00 | 1000.00 | 880.86 | 1019.88 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1.00 | 1000.00 | 973.43 | 1006.07 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 4.00 | 1000.00 | 904.00 | 1016.43 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 12.00 | 1266.67 | 1161.94 | 905.41 |
| ========== | 208-00034 | Gravel Bag | | Lin Foot | | | |
| C0704-225 | | I-70 EAST OF BENNETT | 01/06/11 | 100.00 | 6.00 | 4.65 | 3.18 |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 100.00 | 5.00 | 4.66 | 2.50 |
| ITS4701-121 | | C470 (SANTA FE TO I-25) AND R | 01/20/11 | 1,000.00 | 3.00 | 2.64 | 2.55 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 4,200.00 | 8.00 | 7.05 | 3.60 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 100.00 | 18.00 | 20.16 | 115.00 |
| STA0504-061 | | US 50 M.P.369.9 -M.P.373.2 | 03/03/11 | 20.00 | 9.00 | 10.00 | 6.71 |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 100.00 | 6.00 | 6.82 | 6.65 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 208-00034 | Gravel Bag | | Lin Foot | ========== | ========== | ========== |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 1,000.00 | 6.00 | 5.81 | 1.52 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 6,620.00 | 6.99 | 5.64 | 5.16 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 1,500.00 | 6.00 | 5.53 | 7.00 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 4,000.00 | 4.00 | 5.25 | 6.59 |
| STA0343-032 | | US 34 EAST OF AKRON | 04/07/11 | 50.00 | 10.00 | 3.50 | 3.50 |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 320.00 | 5.00 | 6.47 | 6.80 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 150.00 | 6.00 | 5.81 | 6.00 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 100.00 | 8.00 | 3.82 | 3.70 |
| SHE074A-001 | | SH 74 - EVERGREEN - JEFFERSON | 04/28/11 | 100.00 | 6.00 | 5.55 | 5.15 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 50.00 | 8.00 | 5.77 | 6.50 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 220.00 | 8.00 | 4.97 | 3.30 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 250.00 | 7.00 | 5.96 | 5.20 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 1,000.00 | 7.00 | 4.49 | 4.31 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 500.00 | 6.00 | 4.53 | 6.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 80.00 | 20.00 | 10.96 | 38.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 618.00 | 6.00 | 3.38 | 2.50 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 4,280.00 | 4.00 | 5.11 | 4.60 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 4,101.00 | 5.00 | 4.87 | 4.75 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 100.00 | 6.00 | 7.81 | 7.25 |
| ITS0703-370 | | EAST OF EJMT ON I-70 EB LANES | 06/16/11 | 250.00 | 6.00 | 5.89 | 5.85 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 200.00 | 8.00 | 6.50 | 5.50 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 100.00 | 11.00 | 6.59 | 4.15 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 240.00 | 6.00 | 9.25 | 5.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 18,209.00 | 5.08 | 5.25 | 5.44 |
| C006A-051 | | US 6 (LOVELAND PASS), CLEAR C | 07/14/11 | 250.00 | 5.60 | 11.38 | 10.50 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 300.00 | 6.00 | 5.34 | 4.86 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 500.00 | 7.00 | 4.97 | 3.60 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 550.00 | 7.00 | 6.30 | 3.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 64.00 | 6.00 | 6.62 | 12.80 |
| NH0403-053 | | US 40 RETAINING WALL REPAIR | 07/28/11 | 200.00 | 10.00 | 8.07 | 3.50 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 500.00 | 5.00 | 5.52 | 5.00 |
| BR2706-036 | | I-270 BRIDGE DECK REHABILITAT | 08/11/11 | 50.00 | 8.00 | 11.88 | 15.00 |
| NH5502-070 | | US 550 4 MILES SOUTH OF OURAY | 08/18/11 | 100.00 | 7.00 | 11.45 | 10.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 200.00 | 6.00 | 5.39 | 5.00 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 500.00 | 6.00 | 4.56 | 4.25 |
| STR096A-040 | | SH 96 MP 193 TO MP 201 | 09/01/11 | 25.00 | 6.00 | 7.34 | 8.53 |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 50.00 | 7.00 | 12.38 | 8.75 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 150.00 | 5.00 | 7.17 | 6.50 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 3,439.00 | 6.39 | 6.14 | 4.22 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 208-00034 | Gravel Bag | | Lin Foot | ========== | ========== | ========== |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 100.00 | 6.50 | 4.48 | 4.95 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 200.00 | 6.00 | 7.42 | 4.15 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 170.00 | 6.00 | 6.24 | 2.00 |
| ITSSW00-928 | | NB I-225 AT MM 2.28 | 11/03/11 | 50.00 | 8.00 | 6.63 | 4.00 |
| STA0343-033 | | SH 34 ECKLEY | 11/10/11 | 50.00 | 3.50 | 9.13 | 1.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 720.00 | 5.00 | 5.49 | 6.34 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 2,751.00 | 4.00 | 5.03 | 3.52 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 30.00 | 10.00 | 32.50 | 5.00 |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 60.00 | 7.00 | 10.95 | 13.55 |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 125.00 | 7.00 | 4.50 | 5.00 |
| IM0703-368 | | GEORGETOWN HILL CHUTES 6,7,9, | 12/01/11 | 600.00 | 5.54 | 8.41 | 6.00 |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 100.00 | 4.00 | 6.16 | 6.00 |
| C2854-125 | | US 285, ASPEN PARK TO MORRISO | 12/08/11 | 100.00 | 6.00 | 5.17 | 5.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 5,056.00 | 4.74 | 5.57 | 4.43 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 33,324.00 | 5.54 | 5.50 | 5.05 |
| ========== | 208-00040 | Check Dam | | Each | ========== | ========== | ========== |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 272.00 | 200.00 | 289.41 | 100.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 3.00 | 500.00 | 743.76 | 718.64 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 275.00 | 203.27 | 306.56 | 126.14 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 3.00 | 200.00 | 245.71 | 146.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 3.00 | 200.00 | 245.71 | 146.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 187.00 | 200.00 | 299.29 | 350.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 16.00 | 800.00 | 448.83 | 254.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 21.00 | 300.00 | 361.48 | 301.82 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 224.00 | 252.23 | 313.68 | 338.63 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 502.00 | 225.10 | 312.39 | 286.51 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 208-00045 | Conc Washout Str | | Each | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 1.00 | 800.00 | 861.76 | 500.00 |
| C0704-225 | | I-70 EAST OF BENNETT | 01/06/11 | 1.00 | 500.00 | 522.75 | 166.00 |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 2.00 | 500.00 | 720.49 | 160.00 |
| ITS4701-121 | | C470 (SANTA FE TO I-25) AND R | 01/20/11 | 3.00 | 200.00 | 187.25 | 192.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 72.00 | 600.00 | 1075.83 | 475.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 1.00 | 700.00 | 748.86 | 1130.00 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 2.00 | 640.00 | 926.68 | 870.00 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 3.00 | 900.00 | 887.84 | 1000.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 8.00 | 615.00 | 1175.72 | 715.34 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 93.00 | 598.92 | 1002.05 | 585.71 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 3.00 | 1200.00 | 683.18 | 600.00 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 8.00 | 900.00 | 921.59 | 500.00 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 2.00 | 800.00 | 1222.33 | 875.00 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 1.00 | 500.00 | 2840.67 | 3844.00 |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 2.00 | 750.00 | 473.05 | 485.00 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 6.00 | 500.00 | 1131.52 | 1003.32 |
| SHE074A-001 | | SH 74 - EVERGREEN - JEFFERSON | 04/28/11 | 1.00 | 615.00 | 478.33 | 275.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 13.00 | 700.00 | 772.15 | 700.00 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 2.00 | 700.00 | 1113.25 | 932.00 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 3.00 | 700.00 | 579.66 | 600.00 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 1.00 | 1000.00 | 1039.46 | 1100.00 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 4.00 | 700.00 | 373.63 | 5.39 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 2.00 | 1200.00 | 1600.00 | 3300.00 |
| C0241-055 | | SH 24 MP 148-152 | 05/26/11 | 1.00 | 750.00 | 1454.13 | 1000.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 2.00 | 370.00 | 973.85 | 1300.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 2.00 | 900.00 | 1027.00 | 1000.00 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 4.00 | 1000.00 | 668.37 | 311.73 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 6.00 | 600.00 | 668.49 | 460.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 2.00 | 900.00 | 1080.00 | 1100.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 9.00 | 500.00 | 631.21 | 562.82 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 2.00 | 800.00 | 483.98 | 370.00 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 2.00 | 1000.00 | 823.75 | 616.00 |
| ITS0703-370 | | EAST OF EJMT ON I-70 EB LANES | 06/16/11 | 1.00 | 900.00 | 574.00 | 680.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 2.00 | 800.00 | 748.00 | 435.00 |
| FSA 0502-064 | | US 50 EAST OF SARGENTS | 06/23/11 | 1.00 | 850.00 | 1178.98 | 995.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 5.00 | 800.00 | 1160.01 | 1036.81 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 2.00 | 400.00 | 420.00 | 440.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 89.00 | 738.82 | 859.01 | 752.93 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 208-00045 | Conc Washout Str | | Each | | | |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 1.00 | 1000.00 | 1350.83 | 860.00 |
| C006A-051 | | US 6 (LOVELAND PASS), CLEAR C | 07/14/11 | 1.00 | 1000.00 | 993.75 | 800.00 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 1.00 | 1000.00 | 795.00 | 550.00 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 1.00 | 610.00 | 821.04 | 701.68 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 2.00 | 800.00 | 910.56 | 515.00 |
| NH2872-018 | | US 287 RUSH CREEK NORTH | 07/21/11 | 2.00 | 550.00 | 1119.58 | 1000.00 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 1.00 | 700.00 | 640.00 | 600.00 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 1.00 | 800.00 | 932.05 | 1076.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 8.00 | 750.00 | 764.11 | 1100.00 |
| NH0403-053 | | US 40 RETAINING WALL REPAIR | 07/28/11 | 1.00 | 1000.00 | 1145.42 | 636.27 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 4.00 | 650.00 | 1199.46 | 950.00 |
| BR2706-036 | | I-270 BRIDGE DECK REHABILITAT | 08/11/11 | 5.00 | 1000.00 | 787.00 | 513.00 |
| NH5502-070 | | US 550 4 MILES SOUTH OF OURAY | 08/18/11 | 1.00 | 900.00 | 2174.13 | 2800.00 |
| C0091-038 | | SH 9 MM 81.9 BLUE RIVER EMERG | 08/24/11 | 1.00 | 1000.00 | 731.97 | 621.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 2.00 | 1000.00 | 758.80 | 445.00 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 4.00 | 750.00 | 738.44 | 625.00 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 3.00 | 400.00 | 752.33 | 285.00 |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 1.00 | 1000.00 | 712.50 | 625.00 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 3.00 | 1000.00 | 813.33 | 1000.00 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 1.00 | 1200.00 | 1147.80 | 600.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 44.00 | 811.59 | 817.06 | 830.44 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 2.00 | 1000.00 | 843.42 | 668.60 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 2.00 | 650.00 | 849.64 | 275.58 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 4.00 | 1000.00 | 1208.29 | 1700.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 5.00 | 800.00 | 952.77 | 938.00 |
| SHE0402-081 | | US 40 - MP 113 TO 120 ROUTT C | 10/27/11 | 1.00 | 1000.00 | 2185.12 | 2817.70 |
| ITSSW00-928 | | NB I-225 AT MM 2.28 | 11/03/11 | 1.00 | 800.00 | 323.67 | 400.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 6.00 | 650.00 | 953.37 | 1663.26 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 5.00 | 700.00 | 1109.65 | 955.77 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 1.00 | 1000.00 | 1900.00 | 1800.00 |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 9.00 | 250.00 | 644.64 | 243.56 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 1.00 | 1000.00 | 1770.28 | 3400.00 |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 1.00 | 900.00 | 1150.00 | 1700.00 |
| C2854-125 | | US 285, ASPEN PARK TO MORRISO | 12/08/11 | 1.00 | 1000.00 | 613.33 | 550.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 2.00 | 500.00 | 947.98 | 740.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 41.00 | 674.39 | 980.92 | 1036.01 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 267.00 | 692.19 | 902.28 | 786.86 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 208-00050 | Storm Drain Inlet Protection | | Each | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 3.00 | 300.00 | 167.15 | 140.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 764.00 | 150.00 | 159.78 | 3.50 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 80.00 | 150.00 | 192.20 | 159.58 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 847.00 | 150.53 | 168.21 | 53.09 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 64.00 | 150.00 | 167.08 | 116.00 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 13.00 | 200.00 | 209.04 | 158.42 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 26.00 | 200.00 | 174.36 | 110.00 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 39.00 | 200.00 | 210.46 | 196.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 3.00 | 350.00 | 220.23 | 177.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 21.00 | 200.00 | 169.47 | 150.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 166.00 | 183.43 | 186.58 | 148.79 |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 4.00 | 175.00 | 163.77 | 125.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 4.00 | 175.00 | 172.78 | 135.71 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 2.00 | 60.00 | 242.47 | 210.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 60.00 | 242.47 | 210.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,019.00 | 155.81 | 174.30 | 92.78 |
| ========== | 208-00051 | Storm Drain Inlet Protection (Type 1) | | Lin Foot | | | |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 140.00 | 9.00 | 7.01 | 6.25 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 40.00 | 10.00 | 5.14 | 5.39 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 70.00 | 15.00 | 8.04 | 11.75 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 900.00 | 10.00 | 7.19 | 4.67 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 35.00 | 8.00 | 12.73 | 11.95 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 1,185.00 | 10.12 | 7.19 | 5.35 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 208-00051 | Storm Drain Inlet Protection (Type 1) | | Lin Foot | | | |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 190.00 | 13.00 | 9.77 | 10.60 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 50.00 | 12.00 | 14.10 | 12.30 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 60.00 | 8.00 | 13.46 | 13.30 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 1,136.00 | 5.00 | 7.07 | 7.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 280.00 | 10.00 | 6.61 | 4.70 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 20.00 | 6.00 | 9.80 | 7.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1,736.00 | 7.00 | 7.47 | 7.39 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 582.00 | 10.00 | 10.22 | 5.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 4,884.00 | 6.00 | 3.50 | 3.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 131.00 | 6.00 | 8.26 | 4.28 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 5,597.00 | 6.42 | 4.60 | 3.24 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 8,518.00 | 7.05 | 5.70 | 4.39 |
| ========== | 208-00052 | Storm Drain Inlet Protection (Type 2) | | Lin Foot | | | |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 10.00 | 10.00 | 12.17 | 6.25 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 20.00 | 10.00 | 5.54 | 5.39 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 16.00 | 20.00 | 111.13 | 8.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 46.00 | 13.48 | 15.44 | 4.39 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 36.00 | 11.00 | 14.68 | 5.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 200.00 | 5.00 | 4.89 | 3.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 495.00 | 8.00 | 6.75 | 6.34 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 20.00 | 6.00 | 22.89 | 6.54 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 751.00 | 7.29 | 7.26 | 5.39 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 797.00 | 7.65 | 8.98 | 5.08 |
| ========== | 208-00060 | Temporary Slope Drain | | Lin Foot | | | |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 90.00 | 8.00 | 23.88 | 13.24 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 90.00 | 8.00 | 23.88 | 13.24 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 90.00 | 8.00 | 21.68 | 11.53 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 208-00070 | Vehicle Tracking Pad | | Each | | | |
| C0704-225 | | I-70 EAST OF BENNETT | 01/06/11 | 1.00 | 1200.00 | 1418.00 | 912.00 |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 1.00 | 1350.00 | 1226.87 | 1100.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 60.00 | 1500.00 | 1710.30 | 1500.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 2.00 | 1500.00 | 1192.21 | 955.00 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 3.00 | 1000.00 | 1855.04 | 2000.00 |
| STA0504-061 | | US 50 M.P.369.9 -M.P.373.2 | 03/03/11 | 4.00 | 300.00 | 1093.10 | 1630.52 |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 1.00 | 1500.00 | 1898.60 | 2256.00 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 2.00 | 1500.00 | 2036.91 | 2100.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 8.00 | 1500.00 | 1490.96 | 1112.63 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 82.00 | 1417.68 | 1607.48 | 1604.57 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 4.00 | 1400.00 | 1424.45 | 1200.00 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 2.00 | 1300.00 | 1249.63 | 1448.50 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 6.00 | 1350.00 | 1684.92 | 1372.97 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 8.00 | 1500.00 | 1290.01 | 1200.00 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 1.00 | 1400.00 | 2058.92 | 2870.00 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 2.00 | 1000.00 | 2028.95 | 1670.00 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 1.00 | 1400.00 | 1247.53 | 700.79 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 1.00 | 2000.00 | 1800.00 | 1900.00 |
| C0241-055 | | SH 24 MP 148-152 | 05/26/11 | 1.00 | 1400.00 | 2129.94 | 1500.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 2.00 | 2500.00 | 1622.94 | 2150.00 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 2.00 | 1500.00 | 1628.98 | 1282.95 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 12.00 | 1350.00 | 1143.60 | 1100.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 2.00 | 2000.00 | 1948.33 | 2200.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 6.00 | 1250.00 | 1216.54 | 1279.14 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 58.00 | 1250.00 | 952.50 | 735.00 |
| FSA 0502-064 | | US 50 EAST OF SARGENTS | 06/23/11 | 3.00 | 1200.00 | 1699.32 | 1550.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 8.00 | 1500.00 | 1679.49 | 2500.21 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 119.00 | 1347.06 | 1324.93 | 1123.25 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 1.00 | 1500.00 | 1356.71 | 1350.00 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 1.00 | 1200.00 | 1870.00 | 1540.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 8.00 | 1500.00 | 1820.65 | 1190.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 2.00 | 1600.00 | 1935.95 | 2000.00 |
| BR2706-036 | | I-270 BRIDGE DECK REHABILITAT | 08/11/11 | 1.00 | 1500.00 | 1609.50 | 1553.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 208-00070 | Vehicle Tracking Pad | | Each | | | |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 2.00 | 2000.00 | 2165.00 | 1260.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 2.00 | 1500.00 | 1284.00 | 820.00 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 2.00 | 1200.00 | 1053.29 | 500.00 |
| STR096A-040 | | SH 96 MP 193 TO MP 201 | 09/01/11 | 2.00 | 1450.00 | 876.30 | 1278.89 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 3.00 | 1200.00 | 1395.42 | 1200.00 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 1.00 | 2200.00 | 2758.40 | 1900.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 25.00 | 1500.00 | 1523.40 | 1159.03 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 2.00 | 900.00 | 1684.22 | 1334.71 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 10.00 | 1200.00 | 1410.93 | 1004.14 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 10.00 | 1300.00 | 1360.00 | 1400.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 6.00 | 1350.00 | 1381.25 | 1100.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 19.00 | 1250.00 | 1283.65 | 374.86 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 5.00 | 1500.00 | 1848.67 | 1408.50 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 2.00 | 1000.00 | 1681.67 | 1600.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 1.00 | 1700.00 | 1918.14 | 2200.00 |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 2.00 | 1400.00 | 1636.64 | 1400.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 2.00 | 1000.00 | 1583.61 | 1300.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 59.00 | 1265.25 | 1428.85 | 987.72 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 285.00 | 1363.86 | 1437.07 | 1175.75 |
| ========== | 208-00103 | Removal and Disposal of Sediment (Labor) | | Hour | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 2.00 | 60.00 | 45.69 | 32.50 |
| C0704-225 | | I-70 EAST OF BENNETT | 01/06/11 | 15.00 | 40.00 | 34.70 | 31.80 |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 25.00 | 40.00 | 46.53 | 38.00 |
| ITS4701-121 | | C470 (SANTA FE TO I-25) AND R | 01/20/11 | 20.00 | 40.00 | 36.50 | 32.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 1,680.00 | 35.00 | 37.97 | 26.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 30.00 | 42.00 | 31.47 | 30.00 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 200.00 | 40.00 | 42.06 | 35.00 |
| NH 2852-017 | | US 285 PONCHA PASS SOUTH RESU | 03/03/11 | 10.00 | 40.00 | 39.30 | 40.00 |
| NH 0241-056 | | US 24 BUENA VISTA NORTH | 03/03/11 | 4.00 | 40.00 | 37.96 | 56.00 |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 60.00 | 40.00 | 39.44 | 35.00 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 52.00 | 55.00 | 52.91 | 35.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 300.00 | 35.00 | 42.33 | 43.15 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 2,398.00 | 36.24 | 41.12 | 34.11 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 208-00103 | Removal and Disposal of Sediment (Labor) | | Hour | | | |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 20.00 | 40.00 | 39.60 | 35.00 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 40.00 | 40.00 | 37.73 | 38.00 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 20.00 | 40.00 | 45.28 | 37.00 |
| STA0343-032 | | US 34 EAST OF AKRON | 04/07/11 | 4.00 | 50.00 | 43.67 | 36.00 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 60.00 | 40.00 | 42.00 | 36.00 |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 30.00 | 40.00 | 38.73 | 38.20 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 15.00 | 40.00 | 34.68 | 36.20 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 160.00 | 40.00 | 33.67 | 31.68 |
| SHE074A-001 | | SH 74 - EVERGREEN - JEFFERSON | 04/28/11 | 6.00 | 37.00 | 41.33 | 32.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 700.00 | 36.00 | 36.03 | 30.00 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 156.00 | 40.00 | 46.66 | 38.50 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 40.00 | 60.00 | 52.00 | 36.50 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 40.00 | 45.00 | 49.50 | 54.00 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 100.00 | 60.00 | 38.65 | 37.73 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 20.00 | 45.00 | 75.72 | 54.00 |
| C0241-055 | | SH 24 MP 148-152 | 05/26/11 | 32.00 | 40.00 | 54.76 | 32.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 120.00 | 37.00 | 44.75 | 30.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 30.00 | 50.00 | 54.07 | 46.00 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 10.00 | 60.00 | 52.03 | 56.55 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 40.00 | 40.00 | 44.66 | 30.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 40.00 | 40.00 | 56.00 | 90.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 60.00 | 40.00 | 36.52 | 25.58 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 53.00 | 40.00 | 41.33 | 42.00 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 15.00 | 40.00 | 53.00 | 35.00 |
| ITS0703-370 | | EAST OF EJMT ON I-70 EB LANES | 06/16/11 | 30.00 | 37.00 | 45.67 | 73.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 30.00 | 35.00 | 48.17 | 65.00 |
| FSA 0502-064 | | US 50 EAST OF SARGENTS | 06/23/11 | 20.00 | 40.00 | 71.90 | 51.75 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 20.00 | 40.00 | 51.50 | 25.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1,911.00 | 40.12 | 41.45 | 36.54 |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 20.00 | 40.00 | 44.13 | 43.00 |
| C006A-051 | | US 6 (LOVELAND PASS), CLEAR C | 07/14/11 | 10.00 | 41.10 | 66.75 | 50.00 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 10.00 | 50.00 | 60.38 | 30.00 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 40.00 | 40.00 | 57.12 | 48.58 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 60.00 | 40.00 | 55.24 | 53.55 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 16.00 | 40.00 | 76.30 | 30.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 80.00 | 35.00 | 44.18 | 40.00 |
| NH0403-053 | | US 40 RETAINING WALL REPAIR | 07/28/11 | 15.00 | 25.00 | 46.20 | 39.59 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 200.00 | 40.00 | 47.42 | 45.00 |
| BR2706-036 | | I-270 BRIDGE DECK REHABILITAT | 08/11/11 | 12.00 | 40.00 | 40.75 | 31.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 208-00103 | Removal and Disposal of Sediment (Labor) | | Hour | | | |
| NH5502-070 | | US 550 4 MILES SOUTH OF OURAY | 08/18/11 | 5.00 | 40.00 | 85.56 | 45.00 |
| C0091-038 | | SH 9 MM 81.9 BLUE RIVER EMERG | 08/24/11 | 20.00 | 25.00 | 70.33 | 108.00 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 100.00 | 80.00 | 46.45 | 54.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 30.00 | 40.00 | 38.80 | 38.00 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 20.00 | 50.00 | 43.90 | 44.00 |
| STR096A-040 | | SH 96 MP 193 TO MP 201 | 09/01/11 | 40.00 | 35.00 | 39.21 | 42.63 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 80.00 | 38.00 | 46.64 | 33.50 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 20.00 | 50.00 | 41.00 | 43.00 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 30.00 | 60.00 | 44.56 | 25.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 808.00 | 44.74 | 48.44 | 50.90 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 50.00 | 100.00 | 47.94 | 70.41 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 80.00 | 40.00 | 56.26 | 97.02 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 100.00 | 45.00 | 37.36 | 55.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 440.00 | 40.00 | 34.16 | 32.00 |
| SHE0402-081 | | US 40 - MP 113 TO 120 ROUTT C | 10/27/11 | 12.00 | 40.00 | 70.57 | 21.40 |
| ITSSW00-928 | | NB I-225 AT MM 2.28 | 11/03/11 | 20.00 | 40.00 | 41.25 | 45.00 |
| STA0343-033 | | SH 34 ECKLEY | 11/10/11 | 4.00 | 36.00 | 33.50 | 1.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 45.00 | 40.00 | 36.98 | 44.12 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 160.00 | 40.00 | 43.65 | 30.18 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 10.00 | 50.00 | 52.50 | 45.00 |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 40.00 | 40.00 | 51.00 | 54.00 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 20.00 | 45.00 | 42.67 | 43.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 80.00 | 40.00 | 40.44 | 50.00 |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 5.00 | 40.00 | 50.00 | 60.00 |
| IM0703-368 | | GEORGETOWN HILL CHUTES 6,7,9, | 12/01/11 | 12.00 | 35.25 | 61.21 | 40.00 |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 90.00 | 30.00 | 44.23 | 45.00 |
| C2854-125 | | US 285, ASPEN PARK TO MORRISO | 12/08/11 | 10.00 | 50.00 | 48.33 | 50.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 360.00 | 40.00 | 38.70 | 48.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 1,538.00 | 41.84 | 40.17 | 44.78 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 6,655.00 | 39.68 | 42.04 | 40.69 |
| ========== | 208-00105 | Removal and Disposal of Sediment (Equip) | | Hour | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 1.00 | 100.00 | 232.80 | 100.00 |
| C0704-225 | | I-70 EAST OF BENNETT | 01/06/11 | 6.00 | 100.00 | 44.28 | 37.10 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 1,440.00 | 55.00 | 88.57 | 50.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 208-00105 | Removal and Disposal of Sediment (Equip) | | Hour | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 15.00 | 98.00 | 57.36 | 60.00 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 100.00 | 70.00 | 89.96 | 87.00 |
| NH 2852-017 | | US 285 PONCHA PASS SOUTH RESU | 03/03/11 | 10.00 | 80.00 | 84.00 | 100.00 |
| NH 0241-056 | | US 24 BUENA VISTA NORTH | 03/03/11 | 4.00 | 80.00 | 84.58 | 125.00 |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 30.00 | 75.00 | 61.10 | 50.00 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 52.00 | 85.00 | 101.19 | 60.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 300.00 | 55.00 | 91.50 | 92.26 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1,958.00 | 57.54 | 87.78 | 69.29 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 10.00 | 80.00 | 71.30 | 50.00 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 10.00 | 90.00 | 59.21 | 55.00 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 40.00 | 80.00 | 75.37 | 75.00 |
| STA0343-032 | | US 34 EAST OF AKRON | 04/07/11 | 4.00 | 100.00 | 51.67 | 50.00 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 60.00 | 60.00 | 83.67 | 62.00 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 8.00 | 80.00 | 69.26 | 54.30 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 160.00 | 60.00 | 68.69 | 68.65 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 560.00 | 56.00 | 63.16 | 71.00 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 40.00 | 75.00 | 76.50 | 78.00 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 10.00 | 80.00 | 96.00 | 78.00 |
| C0241-055 | | SH 24 MP 148-152 | 05/26/11 | 32.00 | 80.00 | 108.27 | 63.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 120.00 | 64.00 | 85.70 | 131.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 30.00 | 70.00 | 87.81 | 85.00 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 10.00 | 90.00 | 106.04 | 122.08 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 40.00 | 80.00 | 76.71 | 71.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 20.00 | 80.00 | 85.33 | 150.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 60.00 | 60.00 | 57.61 | 40.93 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 6.00 | 80.00 | 58.75 | 50.00 |
| ITS0703-370 | | EAST OF EJMT ON I-70 EB LANES | 06/16/11 | 15.00 | 67.00 | 72.33 | 73.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 10.00 | 80.00 | 85.58 | 145.00 |
| FSA 0502-064 | | US 50 EAST OF SARGENTS | 06/23/11 | 20.00 | 60.00 | 137.76 | 97.75 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 200.00 | 25.00 | 69.85 | 115.31 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1,465.00 | 57.63 | 73.06 | 79.79 |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 20.00 | 80.00 | 90.76 | 80.00 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 10.00 | 100.00 | 118.87 | 135.00 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 16.00 | 65.00 | 50.18 | 40.48 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 10.00 | 75.00 | 78.80 | 70.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 40.00 | 60.00 | 84.95 | 50.00 |
| NH0403-053 | | US 40 RETAINING WALL REPAIR | 07/28/11 | 5.00 | 100.00 | 124.18 | 152.53 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 100.00 | 75.00 | 75.24 | 75.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 208-00105 | Removal and Disposal of Sediment (Equip) | | Hour | | | |
| BR2706-036 | | I-270 BRIDGE DECK REHABILITAT | 08/11/11 | 12.00 | 60.00 | 85.88 | 76.00 |
| NH5502-070 | | US 550 4 MILES SOUTH OF OURAY | 08/18/11 | 5.00 | 115.00 | 156.62 | 165.00 |
| C0091-038 | | SH 9 MM 81.9 BLUE RIVER EMERG | 08/24/11 | 20.00 | 100.00 | 219.86 | 254.00 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 100.00 | 90.00 | 93.06 | 78.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 10.00 | 150.00 | 75.00 | 70.00 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 10.00 | 80.00 | 75.33 | 70.00 |
| STR096A-040 | | SH 96 MP 193 TO MP 201 | 09/01/11 | 20.00 | 70.00 | 76.42 | 69.27 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 40.00 | 65.00 | 90.81 | 39.00 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 5.00 | 80.00 | 84.67 | 59.00 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 15.00 | 100.00 | 145.46 | 105.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 438.00 | 80.56 | 91.42 | 88.55 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 80.00 | 120.00 | 95.65 | 118.43 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 100.00 | 100.00 | 81.43 | 70.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 440.00 | 75.00 | 73.68 | 55.00 |
| SHE0402-081 | | US 40 - MP 113 TO 120 ROUTT C | 10/27/11 | 12.00 | 50.00 | 118.97 | 48.83 |
| STA0343-033 | | SH 34 ECKLEY | 11/10/11 | 4.00 | 50.00 | 84.00 | 1.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 45.00 | 60.00 | 70.02 | 82.73 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 160.00 | 60.00 | 73.59 | 65.39 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 10.00 | 80.00 | 95.00 | 70.00 |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 10.00 | 70.00 | 124.13 | 191.50 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 20.00 | 75.00 | 114.65 | 68.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 80.00 | 60.00 | 84.38 | 75.00 |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 5.00 | 115.00 | 118.00 | 156.00 |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 60.00 | 60.00 | 82.46 | 80.00 |
| C2854-125 | | US 285, ASPEN PARK TO MORRISO | 12/08/11 | 4.00 | 90.00 | 83.17 | 85.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 360.00 | 100.00 | 74.75 | 97.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1,390.00 | 82.04 | 77.10 | 76.39 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 5,251.00 | 65.97 | 79.87 | 77.85 |
| ========== | 208-00106 | Sweeping (Sediment Removal) | | Hour | | | |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 12.00 | 100.00 | 135.90 | 185.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 12.00 | 100.00 | 135.90 | 185.00 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 40.00 | 146.00 | 106.29 | 45.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 208-00106 | Sweeping (Sediment Removal) | | Hour | | | |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 450.00 | 50.00 | 146.80 | 50.00 |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 100.00 | 100.00 | 111.06 | 105.50 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 6.00 | 70.00 | 166.88 | 252.50 |
| SHE074A-001 | | SH 74 - EVERGREEN - JEFFERSON | 04/28/11 | 3.00 | 65.00 | 119.00 | 77.00 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 100.00 | 75.00 | 135.31 | 222.00 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 140.00 | 75.00 | 137.43 | 140.16 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 16.00 | 80.00 | 184.67 | 264.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 160.00 | 135.00 | 135.41 | 138.15 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 10.00 | 70.00 | 152.00 | 75.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 30.00 | 90.00 | 149.17 | 165.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 1,055.00 | 78.90 | 139.80 | 107.38 |
| C006A-051 | | US 6 (LOVELAND PASS), CLEAR C | 07/14/11 | 10.00 | 100.00 | 159.50 | 78.00 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 20.00 | 70.00 | 137.21 | 102.55 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 12.00 | 80.00 | 187.49 | 133.00 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 130.00 | 100.00 | 125.10 | 71.22 |
| NH0403-053 | | US 40 RETAINING WALL REPAIR | 07/28/11 | 25.00 | 100.00 | 157.67 | 138.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 90.00 | 75.00 | 121.24 | 155.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 10.00 | 146.00 | 133.00 | 165.00 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 18.00 | 80.00 | 116.03 | 105.00 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 10.00 | 150.00 | 128.33 | 105.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 325.00 | 92.34 | 123.57 | 102.41 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 25.00 | 80.00 | 115.29 | 94.87 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 650.00 | 120.00 | 91.53 | 59.98 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 600.00 | 125.00 | 113.64 | 145.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 50.00 | 130.00 | 184.15 | 150.00 |
| ITSSW00-928 | | NB I-225 AT MM 2.28 | 11/03/11 | 10.00 | 60.00 | 106.53 | 45.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 160.00 | 100.00 | 106.46 | 94.56 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 500.00 | 130.00 | 130.78 | 100.61 |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 30.00 | 155.00 | 117.55 | 70.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 2,025.00 | 122.35 | 114.06 | 100.66 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3,417.00 | 106.00 | 122.44 | 103.31 |
| ========== | 208-00107 | Rem Trash | | Hour | | | |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 600.00 | 50.00 | 58.18 | 30.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 208-00107 | Rem Trash | | Hour | | | |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 50.00 | 50.00 | 40.48 | 38.20 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 6.00 | 25.00 | 38.93 | 30.70 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 150.00 | 25.00 | 48.67 | 36.50 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 16.00 | 45.00 | 85.98 | 54.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 5.00 | 50.00 | 47.67 | 60.00 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 10.00 | 25.00 | 115.00 | 35.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 837.00 | 44.95 | 59.05 | 35.75 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 20.00 | 25.00 | 83.60 | 53.98 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 8.00 | 60.00 | 73.40 | 53.00 |
| NH0403-053 | | US 40 RETAINING WALL REPAIR | 07/28/11 | 5.00 | 20.00 | 119.53 | 39.59 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 90.00 | 25.00 | 78.32 | 115.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 10.00 | 25.00 | 50.00 | 42.00 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 15.00 | 50.00 | 48.99 | 40.00 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 5.00 | 50.00 | 57.67 | 43.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 153.00 | 29.93 | 57.17 | 86.06 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 650.00 | 30.00 | 57.07 | 54.36 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 431.00 | 45.00 | 38.50 | 55.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 80.00 | 50.00 | 64.23 | 33.09 |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 30.00 | 35.00 | 47.23 | 40.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1,191.00 | 36.90 | 49.57 | 52.80 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,181.00 | 39.50 | 54.53 | 51.23 |
| ========== | 208-00205 | Erosion Control Supervisor | | Hour | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 40.00 | 50.00 | 65.39 | 49.00 |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 50.00 | 60.00 | 58.81 | 58.00 |
| ITS4701-121 | | C470 (SANTA FE TO I-25) AND R | 01/20/11 | 70.00 | 60.00 | 62.25 | 70.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 2,400.00 | 60.00 | 62.35 | 10.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 800.00 | 45.00 | 51.10 | 15.00 |
| NH 0241-056 | | US 24 BUENA VISTA NORTH | 03/03/11 | 40.00 | 50.00 | 86.17 | 70.00 |
| STA0504-061 | | US 50 M.P.369.9 -M.P.373.2 | 03/03/11 | 50.00 | 60.00 | 62.08 | 45.40 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 208-00205 | Erosion Control Supervisor | | Hour | | | |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 60.00 | 50.00 | 60.65 | 60.00 |
| NH 0402-079 | | US40 MP 165.0 - 179.0 GRAND C | 03/31/11 | 100.00 | 35.00 | 53.56 | 47.40 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 3,610.00 | 55.60 | 57.40 | 30.88 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 100.00 | 45.00 | 56.79 | 55.00 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 200.00 | 60.00 | 67.17 | 60.50 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 150.00 | 50.00 | 74.05 | 78.20 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 240.00 | 50.00 | 66.75 | 68.50 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 250.00 | 50.00 | 61.36 | 59.30 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 480.00 | 60.00 | 51.00 | 68.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 50.00 | 65.00 | 82.50 | 95.00 |
| FSA 0502-064 | | US 50 EAST OF SARGENTS | 06/23/11 | 40.00 | 80.00 | 64.78 | 69.00 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 50.00 | 60.00 | 70.50 | 63.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1,560.00 | 55.61 | 55.66 | 60.88 |
| NH2872-018 | | US 287 RUSH CREEK NORTH | 07/21/11 | 50.00 | 25.00 | 87.33 | 52.00 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 260.00 | 60.00 | 152.81 | 69.55 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 300.00 | 50.00 | 63.77 | 80.00 |
| BR2706-036 | | I-270 BRIDGE DECK REHABILITAT | 08/11/11 | 36.00 | 60.00 | 55.25 | 46.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 80.00 | 45.00 | 70.80 | 69.00 |
| STR096A-040 | | SH 96 MP 193 TO MP 201 | 09/01/11 | 120.00 | 23.00 | 42.55 | 27.64 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 180.00 | 35.00 | 60.86 | 44.50 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 20.00 | 100.00 | 72.17 | 64.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1,046.00 | 46.53 | 73.72 | 73.68 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 800.00 | 60.00 | 49.13 | 51.15 |
| NH0501-060 | | US50 MP 74.0 TO 81, 94.2 TO 1 | 10/20/11 | 20.00 | 150.00 | 52.91 | 40.00 |
| ITSSW00-928 | | NB I-225 AT MM 2.28 | 11/03/11 | 20.00 | 60.00 | 68.65 | 45.00 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 20.00 | 100.00 | 70.00 | 90.00 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 100.00 | 50.00 | 95.82 | 96.00 |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 150.00 | 57.00 | 65.42 | 60.00 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 200.00 | 70.00 | 55.17 | 58.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1,310.00 | 62.40 | 54.78 | 56.96 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 7,526.00 | 55.52 | 59.62 | 53.52 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 208-00206 | Erosion Control Supervisor | | Day | | | |
| NH 2852-017 | | US 285 PONCHA PASS SOUTH RESU | 03/03/11 | 30.00 | 250.00 | 165.33 | 40.00 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 100.00 | 175.00 | 249.59 | 110.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 550.00 | 90.00 | 147.81 | 134.95 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 680.00 | 109.56 | 157.64 | 130.68 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 85.00 | 100.00 | 74.60 | 75.00 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 150.00 | 100.00 | 124.40 | 75.00 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 80.00 | 110.00 | 110.50 | 113.50 |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 40.00 | 100.00 | 127.50 | 120.60 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 30.00 | 100.00 | 92.15 | 96.60 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 390.00 | 90.00 | 84.83 | 105.61 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 540.00 | 100.00 | 71.49 | 20.00 |
| C0241-055 | | SH 24 MP 148-152 | 05/26/11 | 16.00 | 150.00 | 120.79 | 115.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 200.00 | 200.00 | 204.71 | 185.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 190.00 | 70.00 | 95.71 | 65.00 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 20.00 | 950.00 | 250.00 | 315.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 413.00 | 100.00 | 81.43 | 15.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 180.00 | 150.00 | 151.00 | 110.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 240.00 | 90.00 | 167.71 | 102.33 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 120.00 | 100.00 | 230.87 | 231.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 315.00 | 20.00 | 85.08 | 25.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 3,009.00 | 103.46 | 112.67 | 76.71 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 24.00 | 200.00 | 146.07 | 130.00 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 81.00 | 80.00 | 108.48 | 91.76 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 352.00 | 100.00 | 74.62 | 92.00 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 55.00 | 450.00 | 242.75 | 401.00 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 33.00 | 150.00 | 522.20 | 155.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 545.00 | 139.78 | 116.95 | 137.27 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 160.00 | 160.00 | 98.26 | 91.51 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 431.00 | 110.00 | 92.06 | 76.39 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 600.00 | 100.00 | 55.83 | 10.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 320.00 | 90.00 | 85.61 | 88.24 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 208-00206 | Erosion Control Supervisor | | Day | | | |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 452.00 | 100.00 | 87.44 | 62.30 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 57.00 | 240.00 | 161.75 | 247.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 200.00 | 120.00 | 159.85 | 50.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2,220.00 | 110.22 | 92.31 | 60.38 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 6,454.00 | 109.49 | 111.73 | 82.57 |
| ========== | 208-00300 | Temporary Berms | | Lin Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 6,000.00 | 8.00 | 4.90 | 4.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 6,000.00 | 8.00 | 4.90 | 4.00 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 2,000.00 | 6.00 | 2.96 | 1.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 400.00 | 5.00 | 2.91 | 1.80 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 1,000.00 | 10.00 | 3.07 | 1.10 |
| FSA 0502-064 | | US 50 EAST OF SARGENTS | 06/23/11 | 100.00 | 20.00 | 27.26 | 25.25 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 3,500.00 | 7.43 | 2.09 | 1.21 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 60.00 | 4.00 | 7.04 | 7.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 90.00 | 10.00 | 8.54 | 3.96 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 150.00 | 7.60 | 7.99 | 5.18 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 9,650.00 | 7.79 | 2.52 | 1.63 |
| ========== | 208-00400 | Water Control | | LUMP SUM | | | |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 1.00 | 25000.00 | 64456.34 | 52300.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1.00 | 25000.00 | 64456.34 | 52300.00 |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 1.00 | 30000.00 | 51140.74 | 63000.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 208-00400 | Water Control | | LUMP SUM | ========== | ========== | ========== |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 1.00 | 15000.00 | 27013.57 | 10000.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 2.00 | 22500.00 | 32505.47 | 27666.67 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 1.00 | 20000.00 | 61278.87 | 11152.94 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1.00 | 30000.00 | 10649.61 | 5080.99 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 25000.00 | 35964.24 | 8116.97 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 5.00 | 24000.00 | 39480.38 | 25255.66 |
| ========== | 209-00100 | Water (Landscaping) | | M Gallon | ========== | ========== | ========== |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 36.00 | 150.00 | 107.97 | 137.30 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 17.00 | 150.00 | 269.37 | 180.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 5.00 | 300.00 | 921.67 | 2000.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 0.13 | 1000.00 | 95566.91 | 2558.28 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 58.13 | 164.76 | 297.09 | 315.30 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 10.00 | 500.00 | 192.04 | 65.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 10.00 | 500.00 | 192.04 | 65.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 158.00 | 50.00 | 91.37 | 143.39 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 158.00 | 50.00 | 91.37 | 143.39 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 226.13 | 99.40 | 144.32 | 184.11 |
| ========== | 209-00200 | Time-Released Water Product | | Each | ========== | ========== | ========== |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 1,452.00 | 10.00 | 3.82 | 4.17 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 660.00 | 6.00 | 5.64 | 4.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 3,112.00 | 6.00 | 6.20 | 4.04 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 5,224.00 | 7.11 | 5.15 | 4.07 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 209-00200 | Time-Released Water Product | | Each | | | |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 4,136.00 | 4.00 | 5.97 | 8.06 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1.00 | 20.00 | 92.95 | 51.25 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 4,137.00 | 4.00 | 5.99 | 8.07 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 9,361.00 | 5.74 | 5.60 | 5.84 |
| ========== | 209-00600 | Dust Palliative (Mg Cl) | | Gallon | | | |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 30,333.00 | 0.90 | 0.70 | 0.08 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 30,333.00 | 0.90 | 0.70 | 0.08 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 15,000.00 | 1.00 | 1.05 | 0.80 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 15,000.00 | 1.00 | 1.05 | 0.80 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 4,700.00 | 2.00 | 1.11 | 0.85 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 4,700.00 | 2.00 | 1.11 | 0.85 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 50,033.00 | 1.03 | 0.86 | 0.37 |
| ========== | 210-00001 | Res Structure | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 4.00 | 2000.00 | 4631.66 | 2995.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 4.00 | 2000.00 | 4631.66 | 2995.00 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 1.00 | 7000.00 | 2311.00 | 1350.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 210-00001 | Res Structure | | Each | | | |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 2.00 | 300.00 | 1487.33 | 620.00 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 3.00 | 2533.33 | 1605.00 | 863.33 |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 16.00 | 200.00 | 322.83 | 76.00 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 16.00 | 200.00 | 322.83 | 76.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 15.00 | 1000.00 | 789.37 | 1207.29 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 1.00 | 1000.00 | 3174.04 | 3188.00 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 16.00 | 1000.00 | 828.46 | 1331.08 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 39.00 | 892.31 | 814.19 | 780.51 |
| ========== | 210-00010 | Res Mailbox Str | | Each | | | |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 5.00 | 150.00 | 232.33 | 250.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 4.00 | 300.00 | 181.04 | 200.00 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 9.00 | 216.67 | 197.41 | 227.78 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 1.00 | 300.00 | 373.50 | 130.00 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 1.00 | 300.00 | 373.50 | 130.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 10.00 | 225.00 | 225.71 | 218.00 |
| ========== | 210-00011 | Res Mailbox Str (Ty 1) | | Each | | | |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 16.00 | 200.00 | 208.63 | 129.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 16.00 | 200.00 | 208.63 | 129.00 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 1.00 | 200.00 | 257.00 | 264.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 210-00011 | Res Mailbox Str (Ty 1) | | Each | | | |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 5.00 | 150.00 | 334.00 | 410.00 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 6.00 | 158.33 | 343.57 | 388.86 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 1.00 | 190.00 | 146.11 | 129.54 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 4.00 | 125.00 | 445.34 | 389.00 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 5.00 | 138.00 | 374.10 | 337.11 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 12.00 | 190.00 | 172.14 | 190.00 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 12.00 | 190.00 | 172.14 | 190.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 39.00 | 182.56 | 224.38 | 218.79 |
| ========== | 210-00012 | Res Mailbox Str (Ty 2) | | Each | | | |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 2.00 | 225.00 | 385.00 | 395.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 1.00 | 170.00 | 334.00 | 410.00 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 3.00 | 206.67 | 384.82 | 402.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 3.00 | 200.00 | 184.29 | 225.00 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 3.00 | 200.00 | 184.29 | 225.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 6.00 | 203.33 | 253.22 | 326.14 |
| ========== | 210-00013 | Res Mailbox Str (Ty 3) | | Each | | | |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 1.00 | 400.00 | 392.33 | 410.00 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 1.00 | 400.00 | 417.95 | 408.40 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 11.00 | 240.00 | 317.71 | 345.00 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 11.00 | 240.00 | 317.71 | 345.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 12.00 | 253.33 | 337.55 | 364.81 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 210-00015 | Res End Section | | Each | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1.00 | 120.00 | 385.83 | 338.28 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1.00 | 120.00 | 385.83 | 338.28 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 2.00 | 400.00 | 406.88 | 447.39 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 400.00 | 406.88 | 447.39 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3.00 | 306.67 | 398.99 | 411.02 |
| ========== | 210-00030 | Res Water Service | | Each | | | |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 15.00 | 1000.00 | 1767.09 | 2000.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 15.00 | 1000.00 | 1767.09 | 2000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 15.00 | 1000.00 | 1767.09 | 2000.00 |
| ========== | 210-00035 | Res Water Meter | | Each | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 8.00 | 900.00 | 744.29 | 220.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 8.00 | 900.00 | 744.29 | 220.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 8.00 | 900.00 | 744.29 | 220.00 |
| ========== | 210-00060 | Res Marker | | Each | | | |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 10.00 | 12.00 | 56.00 | 20.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 18.00 | 150.00 | 103.30 | 97.21 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 28.00 | 100.71 | 89.39 | 69.64 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 28.00 | 100.71 | 114.43 | 81.06 |
| ========== | 210-00065 | Res Monument (Ty 3A) | | Each | | | |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 1.00 | 560.00 | 602.92 | 511.66 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1.00 | 560.00 | 602.92 | 511.66 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 210-00065 | Res Monument (Ty 3A) | | Each | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 3.00 | 1500.00 | 442.00 | 360.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 3.00 | 1500.00 | 442.00 | 360.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4.00 | 1265.00 | 467.75 | 397.92 |
| ========== | 210-00090 | Res Delineator | | Each | | | |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 41.00 | 26.00 | 19.79 | 19.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 41.00 | 26.00 | 25.67 | 21.42 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 41.00 | 26.00 | 25.67 | 21.42 |
| ========== | 210-00440 | Repair Curb | | Lin Foot | | | |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 55.00 | 30.00 | 82.33 | 74.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 55.00 | 30.00 | 82.33 | 74.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 55.00 | 30.00 | 82.33 | 74.00 |
| ========== | 210-00473 | Res TV Cameras | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 4.00 | 600.00 | 2576.90 | 1400.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 4.00 | 600.00 | 2576.90 | 1400.00 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 1.00 | 700.00 | 949.00 | 603.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1.00 | 700.00 | 949.00 | 603.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1.00 | 500.00 | 1490.86 | 1609.72 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 500.00 | 1490.86 | 1609.72 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 6.00 | 600.00 | 1948.27 | 1204.24 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 210-00500 | Reb Port Present Str | | Each | | | |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 4.00 | 5000.00 | 2128.30 | 1100.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 4.00 | 5000.00 | 2128.30 | 1100.00 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 1.00 | 3000.00 | 521.88 | 524.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 3000.00 | 521.88 | 524.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 5.00 | 4600.00 | 374.21 | 273.70 |
| ========== | 210-00750 | Res Light Standard | | Each | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 3.00 | 400.00 | 1215.58 | 1285.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 3.00 | 400.00 | 1215.58 | 1285.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1.00 | 1100.00 | 1560.00 | 1500.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 1100.00 | 1560.00 | 1500.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4.00 | 575.00 | 1325.17 | 1338.75 |
| ========== | 210-00805 | Res Overhead Sign Str | | Each | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 2.00 | 4000.00 | 5214.04 | 9243.23 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 2.00 | 4000.00 | 5214.04 | 9243.23 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1.00 | 8000.00 | 6645.64 | 7000.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 8000.00 | 6645.64 | 7000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3.00 | 5333.33 | 5554.89 | 8495.49 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 210-00810 | Res Ground Sign | | Each | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 4.00 | 300.00 | 311.11 | 350.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 4.00 | 300.00 | 594.71 | 832.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 8.00 | 250.00 | 298.24 | 240.00 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 1.00 | 200.00 | 214.39 | 350.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 1.00 | 300.00 | 254.25 | 165.07 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 18.00 | 272.22 | 323.33 | 292.83 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 3.00 | 100.00 | 151.80 | 100.00 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 60.00 | 200.00 | 163.44 | 185.00 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 5.00 | 200.00 | 164.33 | 100.00 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 1.00 | 250.00 | 441.25 | 765.00 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 7.00 | 200.00 | 276.36 | 200.03 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 11.00 | 150.00 | 190.00 | 195.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 16.00 | 300.00 | 285.81 | 337.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 2.00 | 250.00 | 41.39 | 95.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 2.00 | 300.00 | 523.17 | 660.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 4.00 | 250.00 | 234.33 | 150.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 10.00 | 300.00 | 269.71 | 255.83 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 2.00 | 200.00 | 502.67 | 455.00 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 1.00 | 250.00 | 172.00 | 73.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 35.00 | 50.00 | 131.57 | 60.34 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 159.00 | 181.76 | 199.32 | 191.39 |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 8.00 | 50.00 | 296.96 | 430.00 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 4.00 | 200.00 | 159.14 | 199.71 |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 2.00 | 150.00 | 233.00 | 70.00 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 2.00 | 250.00 | 397.38 | 153.00 |
| NH0403-053 | | US 40 RETAINING WALL REPAIR | 07/28/11 | 1.00 | 400.00 | 268.94 | 246.82 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 20.00 | 150.00 | 166.66 | 182.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 1.00 | 100.00 | 260.80 | 250.00 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 2.00 | 250.00 | 291.13 | 200.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 40.00 | 150.00 | 174.26 | 134.57 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 53.00 | 200.00 | 164.57 | 160.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 210-00810 | Res Ground Sign | | Each | | | |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 16.00 | 200.00 | 304.77 | 300.00 |
| SHE025A-013 | | I 25 BETWEEN MP 122 AND MP 12 | 11/03/11 | 2.00 | 310.00 | 443.33 | 200.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 12.00 | 300.00 | 147.50 | 204.06 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 3.00 | 500.00 | 481.63 | 559.00 |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 2.00 | 200.00 | 752.63 | 578.50 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 4.00 | 150.00 | 169.28 | 170.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 3.00 | 850.00 | 1701.89 | 1600.00 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 4.00 | 150.00 | 365.67 | 390.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 99.00 | 239.09 | 231.68 | 262.65 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 316.00 | 200.85 | 210.94 | 199.62 |
| ========== | 210-00815 | Res Sign Panel | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 4.00 | 150.00 | 204.90 | 50.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 10.00 | 80.00 | 81.50 | 45.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 2.00 | 450.00 | 173.16 | 110.05 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 16.00 | 143.75 | 112.10 | 57.88 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 8.00 | 500.00 | 84.30 | 100.00 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 2.00 | 100.00 | 470.82 | 108.16 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 14.00 | 60.00 | 76.60 | 55.31 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 24.00 | 210.00 | 121.71 | 74.61 |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 2.00 | 100.00 | 86.00 | 35.00 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 12.00 | 100.00 | 110.68 | 48.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 3.00 | 500.00 | 136.68 | 155.00 |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 9.00 | 70.00 | 46.00 | 48.00 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 2.00 | 50.00 | 181.43 | 105.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 28.00 | 129.64 | 103.19 | 57.69 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 3.00 | 100.00 | 86.54 | 109.48 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 210-00815 | Res Sign Panel | | Each | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 8.00 | 65.00 | 60.14 | 57.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 35.00 | 50.00 | 74.23 | 175.00 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 6.00 | 250.00 | 115.63 | 58.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 52.00 | 78.27 | 73.81 | 139.57 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 120.00 | 125.33 | 96.99 | 94.43 |
| ========== | 210-00820 | Res Var Mesg Sign | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 4.00 | 8000.00 | 3822.84 | 2700.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 4.00 | 8000.00 | 3822.84 | 2700.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1.00 | 3000.00 | 8203.20 | 8756.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 3000.00 | 8203.20 | 8756.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 5.00 | 7000.00 | 5387.25 | 5728.00 |
| ========== | 210-00825 | Res Flashing Beacon | | Each | | | |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 1.00 | 1500.00 | 1830.00 | 1160.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1.00 | 1500.00 | 1830.00 | 1160.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 1500.00 | 965.43 | 841.58 |
| ========== | 210-00827 | Res Pull Box | | Each | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 1.00 | 250.00 | 651.95 | 65.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1.00 | 250.00 | 338.33 | 215.00 |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 1.00 | 250.00 | 270.40 | 200.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1.00 | 250.00 | 476.60 | 416.78 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 250.00 | 374.40 | 368.83 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 210-00831 | Res Traf Sig Head | | Each | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 13.00 | 100.00 | 142.07 | 135.77 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 13.00 | 100.00 | 142.07 | 135.77 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 13.00 | 100.00 | 142.07 | 135.77 |
| ========== | 210-00840 | Res Traf Sig Pole | | Each | | | |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 9.00 | 2000.00 | 1528.16 | 1664.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 9.00 | 2000.00 | 1528.16 | 1664.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 9.00 | 2000.00 | 1528.16 | 1664.00 |
| ========== | 210-00848 | Res Traf Sig Control+Cab | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 4.00 | 4000.00 | 4890.69 | 5000.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 4.00 | 4000.00 | 4890.69 | 5000.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 1.00 | 5000.00 | 2889.33 | 2900.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1.00 | 1500.00 | 2218.88 | 2108.97 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 2.00 | 3250.00 | 2554.11 | 2504.49 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 6.00 | 3750.00 | 3385.02 | 2898.49 |
| ========== | 210-00855 | Res Traf Sig Control Cab | | Each | | | |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 2.00 | 1500.00 | 1241.14 | 1810.93 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 1500.00 | 1241.14 | 1810.93 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 1500.00 | 1241.14 | 1810.93 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 210-00858 | Res Pedestal Pole | | Each | | | |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 2.00 | 700.00 | 228.91 | 92.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 700.00 | 228.91 | 92.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 700.00 | 228.91 | 92.00 |
| ========== | 210-00860 | Res Ped Push Button | | Each | | | |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 8.00 | 100.00 | 113.33 | 37.30 |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 13.00 | 25.00 | 114.00 | 118.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 21.00 | 53.57 | 113.63 | 87.26 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1.00 | 500.00 | 133.29 | 110.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 500.00 | 133.29 | 110.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 22.00 | 73.86 | 115.75 | 88.29 |
| ========== | 210-00865 | Res Ped Sig Head | | Each | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 4.00 | 100.00 | 52.43 | 50.29 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 4.00 | 100.00 | 52.43 | 50.29 |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 13.00 | 100.00 | 228.00 | 236.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 13.00 | 100.00 | 228.00 | 236.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 17.00 | 100.00 | 143.73 | 192.30 |
| ========== | 210-00866 | Res Fire Preempt Unit+Timer | | Each | | | |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 1.00 | 100.00 | 204.42 | 286.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 210-00866 | Res Fire Preempt Unit+Timer | | Each | | | |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 1.00 | 500.00 | 1084.32 | 407.28 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2.00 | 300.00 | 556.38 | 346.64 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 1.00 | 200.00 | 1491.67 | 715.00 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 6.00 | 550.00 | 536.94 | 295.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 7.00 | 500.00 | 643.02 | 355.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 4.00 | 400.00 | 988.93 | 1207.29 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 4.00 | 400.00 | 988.93 | 1207.29 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 13.00 | 438.46 | 790.89 | 615.96 |
| ========== | 210-00890 | Res Int Detect Sys (Camera) | | Each | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1.00 | 400.00 | 2288.82 | 2180.38 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1.00 | 400.00 | 2288.82 | 2180.38 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 400.00 | 2288.82 | 2180.38 |
| ========== | 210-00910 | Res Traffic Counter (Perm) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 16.00 | 750.00 | 1344.57 | 445.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 16.00 | 750.00 | 1344.57 | 445.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 16.00 | 750.00 | 1344.57 | 445.00 |
| ========== | 210-01000 | Res Fence | | Lin Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 2,168.00 | 6.00 | 15.39 | 12.55 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 210-01000 | Res Fence | | Lin Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 2,168.00 | 6.00 | 15.39 | 12.55 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 439.00 | 5.00 | 6.46 | 6.13 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 439.00 | 5.00 | 6.46 | 6.13 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 61.00 | 10.00 | 3.50 | 5.00 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 505.00 | 35.00 | 10.55 | 12.50 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 566.00 | 32.31 | 9.18 | 8.84 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 212.00 | 20.00 | 24.27 | 25.00 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 212.00 | 20.00 | 24.27 | 25.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 3,385.00 | 11.15 | 11.18 | 10.79 |
| ========== | 210-01005 | Res Fence Post | | Each | | | |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 4.00 | 30.00 | 43.32 | 50.00 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 4.00 | 30.00 | 43.32 | 50.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 4.00 | 30.00 | 43.32 | 50.00 |
| ========== | 210-01011 | Res Gate | | Each | | | |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 1.00 | 500.00 | 568.70 | 635.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1.00 | 250.00 | 291.06 | 266.51 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 2.00 | 375.00 | 440.55 | 450.76 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 210-01011 | Res Gate | | Each | | | |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 1.00 | 200.00 | 329.33 | 500.00 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 6.00 | 600.00 | 356.72 | 450.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 7.00 | 542.86 | 354.40 | 457.14 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 1.00 | 400.00 | 418.82 | 492.68 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 2.00 | 400.00 | 110.57 | 110.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 3.00 | 400.00 | 191.69 | 237.56 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 12.00 | 479.17 | 332.73 | 401.18 |
| ========== | 210-01130 | Res Gdrail Ty 3 | | Lin Foot | | | |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 988.00 | 6.00 | 8.31 | 13.00 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 1,121.00 | 5.00 | 7.78 | 6.80 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 24.00 | 50.00 | 112.16 | 49.32 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2,133.00 | 5.97 | 8.93 | 9.98 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 175.00 | 9.00 | 8.57 | 8.80 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 175.00 | 9.00 | 12.99 | 9.51 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 762.00 | 11.00 | 7.29 | 5.90 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 762.00 | 11.00 | 7.29 | 5.90 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3,070.00 | 7.39 | 9.05 | 9.24 |
| ========== | 210-01180 | Reset Guardrail (Special) | | Lin Foot | | | |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 14,419.00 | 7.50 | 2.12 | 2.10 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 14,419.00 | 7.50 | 2.12 | 2.10 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 14,419.00 | 7.50 | 2.12 | 2.10 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 210-01200 | Res End Anchorage | | Each | | | |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 2.00 | 500.00 | 787.15 | 885.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2.00 | 500.00 | 864.74 | 919.17 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 11.00 | 825.00 | 304.51 | 312.57 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 11.00 | 825.00 | 304.51 | 312.57 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 1.00 | 600.00 | 699.28 | 446.57 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 600.00 | 699.28 | 446.57 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 14.00 | 762.50 | 609.89 | 572.91 |
| ========== | 210-01720 | Res Air Vent | | Each | | | |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1.00 | 1000.00 | 1347.71 | 1385.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 1000.00 | 1347.71 | 1385.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 1000.00 | 1347.71 | 1385.00 |
| ========== | 210-02024 | Relay Pipe (24 In) | | Lin Foot | | | |
| NH0403-053 | | US 40 RETAINING WALL REPAIR | 07/28/11 | 20.00 | 400.00 | 308.33 | 115.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 20.00 | 400.00 | 308.33 | 115.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 20.00 | 400.00 | 308.33 | 115.00 |
| ========== | 210-02510 | Relay Sprinkler System | | LUMP SUM | | | |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 1.00 | 800.00 | 4463.67 | 3100.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1.00 | 800.00 | 4463.67 | 3100.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 210-02510 | Relay Sprinkler System | | LUMP SUM | | | |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 1.00 | 500.00 | 1034.00 | 1400.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1.00 | 500.00 | 1034.00 | 1400.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 650.00 | 6183.03 | 3000.00 |
| ========== | 210-02900 | Relay Riprap | | Cubic Yard | | | |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 476.00 | 25.00 | 25.61 | 29.19 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 476.00 | 25.00 | 25.61 | 29.19 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 2.00 | 80.00 | 176.60 | 75.02 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 80.00 | 176.60 | 75.02 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 478.00 | 25.23 | 26.01 | 29.38 |
| ========== | 210-03100 | Replace Conc Pvmt | | Sq Yard | | | |
| NH2872-018 | | US 287 RUSH CREEK NORTH | 07/21/11 | 1,972.00 | 117.00 | 158.45 | 135.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1,972.00 | 117.00 | 158.45 | 135.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,972.00 | 117.00 | 158.45 | 135.00 |
| ========== | 210-04006 | Heat Straightening (Spec) | | LUMP SUM | | | |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 1.00 | 25000.00 | 35761.09 | 31300.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1.00 | 25000.00 | 35761.09 | 31300.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 25000.00 | 35761.09 | 31300.00 |
| ========== | 210-04010 | Adj Manhole | | Each | | | |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 6.00 | 350.00 | 383.50 | 370.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 210-04010 | Adj Manhole | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 24.00 | 550.00 | 780.27 | 1200.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 6.00 | 500.00 | 824.84 | 400.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 36.00 | 508.33 | 676.78 | 656.00 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 3.00 | 400.00 | 427.50 | 400.00 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 10.00 | 400.00 | 511.11 | 550.00 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 2.00 | 500.00 | 1348.50 | 1100.00 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 34.00 | 400.00 | 456.50 | 433.18 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 4.00 | 600.00 | 439.67 | 450.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 53.00 | 418.87 | 393.23 | 429.06 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 1.00 | 500.00 | 875.83 | 705.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1.00 | 500.00 | 875.83 | 705.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 17.00 | 800.00 | 686.14 | 560.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 2.00 | 450.00 | 842.83 | 941.00 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 8.00 | 650.00 | 814.00 | 628.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 27.00 | 729.63 | 711.06 | 608.37 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 117.00 | 518.80 | 512.76 | 500.59 |
| ========== | 210-04015 | Modify Manhole | | Each | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 1.00 | 500.00 | 1251.00 | 425.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 4.00 | 1200.00 | 2007.36 | 2500.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 5.00 | 1060.00 | 1737.23 | 1462.50 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 210-04015 | Modify Manhole | | Each | | | |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 1.00 | 1250.00 | 2791.69 | 6965.92 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 1.00 | 1200.00 | 2749.68 | 1300.00 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 6.00 | 1600.00 | 1713.00 | 1500.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 8.00 | 1506.25 | 2284.14 | 2158.24 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 1.00 | 1250.00 | 2219.94 | 1400.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1.00 | 1250.00 | 2219.94 | 1400.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 9.00 | 1500.00 | 1919.30 | 1021.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 9.00 | 1500.00 | 1919.30 | 1021.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 23.00 | 1395.65 | 2019.75 | 1539.00 |
| ========== | 210-04020 | Modify Inlet | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 8.00 | 3000.00 | 2954.19 | 1750.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 4.00 | 2200.00 | 1850.49 | 605.11 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 12.00 | 2733.33 | 2249.17 | 917.21 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 15.00 | 1300.00 | 2112.59 | 3925.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 2.00 | 3000.00 | 2034.06 | 920.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 1.00 | 2000.00 | 1814.82 | 1100.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 18.00 | 1527.78 | 2084.82 | 3434.17 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 4.00 | 1300.00 | 2078.24 | 1720.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 210-04020 | Modify Inlet | | Each | | | |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 1.00 | 1000.00 | 1903.00 | 1125.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 5.00 | 1240.00 | 2169.48 | 2882.94 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 2.00 | 2000.00 | 1934.43 | 1565.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 5.00 | 1000.00 | 2758.13 | 878.00 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 39.00 | 1500.00 | 1121.00 | 1192.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 46.00 | 1467.39 | 1568.15 | 1174.09 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 81.00 | 1654.32 | 1960.90 | 1956.59 |
| ========== | 210-04030 | Modify Guardrail | | Lin Foot | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 605.00 | 20.00 | 11.95 | 16.00 |
| NH 0402-079 | | US40 MP 165.0 - 179.0 GRAND C | 03/31/11 | 100.00 | 25.00 | 9.90 | 9.12 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 705.00 | 20.71 | 11.61 | 15.02 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 3,613.00 | 3.00 | 5.74 | 3.75 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 7,658.00 | 4.00 | 12.90 | 12.80 |
| C0241-055 | | SH 24 MP 148-152 | 05/26/11 | 50.00 | 4.00 | 61.01 | 63.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 11,321.00 | 3.68 | 9.94 | 10.13 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 363.00 | 15.00 | 19.23 | 21.00 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 25.00 | 50.00 | 10.27 | 9.50 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 388.00 | 17.26 | 18.79 | 20.26 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 12,414.00 | 5.07 | 10.38 | 10.73 |
| ========== | 210-04050 | Adj Valve Box | | Each | | | |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 102.00 | 175.00 | 170.55 | 110.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 102.00 | 175.00 | 170.55 | 110.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 210-04050 | Adj Valve Box | | Each | | | |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 34.00 | 200.00 | 273.83 | 200.00 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 12.00 | 200.00 | 263.24 | 240.00 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 118.00 | 200.00 | 214.94 | 124.47 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 4.00 | 500.00 | 290.83 | 220.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 2.00 | 100.00 | 326.10 | 251.43 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 170.00 | 205.88 | 204.89 | 160.00 |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 1.00 | 200.00 | 310.50 | 236.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1.00 | 200.00 | 310.50 | 236.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 8.00 | 200.00 | 329.14 | 325.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 6.00 | 250.00 | 313.62 | 269.00 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 14.00 | 400.00 | 370.00 | 220.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 28.00 | 310.71 | 335.09 | 260.50 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 301.00 | 205.15 | 201.69 | 153.84 |
| ========== | 210-04060 | Adj Water Meter | | Each | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 8.00 | 350.00 | 380.57 | 240.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 8.00 | 350.00 | 380.57 | 240.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 8.00 | 350.00 | 380.57 | 240.00 |
| ========== | 210-04200 | Adj Gdrail | | Lin Foot | | | |
| NH 2852-017 | | US 285 PONCHA PASS SOUTH RESU | 03/03/11 | 775.00 | 4.00 | 7.32 | 6.30 |
| NH 0241-056 | | US 24 BUENA VISTA NORTH | 03/03/11 | 4,596.00 | 2.00 | 4.28 | 3.00 |
| NH 0402-079 | | US40 MP 165.0 - 179.0 GRAND C | 03/31/11 | 10,565.00 | 2.50 | 2.30 | 2.12 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 15,936.00 | 2.43 | 3.04 | 2.58 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 210-04200 | Adj Gdrail | | Lin Foot | | | |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 1,453.00 | 3.00 | 3.71 | 2.50 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 3,710.00 | 8.00 | 2.42 | 2.25 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 2,983.00 | 8.00 | 6.63 | 7.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 8,146.00 | 7.11 | 3.83 | 4.03 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 375.00 | 6.00 | 4.92 | 5.07 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 375.00 | 6.00 | 4.92 | 5.07 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 500.00 | 10.00 | 13.06 | 4.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 1,062.00 | 6.00 | 4.56 | 4.50 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 4,298.00 | 2.50 | 5.15 | 8.00 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 88.00 | 20.00 | 8.20 | 8.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 5,948.00 | 4.01 | 5.29 | 7.04 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 30,405.00 | 4.04 | 3.73 | 3.87 |
| ========== | 211-00100 | Drilling Hole | | Lin Foot | | | |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 331.00 | 40.00 | 29.22 | 22.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 331.00 | 40.00 | 29.22 | 22.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 331.00 | 40.00 | 29.22 | 22.00 |
| ========== | 211-01111 | Rock Reinf (Dowels) | | Lin Foot | | | |
| NH5502-070 | | US 550 4 MILES SOUTH OF OURAY | 08/18/11 | 80.00 | 100.00 | 189.52 | 107.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 80.00 | 100.00 | 189.52 | 107.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 80.00 | 100.00 | 189.52 | 107.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 211-01115 | Rock Reinf (No.10) | | Lin Foot | | | |
| NH5502-070 | | US 550 4 MILES SOUTH OF OURAY | 08/18/11 | 900.00 | 80.00 | 116.01 | 130.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 900.00 | 80.00 | 116.01 | 130.00 |
| SHE0402-081 | | US 40 - MP 113 TO 120 ROUTT C | 10/27/11 | 250.00 | 50.00 | 116.44 | 70.63 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 250.00 | 50.00 | 116.44 | 70.63 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,150.00 | 73.48 | 116.16 | 117.09 |
| ========== | 211-01160 | Trial Pull Test | | Each | | | |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 18.00 | 600.00 | 209.33 | 120.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 18.00 | 600.00 | 209.33 | 120.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 18.00 | 600.00 | 209.33 | 120.00 |
| ========== | 211-01300 | Rock Anchor | | Each | | | |
| SHE0402-081 | | US 40 - MP 113 TO 120 ROUTT C | 10/27/11 | 170.00 | 225.00 | 485.56 | 212.36 |
| IM0703-368 | | GEORGETOWN HILL CHUTES 6,7,9, | 12/01/11 | 40.00 | 350.00 | 327.61 | 330.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 210.00 | 248.81 | 468.93 | 234.77 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 210.00 | 248.81 | 468.93 | 234.77 |
| ========== | 211-02275 | Cement Grout | | Cubic Yard | | | |
| C0241-055 | | SH 24 MP 148-152 | 05/26/11 | 10.00 | 50.00 | 503.25 | 300.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 10.00 | 50.00 | 503.25 | 300.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 10.00 | 50.00 | 503.25 | 300.00 |
| ========== | 211-03005 | Dewatering | | LUMP SUM | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 1.00 | 400000.00 | 120160.30 | 17182.40 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1.00 | 400000.00 | 120160.30 | 17182.40 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 211-03005 | Dewatering | | LUMP SUM | ========== | ========== | ========== |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 1.00 | 20000.00 | 19665.70 | 6600.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 1.00 | 30000.00 | 26445.99 | 15400.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 2.00 | 25000.00 | 23316.63 | 11000.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 1.00 | 50000.00 | 61034.64 | 41620.15 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 50000.00 | 61034.64 | 41620.15 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4.00 | 125000.00 | 60437.09 | 20200.64 |
| ========== | 212-00006 | Seeding (Native) | | Acre | ========== | ========== | ========== |
| C0704-225 | | I-70 EAST OF BENNETT | 01/06/11 | 0.50 | 500.00 | 697.88 | 556.50 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 168.00 | 350.00 | 918.78 | 400.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 0.60 | 2500.00 | 967.17 | 1335.00 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 12.00 | 450.00 | 878.23 | 820.00 |
| NH 2852-017 | | US 285 PONCHA PASS SOUTH RESU | 03/03/11 | 2.00 | 600.00 | 677.50 | 518.00 |
| NH 0241-056 | | US 24 BUENA VISTA NORTH | 03/03/11 | 0.50 | 5000.00 | 1031.92 | 1000.00 |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 0.50 | 1000.00 | 910.51 | 694.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 2.00 | 800.00 | 855.05 | 896.38 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 186.10 | 385.55 | 802.03 | 507.44 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 0.14 | 3000.00 | 2364.01 | 1520.04 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 0.32 | 2000.00 | 1780.32 | 2500.00 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 5.00 | 400.00 | 399.50 | 422.50 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 0.50 | 400.00 | 1244.12 | 3358.00 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 1.20 | 600.00 | 612.03 | 543.00 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 13.00 | 350.00 | 665.94 | 686.48 |
| SHE074A-001 | | SH 74 - EVERGREEN - JEFFERSON | 04/28/11 | 0.10 | 1800.00 | 4804.00 | 3862.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 3.00 | 1000.00 | 983.16 | 410.00 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 1.36 | 700.00 | 593.90 | 610.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 212-00006 | Seeding (Native) | | Acre | | | |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 0.25 | 2000.00 | 1491.00 | 1700.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 14.00 | 700.00 | 663.73 | 627.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 1.50 | 4000.00 | 685.07 | 986.00 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 0.70 | 2000.00 | 861.33 | 832.65 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 13.00 | 500.00 | 589.36 | 490.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 10.00 | 500.00 | 621.00 | 580.00 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 8.30 | 400.00 | 483.38 | 450.00 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 0.40 | 600.00 | 1318.75 | 1400.00 |
| ITS0703-370 | | EAST OF EJMT ON I-70 EB LANES | 06/16/11 | 0.50 | 1240.00 | 1377.00 | 1445.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 0.25 | 700.00 | 2165.00 | 2100.00 |
| FSA 0502-064 | | US 50 EAST OF SARGENTS | 06/23/11 | 0.30 | 700.00 | 2722.53 | 2846.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 59.00 | 250.00 | 710.37 | 699.85 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 132.82 | 460.60 | 641.07 | 543.87 |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 0.03 | 7000.00 | 32489.61 | 43908.67 |
| C006A-051 | | US 6 (LOVELAND PASS), CLEAR C | 07/14/11 | 0.10 | 1500.00 | 5825.00 | 10400.00 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 0.27 | 550.00 | 2553.00 | 2500.00 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 0.60 | 1000.00 | 1139.58 | 1295.40 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 0.20 | 2500.00 | 1266.30 | 680.00 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 0.20 | 2500.00 | 3706.67 | 4520.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 9.10 | 400.00 | 580.48 | 595.00 |
| NH0403-053 | | US 40 RETAINING WALL REPAIR | 07/28/11 | 0.50 | 1000.00 | 2733.33 | 2300.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 6.75 | 450.00 | 563.43 | 450.00 |
| NH5502-070 | | US 550 4 MILES SOUTH OF OURAY | 08/18/11 | 0.10 | 500.00 | 6895.47 | 8200.00 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 2.80 | 500.00 | 683.26 | 624.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 0.04 | 5000.00 | 12520.00 | 5200.00 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 0.80 | 600.00 | 761.20 | 950.00 |
| STR096A-040 | | SH 96 MP 193 TO MP 201 | 09/01/11 | 4.00 | 525.00 | 1445.52 | 511.55 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 18.00 | 280.00 | 722.56 | 650.00 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 2.00 | 2000.00 | 995.00 | 585.00 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 1.30 | 750.00 | 679.35 | 800.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 46.79 | 502.91 | 792.82 | 797.09 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 4.00 | 600.00 | 589.31 | 364.20 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 29.00 | 400.00 | 424.36 | 397.66 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 25.00 | 600.00 | 1394.00 | 900.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 2.02 | 1000.00 | 808.89 | 680.00 |
| SHE025A-013 | | I 25 BETWEEN MP 122 AND MP 12 | 11/03/11 | 0.50 | 750.00 | 968.80 | 1200.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 4.90 | 500.00 | 676.01 | 545.99 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 3.40 | 750.00 | 1882.81 | 679.10 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 212-00006 | Seeding (Native) | | Acre | | | |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 0.30 | 3000.00 | 5243.33 | 8323.33 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 2.50 | 700.00 | 677.17 | 680.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 1.80 | 550.00 | 776.01 | 525.00 |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 0.21 | 10000.00 | 2750.00 | 2500.00 |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 13.30 | 500.00 | 461.65 | 455.00 |
| C2854-125 | | US 285, ASPEN PARK TO MORRISO | 12/08/11 | 0.30 | 3000.00 | 1993.33 | 1900.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 21.40 | 600.00 | 513.65 | 320.00 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 0.50 | 1100.00 | 2305.67 | 3560.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 109.13 | 577.98 | 798.24 | 580.62 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 474.84 | 462.33 | 736.80 | 576.58 |
| ========== | 212-00007 | Seeding (Native) (Hydraulic) | | Acre | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 7.24 | 1000.00 | 754.47 | 780.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 7.24 | 1000.00 | 754.47 | 780.00 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 4.50 | 1000.00 | 1010.46 | 855.00 |
| C0241-055 | | SH 24 MP 148-152 | 05/26/11 | 0.11 | 2000.00 | 5846.67 | 9000.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 12.00 | 500.00 | 754.41 | 741.90 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 16.61 | 645.39 | 868.49 | 827.23 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 23.85 | 753.04 | 826.79 | 812.89 |
| ========== | 212-00009 | Seeding (Temporary) | | Acre | | | |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 1.00 | 500.00 | 1108.32 | 1918.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 13.00 | 300.00 | 401.91 | 290.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 14.00 | 314.29 | 452.37 | 406.29 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1.57 | 2000.00 | 627.07 | 704.25 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 1.57 | 2000.00 | 627.07 | 704.25 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 15.57 | 484.26 | 490.85 | 560.87 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 212-00028 | Seeding (Wetlands) | | Acre | | | |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 0.10 | 750.00 | 6150.00 | 6300.00 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 0.10 | 2500.00 | 2252.50 | 2625.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 2.00 | 1200.00 | 1221.00 | 1600.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2.20 | 1238.64 | 1407.27 | 1860.23 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 0.20 | 4500.00 | 2486.54 | 3800.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 0.20 | 4500.00 | 2486.54 | 3800.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 0.60 | 2000.00 | 1367.73 | 1321.41 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 0.05 | 750.00 | 5224.70 | 5200.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 0.65 | 1903.85 | 1484.60 | 1619.76 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3.05 | 1594.26 | 1509.84 | 1936.18 |
| ========== | 212-00032 | Soil Conditioning | | Acre | | | |
| C0704-225 | | I-70 EAST OF BENNETT | 01/06/11 | 0.50 | 1000.00 | 2328.00 | 2067.00 |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 0.60 | 1450.00 | 2928.90 | 4840.00 |
| NH 0241-056 | | US 24 BUENA VISTA NORTH | 03/03/11 | 0.50 | 6000.00 | 3262.50 | 2000.00 |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 0.50 | 2000.00 | 2851.24 | 459.00 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 7.24 | 1200.00 | 2730.43 | 1500.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 2.00 | 2000.00 | 4360.19 | 4753.14 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 11.34 | 1592.42 | 2284.28 | 1744.10 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 0.14 | 3000.00 | 2960.01 | 1950.05 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 0.32 | 2000.00 | 3531.10 | 3300.00 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 5.00 | 5000.00 | 3160.00 | 6592.00 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 0.50 | 400.00 | 4637.21 | 1633.00 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 1.20 | 1500.00 | 2015.87 | 2414.00 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 13.00 | 1000.00 | 1956.83 | 2112.26 |
| SHE074A-001 | | SH 74 - EVERGREEN - JEFFERSON | 04/28/11 | 0.10 | 2000.00 | 10931.33 | 5794.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 212-00032 | Soil Conditioning | | Acre | | | |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 4.50 | 2000.00 | 2347.08 | 1738.00 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 1.36 | 1400.00 | 838.43 | 860.00 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 0.25 | 2500.00 | 1570.00 | 1300.00 |
| C0241-055 | | SH 24 MP 148-152 | 05/26/11 | 0.11 | 2000.00 | 6395.97 | 10000.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 14.00 | 2500.00 | 2165.86 | 1750.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 1.50 | 2500.00 | 3221.50 | 1785.00 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 0.70 | 2000.00 | 3350.68 | 4711.35 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 13.00 | 1800.00 | 2744.42 | 3000.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 10.00 | 1000.00 | 3206.33 | 3200.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 12.00 | 1500.00 | 707.98 | 665.15 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 8.30 | 2500.00 | 2912.17 | 3435.00 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 0.40 | 1500.00 | 3306.25 | 1960.00 |
| ITS0703-370 | | EAST OF EJMT ON I-70 EB LANES | 06/16/11 | 0.50 | 1650.00 | 2025.33 | 2050.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 0.25 | 2000.00 | 6547.00 | 6900.00 |
| FSA 0502-064 | | US 50 EAST OF SARGENTS | 06/23/11 | 0.30 | 2000.00 | 2854.30 | 2125.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 30.00 | 1600.00 | 2174.59 | 2384.67 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 117.43 | 1837.98 | 2283.32 | 2464.16 |
| C006A-051 | | US 6 (LOVELAND PASS), CLEAR C | 07/14/11 | 0.10 | 1500.00 | 11555.00 | 14420.00 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 0.27 | 1500.00 | 5566.43 | 5500.00 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 0.60 | 1500.00 | 2656.64 | 3533.22 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 0.20 | 7000.00 | 3271.47 | 2580.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 4.50 | 2000.00 | 572.99 | 85.00 |
| NH0403-053 | | US 40 RETAINING WALL REPAIR | 07/28/11 | 0.50 | 500.00 | 2108.33 | 1725.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 6.75 | 1500.00 | 2088.24 | 1500.00 |
| NH5502-070 | | US 550 4 MILES SOUTH OF OURAY | 08/18/11 | 0.10 | 1800.00 | 7011.53 | 6000.00 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 2.80 | 1000.00 | 3429.86 | 5000.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 0.04 | 5000.00 | 8950.00 | 5800.00 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 0.80 | 1500.00 | 2445.21 | 3000.00 |
| STR096A-040 | | SH 96 MP 193 TO MP 201 | 09/01/11 | 4.00 | 1900.00 | 2326.53 | 479.58 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 17.00 | 1500.00 | 2020.30 | 1750.00 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 2.00 | 2000.00 | 1650.00 | 1550.00 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 1.30 | 3500.00 | 4901.36 | 3900.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 40.96 | 1666.50 | 2102.09 | 2028.72 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 4.00 | 3500.00 | 2912.49 | 3694.93 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 29.00 | 750.00 | 2628.18 | 2573.08 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 2.02 | 4500.00 | 2247.47 | 1750.00 |
| SHE025A-013 | | I 25 BETWEEN MP 122 AND MP 12 | 11/03/11 | 0.50 | 750.00 | 3189.94 | 2400.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 3.30 | 1800.00 | 2303.06 | 2348.32 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 212-00032 | Soil Conditioning | | Acre | | | |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 0.30 | 3000.00 | 5543.33 | 6423.33 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 2.50 | 1600.00 | 900.67 | 900.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 1.80 | 2500.00 | 3436.89 | 3580.00 |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 0.21 | 10000.00 | 6600.00 | 6200.00 |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 13.30 | 2000.00 | 1877.00 | 1250.00 |
| C2854-125 | | US 285, ASPEN PARK TO MORRISO | 12/08/11 | 0.30 | 2500.00 | 2226.67 | 1900.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 21.40 | 650.00 | 2109.04 | 1000.00 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 0.50 | 4200.00 | 6919.00 | 10700.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 79.13 | 1339.76 | 2330.71 | 1993.57 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 248.86 | 1640.15 | 2264.37 | 2208.86 |
| ========== | 212-00047 | Soil Preparation (Spec) | | Acre | | | |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 2.20 | 4000.00 | 2185.16 | 1776.96 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 2.20 | 4000.00 | 2185.16 | 1776.96 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.20 | 4000.00 | 2185.16 | 1776.96 |
| ========== | 212-00048 | Soil Preparation (Spec) | | Cubic Yard | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 28.00 | 50.00 | 51.60 | 30.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 28.00 | 50.00 | 51.60 | 30.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 28.00 | 50.00 | 51.60 | 30.00 |
| ========== | 212-00050 | Sod | | Sq Foot | | | |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 36,400.00 | 1.00 | 0.59 | 0.45 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 36,400.00 | 1.00 | 0.59 | 0.45 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 3,365.00 | 1.25 | 0.71 | 0.40 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 212-00050 | Sod | | Sq Foot | | | |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 500.00 | 1.00 | 3.38 | 0.60 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 3,865.00 | 1.22 | 1.06 | 0.43 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 14,560.00 | 1.00 | 0.91 | 1.15 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1,695.00 | 1.00 | 1.01 | 1.45 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 16,255.00 | 1.00 | 0.92 | 1.18 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 56,520.00 | 1.01 | 0.72 | 0.66 |
| ========== | 212-01200 | Landscape Restoration | | LUMP SUM | | | |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1.00 | 5000.00 | 11721.79 | 3500.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 5000.00 | 11721.79 | 3500.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 5000.00 | 11721.79 | 3500.00 |
| ========== | 213-00002 | Mulching (Weed Free Hay) | | Acre | | | |
| C0704-225 | | I-70 EAST OF BENNETT | 01/06/11 | 0.50 | 500.00 | 742.88 | 556.50 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 24.00 | 360.00 | 315.11 | 300.00 |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 0.50 | 750.00 | 884.51 | 664.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 25.00 | 370.60 | 326.74 | 334.16 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 1.00 | 500.00 | 525.27 | 422.50 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 13.00 | 400.00 | 572.17 | 633.68 |
| SHE074A-001 | | SH 74 - EVERGREEN - JEFFERSON | 04/28/11 | 0.10 | 450.00 | 3458.33 | 2575.00 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 0.40 | 500.00 | 1072.75 | 960.00 |
| ITS0703-370 | | EAST OF EJMT ON I-70 EB LANES | 06/16/11 | 0.50 | 895.00 | 991.67 | 1080.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 0.25 | 700.00 | 1273.33 | 850.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 15.25 | 430.66 | 523.85 | 386.17 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 0.60 | 420.00 | 1185.17 | 1403.37 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 213-00002 | Mulching (Weed Free Hay) | | Acre | | | |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 0.20 | 2500.00 | 801.63 | 760.00 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 0.20 | 2000.00 | 4382.00 | 5117.00 |
| NH0403-053 | | US 40 RETAINING WALL REPAIR | 07/28/11 | 0.25 | 800.00 | 2566.67 | 2300.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 7.50 | 400.00 | 654.13 | 525.00 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 1.00 | 450.00 | 759.36 | 630.00 |
| STR096A-040 | | SH 96 MP 193 TO MP 201 | 09/01/11 | 4.00 | 300.00 | 1410.96 | 532.87 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 13.75 | 436.51 | 745.77 | 651.66 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 4.00 | 1000.00 | 682.54 | 540.77 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 2.00 | 400.00 | 597.45 | 505.05 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 25.00 | 300.00 | 646.00 | 650.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 2.02 | 500.00 | 734.20 | 750.00 |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 13.30 | 500.00 | 452.59 | 460.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 46.32 | 430.92 | 607.56 | 584.11 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 100.32 | 416.61 | 530.77 | 466.04 |
| ========== | 213-00003 | Mulching (Weed Free) | | Acre | | | |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 0.32 | 2000.00 | 1670.43 | 2500.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 3.00 | 1000.00 | 484.91 | 410.00 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 4.50 | 1000.00 | 1855.54 | 1907.00 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 1.46 | 800.00 | 642.85 | 660.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 13.00 | 500.00 | 481.11 | 410.00 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 8.30 | 490.00 | 784.23 | 815.00 |
| FSA 0502-064 | | US 50 EAST OF SARGENTS | 06/23/11 | 0.30 | 1400.00 | 1710.00 | 1705.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 89.00 | 250.00 | 620.31 | 622.09 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 119.88 | 354.90 | 657.45 | 663.56 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 0.04 | 5000.00 | 13680.00 | 1300.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 0.04 | 5000.00 | 4748.61 | 4588.89 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 7.90 | 500.00 | 569.33 | 501.87 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 213-00003 | Mulching (Weed Free) | | Acre | | | |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1.78 | 800.00 | 608.07 | 628.80 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 2.50 | 800.00 | 843.17 | 840.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 12.18 | 605.42 | 600.00 | 589.82 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 132.10 | 379.40 | 658.94 | 667.45 |
| ========== | 213-00004 | Mulching (Weed Free Straw) | | Acre | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 168.00 | 400.00 | 489.92 | 500.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| NH 2852-017 | | US 285 PONCHA PASS SOUTH RESU | 03/03/11 | 2.00 | 800.00 | 707.83 | 504.00 |
| NH 0241-056 | | US 24 BUENA VISTA NORTH | 03/03/11 | 0.50 | 5000.00 | 1544.75 | 1200.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 2.00 | 800.00 | 776.11 | 680.13 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 172.50 | 422.61 | 498.03 | 464.61 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 0.14 | 2000.00 | 2090.01 | 950.03 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 5.00 | 400.00 | 551.17 | 463.50 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 0.50 | 5000.00 | 886.28 | 814.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 8.00 | 500.00 | 603.16 | 538.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 0.20 | 1200.00 | 1530.46 | 730.00 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 0.80 | 2000.00 | 824.75 | 682.50 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 10.00 | 500.00 | 728.00 | 750.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 24.64 | 633.93 | 620.18 | 580.48 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 0.07 | 2000.00 | 7208.57 | 5500.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 9.10 | 400.00 | 541.98 | 600.00 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 2.00 | 500.00 | 706.78 | 628.00 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 1.30 | 700.00 | 686.14 | 650.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 12.47 | 456.79 | 631.26 | 725.67 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 1.10 | 600.00 | 861.88 | 610.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 213-00004 | Mulching (Weed Free Straw) | | Acre | | | |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 13.50 | 600.00 | 1102.92 | 3000.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 14.60 | 600.00 | 1094.50 | 2819.93 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 224.21 | 459.28 | 611.00 | 724.54 |
| ========== | 213-00005 | Mulching (Decorative) | | Cubic Foot | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 47.00 | 10.00 | 6.84 | 6.70 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 47.00 | 10.00 | 6.84 | 6.70 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 47.00 | 10.00 | 6.84 | 6.70 |
| ========== | 213-00008 | Mulching (Wood Chip) | | Cubic Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 24.00 | 50.00 | 34.37 | 35.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 24.00 | 50.00 | 34.37 | 35.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 28,500.00 | 5.00 | 2.10 | 2.31 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 28,500.00 | 5.00 | 2.10 | 2.31 |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 315.00 | 10.00 | 14.36 | 3.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 315.00 | 10.00 | 14.36 | 3.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 28,839.00 | 5.09 | 2.23 | 2.32 |
| ========== | 213-00009 | Flexible Growth Medium | | Acre | | | |
| NH5502-070 | | US 550 4 MILES SOUTH OF OURAY | 08/18/11 | 0.10 | 400.00 | 10293.17 | 8200.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 0.10 | 400.00 | 5909.69 | 6366.67 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 213-00009 | Flexible Growth Medium | | Acre | | | |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 0.21 | 10000.00 | 8500.00 | 8000.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 0.21 | 10000.00 | 8500.00 | 8000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 0.31 | 6903.23 | 4104.65 | 4209.95 |
| ========== | 213-00011 | Mulching (Hydraulic) | | Acre | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 7.24 | 600.00 | 1347.14 | 2000.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 7.24 | 600.00 | 1347.14 | 2000.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 0.50 | 3000.00 | 1484.94 | 2200.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 0.50 | 3000.00 | 1484.94 | 2200.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 0.60 | 2000.00 | 1368.35 | 1654.52 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 0.60 | 2000.00 | 1368.35 | 1654.52 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 8.34 | 844.60 | 1358.43 | 1987.14 |
| ========== | 213-00012 | Spray-on Mulch Blanket | | Acre | | | |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 0.15 | 3000.00 | 4402.96 | 664.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 0.15 | 3000.00 | 3398.97 | 3436.74 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 0.50 | 3000.00 | 4788.80 | 5431.50 |
| C0241-055 | | SH 24 MP 148-152 | 05/26/11 | 0.11 | 4000.00 | 8898.33 | 10000.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 6.00 | 2000.00 | 3024.83 | 2700.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 213-00012 | Spray-on Mulch Blanket | | Acre | | | |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 6.00 | 1500.00 | 2947.83 | 3600.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 12.00 | 2500.00 | 2904.41 | 2507.12 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 0.15 | 3000.00 | 3362.50 | 3350.00 |
| FSA 0502-064 | | US 50 EAST OF SARGENTS | 06/23/11 | 0.30 | 3000.00 | 4632.00 | 4025.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 25.06 | 2166.40 | 3115.03 | 2948.03 |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 0.03 | 10000.00 | 22346.78 | 27855.67 |
| C006A-051 | | US 6 (LOVELAND PASS), CLEAR C | 07/14/11 | 0.10 | 1500.00 | 8162.50 | 6650.00 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 0.20 | 7000.00 | 4537.73 | 5770.00 |
| NH0403-053 | | US 40 RETAINING WALL REPAIR | 07/28/11 | 0.25 | 500.00 | 4693.04 | 4179.12 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 5.00 | 3000.00 | 2949.37 | 3000.00 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 2.80 | 3200.00 | 3815.46 | 4100.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 0.04 | 3000.00 | 8205.00 | 5200.00 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 1.00 | 700.00 | 3343.50 | 3600.00 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 17.00 | 2500.00 | 2547.45 | 2580.00 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 2.00 | 1000.00 | 3506.67 | 3420.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 28.42 | 2507.21 | 2830.41 | 3056.36 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 5.00 | 500.00 | 3504.29 | 3450.00 |
| SHE025A-013 | | I 25 BETWEEN MP 122 AND MP 12 | 11/03/11 | 0.50 | 1500.00 | 3926.84 | 4050.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 3.00 | 2500.00 | 3379.93 | 3360.89 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 0.70 | 800.00 | 4070.65 | 4140.00 |
| C2854-125 | | US 285, ASPEN PARK TO MORRISO | 12/08/11 | 0.30 | 3000.00 | 4000.00 | 3200.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 7.90 | 3600.00 | 3243.37 | 1200.00 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 0.50 | 3600.00 | 5498.33 | 4450.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 17.90 | 2371.51 | 3395.98 | 2509.53 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 71.53 | 2354.89 | 3111.34 | 2952.19 |
| ========== | 213-00061 | Mulch Tackifier | | Pound | | | |
| C0704-225 | | I-70 EAST OF BENNETT | 01/06/11 | 100.00 | 3.00 | 6.89 | 6.89 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 33,600.00 | 2.00 | 1.37 | 1.34 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 4,800.00 | 1.80 | 1.89 | 1.40 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 213-00061 | Mulch Tackifier | | Pound | | | |
| NH 2852-017 | | US 285 PONCHA PASS SOUTH RESU | 03/03/11 | 400.00 | 2.50 | 3.14 | 3.10 |
| NH 0241-056 | | US 24 BUENA VISTA NORTH | 03/03/11 | 100.00 | 10.00 | 6.52 | 5.00 |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 100.00 | 5.00 | 4.49 | 4.10 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 90.00 | 3.50 | 3.46 | 5.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 400.00 | 2.00 | 2.77 | 1.41 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 39,590.00 | 2.01 | 1.80 | 1.83 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 420.00 | 5.00 | 3.39 | 2.85 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 64.00 | 5.00 | 3.37 | 5.00 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 1,000.00 | 2.00 | 2.73 | 2.75 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 100.00 | 2.00 | 3.37 | 4.00 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 200.00 | 3.00 | 4.14 | 6.00 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 1,340.00 | 2.00 | 2.25 | 2.38 |
| SHE074A-001 | | SH 74 - EVERGREEN - JEFFERSON | 04/28/11 | 20.00 | 4.00 | 11.88 | 5.15 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 600.00 | 2.00 | 2.28 | 1.90 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 450.00 | 3.00 | 2.63 | 2.20 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 292.00 | 2.50 | 3.10 | 3.20 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 2,800.00 | 2.50 | 2.20 | 2.20 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 225.00 | 10.00 | 3.11 | 3.15 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 240.00 | 3.00 | 2.66 | 2.77 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 2,585.00 | 2.00 | 1.86 | 2.10 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 1,000.00 | 3.00 | 4.20 | 7.00 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 830.00 | 3.00 | 230.77 | 2.10 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 80.00 | 3.00 | 3.30 | 3.00 |
| ITS0703-370 | | EAST OF EJMT ON I-70 EB LANES | 06/16/11 | 100.00 | 2.30 | 3.59 | 4.60 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 50.00 | 5.00 | 2.58 | 3.00 |
| FSA 0502-064 | | US 50 EAST OF SARGENTS | 06/23/11 | 900.00 | 3.00 | 3.01 | 3.14 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 12,600.00 | 1.00 | 2.59 | 2.70 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 25,896.00 | 1.85 | 5.03 | 2.31 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 15.00 | 15.00 | 13.62 | 30.00 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 120.00 | 1.70 | 4.82 | 3.13 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 40.00 | 12.00 | 4.97 | 5.60 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 20.00 | 10.00 | 8.78 | 5.15 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 1,820.00 | 2.00 | 2.33 | 3.25 |
| NH0403-053 | | US 40 RETAINING WALL REPAIR | 07/28/11 | 50.00 | 5.00 | 4.06 | 3.89 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 1,500.00 | 2.00 | 2.75 | 3.00 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 400.00 | 5.00 | 3.43 | 4.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 8.00 | 20.00 | 19.00 | 7.00 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 200.00 | 2.00 | 134.81 | 530.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 213-00061 | Mulch Tackifier | | Pound | | | |
| STR096A-040 | | SH 96 MP 193 TO MP 201 | 09/01/11 | 400.00 | 1.50 | 3.05 | 3.20 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 130.00 | 2.50 | 4.09 | 4.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 4,703.00 | 2.44 | 5.13 | 15.50 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 400.00 | 2.00 | 2.20 | 2.34 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 5,000.00 | 2.10 | 2.47 | 2.50 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 404.00 | 3.00 | 2.15 | 2.45 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 1,260.00 | 2.00 | 2.19 | 2.04 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 178.00 | 2.00 | 2.36 | 2.26 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 250.00 | 2.50 | 3.96 | 4.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 220.00 | 3.50 | 3.54 | 3.00 |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 2,660.00 | 2.00 | 2.57 | 2.10 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 10,372.00 | 2.13 | 2.46 | 2.38 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 80,561.00 | 2.00 | 3.62 | 3.45 |
| ========== | 213-00065 | Inorg Mulch | | Cubic Yard | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 20.00 | 1.00 | 172.10 | 207.36 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 20.00 | 1.00 | 172.10 | 207.36 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 20.00 | 1.00 | 172.10 | 207.36 |
| ========== | 213-00100 | Soil Binder | | Acre | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 116.00 | 400.00 | 714.13 | 346.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 3.00 | 700.00 | 849.71 | 837.49 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 119.00 | 407.56 | 725.55 | 392.08 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 2.00 | 800.00 | 679.08 | 650.00 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 13.00 | 400.00 | 855.09 | 792.10 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 213-00100 | Soil Binder | | Acre | ========== | ========== | ========== |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 3.00 | 1000.00 | 893.33 | 820.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 13.00 | 600.00 | 672.19 | 910.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 12.00 | 500.00 | 607.56 | 537.24 |
| FSA 0502-064 | | US 50 EAST OF SARGENTS | 06/23/11 | 0.30 | 600.00 | 1566.18 | 1463.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 59.00 | 250.00 | 778.41 | 829.45 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 102.30 | 376.64 | 766.89 | 794.04 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 2.00 | 1000.00 | 779.46 | 910.00 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 8.00 | 900.00 | 755.61 | 550.00 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 10.00 | 920.00 | 749.30 | 697.92 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 60.00 | 500.00 | 492.76 | 531.63 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1.92 | 1000.00 | 760.76 | 550.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 3.00 | 800.00 | 682.50 | 501.87 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 3.00 | 800.00 | 704.98 | 830.01 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 67.92 | 540.64 | 526.93 | 544.01 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 299.22 | 444.32 | 697.41 | 653.31 |
| ========== | 213-00150 | Bonded Fiber Matrix | | Acre | ========== | ========== | ========== |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 6.81 | 2000.00 | 3975.58 | 4800.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 6.81 | 2000.00 | 3975.58 | 4800.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 6.81 | 2000.00 | 3975.58 | 4800.00 |
| ========== | 213-00460 | Landscape Border (3/16x4 In) | | Lin Foot | ========== | ========== | ========== |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 138.00 | 5.00 | 3.71 | 3.25 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 138.00 | 5.00 | 3.71 | 3.25 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 138.00 | 5.00 | 3.71 | 3.25 |
| ========== | 213-00705 | Landscape Boulder (Special) | | Each | ========== | ========== | ========== |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 679.00 | 5.00 | 764.30 | 653.71 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 679.00 | 5.00 | 764.30 | 653.71 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 679.00 | 5.00 | 764.30 | 653.71 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 214-00000 | Landscape Maintenance | | LUMP SUM | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 1.00 | 10000.00 | 7029.67 | 5700.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 1.00 | 15000.00 | 11417.58 | 11005.21 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 2.00 | 11000.00 | 9094.56 | 8352.61 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 1.00 | 5000.00 | 6068.32 | 5280.64 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 1.00 | 15000.00 | 30552.60 | 50101.39 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1.00 | 20000.00 | 34359.04 | 19181.02 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 3.00 | 13333.33 | 20939.51 | 24854.35 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 1.00 | 10000.00 | 11509.87 | 13700.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 1.00 | 10000.00 | 11509.87 | 13700.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1.00 | 10000.00 | 13585.71 | 19000.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1.00 | 5000.00 | 8799.00 | 18125.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 7500.00 | 11591.25 | 18562.50 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 8.00 | 10909.09 | 13867.14 | 17761.66 |
| ========== | 214-00005 | Landscape Maintenance (24 Month) | | LUMP SUM | | | |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 1.00 | 5000.00 | 10495.01 | 3300.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 1.00 | 5000.00 | 10495.01 | 3300.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 1.00 | 5000.00 | 7219.08 | 4963.57 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 5000.00 | 7219.08 | 4963.57 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 5000.00 | 8747.85 | 4131.79 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 214-00205 | Deciduous Tree (5 Gal) | | Each | | | |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 31.00 | 70.00 | 71.45 | 56.54 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 31.00 | 70.00 | 71.45 | 56.54 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 40.00 | 60.00 | 88.12 | 53.16 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 40.00 | 60.00 | 88.12 | 53.16 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 71.00 | 64.37 | 81.74 | 54.64 |
| ========== | 214-00215 | Deciduous Tree (1.5 In C) | | Each | | | |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 60.00 | 380.00 | 375.06 | 350.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 60.00 | 380.00 | 375.06 | 350.00 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 13.00 | 350.00 | 183.35 | 176.58 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 13.00 | 350.00 | 183.35 | 176.58 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 73.00 | 374.66 | 344.10 | 319.12 |
| ========== | 214-00220 | Deciduous Tree (2 In C) | | Each | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 12.00 | 400.00 | 516.12 | 445.71 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 12.00 | 400.00 | 516.12 | 445.71 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 33.00 | 350.00 | 364.62 | 422.45 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 15.00 | 350.00 | 328.90 | 330.00 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 48.00 | 350.00 | 354.45 | 393.56 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 25.00 | 400.00 | 347.70 | 365.00 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 25.00 | 400.00 | 347.70 | 365.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 214-00220 | Deciduous Tree (2 In C) | | Each | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 12.00 | 300.00 | 421.71 | 430.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 18.00 | 350.00 | 343.80 | 426.87 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1.00 | 500.00 | 834.66 | 201.21 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 31.00 | 335.48 | 388.17 | 420.80 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 116.00 | 362.07 | 379.01 | 400.08 |
| ========== | 214-00222 | Furn Decid Tree (2 In C) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 512.00 | 200.00 | 227.68 | 200.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 512.00 | 200.00 | 227.68 | 200.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 87.00 | 360.00 | 376.49 | 285.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 87.00 | 360.00 | 376.49 | 285.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 599.00 | 223.24 | 268.47 | 234.40 |
| ========== | 214-00225 | Deciduous Tree (2.5 In C) | | Each | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 19.00 | 400.00 | 349.86 | 331.78 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 19.00 | 400.00 | 349.86 | 331.78 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 19.00 | 400.00 | 349.86 | 331.78 |
| ========== | 214-00230 | Deciduous Tree (3 In C) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 64.00 | 550.00 | 549.42 | 514.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 214-00230 | Deciduous Tree (3 In C) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 64.00 | 550.00 | 549.42 | 514.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 64.00 | 550.00 | 549.42 | 514.00 |
| ========== | 214-00280 | Deciduous Tree (8 Ft) | | Each | | | |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 11.00 | 140.00 | 151.73 | 117.68 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 11.00 | 140.00 | 151.73 | 117.68 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 9.00 | 130.00 | 312.72 | 336.42 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 9.00 | 130.00 | 312.72 | 336.42 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 20.00 | 135.50 | 251.65 | 216.11 |
| ========== | 214-00350 | Deciduous Shrub (5 Gal) | | Each | | | |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 120.00 | 50.00 | 48.47 | 38.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 204.00 | 35.00 | 34.00 | 33.26 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 3,612.00 | 22.00 | 26.51 | 22.81 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 3,936.00 | 23.53 | 27.12 | 23.81 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 110.00 | 35.00 | 33.74 | 42.26 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 110.00 | 35.00 | 33.74 | 42.26 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 4,046.00 | 23.84 | 27.37 | 24.32 |
| ========== | 214-00450 | Evergreen Tree (5 Gal) | | Each | | | |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 32.00 | 75.00 | 74.40 | 58.58 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 32.00 | 75.00 | 74.40 | 58.58 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 214-00450 | Evergreen Tree (5 Gal) | | Each | | | |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 35.00 | 75.00 | 76.50 | 58.48 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 35.00 | 75.00 | 76.50 | 58.48 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 67.00 | 75.00 | 78.62 | 41.61 |
| ========== | 214-00504 | Evergreen Tree (4 Ft)(B-B) | | Each | | | |
| NH0403-053 | | US 40 RETAINING WALL REPAIR | 07/28/11 | 14.00 | 450.00 | 330.83 | 287.50 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 14.00 | 450.00 | 330.83 | 287.50 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 14.00 | 450.00 | 330.83 | 287.50 |
| ========== | 214-00506 | Evergreen Tree (6 Ft)(B-B) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 68.00 | 400.00 | 313.63 | 295.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 68.00 | 400.00 | 313.63 | 295.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 69.00 | 450.00 | 212.28 | 155.52 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 69.00 | 450.00 | 212.28 | 155.52 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 12.00 | 330.00 | 267.23 | 62.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 12.00 | 330.00 | 267.23 | 62.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 149.00 | 417.52 | 243.63 | 168.26 |
| ========== | 214-00507 | Furn Evergreen Tree (6 Ft)(B-B) | | Each | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 4.00 | 300.00 | 333.48 | 265.22 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 4.00 | 300.00 | 333.48 | 265.22 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4.00 | 300.00 | 333.48 | 265.22 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 214-00508 | Evergreen Tree (8 Ft)(B-B) | | Each | | | |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 1.00 | 800.00 | 480.67 | 500.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 106.00 | 500.00 | 420.37 | 414.73 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 107.00 | 502.80 | 420.94 | 415.53 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 107.00 | 502.80 | 420.94 | 415.53 |
| ========== | 214-00511 | Furn Evergreen Tree (10 Ft)(B-B) | | Each | | | |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 8.00 | 600.00 | 482.61 | 850.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 8.00 | 600.00 | 482.61 | 850.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 8.00 | 600.00 | 482.61 | 850.00 |
| ========== | 214-00650 | Evergreen Shrub (5 Gal) | | Each | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 32.00 | 35.00 | 36.50 | 41.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 32.00 | 35.00 | 36.50 | 41.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 32.00 | 35.00 | 36.50 | 41.00 |
| ========== | 214-00910 | Perennials (1 Gal) | | Each | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 2,398.00 | 10.00 | 10.81 | 10.37 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2,398.00 | 10.00 | 10.81 | 10.37 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,398.00 | 10.00 | 10.81 | 10.37 |
| ========== | 214-01010 | Brush Layer Cutting | | Each | | | |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 250.00 | 2.20 | 6.85 | 5.50 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 250.00 | 2.20 | 6.85 | 5.50 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 200.00 | 3.00 | 9.62 | 25.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 200.00 | 3.00 | 9.62 | 25.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 214-01010 | Brush Layer Cutting | | Each | | | |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 200.00 | 3.00 | 4.05 | 12.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 200.00 | 3.00 | 4.05 | 12.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 340.00 | 1.00 | 5.82 | 4.30 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 340.00 | 1.00 | 5.82 | 4.30 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 990.00 | 2.11 | 6.28 | 10.34 |
| ========== | 214-01015 | Willow Cuttings | | Each | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 500.00 | 2.00 | 5.01 | 6.60 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 500.00 | 2.00 | 5.01 | 6.60 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 246.00 | 5.00 | 5.77 | 6.86 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 246.00 | 5.00 | 5.77 | 6.86 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 746.00 | 2.99 | 5.26 | 6.69 |
| ========== | 215-00000 | Transplant Shrub | | Each | | | |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 20.00 | 60.00 | 116.54 | 70.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 20.00 | 60.00 | 116.54 | 70.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 20.00 | 60.00 | 116.54 | 70.00 |
| ========== | 215-00100 | Transplant Tree (6+ In) | | Each | | | |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 5.00 | 5000.00 | 653.83 | 425.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 5.00 | 5000.00 | 653.83 | 425.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 5.00 | 5000.00 | 653.83 | 425.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 215-00600 | Transplant Plug | | Each | | | |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 30.00 | 10.00 | 64.53 | 89.25 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 30.00 | 10.00 | 64.53 | 89.25 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 200.00 | 4.00 | 28.79 | 46.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 200.00 | 4.00 | 28.79 | 46.00 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 30.00 | 3.00 | 15.85 | 16.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 30.00 | 3.00 | 15.85 | 16.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 260.00 | 4.58 | 29.82 | 47.53 |
| ========== | 216-00015 | Soil Reten Blanket (Excel) | | Sq Yard | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 100.00 | 3.00 | 3.19 | 5.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 100.00 | 3.00 | 3.19 | 5.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 100.00 | 3.00 | 3.19 | 5.00 |
| ========== | 216-00021 | Soil Reten Blanket (Cl 1) | | Sq Yard | | | |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 2,000.00 | 1.50 | 1.66 | 1.50 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 2,000.00 | 1.50 | 1.66 | 1.50 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 3,850.00 | 2.00 | 1.49 | 1.52 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 7,000.00 | 2.00 | 2.45 | 2.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 10,850.00 | 2.00 | 2.13 | 1.83 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 12,850.00 | 1.92 | 2.06 | 1.95 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 216-00030 | Soil Reten Blanket (Spec) | | Sq Yard | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 38,100.00 | 2.50 | 1.53 | 1.50 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 38,100.00 | 2.50 | 1.53 | 1.50 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1,700.00 | 3.00 | 4.97 | 4.98 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 1,700.00 | 3.00 | 4.97 | 4.98 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 39,800.00 | 2.52 | 2.00 | 2.03 |
| ========== | 216-00037 | Soil Reten Blanket (Coconut) | | Sq Yard | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 8,728.00 | 2.00 | 2.41 | 2.59 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 8,728.00 | 2.00 | 2.41 | 2.59 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 4,182.00 | 4.00 | 1.72 | 2.50 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 4,182.00 | 4.00 | 1.72 | 2.50 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 12,910.00 | 2.65 | 2.21 | 2.56 |
| ========== | 216-00039 | Soil Reten Blanket (Straw) | | Sq Yard | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 277.00 | 15.00 | 4.94 | 8.20 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 277.00 | 15.00 | 4.94 | 8.20 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 277.00 | 15.00 | 4.94 | 8.20 |
| ========== | 216-00041 | Soil Reten Blanket (S/C) | | Sq Yard | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 78,420.00 | 1.50 | 1.83 | 1.96 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 216-00041 | Soil Reten Blanket (S/C) | | Sq Yard | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 78,420.00 | 1.50 | 1.84 | 1.99 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 200.00 | 4.00 | 1.94 | 1.70 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 809.00 | 3.00 | 2.61 | 2.66 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 3,410.00 | 2.00 | 3.17 | 4.20 |
| FSA 0502-064 | | US 50 EAST OF SARGENTS | 06/23/11 | 100.00 | 3.00 | 3.39 | 3.39 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 8,200.00 | 2.00 | 1.65 | 1.35 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 12,719.00 | 2.10 | 1.94 | 2.22 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 937.00 | 3.00 | 2.56 | 2.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 1,715.00 | 2.00 | 2.21 | 3.90 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 115.00 | 3.00 | 3.55 | 3.00 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 4,680.00 | 2.00 | 2.61 | 2.25 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 7,666.00 | 4.00 | 2.62 | 2.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 15,113.00 | 3.08 | 2.57 | 2.41 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 12,100.00 | 3.00 | 2.84 | 2.90 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 12,100.00 | 3.00 | 2.84 | 2.90 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 118,352.00 | 1.92 | 2.15 | 2.33 |
| ========== | 216-00042 | Soil Retent Blanket (BioD S/C) | | Sq Yard | | | |
| ITS4701-121 | | C470 (SANTA FE TO I-25) AND R | 01/20/11 | 100.00 | 3.00 | 7.66 | 6.15 |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 2,420.00 | 3.75 | 2.10 | 1.40 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 2,520.00 | 3.72 | 2.23 | 1.59 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 1,000.00 | 2.00 | 2.49 | 3.50 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 216-00042 | Soil Retent Blanket (BioD S/C) | | Sq Yard | | | |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 19,160.00 | 1.50 | 1.64 | 1.48 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 87.00 | 3.00 | 2.78 | 3.05 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 600.00 | 2.00 | 3.18 | 2.50 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 20,847.00 | 1.54 | 1.78 | 1.68 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 900.00 | 2.00 | 1.93 | 2.10 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 12,032.00 | 1.50 | 1.52 | 1.41 |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 1,452.00 | 4.00 | 6.85 | 3.15 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 14,384.00 | 1.78 | 1.83 | 1.63 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 37,751.00 | 1.78 | 1.84 | 1.68 |
| ========== | 216-00201 | Soil Reten Blanket (S-C)(BioD Cl 1) | | Sq Yard | | | |
| C0704-225 | | I-70 EAST OF BENNETT | 01/06/11 | 50.00 | 2.50 | 4.43 | 3.45 |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 200.00 | 5.00 | 2.83 | 2.90 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 250.00 | 4.50 | 2.25 | 2.06 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 1,200.00 | 2.00 | 2.53 | 2.70 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 14,480.00 | 2.00 | 1.90 | 2.05 |
| ITS0703-370 | | EAST OF EJMT ON I-70 EB LANES | 06/16/11 | 2,250.00 | 2.00 | 2.28 | 1.95 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 17,930.00 | 2.00 | 2.04 | 2.00 |
| C006A-051 | | US 6 (LOVELAND PASS), CLEAR C | 07/14/11 | 600.00 | 2.25 | 3.54 | 2.60 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 140.00 | 3.00 | 2.81 | 2.54 |
| NH0403-053 | | US 40 RETAINING WALL REPAIR | 07/28/11 | 1,200.00 | 6.00 | 2.20 | 1.90 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 1,080.00 | 3.00 | 2.21 | 2.25 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 1,000.00 | 4.00 | 3.07 | 3.20 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 4,020.00 | 4.03 | 2.45 | 2.40 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 140,000.00 | 2.00 | 1.47 | 1.24 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 216-00201 | Soil Reten Blanket (S-C)(BioD Cl 1) | | Sq Yard | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1,126.00 | 2.00 | 2.09 | 1.90 |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 500.00 | 1.75 | 2.82 | 2.30 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 141,626.00 | 2.00 | 1.48 | 1.25 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 163,826.00 | 2.05 | 1.64 | 1.48 |
| ========== | 216-00211 | Soil Reten Blanket (Exc)(BioD Cl 1) | | Sq Yard | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 6,483.00 | 6.00 | 2.00 | 1.76 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 6,483.00 | 6.00 | 2.00 | 1.76 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 2,563.00 | 3.00 | 1.71 | 1.56 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 2,563.00 | 3.00 | 1.71 | 1.56 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 9,046.00 | 5.15 | 1.93 | 1.70 |
| ========== | 216-00303 | Turf Reinf Mat (Cl 3) | | Sq Yard | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 6,483.00 | 7.00 | 8.42 | 9.33 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 6,483.00 | 7.00 | 8.42 | 9.33 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 6,483.00 | 7.00 | 8.42 | 9.33 |
| ========== | 217-00000 | Herbicide Treatment | | Sq Yard | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 286,528.00 | 0.20 | 0.11 | 0.06 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 286,528.00 | 0.20 | 0.11 | 0.06 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 100.00 | 1.50 | 6.45 | 5.32 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 100.00 | 1.50 | 6.45 | 5.32 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 286,628.00 | 0.20 | 0.12 | 0.07 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 217-00015 | Noxious Weed Management | | Sq Yard | | | |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 9,793.00 | 0.25 | 1.23 | 0.95 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 9,793.00 | 0.25 | 1.23 | 0.95 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 9,793.00 | 0.25 | 1.23 | 0.95 |
| ========== | 217-00020 | Herbicide Treatment | | Hour | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 480.00 | 110.00 | 82.28 | 75.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 100.00 | 100.00 | 95.63 | 95.44 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 580.00 | 108.28 | 87.96 | 84.29 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 300.00 | 80.00 | 90.73 | 78.15 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 20.00 | 110.00 | 204.52 | 190.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 320.00 | 81.88 | 97.00 | 85.14 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 80.00 | 100.00 | 96.09 | 115.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 80.00 | 100.00 | 96.09 | 115.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 70.00 | 110.00 | 92.31 | 77.21 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 40.00 | 150.00 | 143.70 | 160.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 110.00 | 124.55 | 112.42 | 107.32 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,090.00 | 101.56 | 96.43 | 91.50 |
| ========== | 218-00000 | Noxious Weed Management | | LUMP SUM | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 1.00 | 5000.00 | 4014.66 | 5200.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 1.00 | 5000.00 | 4014.66 | 5200.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 5000.00 | 4014.66 | 5200.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 240-00000 | Wildlife Biologist | | Hour | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 320.00 | 70.00 | 86.32 | 78.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 320.00 | 70.00 | 86.32 | 78.00 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 20.00 | 80.00 | 51.58 | 52.81 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 20.00 | 80.00 | 108.13 | 100.00 |
| C0241-055 | | SH 24 MP 148-152 | 05/26/11 | 10.00 | 150.00 | 226.33 | 375.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 10.00 | 150.00 | 92.64 | 79.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 20.00 | 80.00 | 56.74 | 55.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 80.00 | 97.50 | 80.92 | 100.22 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 20.00 | 80.00 | 91.49 | 55.15 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 10.00 | 150.00 | 113.00 | 99.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 40.00 | 80.00 | 84.91 | 90.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 70.00 | 90.00 | 88.80 | 81.33 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 470.00 | 77.66 | 85.34 | 87.82 |
| ========== | 240-00010 | Rem of Nests | | Hour | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 20.00 | 80.00 | 104.79 | 100.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 4.00 | 45.00 | 98.43 | 65.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 24.00 | 74.17 | 72.07 | 48.85 |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 8.00 | 50.00 | 90.38 | 160.00 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 20.00 | 65.00 | 109.45 | 62.61 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 5.00 | 150.00 | 204.74 | 500.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 33.00 | 74.24 | 126.93 | 152.49 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 240-00010 | Rem of Nests | | Hour | | | |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 10.00 | 35.00 | 57.20 | 40.11 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 40.00 | 70.00 | 86.47 | 75.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 50.00 | 63.00 | 81.15 | 68.02 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 107.00 | 68.97 | 79.22 | 67.97 |
| ========== | 240-00020 | Netting | | Sq Yard | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 100.00 | 30.00 | 75.41 | 21.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 100.00 | 30.00 | 9.39 | 3.64 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 200.00 | 2.00 | 13.14 | 14.03 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 200.00 | 2.00 | 13.14 | 14.03 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 300.00 | 11.33 | 9.73 | 5.57 |
| ========== | 240-00100 | Prairie Dog Mgmt | | LUMP SUM | | | |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 1.00 | 7500.00 | 4917.55 | 4752.58 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1.00 | 7000.00 | 9895.91 | 20114.16 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2.00 | 7250.00 | 7051.13 | 12433.37 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 1.00 | 5500.00 | 7423.44 | 4941.51 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 5500.00 | 7423.44 | 4941.51 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3.00 | 6666.67 | 7186.52 | 9936.08 |
| ========== | 250-00010 | Envir Health/Safety Mngmt | | LUMP SUM | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 1.00 | 4000.00 | 2595.32 | 2500.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 250-00010 | Envir Health/Safety Mngmt | | LUMP SUM | ========== | ========== | ========== |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 1.00 | 10000.00 | 5000.95 | 4200.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 2.00 | 8800.00 | 4141.79 | 3350.00 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 1.00 | 7500.00 | 4582.67 | 5508.00 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 1.00 | 7000.00 | 6115.50 | 3795.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 1.00 | 4000.00 | 4355.94 | 5200.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 3.00 | 6166.67 | 5058.29 | 4834.33 |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 1.00 | 200000.00 | 6496.40 | 8700.00 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 1.00 | 4000.00 | 1189.55 | 1113.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 1.00 | 4000.00 | 2564.49 | 3120.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 1.00 | 2000.00 | 3528.41 | 4000.00 |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 1.00 | 1500.00 | 4506.00 | 4012.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 5.00 | 42300.00 | 3636.27 | 4189.00 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 1.00 | 5000.00 | 3402.71 | 2865.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1.00 | 10000.00 | 2012.86 | 2900.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 7500.00 | 2754.11 | 2882.50 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 12.00 | 19266.67 | 3873.37 | 3992.75 |
| ========== | 250-00050 | Monitoring Technician | | Hour | ========== | ========== | ========== |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 8.00 | 100.00 | 100.20 | 110.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 4,000.00 | 40.00 | 42.08 | 38.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 4,008.00 | 40.12 | 42.34 | 38.57 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 250-00050 | Monitoring Technician | | Hour | | | |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 50.00 | 110.00 | 134.33 | 136.00 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 50.00 | 110.00 | 90.67 | 110.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 100.00 | 70.00 | 73.41 | 62.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 200.00 | 90.00 | 85.86 | 92.50 |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 400.00 | 75.00 | 84.50 | 82.00 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 28.00 | 75.00 | 92.93 | 87.00 |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 30.00 | 100.00 | 119.00 | 138.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 458.00 | 76.64 | 85.67 | 85.97 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 80.00 | 80.00 | 72.17 | 56.90 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 20.00 | 60.00 | 81.21 | 86.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 100.00 | 76.00 | 73.79 | 62.72 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4,766.00 | 46.48 | 56.08 | 58.34 |
| ========== | 250-00100 | Environmental Health and Safety | | LUMP SUM | | | |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 1.00 | 2500.00 | 3201.67 | 725.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1.00 | 2500.00 | 3201.67 | 725.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 2500.00 | 3484.91 | 1112.50 |
| ========== | 250-00110 | Health and Safety Officer | | Hour | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 4.00 | 100.00 | 161.78 | 175.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 2,600.00 | 60.00 | 56.83 | 52.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 2,604.00 | 60.06 | 57.19 | 52.75 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 250-00110 | Health and Safety Officer | | Hour | | | |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 50.00 | 150.00 | 103.83 | 82.50 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 50.00 | 150.00 | 117.00 | 87.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 40.00 | 100.00 | 86.71 | 79.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 140.00 | 135.71 | 102.68 | 83.11 |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 80.00 | 100.00 | 111.17 | 91.00 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 6.00 | 90.00 | 92.85 | 87.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 40.00 | 110.00 | 87.98 | 100.00 |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 8.00 | 100.00 | 228.50 | 307.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 134.00 | 102.54 | 106.72 | 106.40 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 40.00 | 120.00 | 76.05 | 60.70 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 20.00 | 75.00 | 94.07 | 97.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 60.00 | 105.00 | 81.53 | 72.80 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,938.00 | 66.52 | 67.48 | 65.55 |
| ========== | 250-00120 | Material Sampling and Delivery | | Each | | | |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 8.00 | 500.00 | 294.14 | 365.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 8.00 | 500.00 | 294.14 | 365.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 8.00 | 500.00 | 294.14 | 365.00 |
| ========== | 250-00200 | Material Handling (Stockpile) | | Cubic Yard | | | |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 10.00 | 100.00 | 73.65 | 80.00 |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 20.00 | 50.00 | 54.50 | 71.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 30.00 | 66.67 | 65.14 | 74.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 30.00 | 66.67 | 65.14 | 74.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 250-00210 | Solid Waste Disposal | | Cubic Yard | | | |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 10.00 | 650.00 | 114.30 | 80.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 10.00 | 650.00 | 114.30 | 80.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 10.00 | 650.00 | 114.30 | 80.00 |
| ========== | 250-00220 | Hazardous Waste Disposal | | Cubic Yard | | | |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 140.00 | 40.00 | 239.47 | 413.99 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 140.00 | 40.00 | 239.47 | 413.99 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 140.00 | 40.00 | 242.79 | 305.61 |
| ========== | 304-01000 | ABC (CL 1) | | Ton | | | |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 9,665.00 | 15.00 | 19.50 | 16.50 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 69,045.00 | 15.00 | 22.46 | 19.25 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 78,710.00 | 15.00 | 22.31 | 18.91 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 54,232.00 | 15.00 | 14.89 | 13.95 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 54,232.00 | 15.00 | 14.89 | 13.95 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 132,942.00 | 15.00 | 18.92 | 16.89 |
| ========== | 304-02000 | ABC (CL 2) | | Ton | | | |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 6,509.00 | 16.00 | 16.92 | 16.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 6,509.00 | 16.00 | 14.63 | 13.71 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 5,350.00 | 20.00 | 22.65 | 20.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 5,350.00 | 20.00 | 22.65 | 20.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 304-02000 | ABC (CL 2) | | Ton | | | |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 411.00 | 20.00 | 18.81 | 21.32 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 7,527.00 | 14.00 | 15.80 | 12.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 36,816.00 | 18.00 | 17.00 | 15.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 44,754.00 | 17.35 | 16.94 | 14.55 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 56,613.00 | 17.44 | 16.48 | 14.48 |
| ========== | 304-02005 | ABC (CL 2) | | Cubic Yard | | | |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 22,109.00 | 16.00 | 32.00 | 29.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 22,109.00 | 16.00 | 32.00 | 29.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 22,109.00 | 16.00 | 32.00 | 29.00 |
| ========== | 304-03000 | ABC (CL 3) | | Ton | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 448.00 | 20.00 | 28.93 | 36.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 448.00 | 20.00 | 28.93 | 36.00 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 2,002.00 | 10.00 | 24.75 | 18.50 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 4,868.00 | 15.00 | 19.04 | 15.55 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 6,870.00 | 13.54 | 20.53 | 16.41 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 7,318.00 | 13.94 | 20.92 | 17.61 |
| ========== | 304-03005 | ABC (CL 3) | | Cubic Yard | | | |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 44.00 | 35.00 | 54.55 | 30.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 44.00 | 35.00 | 54.55 | 30.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 44.00 | 35.00 | 54.55 | 30.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 304-05000 | ABC (CL 5) | | Ton | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 2,335.00 | 22.00 | 17.92 | 20.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2,335.00 | 22.00 | 17.92 | 20.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,335.00 | 22.00 | 17.92 | 20.00 |
| ========== | 304-06000 | ABC (CL 6) | | Ton | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 517.00 | 20.00 | 30.13 | 32.75 |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 203.00 | 35.00 | 26.53 | 25.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 173,344.00 | 15.00 | 13.68 | 14.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 6,540.00 | 15.00 | 15.08 | 19.66 |
| NH 0402-079 | | US40 MP 165.0 - 179.0 GRAND C | 03/31/11 | 3,605.00 | 22.00 | 22.50 | 19.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 184,209.00 | 15.17 | 14.43 | 15.24 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 5,696.00 | 20.00 | 20.58 | 19.75 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 573.00 | 15.00 | 32.46 | 21.75 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 365.00 | 25.00 | 29.88 | 27.00 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 8,204.00 | 20.00 | 13.22 | 13.72 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 5,240.00 | 18.00 | 13.57 | 18.00 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 2,847.00 | 18.00 | 17.51 | 16.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 18,327.00 | 18.00 | 24.44 | 23.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 1,993.00 | 25.00 | 23.05 | 21.60 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 30.00 | 50.00 | 48.74 | 42.22 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 15,220.00 | 12.00 | 15.18 | 11.83 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 720.00 | 40.00 | 27.60 | 27.30 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 269.00 | 30.00 | 27.25 | 33.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 1,239.00 | 25.00 | 25.25 | 19.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 19,919.00 | 15.00 | 14.78 | 12.19 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 80,642.00 | 17.01 | 18.09 | 16.73 |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 126.00 | 30.00 | 62.75 | 61.00 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 350.00 | 30.00 | 27.86 | 21.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 304-06000 | ABC (CL 6) | | Ton | | | |
| NH2872-018 | | US 287 RUSH CREEK NORTH | 07/21/11 | 100.00 | 15.00 | 43.44 | 35.00 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 328.00 | 25.00 | 31.83 | 32.00 |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 60.00 | 20.00 | 26.80 | 24.00 |
| C0091-038 | | SH 9 MM 81.9 BLUE RIVER EMERG | 08/24/11 | 60.00 | 30.00 | 49.80 | 21.40 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 2,318.00 | 22.00 | 26.82 | 23.00 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 19,232.00 | 17.00 | 18.02 | 16.95 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 22,574.00 | 17.94 | 19.53 | 19.60 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 22,750.00 | 19.00 | 13.66 | 13.67 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 1,760.00 | 18.00 | 19.60 | 17.00 |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 115.00 | 150.00 | 97.50 | 80.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 14,067.00 | 20.00 | 20.02 | 21.00 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 4,214.00 | 25.00 | 22.33 | 25.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 42,906.00 | 20.23 | 17.39 | 17.50 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 330,331.00 | 16.47 | 17.14 | 16.94 |
| ========== | 304-06007 | ABC (CL 6) | | Cubic Yard | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 61,456.00 | 25.00 | 18.45 | 19.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 2,898.00 | 25.00 | 28.02 | 22.00 |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 1,090.00 | 25.00 | 52.79 | 30.00 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 1,024.20 | 35.00 | 60.87 | 58.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 66,468.20 | 25.15 | 22.41 | 21.98 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 163.00 | 40.00 | 32.98 | 26.41 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 177.00 | 40.00 | 41.42 | 22.45 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 10,284.00 | 20.00 | 21.99 | 24.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 9,566.00 | 30.00 | 37.33 | 35.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 20,190.00 | 25.07 | 26.64 | 29.25 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 1,408.00 | 25.00 | 24.82 | 30.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 304-06007 | ABC (CL 6) | | Cubic Yard | | | |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 12.00 | 25.00 | 89.30 | 88.00 |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 5.00 | 60.00 | 97.00 | 94.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1,425.00 | 25.12 | 28.63 | 33.10 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 2,301.00 | 22.00 | 23.00 | 22.64 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 16,924.00 | 23.00 | 25.95 | 22.90 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 9,109.00 | 20.00 | 23.62 | 24.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 1,915.00 | 35.00 | 25.98 | 23.71 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 2,794.20 | 22.00 | 25.63 | 21.63 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 7,030.00 | 50.00 | 48.13 | 42.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 40,073.20 | 27.50 | 27.79 | 26.44 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 128,156.40 | 25.88 | 25.84 | 26.18 |
| ========== | 304-06008 | ABC (CL 6) (Spec) | | Cubic Yard | | | |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 2,069.00 | 22.00 | 21.23 | 26.41 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 20.00 | 40.00 | 60.82 | 34.12 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2,089.00 | 22.17 | 21.48 | 26.48 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,089.00 | 22.17 | 21.48 | 26.48 |
| ========== | 304-07000 | ABC (CL 7) | | Ton | | | |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 2,796.00 | 25.00 | 22.03 | 20.14 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 1,204.00 | 20.00 | 29.33 | 17.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 4,000.00 | 23.50 | 23.53 | 19.19 |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 9.00 | 50.00 | 77.14 | 190.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 9.00 | 50.00 | 77.14 | 190.00 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 2,590.00 | 30.00 | 32.00 | 24.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2,590.00 | 30.00 | 32.00 | 24.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 6,599.00 | 26.08 | 25.58 | 21.31 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 304-07005 | ABC (CL 7) | | Cubic Yard | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 30.00 | 40.00 | 70.25 | 63.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 30.00 | 40.00 | 70.25 | 63.00 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 191.00 | 25.00 | 31.17 | 50.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 191.00 | 25.00 | 31.17 | 50.00 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 2,097.00 | 20.00 | 24.99 | 30.02 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 2,097.00 | 20.00 | 24.99 | 30.02 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 37.00 | 20.00 | 36.44 | 17.60 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 1,507.00 | 52.00 | 49.97 | 50.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1,544.00 | 51.23 | 49.42 | 49.22 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3,862.00 | 32.89 | 34.35 | 38.94 |
| ========== | 304-09000 | ABC (Spec) | | Cubic Yard | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 38.00 | 30.00 | 46.41 | 51.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 38.00 | 30.00 | 15.65 | 12.07 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 1,106.00 | 30.00 | 30.19 | 32.50 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 626.00 | 35.00 | 51.00 | 44.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1,732.00 | 31.81 | 38.40 | 36.11 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 272.00 | 25.00 | 28.79 | 10.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 272.00 | 25.00 | 28.79 | 10.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 304-09000 | ABC (Spec) | | Cubic Yard | | | |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 750.00 | 30.00 | 35.88 | 30.00 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 1,331.00 | 25.00 | 30.70 | 29.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 2,081.00 | 26.80 | 33.21 | 29.36 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4,123.00 | 28.82 | 29.00 | 24.95 |
| ========== | 304-09014 | ABC (Spec) | | Ton | | | |
| NH 2852-017 | | US 285 PONCHA PASS SOUTH RESU | 03/03/11 | 3,717.30 | 13.00 | 16.00 | 9.00 |
| NH 0241-056 | | US 24 BUENA VISTA NORTH | 03/03/11 | 3,073.00 | 20.00 | 17.03 | 15.50 |
| STA0504-061 | | US 50 M.P.369.9 -M.P.373.2 | 03/03/11 | 500.00 | 12.00 | 13.03 | 13.75 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 7,290.30 | 15.88 | 16.27 | 12.07 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 15.00 | 60.00 | 67.90 | 70.29 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 15.00 | 60.00 | 67.90 | 70.29 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 4,469.00 | 25.00 | 27.30 | 23.50 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 4,469.00 | 25.00 | 27.30 | 23.50 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 11,774.30 | 19.40 | 19.52 | 16.48 |
| ========== | 307-00000 | Hydrated Lime | | Ton | | | |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 590.00 | 150.00 | 215.47 | 199.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 590.00 | 150.00 | 215.47 | 199.00 |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 1,378.00 | 150.00 | 152.89 | 140.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 1,378.00 | 150.00 | 152.89 | 140.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,968.00 | 150.00 | 168.71 | 155.38 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 310-00608 | Full Depth Reclam. of HMA Pvmt (0-8 in.) | | Sq Yard | | | |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 29,867.00 | 1.80 | 2.67 | 2.50 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 29,867.00 | 1.80 | 2.27 | 1.68 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 15,700.00 | 4.00 | 2.95 | 2.15 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 15,700.00 | 4.00 | 2.95 | 2.15 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 45,567.00 | 2.56 | 2.40 | 1.73 |
| ========== | 310-00610 | Full Depth Reclam. of HMA Pvmt (8-12 in) | | Sq Yard | | | |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 7,467.00 | 2.25 | 4.02 | 3.30 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 7,467.00 | 2.25 | 3.56 | 2.88 |
| STR096A-040 | | SH 96 MP 193 TO MP 201 | 09/01/11 | 110,880.00 | 2.50 | 2.35 | 2.59 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 4,000.00 | 5.00 | 4.52 | 2.80 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 114,880.00 | 2.59 | 2.56 | 2.60 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 122,347.00 | 2.57 | 2.80 | 2.64 |
| ========== | 403-00720 | HMA (Patching) (Asph) | | Ton | | | |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 100.00 | 125.00 | 107.38 | 110.00 |
| ITS4701-121 | | C470 (SANTA FE TO I-25) AND R | 01/20/11 | 10.00 | 150.00 | 422.25 | 384.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 10,700.00 | 100.00 | 64.73 | 80.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| STA0504-061 | | US 50 M.P.369.9 -M.P.373.2 | 03/03/11 | 100.00 | 80.00 | 149.98 | 169.92 |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 100.00 | 150.00 | 126.03 | 95.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 2,000.00 | 80.00 | 86.36 | 91.34 |
| NH 0402-079 | | US40 MP 165.0 - 179.0 GRAND C | 03/31/11 | 50.00 | 160.00 | 161.26 | 100.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 13,060.00 | 97.63 | 87.16 | 96.35 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 403-00720 | HMA (Patching) (Asph) | | Ton | | | |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 20.00 | 200.00 | 134.34 | 104.69 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 318.00 | 80.00 | 90.97 | 100.00 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 590.00 | 90.00 | 108.48 | 100.00 |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 701.00 | 150.00 | 109.36 | 91.25 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 15.00 | 120.00 | 170.61 | 114.00 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 250.00 | 110.00 | 129.25 | 175.32 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 1,000.00 | 90.00 | 125.50 | 95.00 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 529.00 | 115.00 | 94.35 | 90.00 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 100.00 | 175.00 | 150.13 | 130.00 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 183.00 | 100.00 | 105.41 | 98.93 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 2,458.00 | 120.00 | 117.77 | 85.50 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 373.00 | 125.00 | 155.21 | 138.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 32.00 | 175.00 | 152.33 | 151.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 481.00 | 100.00 | 166.96 | 160.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 154.00 | 200.00 | 171.33 | 149.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 1,050.00 | 90.00 | 134.05 | 87.23 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 1,371.00 | 120.00 | 98.25 | 94.50 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 4.00 | 120.00 | 284.00 | 125.00 |
| ITS0703-370 | | EAST OF EJMT ON I-70 EB LANES | 06/16/11 | 10.00 | 300.00 | 454.67 | 585.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 50.00 | 150.00 | 170.67 | 173.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 200.00 | 90.00 | 156.31 | 134.76 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 9,889.00 | 113.03 | 127.19 | 104.04 |
| C006A-051 | | US 6 (LOVELAND PASS), CLEAR C | 07/14/11 | 50.00 | 165.00 | 268.00 | 297.00 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 70.00 | 175.00 | 255.59 | 300.00 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 22.00 | 110.00 | 158.68 | 103.92 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 100.00 | 150.00 | 139.61 | 95.00 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 40.00 | 200.00 | 229.00 | 270.00 |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 40.00 | 100.00 | 172.00 | 135.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 318.00 | 100.00 | 125.84 | 148.00 |
| NH0403-053 | | US 40 RETAINING WALL REPAIR | 07/28/11 | 28.00 | 200.00 | 360.00 | 230.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 500.00 | 150.00 | 147.76 | 165.00 |
| BR2706-036 | | I-270 BRIDGE DECK REHABILITAT | 08/11/11 | 154.00 | 125.00 | 297.38 | 273.00 |
| NH5502-070 | | US 550 4 MILES SOUTH OF OURAY | 08/18/11 | 55.00 | 225.00 | 344.50 | 300.00 |
| C0091-038 | | SH 9 MM 81.9 BLUE RIVER EMERG | 08/24/11 | 75.00 | 150.00 | 228.35 | 205.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 27.00 | 225.00 | 257.40 | 250.00 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 300.00 | 180.00 | 157.11 | 140.00 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 100.00 | 200.00 | 246.67 | 240.00 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 10.00 | 250.00 | 1122.80 | 1500.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 1,889.00 | 152.34 | 177.09 | 176.28 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 403-00720 | HMA (Patching) (Asph) | | Ton | | | |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 100.00 | 90.00 | 120.03 | 120.76 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 54.00 | 125.00 | 183.00 | 195.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 200.00 | 110.00 | 144.47 | 138.57 |
| SHE0402-081 | | US 40 - MP 113 TO 120 ROUTT C | 10/27/11 | 4.00 | 75.00 | 451.67 | 453.04 |
| ITSSW00-928 | | NB I-225 AT MM 2.28 | 11/03/11 | 10.00 | 150.00 | 272.38 | 266.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 50.00 | 150.00 | 144.37 | 146.15 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 738.40 | 100.00 | 106.26 | 89.94 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 20.00 | 180.00 | 314.50 | 129.00 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 100.00 | 100.00 | 195.99 | 210.00 |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 78.00 | 334.00 | 400.00 | 400.00 |
| MC0504-065 | | US50B FROM MP 318 TO MP 359 | 12/01/11 | 75.00 | 100.00 | 214.67 | 140.00 |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 100.00 | 150.00 | 135.21 | 122.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 50.00 | 200.00 | 137.96 | 130.00 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 145.00 | 160.00 | 133.33 | 130.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1,724.40 | 125.40 | 130.40 | 134.16 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 26,562.40 | 109.05 | 116.07 | 111.76 |
| ========== | 403-00721 | HMA (Patching) (Asph) | | Sq Yard | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 52.00 | 100.00 | 64.07 | 70.20 |
| NH 2852-017 | | US 285 PONCHA PASS SOUTH RESU | 03/03/11 | 50.00 | 40.00 | 53.62 | 10.00 |
| NH 0241-056 | | US 24 BUENA VISTA NORTH | 03/03/11 | 40.00 | 45.00 | 62.33 | 30.00 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 40.00 | 80.00 | 164.72 | 200.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 182.00 | 67.03 | 83.88 | 73.35 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 200.00 | 60.00 | 103.64 | 130.00 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 111.00 | 215.00 | 191.88 | 183.75 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 311.00 | 115.32 | 117.42 | 149.18 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 122.00 | 75.00 | 117.67 | 72.23 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 83.00 | 190.00 | 82.19 | 37.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 5.00 | 150.00 | 200.40 | 250.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 403-00721 | HMA (Patching) (Asph) | | Sq Yard | | | |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 438.00 | 70.00 | 82.50 | 85.00 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 648.00 | 86.93 | 94.13 | 77.72 |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 170.00 | 200.00 | 175.92 | 138.67 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 170.00 | 200.00 | 175.92 | 138.67 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 1,311.00 | 105.56 | 110.18 | 101.97 |
| ========== | 403-00800 | Emerg Pothole Rep | | Ton | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 150.00 | 150.00 | 238.33 | 188.61 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 150.00 | 150.00 | 238.33 | 188.61 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 20.00 | 220.00 | 330.96 | 408.47 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 50.00 | 200.00 | 280.15 | 149.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 20.00 | 220.00 | 304.44 | 520.00 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 90.00 | 208.89 | 299.37 | 289.10 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 20.00 | 220.00 | 353.48 | 520.00 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 20.00 | 220.00 | 353.48 | 520.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 50.00 | 180.00 | 292.34 | 343.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 20.00 | 220.00 | 316.55 | 396.88 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 70.00 | 191.43 | 301.79 | 358.39 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 330.00 | 179.09 | 272.54 | 272.12 |
| ========== | 403-02000 | HMA (Spec) | | Ton | | | |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 3,670.00 | 60.00 | 71.83 | 67.00 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 3,670.00 | 60.00 | 71.83 | 67.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 403-02000 | HMA (Spec) | | Ton | | | |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 1,000.00 | 95.00 | 106.43 | 102.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1,000.00 | 95.00 | 106.43 | 102.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4,670.00 | 67.49 | 82.64 | 74.49 |
| ========== | 403-09210 | SMA | | Ton | | | |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 23,332.00 | 82.00 | 101.85 | 95.65 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 23,332.00 | 82.00 | 101.85 | 95.65 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 23,332.00 | 82.00 | 99.57 | 90.70 |
| ========== | 403-09221 | SMA (Fibers)(Asph) | | Ton | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 5,380.00 | 92.50 | 84.87 | 82.75 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 10,394.00 | 75.00 | 89.71 | 91.34 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 15,774.00 | 80.97 | 89.00 | 90.47 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 5,626.00 | 80.00 | 87.22 | 91.88 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 225.00 | 100.00 | 109.29 | 100.00 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 10,447.60 | 88.00 | 101.93 | 84.50 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 1,864.00 | 85.00 | 89.60 | 88.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 18,162.60 | 85.36 | 95.27 | 87.34 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 4,278.00 | 95.00 | 98.83 | 95.00 |
| BR2706-036 | | I-270 BRIDGE DECK REHABILITAT | 08/11/11 | 1,062.00 | 95.00 | 207.75 | 199.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 5,340.00 | 95.00 | 110.86 | 115.68 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 403-09221 | SMA (Fibers)(Asph) | | Ton | | | |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 2,232.00 | 95.00 | 98.80 | 93.70 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 256.00 | 120.00 | 133.89 | 139.42 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 3,375.60 | 92.00 | 94.68 | 90.50 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 5,863.60 | 94.36 | 97.82 | 93.85 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 45,140.20 | 86.14 | 95.58 | 92.86 |
| ========== | 403-09500 | Furnish HMA | | Ton | | | |
| NH 0402-079 | | US40 MP 165.0 - 179.0 GRAND C | 03/31/11 | 4,353.00 | 80.00 | 74.56 | 65.13 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 4,353.00 | 80.00 | 74.56 | 65.13 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 4,695.00 | 65.00 | 69.28 | 60.42 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 3,494.00 | 80.00 | 50.50 | 52.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 8,189.00 | 71.40 | 63.49 | 56.83 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 1,859.00 | 70.00 | 78.33 | 70.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 1,859.00 | 70.00 | 78.33 | 70.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 14,401.00 | 73.82 | 69.49 | 61.04 |
| ========== | 403-33751 | HMA (Gr S) (75) (PG 64-28) | | Ton | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 3,447.00 | 80.00 | 77.01 | 72.31 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 3,447.00 | 80.00 | 77.01 | 72.31 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 39,838.00 | 57.00 | 61.79 | 55.57 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 39,838.00 | 57.00 | 61.79 | 55.57 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 43,285.00 | 58.83 | 63.22 | 56.90 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 403-33841 | HMA (Gr S) (100) (PG 64-22) | | Ton | | | |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 238.00 | 80.00 | 78.04 | 80.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 40,320.00 | 56.25 | 55.79 | 47.60 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 40,558.00 | 56.39 | 56.13 | 48.35 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 2,186.00 | 50.00 | 70.47 | 65.00 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 10,027.00 | 50.00 | 52.33 | 50.00 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 905.60 | 65.00 | 104.69 | 68.00 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 200.00 | 70.00 | 68.84 | 60.36 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 15,820.00 | 55.00 | 62.75 | 46.08 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 29,138.60 | 53.32 | 59.66 | 49.63 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 2,712.00 | 65.00 | 62.40 | 62.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 2,712.00 | 65.00 | 62.40 | 62.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 20,299.00 | 57.00 | 56.70 | 57.40 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 7,439.00 | 55.00 | 56.07 | 53.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 2,178.00 | 60.00 | 57.90 | 59.73 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 6,600.10 | 58.00 | 53.71 | 50.50 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 36,516.10 | 56.95 | 56.06 | 55.40 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 108,924.70 | 55.97 | 57.45 | 52.56 |
| ========== | 403-33851 | HMA (Gr S) (100) (PG 64-28) | | Ton | | | |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 1,649.00 | 70.00 | 60.31 | 63.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 1,649.00 | 70.00 | 60.31 | 63.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,649.00 | 70.00 | 60.31 | 63.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 403-33871 | HMA (Gr S) (100) (PG 76-28) | | Ton | | | |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 218.00 | 110.00 | 67.73 | 63.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 218.00 | 110.00 | 67.73 | 63.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 218.00 | 110.00 | 71.50 | 59.33 |
| ========== | 403-34701 | HMA (Gr SX) (75) | | Ton | | | |
| NH 0241-056 | | US 24 BUENA VISTA NORTH | 03/03/11 | 33,063.00 | 35.00 | 30.96 | 24.50 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 32,611.00 | 35.00 | 54.03 | 53.00 |
| NH 0402-079 | | US40 MP 165.0 - 179.0 GRAND C | 03/31/11 | 29,519.00 | 30.00 | 41.90 | 70.70 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 95,193.00 | 33.45 | 42.24 | 48.59 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 27,069.00 | 35.00 | 35.13 | 31.95 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 19,975.00 | 30.00 | 40.48 | 32.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 14,419.00 | 35.00 | 64.23 | 60.50 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 1,884.00 | 60.00 | 75.90 | 73.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 63,347.00 | 34.17 | 49.99 | 42.69 |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 132.00 | 100.00 | 198.38 | 170.00 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 18,895.00 | 36.00 | 38.27 | 34.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 19,027.00 | 36.44 | 39.02 | 34.94 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 60,759.00 | 45.00 | 51.00 | 37.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 11,389.00 | 55.00 | 48.38 | 42.50 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 13,325.00 | 60.00 | 49.00 | 49.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 85,473.00 | 48.67 | 50.04 | 39.60 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 263,040.00 | 38.78 | 45.18 | 43.23 |
| ========== | 403-34721 | HMA (Gr SX) (75) (PG 58-28) | | Ton | | | |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 30,794.00 | 61.00 | 74.35 | 65.50 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 403-34721 | HMA (Gr SX) (75) (PG 58-28) | | Ton | | | |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 22,556.00 | 70.00 | 80.83 | 77.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 1,005.00 | 95.00 | 82.67 | 81.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 54,355.00 | 65.36 | 77.29 | 70.56 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 4,116.00 | 115.00 | 101.08 | 100.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 4,116.00 | 115.00 | 101.08 | 100.00 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 2,807.00 | 100.00 | 99.65 | 95.00 |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 80,005.00 | 60.00 | 73.33 | 71.05 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 82,812.00 | 61.36 | 73.87 | 71.86 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 141,283.00 | 64.46 | 75.59 | 72.18 |
| ========== | 403-34731 | HMA (Gr SX) (75) (PG 58-34) | | Ton | | | |
| NH 2852-017 | | US 285 PONCHA PASS SOUTH RESU | 03/03/11 | 25,828.70 | 70.00 | 70.04 | 64.70 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 25,828.70 | 70.00 | 70.04 | 64.70 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 25,828.70 | 70.00 | 70.04 | 64.70 |
| ========== | 403-34741 | HMA (Gr SX) (75) (PG 64-22) | | Ton | | | |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 1,768.00 | 75.00 | 123.61 | 120.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 1,768.00 | 75.00 | 126.26 | 128.29 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 21,122.00 | 85.00 | 77.75 | 76.00 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 142.00 | 100.00 | 117.25 | 114.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 21,264.00 | 85.10 | 68.29 | 67.76 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 1,222.00 | 62.00 | 75.08 | 73.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 403-34741 | HMA (Gr SX) (75) (PG 64-22) | | Ton | | | |
| STR096A-040 | | SH 96 MP 193 TO MP 201 | 09/01/11 | 13,417.00 | 59.00 | 68.79 | 61.98 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 14,639.00 | 59.25 | 83.93 | 77.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 37,671.00 | 74.58 | 76.50 | 71.73 |
| ========== | 403-34751 | HMA (Gr SX) (75) (PG 64-28) | | Ton | | | |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 3,030.00 | 80.00 | 141.86 | 140.00 |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 15,529.00 | 66.00 | 66.11 | 56.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 18,559.00 | 68.29 | 85.80 | 69.71 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 675.00 | 95.00 | 89.64 | 93.10 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1,650.00 | 85.00 | 79.56 | 75.53 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 2,325.00 | 87.90 | 76.22 | 71.07 |
| STR096A-040 | | SH 96 MP 193 TO MP 201 | 09/01/11 | 13,244.00 | 65.00 | 86.54 | 80.73 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 13,244.00 | 65.00 | 92.43 | 83.29 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 34,128.00 | 68.35 | 83.35 | 73.78 |
| ========== | 403-34801 | HMA (Gr SX) (100) | | Ton | | | |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 1,023.00 | 70.00 | 96.58 | 99.50 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 1,023.00 | 70.00 | 96.58 | 99.50 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 19,312.00 | 60.00 | 45.07 | 43.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 19,312.00 | 60.00 | 45.07 | 43.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 20,335.00 | 60.50 | 46.83 | 45.84 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 403-34821 | HMA (Gr SX) (100) (PG 58-28) | | Ton | | | |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 2,753.00 | 60.00 | 66.96 | 68.03 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 2,753.00 | 60.00 | 66.96 | 68.03 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,753.00 | 60.00 | 66.96 | 68.03 |
| ========== | 403-34841 | HMA (Gr SX) (100) (PG 64-22) | | Ton | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 884.00 | 115.00 | 69.84 | 72.80 |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 1,110.00 | 75.00 | 81.52 | 75.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 23,598.00 | 50.00 | 54.67 | 57.22 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 25,592.00 | 53.33 | 56.46 | 59.48 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 629.00 | 120.00 | 141.24 | 145.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 629.00 | 120.00 | 141.24 | 145.00 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 23,498.00 | 49.00 | 57.29 | 52.46 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 23,498.00 | 49.00 | 57.29 | 52.46 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 49,719.00 | 52.13 | 59.85 | 58.58 |
| ========== | 403-34851 | HMA (Gr SX) (100) (PG 64-28) | | Ton | | | |
| STA0504-061 | | US 50 M.P.369.9 -M.P.373.2 | 03/03/11 | 20,296.00 | 65.00 | 69.93 | 62.17 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 20,296.00 | 65.00 | 69.93 | 62.17 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 23,442.00 | 61.00 | 58.53 | 51.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 1,249.00 | 70.00 | 64.16 | 66.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 551.00 | 110.00 | 83.17 | 76.43 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 25,242.00 | 62.51 | 64.00 | 54.94 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 403-34851 | HMA (Gr SX) (100) (PG 64-28) | | Ton | | | |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 41.00 | 125.00 | 233.00 | 125.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 41.00 | 125.00 | 233.00 | 125.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 1,285.00 | 70.00 | 74.96 | 77.76 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1,285.00 | 70.00 | 74.96 | 77.76 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 46,864.00 | 63.85 | 66.91 | 58.64 |
| ========== | 403-34871 | HMA (Gr SX) (100) (PG 76-28) | | Ton | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 853.00 | 130.00 | 72.27 | 73.90 |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 4,333.00 | 63.00 | 64.82 | 54.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 14,988.00 | 65.00 | 67.08 | 60.10 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 20,174.00 | 67.32 | 66.51 | 58.46 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 402.00 | 65.00 | 88.94 | 75.00 |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 7,248.00 | 70.00 | 59.20 | 52.75 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 9,931.00 | 66.00 | 64.35 | 62.30 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 23,795.00 | 62.00 | 59.86 | 56.71 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 2,339.00 | 66.00 | 67.75 | 66.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 36,672.00 | 65.00 | 70.11 | 56.40 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 80,387.00 | 64.72 | 68.47 | 62.35 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 136.00 | 85.00 | 180.00 | 220.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 136.00 | 85.00 | 248.35 | 271.44 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 403-34871 | HMA (Gr SX) (100) (PG 76-28) | | Ton | | | |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 7,686.00 | 53.00 | 70.41 | 63.35 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 8,756.00 | 63.00 | 78.84 | 78.85 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 2,747.50 | 65.00 | 69.75 | 66.10 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 19,189.50 | 59.28 | 74.53 | 70.82 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 119,886.50 | 64.31 | 69.53 | 63.48 |
| ========== | 405-00100 | Heating and Remixing Treatment | | Sq Yard | | | |
| NH 0402-079 | | US40 MP 165.0 - 179.0 GRAND C | 03/31/11 | 207,264.00 | 5.50 | 5.46 | 5.26 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 207,264.00 | 5.50 | 5.46 | 5.26 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 234,696.00 | 5.55 | 5.35 | 5.15 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 174,680.00 | 5.50 | 5.67 | 5.50 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 409,376.00 | 5.53 | 5.45 | 5.30 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 84,480.00 | 7.00 | 6.88 | 6.70 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 84,480.00 | 7.00 | 6.88 | 6.70 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 701,120.00 | 5.70 | 5.56 | 5.46 |
| ========== | 406-09500 | Cold Bitum Pvmt (Recycle) | | Sq Yard | | | |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 187,052.00 | 2.70 | 2.61 | 2.50 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 187,052.00 | 2.70 | 2.61 | 2.50 |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 416,401.00 | 2.25 | 1.85 | 1.40 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 416,401.00 | 2.25 | 1.85 | 1.40 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 603,453.00 | 2.39 | 2.13 | 1.69 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 408-01000 | Hot Joint-Crack Sealant | | Ton | | | |
| R600-395 | | REGION 6; VARIOUS LOCATIONS | 11/10/11 | 90.00 | 4000.00 | 5979.20 | 2906.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 90.00 | 4000.00 | 5979.20 | 2906.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 90.00 | 4000.00 | 5991.99 | 2926.28 |
| ========== | 408-01400 | Crack Sealant (Special) | | Ton | | | |
| R600-395 | | REGION 6; VARIOUS LOCATIONS | 11/10/11 | 5.00 | 8000.00 | 7971.00 | 4994.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 5.00 | 8000.00 | 7971.00 | 4994.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 5.00 | 8000.00 | 7971.00 | 4994.00 |
| ========== | 409-01015 | CC Matl (Ty I) | | Sq Yard | | | |
| NH0501-060 | | US50 MP 74.0 TO 81, 94.2 TO 1 | 10/20/11 | 584,244.00 | 0.70 | 0.78 | 0.40 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 584,244.00 | 0.70 | 0.78 | 0.40 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 584,244.00 | 0.70 | 0.78 | 0.40 |
| ========== | 409-02030 | CC Matl (Ty I) (Special) | | Sq Yard | | | |
| STA0343-032 | | US 34 EAST OF AKRON | 04/07/11 | 252,733.00 | 1.40 | 1.46 | 1.44 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 252,733.00 | 1.40 | 1.46 | 1.44 |
| STA0343-033 | | SH 34 ECKLEY | 11/10/11 | 275,055.00 | 1.50 | 1.50 | 1.73 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 275,055.00 | 1.50 | 1.51 | 1.66 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 527,788.00 | 1.45 | 1.50 | 1.59 |
| ========== | 411-03342 | Asph Cem (PG 64-28) | | Ton | | | |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 390.00 | 700.00 | 701.12 | 709.75 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 390.00 | 700.00 | 701.12 | 709.75 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 390.00 | 700.00 | 701.12 | 709.75 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 411-03345 | Asph Cem (PG 76-28) | | Ton | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 51.00 | 750.00 | 830.55 | 828.80 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 51.00 | 750.00 | 830.55 | 828.80 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 56.00 | 600.00 | 873.00 | 837.00 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 56.00 | 600.00 | 873.00 | 837.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 591.00 | 950.00 | 882.86 | 850.00 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 591.00 | 950.00 | 882.86 | 850.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 698.00 | 907.31 | 880.04 | 847.41 |
| ========== | 411-03352 | Asph Cem (PG 58-28) | | Ton | | | |
| NH 0241-056 | | US 24 BUENA VISTA NORTH | 03/03/11 | 1,885.00 | 520.00 | 517.00 | 520.00 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 1,957.00 | 500.00 | 434.01 | 505.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 3,842.00 | 509.81 | 474.73 | 512.36 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 435.00 | 510.00 | 627.25 | 615.00 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 435.00 | 510.00 | 606.33 | 578.19 |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 6.48 | 700.00 | 774.59 | 910.00 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 782.00 | 500.00 | 592.52 | 520.00 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 788.48 | 501.64 | 593.52 | 523.21 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 3,585.00 | 530.00 | 602.50 | 625.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 411-03352 | Asph Cem (PG 58-28) | | Ton | | | |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 696.00 | 540.00 | 620.05 | 600.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 4,281.00 | 531.63 | 607.41 | 620.94 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 9,346.48 | 519.12 | 540.20 | 567.11 |
| ========== | 411-03354 | Asph Cem (PG 64-22) | | Ton | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 53.00 | 475.00 | 566.49 | 521.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 53.00 | 475.00 | 566.49 | 521.00 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 1,650.00 | 500.00 | 510.00 | 510.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1,650.00 | 500.00 | 510.00 | 510.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 569.00 | 600.00 | 636.90 | 610.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 569.00 | 600.00 | 636.90 | 610.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,272.00 | 524.46 | 574.32 | 535.30 |
| ========== | 411-03355 | Asph Cem (PG 58-34) | | Ton | | | |
| NH 0402-079 | | US40 MP 165.0 - 179.0 GRAND C | 03/31/11 | 2,037.00 | 600.00 | 477.26 | 1.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 2,037.00 | 600.00 | 477.26 | 1.00 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 1,679.00 | 600.00 | 671.70 | 658.49 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 430.00 | 670.00 | 768.08 | 754.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 117.00 | 700.00 | 854.85 | 838.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2,226.00 | 618.78 | 709.75 | 686.37 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 800.00 | 700.00 | 719.02 | 675.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 800.00 | 700.00 | 719.02 | 675.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 5,063.00 | 624.06 | 597.42 | 408.83 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 411-10217 | Emulsified Asphalt (CRS-2P) | | Ton | | | |
| STA0343-032 | | US 34 EAST OF AKRON | 04/07/11 | 602.00 | 400.00 | 300.00 | 300.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 602.00 | 400.00 | 300.00 | 300.00 |
| NH0501-060 | | US50 MP 74.0 TO 81, 94.2 TO 1 | 10/20/11 | 1,061.00 | 500.00 | 711.38 | 715.00 |
| STA0343-033 | | SH 34 ECKLEY | 11/10/11 | 655.00 | 350.00 | 515.67 | 225.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1,716.00 | 442.74 | 526.64 | 422.27 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,318.00 | 431.64 | 499.57 | 398.78 |
| ========== | 411-10253 | Emul Asph (CSS-1H) | | Gallon | | | |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 13,587.00 | 3.00 | 2.82 | 2.25 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 790.00 | 4.00 | 3.42 | 4.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 14,377.00 | 3.05 | 2.88 | 2.35 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 14,377.00 | 3.05 | 2.88 | 2.35 |
| ========== | 411-10255 | Emul Asph (SS) | | Gallon | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 255.00 | 4.00 | 5.07 | 5.60 |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 1,432.00 | 2.50 | 2.85 | 2.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 26,956.00 | 3.00 | 2.13 | 2.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 351.00 | 2.00 | 4.15 | 3.75 |
| NH 2852-017 | | US 285 PONCHA PASS SOUTH RESU | 03/03/11 | 14,990.10 | 3.00 | 2.29 | 2.70 |
| NH 0241-056 | | US 24 BUENA VISTA NORTH | 03/03/11 | 19,140.00 | 3.00 | 2.32 | 2.50 |
| STA0504-061 | | US 50 M.P.369.9 -M.P.373.2 | 03/03/11 | 6,711.00 | 2.70 | 3.09 | 4.64 |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 28,208.00 | 2.50 | 2.46 | 1.98 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 29,339.80 | 2.00 | 1.65 | 1.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 13,220.00 | 2.00 | 2.35 | 2.20 |
| NH 0402-079 | | US40 MP 165.0 - 179.0 GRAND C | 03/31/11 | 13,264.00 | 2.00 | 2.00 | 1.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 153,866.90 | 2.53 | 2.21 | 2.01 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 31,210.00 | 2.50 | 1.94 | 2.65 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 411-10255 | Emul Asph (SS) | | Gallon | | | |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 637.00 | 3.00 | 3.12 | 3.00 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 8,038.00 | 2.50 | 3.08 | 2.75 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 395.00 | 4.00 | 6.49 | 3.00 |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 2,532.00 | 3.00 | 3.29 | 2.00 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 3,446.00 | 2.50 | 2.53 | 3.70 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 7,432.00 | 3.00 | 3.06 | 2.30 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 6,545.00 | 2.80 | 2.79 | 2.18 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 12,399.00 | 3.00 | 2.55 | 2.50 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 8,900.00 | 2.50 | 3.10 | 2.60 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 3,100.00 | 2.00 | 3.64 | 2.60 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 2,787.00 | 4.00 | 1.22 | 1.20 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 33.00 | 10.00 | 26.35 | 25.20 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 8,397.00 | 4.00 | 3.60 | 3.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 20,116.00 | 2.50 | 2.89 | 3.07 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 115,967.00 | 2.75 | 2.69 | 2.77 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 54,070.00 | 2.30 | 1.95 | 0.01 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 137.00 | 7.50 | 8.81 | 12.15 |
| BR2706-036 | | I-270 BRIDGE DECK REHABILITAT | 08/11/11 | 644.00 | 3.00 | 8.81 | 10.00 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 4,995.00 | 3.00 | 3.29 | 3.00 |
| STR096A-040 | | SH 96 MP 193 TO MP 201 | 09/01/11 | 5,544.00 | 2.00 | 2.60 | 2.40 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 11,027.00 | 3.00 | 2.94 | 3.00 |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 44.00 | 10.00 | 11.50 | 12.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 76,461.00 | 2.44 | 2.46 | 1.16 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 2,956.00 | 3.00 | 2.74 | 2.76 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 11,692.00 | 2.30 | 3.33 | 4.15 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 2,939.00 | 3.00 | 2.18 | 2.15 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 35,833.00 | 2.50 | 2.90 | 2.30 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 856.00 | 3.00 | 3.03 | 3.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 9,688.00 | 2.30 | 2.55 | 2.50 |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 79,520.00 | 2.75 | 1.89 | 1.35 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 8,388.00 | 2.50 | 3.91 | 4.10 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 7,618.00 | 2.50 | 2.88 | 3.40 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 159,490.00 | 2.62 | 2.43 | 2.13 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 505,784.90 | 2.60 | 2.42 | 2.10 |
| ========== | 411-10300 | Emul Asph (Prime Coat) | | Gallon | | | |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 932.00 | 5.00 | 3.06 | 3.70 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 932.00 | 5.00 | 2.82 | 2.58 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 932.00 | 5.00 | 2.82 | 2.58 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 411-90010 | Asph Rejuvenating Agent | | Gallon | | | |
| NH 0402-079 | | US40 MP 165.0 - 179.0 GRAND C | 03/31/11 | 10,881.00 | 3.30 | 3.44 | 3.87 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 10,881.00 | 3.30 | 3.44 | 3.87 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 11,734.00 | 3.50 | 3.59 | 3.75 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 10,481.00 | 3.50 | 2.98 | 2.75 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 22,215.00 | 3.50 | 3.38 | 3.28 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 4,647.00 | 3.50 | 2.75 | 2.50 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 4,647.00 | 3.50 | 2.75 | 2.50 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 37,743.00 | 3.44 | 3.36 | 3.35 |
| ========== | 411-90040 | Recycling Agent | | Gallon | | | |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 235,000.00 | 2.65 | 2.26 | 1.99 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 235,000.00 | 2.65 | 2.26 | 1.99 |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 529,967.00 | 2.50 | 2.79 | 2.75 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 529,967.00 | 2.50 | 2.79 | 2.75 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 764,967.00 | 2.55 | 2.60 | 2.53 |
| ========== | 412-00000 | Furn Conc Pvmt | | Cubic Yard | | | |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 4,159.00 | 70.00 | 64.87 | 46.70 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 4,159.00 | 70.00 | 64.87 | 46.70 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4,159.00 | 70.00 | 64.87 | 46.70 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 412-00600 | Conc Pvmt (6 In) | | Sq Yard | | | |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 102,650.00 | 20.00 | 21.19 | 18.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 102,650.00 | 20.00 | 21.19 | 18.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1,051.00 | 61.00 | 38.14 | 35.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 88.00 | 40.00 | 54.05 | 106.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 97.00 | 50.00 | 42.79 | 38.61 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1,236.00 | 58.64 | 39.38 | 40.34 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 103,886.00 | 20.46 | 21.44 | 18.27 |
| ========== | 412-00605 | Conc Pvmt (6 In) (Fast Track) | | Sq Yard | | | |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 8,268.00 | 35.00 | 40.00 | 23.20 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 114.00 | 50.00 | 50.88 | 72.30 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 8,382.00 | 35.20 | 40.14 | 23.87 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 8,382.00 | 35.20 | 40.14 | 23.87 |
| ========== | 412-00800 | Conc Pvmt (8 In) | | Sq Yard | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 400.00 | 50.00 | 58.72 | 100.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 400.00 | 50.00 | 58.72 | 100.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 477.00 | 55.00 | 72.17 | 85.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 477.00 | 55.00 | 72.17 | 85.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 848.00 | 61.00 | 47.77 | 46.40 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 848.00 | 61.00 | 47.77 | 46.40 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,725.00 | 56.79 | 55.99 | 63.08 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 412-00850 | Conc Pvmt (8-1/2 In) | | Sq Yard | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 14,002.00 | 30.00 | 37.12 | 35.74 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 14,002.00 | 30.00 | 37.12 | 35.74 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 14,002.00 | 30.00 | 37.12 | 35.74 |
| ========== | 412-00870 | Conc Pvmt (8-1/2 In) (Fast Track) | | Sq Yard | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1,749.00 | 50.00 | 60.21 | 54.73 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1,749.00 | 50.00 | 60.21 | 54.73 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,749.00 | 50.00 | 60.21 | 54.73 |
| ========== | 412-00900 | Conc Pvmt (9 In) | | Sq Yard | | | |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 664.00 | 58.00 | 77.13 | 61.50 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 21,629.00 | 35.00 | 39.84 | 38.85 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 22,293.00 | 35.69 | 40.58 | 39.52 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 22,293.00 | 35.69 | 40.58 | 39.52 |
| ========== | 412-00920 | Conc Pvmt (9 In) (Fast Track) | | Sq Yard | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 5,551.00 | 57.00 | 63.56 | 58.61 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 5,551.00 | 57.00 | 63.56 | 58.61 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 5,551.00 | 57.00 | 63.56 | 58.61 |
| ========== | 412-00950 | Conc Pvmt (9-1/2 In) | | Sq Yard | | | |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 977.00 | 45.00 | 46.63 | 53.20 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 977.00 | 45.00 | 46.63 | 53.20 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 591.00 | 55.00 | 65.77 | 80.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 591.00 | 55.00 | 65.77 | 80.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,568.00 | 48.77 | 53.05 | 63.30 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 412-01000 | Conc Pvmt (10 In) | | Sq Yard | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 20,775.00 | 45.00 | 42.22 | 45.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 20,775.00 | 45.00 | 42.22 | 45.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 48.00 | 61.00 | 62.68 | 57.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 7,972.00 | 80.00 | 66.00 | 60.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 8,020.00 | 79.89 | 65.99 | 59.98 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 28,795.00 | 54.72 | 50.92 | 49.17 |
| ========== | 412-01001 | Conc Pvmt (10 In) (Spec) | | Sq Yard | | | |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 1,022.00 | 100.00 | 88.90 | 79.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1,022.00 | 100.00 | 88.90 | 79.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,022.00 | 100.00 | 88.90 | 79.00 |
| ========== | 412-01050 | Conc Pvmt (10-1/2 In) | | Sq Yard | | | |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 69,699.00 | 28.00 | 38.09 | 31.50 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 69,699.00 | 28.00 | 38.09 | 31.50 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 69,699.00 | 28.00 | 38.09 | 31.50 |
| ========== | 412-01100 | Conc Pvmt (11 In) | | Sq Yard | | | |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 94.00 | 75.00 | 67.53 | 60.67 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 94.00 | 75.00 | 67.53 | 60.67 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 94.00 | 75.00 | 67.53 | 60.67 |
| ========== | 412-01120 | Conc Pvmt (11 In) (Fast Track) | | Sq Yard | | | |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 90.00 | 100.00 | 76.92 | 52.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 90.00 | 100.00 | 76.92 | 52.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 412-01120 | Conc Pvmt (11 In) (Fast Track) | | Sq Yard | | | |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 408.00 | 90.00 | 138.33 | 158.86 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 408.00 | 90.00 | 138.33 | 158.86 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 498.00 | 91.81 | 123.06 | 139.55 |
| ========== | 412-01200 | Conc Pvmt (12 In) | | Sq Yard | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 216.00 | 70.00 | 56.44 | 53.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 216.00 | 70.00 | 56.44 | 53.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 216.00 | 70.00 | 56.44 | 53.00 |
| ========== | 412-01300 | Conc Pvmt (13 In) | | Sq Yard | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 169,840.00 | 50.00 | 52.13 | 45.60 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 169,840.00 | 50.00 | 52.13 | 45.60 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 169,840.00 | 50.00 | 52.13 | 45.60 |
| ========== | 412-01350 | Conc Pvmt (13-1/2 In) | | Sq Yard | | | |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 27,523.00 | 50.00 | 49.12 | 49.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 27,523.00 | 50.00 | 49.12 | 49.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 27,523.00 | 50.00 | 49.12 | 49.00 |
| ========== | 412-01352 | Conc Pvmt (13-1/2 In) (Fast Track) | | Sq Yard | | | |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 3,058.00 | 80.00 | 67.71 | 66.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 3,058.00 | 80.00 | 67.71 | 66.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3,058.00 | 80.00 | 67.71 | 66.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 412-14000 | Sawing and Sealing Joints | | Lin Foot | | | |
| NH2872-018 | | US 287 RUSH CREEK NORTH | 07/21/11 | 29,469.00 | 1.40 | 2.13 | 1.75 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 29,469.00 | 1.40 | 2.13 | 1.75 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 29,469.00 | 1.40 | 2.13 | 1.75 |
| ========== | 412-15000 | Routing and Sealing Cracks | | Lin Foot | | | |
| NH2872-018 | | US 287 RUSH CREEK NORTH | 07/21/11 | 19,088.00 | 4.60 | 4.12 | 3.40 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 19,088.00 | 4.60 | 4.12 | 3.40 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 19,088.00 | 4.60 | 4.12 | 3.40 |
| ========== | 412-15050 | Cross Stitching | | Each | | | |
| NH2872-018 | | US 287 RUSH CREEK NORTH | 07/21/11 | 9,545.00 | 35.00 | 22.20 | 23.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 9,545.00 | 35.00 | 22.20 | 23.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 9,545.00 | 35.00 | 22.20 | 23.00 |
| ========== | 420-00000 | Geomembrane | | Sq Yard | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 472.00 | 5.00 | 10.94 | 3.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 4,352.00 | 6.00 | 5.00 | 4.37 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 4,824.00 | 5.90 | 5.44 | 4.24 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 477.00 | 5.00 | 8.13 | 14.80 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 7,392.00 | 4.00 | 7.91 | 8.20 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 7,869.00 | 4.06 | 7.93 | 8.60 |
| NH0403-053 | | US 40 RETAINING WALL REPAIR | 07/28/11 | 422.00 | 8.00 | 65.29 | 63.86 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 422.00 | 8.00 | 65.29 | 63.86 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 420-00000 | Geomembrane | | Sq Yard | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 620.00 | 5.00 | 8.04 | 10.80 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 4,770.00 | 4.00 | 6.44 | 7.04 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 5,390.00 | 4.12 | 6.60 | 7.47 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 18,505.00 | 4.65 | 7.33 | 8.39 |
| ========== | 420-00102 | Geotextile (Er Cont) (CL 1) | | Sq Yard | | | |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 3,880.00 | 2.00 | 2.30 | 1.70 |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 60.00 | 4.00 | 10.46 | 12.00 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 650.00 | 4.00 | 3.79 | 3.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 4,590.00 | 2.31 | 2.51 | 2.02 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 1,254.00 | 3.00 | 3.91 | 2.63 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 109.00 | 3.00 | 4.92 | 7.50 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 66.00 | 4.00 | 5.92 | 6.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 5,671.00 | 2.00 | 3.45 | 2.40 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 7,100.00 | 2.21 | 3.60 | 2.66 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 57.00 | 3.00 | 6.52 | 1.75 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 80.00 | 3.00 | 10.69 | 10.40 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 137.00 | 3.00 | 4.24 | 2.67 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 453.00 | 5.00 | 3.36 | 2.03 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 453.00 | 5.00 | 3.36 | 2.03 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 12,280.00 | 2.36 | 3.21 | 2.42 |
| ========== | 420-00103 | Geotextile (Er Cont) (CL 2) | | Sq Yard | | | |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 1,085.00 | 3.00 | 4.01 | 5.60 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 420-00103 | Geotextile (Er Cont) (CL 2) | | Sq Yard | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1,312.00 | 2.00 | 3.53 | 4.02 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2,397.00 | 2.45 | 3.70 | 4.74 |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 202.00 | 5.00 | 19.08 | 24.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 202.00 | 5.00 | 3.10 | 2.01 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,599.00 | 2.65 | 3.22 | 2.59 |
| ========== | 420-00112 | Geotextile (Drain) (CL 1) | | Sq Yard | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 5.00 | 50.00 | 93.24 | 8.20 |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 7.00 | 9.20 | 34.22 | 17.50 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 12.00 | 26.20 | 54.16 | 13.63 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 2,840.00 | 3.00 | 2.92 | 2.10 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 296.00 | 3.00 | 4.77 | 3.30 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 978.00 | 10.00 | 3.27 | 2.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 4,114.00 | 4.66 | 3.09 | 2.16 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 33.00 | 30.00 | 23.20 | 4.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 33.00 | 30.00 | 2.01 | 1.52 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 287.00 | 3.00 | 4.91 | 3.58 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 287.00 | 3.00 | 4.91 | 3.58 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4,446.00 | 4.80 | 2.78 | 1.87 |
| ========== | 420-00113 | Geotextile (Drain) (CL 2) | | Sq Yard | | | |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 54.00 | 10.00 | 9.70 | 20.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 420-00113 | Geotextile (Drain) (CL 2) | | Sq Yard | | | |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 72.00 | 5.00 | 6.77 | 9.00 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 126.00 | 7.14 | 2.81 | 2.14 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 37.80 | 5.00 | 7.93 | 3.15 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 37.80 | 5.00 | 7.93 | 3.15 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 16.00 | 10.00 | 27.61 | 37.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 5.00 | 9.00 | 57.95 | 72.40 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 307.00 | 3.00 | 3.87 | 5.03 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 328.00 | 3.43 | 5.45 | 7.62 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 491.80 | 4.50 | 2.97 | 2.52 |
| ========== | 420-00114 | Geotextile (Drain) (CL 3) | | Sq Yard | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 27.00 | 11.00 | 15.04 | 5.25 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 27.00 | 11.00 | 15.04 | 5.25 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 27.00 | 11.00 | 15.04 | 5.25 |
| ========== | 420-00132 | Geotextile (Separator) (CL 1) | | Sq Yard | | | |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 508.00 | 4.00 | 4.84 | 6.20 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 360.00 | 6.00 | 4.37 | 3.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 868.00 | 4.83 | 4.64 | 4.87 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 6,756.00 | 2.50 | 2.81 | 1.90 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 500.00 | 2.00 | 4.07 | 1.60 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 7,256.00 | 2.47 | 2.89 | 1.88 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 420-00132 | Geotextile (Separator) (CL 1) | | Sq Yard | | | |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 500.00 | 3.00 | 3.37 | 2.57 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 1,134.00 | 2.00 | 2.11 | 2.50 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 1,634.00 | 2.31 | 2.47 | 2.52 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 9,758.00 | 2.65 | 2.93 | 2.25 |
| ========== | 420-00133 | Geotextile (Separator) (CL 2) | | Sq Yard | | | |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 36,407.00 | 3.00 | 1.38 | 1.40 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 36,407.00 | 3.00 | 1.38 | 1.40 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 36,407.00 | 3.00 | 1.38 | 1.40 |
| ========== | 420-00200 | Geotextile (Weed Barrier) | | Sq Yard | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 4,356.00 | 2.00 | 2.93 | 7.54 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 4,356.00 | 2.00 | 2.93 | 7.54 |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 139.00 | 4.00 | 6.42 | 6.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 139.00 | 4.00 | 6.42 | 6.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4,495.00 | 2.06 | 3.02 | 7.49 |
| ========== | 420-00400 | Media Filter Drain (MFD) mix (Type 1) | | Cubic Yard | | | |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 328.00 | 50.00 | 200.40 | 105.61 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 425.00 | 50.00 | 139.32 | 94.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 753.00 | 50.00 | 167.94 | 99.06 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 753.00 | 50.00 | 167.94 | 99.06 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 420-00511 | Asphalt Reinforcement Geogrid | | Sq Yard | | | |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 321.00 | 25.00 | 19.17 | 9.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 321.00 | 25.00 | 19.17 | 9.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 321.00 | 25.00 | 19.17 | 9.00 |
| ========== | 501-00000 | Steel Sheet Pile (Ty I) | | Sq Foot | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 279.00 | 8.00 | 43.64 | 60.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 279.00 | 8.00 | 43.64 | 60.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 279.00 | 8.00 | 43.64 | 60.00 |
| ========== | 502-00100 | Drill Hole Fac Pile Driving | | Lin Foot | | | |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 558.00 | 50.00 | 307.14 | 156.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 558.00 | 50.00 | 307.14 | 156.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 172.00 | 50.00 | 38.07 | 46.50 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 172.00 | 50.00 | 38.07 | 46.50 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 730.00 | 50.00 | 237.05 | 130.20 |
| ========== | 502-00460 | Pile Tip | | Each | | | |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 46.00 | 150.00 | 137.19 | 168.99 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 6.00 | 150.00 | 131.64 | 100.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 24.00 | 150.00 | 148.39 | 135.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 76.00 | 150.00 | 140.13 | 152.81 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 16.00 | 150.00 | 176.86 | 238.16 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 16.00 | 150.00 | 176.86 | 238.16 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 92.00 | 150.00 | 146.31 | 161.39 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 502-02000 | Dynamic Load Testing | | LUMP SUM | ========== | ========== | ========== |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1.00 | 10000.00 | 875.05 | 100.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 10000.00 | 875.05 | 100.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 10000.00 | 875.05 | 100.00 |
| ========== | 502-11253 | Steel Pile (HP 12x53) | | Lin Foot | ========== | ========== | ========== |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 338.00 | 50.00 | 53.78 | 42.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 338.00 | 50.00 | 53.78 | 42.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 338.00 | 50.00 | 53.78 | 42.00 |
| ========== | 502-11274 | Steel Pile (HP 12x74) | | Lin Foot | ========== | ========== | ========== |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 1,351.00 | 55.00 | 63.39 | 53.48 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 1,376.00 | 60.00 | 48.96 | 47.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1,623.00 | 50.00 | 61.60 | 72.17 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 4,350.00 | 54.72 | 58.65 | 58.40 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 1,370.00 | 52.00 | 58.11 | 56.25 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1,370.00 | 52.00 | 60.70 | 57.56 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 710.00 | 60.00 | 61.22 | 65.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 710.00 | 60.00 | 61.22 | 65.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 6,430.00 | 54.72 | 59.53 | 58.88 |
| ========== | 502-11489 | Steel Pile (HP 14x89) | | Lin Foot | ========== | ========== | ========== |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 984.00 | 80.00 | 72.68 | 62.50 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 984.00 | 80.00 | 72.68 | 62.50 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 984.00 | 80.00 | 72.68 | 62.50 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 502-14117 | Steel Pile (HP 14x117) | | Lin Foot | | | |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 3,135.00 | 60.00 | 75.31 | 67.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 3,135.00 | 60.00 | 75.31 | 67.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3,135.00 | 60.00 | 75.31 | 67.00 |
| ========== | 503-00018 | Drilled Caisson (18 In) | | Lin Foot | | | |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 169.00 | 75.00 | 70.93 | 53.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 24.00 | 50.00 | 77.00 | 70.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 8.00 | 150.00 | 186.08 | 122.80 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 24.00 | 200.00 | 111.21 | 105.60 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 225.00 | 88.33 | 80.40 | 63.66 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 12.00 | 100.00 | 180.00 | 110.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 12.00 | 100.00 | 160.00 | 105.50 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 190.00 | 100.00 | 106.78 | 83.45 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 190.00 | 100.00 | 106.78 | 83.45 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 427.00 | 93.85 | 94.54 | 73.65 |
| ========== | 503-00024 | Drilled Caisson (24 In) | | Lin Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 1,628.00 | 125.00 | 80.22 | 55.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1,628.00 | 125.00 | 80.22 | 55.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 2,160.00 | 75.00 | 72.37 | 64.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2,160.00 | 75.00 | 72.37 | 64.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 503-00024 | Drilled Caisson (24 In) | | Lin Foot | | | |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 323.00 | 100.00 | 142.54 | 140.64 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 225.00 | 200.00 | 125.87 | 112.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 548.00 | 141.06 | 137.48 | 128.88 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4,336.00 | 102.12 | 85.59 | 73.91 |
| ========== | 503-00030 | Drilled Caisson (30 In) | | Lin Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 288.00 | 180.00 | 214.35 | 240.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 1,590.00 | 150.00 | 121.27 | 106.93 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1,878.00 | 154.60 | 125.79 | 112.69 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 2,130.00 | 150.00 | 114.91 | 120.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2,130.00 | 150.00 | 114.91 | 120.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 3,355.00 | 125.00 | 122.57 | 118.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 2,686.00 | 180.00 | 124.47 | 161.27 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 6,041.00 | 149.45 | 123.48 | 137.24 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 10,049.00 | 150.53 | 122.37 | 129.36 |
| ========== | 503-00036 | Drilled Caisson (36 In) | | Lin Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 718.00 | 200.00 | 138.22 | 100.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 503-00036 | Drilled Caisson (36 In) | | Lin Foot | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 252.00 | 400.00 | 204.28 | 185.00 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 1,312.00 | 200.00 | 253.20 | 240.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 2,282.00 | 222.09 | 232.20 | 211.43 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 38.00 | 175.00 | 247.16 | 240.00 |
| SHE074A-001 | | SH 74 - EVERGREEN - JEFFERSON | 04/28/11 | 76.00 | 800.00 | 477.00 | 281.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 1,613.00 | 200.00 | 152.79 | 150.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 30.00 | 300.00 | 200.72 | 191.08 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 88.00 | 220.00 | 238.00 | 176.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1,845.00 | 226.78 | 162.63 | 159.16 |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 201.00 | 300.00 | 1241.63 | 700.00 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 76.00 | 230.00 | 283.33 | 180.00 |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 57.00 | 300.00 | 286.60 | 300.00 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 228.00 | 260.00 | 283.85 | 212.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 562.00 | 274.31 | 723.13 | 391.13 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1,595.00 | 160.00 | 192.29 | 229.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 62.00 | 250.00 | 214.01 | 171.03 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1,657.00 | 163.37 | 193.21 | 226.83 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 6,346.00 | 212.74 | 232.08 | 216.48 |
| ========== | 503-00042 | Drilled Caisson (42 In) | | Lin Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | . | 1,788.00 | 220.00 | 350.28 | . |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 38.00 | 300.00 | 256.26 | 227.08 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1,826.00 | 221.66 | 340.60 | 229.88 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 145.00 | 250.00 | 296.38 | 330.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 503-00042 | Drilled Caisson (42 In) | | Lin Foot | ========== | ========== | ========== |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 51.00 | 400.00 | 214.12 | 204.16 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 196.00 | 289.03 | 274.97 | 297.26 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 38.00 | 250.00 | 343.38 | 380.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 38.00 | 250.00 | 416.70 | 512.08 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 87.00 | 300.00 | 343.89 | 302.16 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 815.00 | 275.00 | 167.41 | 140.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 1,218.00 | 200.00 | 201.62 | 210.42 |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 68.00 | 550.00 | 900.32 | 1291.29 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2,188.00 | 242.79 | 211.74 | 221.43 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4,248.00 | 235.91 | 247.24 | 243.06 |
| ========== | 503-00048 | Drilled Caisson (48 In) | | Lin Foot | ========== | ========== | ========== |
| C0704-225 | | I-70 EAST OF BENNETT | 01/06/11 | 31.00 | 350.00 | 385.25 | 372.00 |
| ITS4701-121 | | C470 (SANTA FE TO I-25) AND R | 01/20/11 | 30.00 | 400.00 | 446.75 | 538.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 2,688.00 | 243.18 | 302.66 | 170.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 31.50 | 1000.00 | 482.89 | 500.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 23.00 | 350.00 | 297.33 | 265.60 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 2,803.50 | 255.42 | 310.46 | 211.15 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 42.00 | 225.00 | 272.89 | 260.00 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 49.00 | 300.00 | 302.43 | 310.73 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 78.00 | 250.00 | 305.68 | 240.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 43.00 | 250.00 | 304.57 | 360.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 42.00 | 350.00 | 443.35 | 301.88 |
| ITS0703-370 | | EAST OF EJMT ON I-70 EB LANES | 06/16/11 | 53.10 | 800.00 | 678.00 | 445.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 21.00 | 450.00 | 278.69 | 264.50 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 328.10 | 368.88 | 376.33 | 369.66 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 503-00048 | Drilled Caisson (48 In) | | Lin Foot | | | |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 21.00 | 350.00 | 344.60 | 350.00 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 42.00 | 320.00 | 369.15 | 251.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 240.00 | 275.00 | 316.22 | 330.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 303.00 | 286.44 | 359.64 | 385.11 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1,516.00 | 210.00 | 325.14 | 350.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 2,108.00 | 300.00 | 214.81 | 183.00 |
| ITSSW00-928 | | NB I-225 AT MM 2.28 | 11/03/11 | 30.00 | 400.00 | 451.50 | 432.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 234.00 | 225.00 | 303.82 | 285.54 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 436.00 | 275.00 | 325.23 | 359.39 |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 160.00 | 650.00 | 1207.63 | 1310.51 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 4,484.00 | 276.38 | 302.64 | 303.86 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 7,918.60 | 273.18 | 312.06 | 303.22 |
| ========== | 503-00054 | Drilled Caisson (54 In) | | Lin Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 800.00 | 300.00 | 417.20 | 225.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 857.00 | 350.00 | 335.02 | 309.68 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1,657.00 | 325.86 | 352.11 | 293.66 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 541.00 | 400.00 | 380.98 | 309.31 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 328.00 | 350.00 | 292.78 | 270.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 63.00 | 500.00 | 333.28 | 316.80 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 932.00 | 389.16 | 352.27 | 295.98 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 42.00 | 450.00 | 449.13 | 333.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 42.00 | 450.00 | 449.13 | 333.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 503-00054 | Drilled Caisson (54 In) | | Lin Foot | | | |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 2,098.00 | 325.00 | 262.97 | 222.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 49.00 | 400.00 | 340.24 | 294.58 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 2,147.00 | 326.71 | 265.75 | 223.66 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4,778.00 | 339.68 | 317.14 | 258.60 |
| ========== | 503-00060 | Drilled Caisson (60 In) | | Lin Foot | | | |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 498.00 | 300.00 | 431.40 | 360.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 210.00 | 400.00 | 359.06 | 330.26 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 708.00 | 329.66 | 412.20 | 351.18 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 708.00 | 329.66 | 412.20 | 351.18 |
| ========== | 503-00072 | Drilled Caisson (72 In) | | Lin Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 142.00 | 450.00 | 579.63 | 600.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 142.00 | 450.00 | 579.63 | 600.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 142.00 | 450.00 | 579.63 | 600.00 |
| ========== | 503-00210 | Agg Column Grnd Impvmt | | LUMP SUM | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1.00 | 1400000.00 | 718423.66 | 621024.71 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 1.00 | 1400000.00 | 718423.66 | 621024.71 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 1400000.00 | 718423.66 | 621024.71 |
| ========== | 503-00400 | Drill and Log Bores | | Lin Foot | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 29.00 | 100.00 | 220.80 | 240.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 29.00 | 100.00 | 220.80 | 240.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 503-00400 | Drill and Log Bores | | Lin Foot | | | |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 30.00 | 140.00 | 221.75 | 132.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 30.00 | 140.00 | 221.75 | 132.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 59.00 | 120.34 | 221.18 | 185.08 |
| ========== | 504-04410 | Block Facing | | Sq Foot | | | |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 2,103.00 | 17.00 | 16.90 | 22.40 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 15,037.00 | 15.00 | 12.38 | 8.53 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 17,140.00 | 15.25 | 13.01 | 10.23 |
| NH0403-053 | | US 40 RETAINING WALL REPAIR | 07/28/11 | 516.00 | 60.00 | 70.23 | 67.68 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 516.00 | 60.00 | 16.83 | 18.15 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1,921.00 | 18.00 | 17.98 | 23.60 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1,921.00 | 18.00 | 17.98 | 23.60 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 19,577.00 | 16.70 | 14.01 | 13.15 |
| ========== | 504-04420 | Precast Panel Facing | | Sq Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 287,836.00 | 18.00 | 17.15 | 13.18 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 20,482.00 | 20.00 | 17.99 | 15.69 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 308,318.00 | 18.13 | 17.32 | 13.74 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 47,886.00 | 15.00 | 16.03 | 18.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 47,886.00 | 15.00 | 16.03 | 18.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 504-04420 | Precast Panel Facing | | Sq Foot | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 12,977.00 | 22.00 | 26.24 | 24.70 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 49,346.00 | 20.00 | 22.79 | 19.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 5,928.00 | 20.00 | 33.50 | 28.93 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 20,856.00 | 16.00 | 14.38 | 10.14 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 89,107.00 | 19.36 | 21.74 | 18.42 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 445,311.00 | 18.04 | 18.57 | 16.44 |
| ========== | 504-05000 | Wire Mesh Facing | | Sq Foot | | | |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 2,304.00 | 15.00 | 11.07 | 11.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 2,304.00 | 15.00 | 11.07 | 11.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,304.00 | 15.00 | 11.07 | 11.00 |
| ========== | 504-06310 | Ground Nail (10 Foot) | | Each | | | |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 17.00 | 250.00 | 210.25 | 192.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 17.00 | 250.00 | 210.25 | 192.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 17.00 | 250.00 | 210.25 | 192.00 |
| ========== | 504-06315 | Ground Nail (15 Foot) | | Each | | | |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 50.00 | 400.00 | 307.96 | 281.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 50.00 | 400.00 | 307.96 | 281.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 50.00 | 400.00 | 307.96 | 281.00 |
| ========== | 504-06320 | Ground Nail (20 Foot) | | Each | | | |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 867.00 | 450.00 | 447.72 | 408.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 867.00 | 450.00 | 447.72 | 408.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 867.00 | 450.00 | 447.72 | 408.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 504-06325 | Ground Nail (25 Foot) | | Each | | | |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 68.00 | 600.00 | 495.78 | 452.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 68.00 | 600.00 | 495.78 | 452.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 68.00 | 600.00 | 495.78 | 452.00 |
| ========== | 504-06330 | Ground Nail (30 Foot) | | Each | | | |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 149.00 | 1000.00 | 659.97 | 600.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 149.00 | 1000.00 | 659.97 | 600.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 149.00 | 1000.00 | 659.97 | 600.00 |
| ========== | 504-08050 | Stone Landscape Wall | | Sq Foot | | | |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 100.00 | 100.00 | 34.92 | 36.55 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 100.00 | 100.00 | 34.92 | 36.55 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 100.00 | 100.00 | 34.92 | 36.55 |
| ========== | 504-08100 | Timber Retaining Wall | | Sq Foot | | | |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 100.00 | 100.00 | 20.51 | 20.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 100.00 | 100.00 | 20.51 | 20.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 100.00 | 100.00 | 20.51 | 20.00 |
| ========== | 504-08255 | Masonry Landscape Wall (Dry Stack) | | Sq Foot | | | |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 198.00 | 27.50 | 35.93 | 44.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 198.00 | 27.50 | 35.93 | 44.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 512.00 | 30.00 | 29.96 | 30.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 512.00 | 30.00 | 29.96 | 30.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 504-08255 | Masonry Landscape Wall (Dry Stack) | | Sq Foot | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 7,480.00 | 30.00 | 36.69 | 45.70 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 7,480.00 | 30.00 | 36.69 | 45.70 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 8,190.00 | 29.94 | 36.37 | 44.68 |
| ========== | 506-00010 | Riprap (Special) | | Cubic Yard | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 820.00 | 80.00 | 68.03 | 42.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 411.00 | 75.00 | 46.26 | 50.17 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1,231.00 | 78.33 | 54.08 | 47.45 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 53.00 | 80.00 | 54.88 | 68.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1,850.00 | 50.00 | 88.54 | 96.51 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1,903.00 | 50.84 | 87.60 | 95.72 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3,134.00 | 61.64 | 77.21 | 83.91 |
| ========== | 506-00030 | Grouted Riprap | | Cubic Yard | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 1,268.00 | 100.00 | 162.46 | 135.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 45.00 | 150.00 | 282.81 | 632.10 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1,313.00 | 101.71 | 175.95 | 196.79 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 15.00 | 200.00 | 373.19 | 375.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 15.00 | 200.00 | 373.19 | 375.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,328.00 | 102.82 | 183.05 | 203.88 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 506-00036 | Grouted Riprap (36 In) (Special) | | Cubic Yard | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 101.00 | 200.00 | 201.29 | 158.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 101.00 | 200.00 | 201.29 | 158.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 101.00 | 200.00 | 201.29 | 158.00 |
| ========== | 506-00100 | Riprap (Gabions) | | Cubic Yard | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 6.00 | 300.00 | 239.12 | 92.45 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 6.00 | 300.00 | 239.12 | 92.45 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 6.00 | 300.00 | 239.12 | 92.45 |
| ========== | 506-00206 | Riprap (6 In) | | Cubic Yard | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 3.00 | 100.00 | 284.36 | 140.00 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 4.00 | 65.00 | 177.35 | 390.00 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 20.00 | 100.00 | 124.55 | 100.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 27.00 | 94.81 | 149.69 | 147.41 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 2,258.00 | 50.00 | 148.33 | 164.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2,258.00 | 50.00 | 148.33 | 164.00 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 11.00 | 45.00 | 245.90 | 230.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 11.00 | 45.00 | 245.90 | 230.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 198.00 | 100.00 | 104.08 | 81.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 198.00 | 100.00 | 104.08 | 81.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,494.00 | 54.43 | 139.86 | 157.52 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 506-00209 | Riprap (9 In) | | Cubic Yard | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 3.00 | 3.00 | 279.49 | 160.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 15.00 | 80.00 | 72.71 | 104.35 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 18.00 | 67.17 | 103.51 | 113.63 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 15.00 | 110.00 | 124.88 | 191.50 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 318.00 | 50.00 | 53.07 | 71.83 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 87.00 | 70.00 | 166.33 | 202.00 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 13.00 | 110.00 | 119.00 | 147.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 6.00 | 120.00 | 111.33 | 91.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 439.00 | 58.75 | 47.78 | 47.73 |
| NH0403-053 | | US 40 RETAINING WALL REPAIR | 07/28/11 | 10.00 | 100.00 | 133.14 | 84.41 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 18.70 | 100.00 | 119.47 | 130.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 28.70 | 100.00 | 80.14 | 73.73 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 9.00 | 60.00 | 104.00 | 48.23 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1,251.00 | 72.00 | 55.64 | 38.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 96.00 | 80.00 | 59.91 | 45.27 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 242.00 | 110.00 | 109.44 | 88.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1,598.00 | 78.17 | 66.17 | 46.07 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,083.70 | 74.28 | 51.21 | 48.09 |
| ========== | 506-00212 | Riprap (12 In) | | Cubic Yard | | | |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 150.00 | 75.00 | 88.60 | 79.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 1,636.00 | 85.00 | 42.34 | 41.33 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1,786.00 | 84.16 | 44.84 | 44.49 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 36.00 | 90.00 | 103.02 | 96.10 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 506-00212 | Riprap (12 In) | | Cubic Yard | | | |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 334.00 | 75.00 | 51.83 | 77.37 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 126.00 | 60.00 | 91.33 | 79.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 17.00 | 85.00 | 115.04 | 70.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 156.00 | 125.00 | 51.37 | 45.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 541.00 | 65.00 | 61.46 | 45.71 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1,210.00 | 76.00 | 65.59 | 71.90 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 19.00 | 120.00 | 120.04 | 105.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 20.00 | 100.00 | 104.70 | 75.00 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 10.00 | 95.00 | 243.33 | 200.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 49.00 | 106.73 | 77.76 | 69.66 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 51.00 | 60.00 | 67.09 | 44.69 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 43.00 | 85.00 | 63.43 | 43.00 |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 3.00 | 50.00 | 492.50 | 635.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 107.00 | 110.00 | 116.83 | 100.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 204.00 | 91.35 | 99.45 | 82.03 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3,249.00 | 81.91 | 58.84 | 59.97 |
| ========== | 506-00218 | Riprap (18 In) | | Cubic Yard | | | |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 3,043.00 | 80.00 | 68.20 | 57.00 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 24.00 | 140.00 | 131.51 | 100.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 3,067.00 | 80.47 | 68.53 | 57.34 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 11.00 | 100.00 | 125.04 | 103.20 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 28.00 | 50.00 | 131.00 | 140.00 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 1,847.00 | 60.00 | 47.32 | 64.36 |
| C0241-055 | | SH 24 MP 148-152 | 05/26/11 | 10.00 | 130.00 | 165.15 | 160.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1,896.00 | 60.45 | 48.32 | 66.21 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 25.00 | 90.00 | 173.57 | 200.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 25.00 | 90.00 | 159.63 | 155.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 506-00218 | Riprap (18 In) | | Cubic Yard | | | |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 135.00 | 85.00 | 61.56 | 37.19 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 135.00 | 85.00 | 61.56 | 37.19 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 5,123.00 | 73.23 | 62.15 | 61.02 |
| ========== | 506-00224 | Riprap (24 In) | | Cubic Yard | | | |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 456.00 | 75.00 | 121.19 | 84.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 4,402.00 | 40.00 | 53.07 | 41.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 4.00 | 200.00 | 137.33 | 135.00 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 4,862.00 | 43.41 | 59.52 | 45.11 |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 1,052.00 | 50.00 | 70.68 | 66.00 |
| C0091-038 | | SH 9 MM 81.9 BLUE RIVER EMERG | 08/24/11 | 10.00 | 100.00 | 123.95 | 164.75 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 94.00 | 150.00 | 155.00 | 100.00 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 1,156.00 | 58.56 | 74.59 | 69.62 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 743.00 | 85.00 | 54.37 | 45.27 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 743.00 | 85.00 | 54.37 | 45.27 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 6,761.00 | 50.57 | 61.01 | 49.32 |
| ========== | 506-00237 | Riprap (36 In) (Spec) | | Cubic Yard | | | |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 69.00 | 60.00 | 124.88 | 75.46 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 69.00 | 60.00 | 124.88 | 75.46 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 69.00 | 60.00 | 124.88 | 75.46 |
| ========== | 506-00409 | Soil Riprap (9 In) | | Cubic Yard | | | |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 7.00 | 80.00 | 120.46 | 146.06 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 7.00 | 80.00 | 120.46 | 146.06 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 7.00 | 80.00 | 120.46 | 146.06 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 506-00412 | Soil Riprap (12 In) | | Cubic Yard | | | |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 29.00 | 75.00 | 71.72 | 50.30 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 29.00 | 75.00 | 71.72 | 50.30 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 29.00 | 75.00 | 71.72 | 50.30 |
| ========== | 506-00418 | Soil Riprap (18 In) | | Cubic Yard | | | |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 2,810.00 | 50.00 | 40.69 | 45.42 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2,810.00 | 50.00 | 40.69 | 45.42 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,810.00 | 50.00 | 40.69 | 45.42 |
| ========== | 506-00424 | Soil Riprap (24 In) | | Cubic Yard | | | |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 308.00 | 50.00 | 58.75 | 68.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 308.00 | 50.00 | 58.75 | 68.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 308.00 | 50.00 | 58.75 | 68.00 |
| ========== | 506-01020 | Geogrid Reinforce | | Sq Yard | | | |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 6,756.00 | 5.00 | 6.02 | 6.50 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 3,360.00 | 5.00 | 23.67 | 17.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 10,116.00 | 5.00 | 3.75 | 2.79 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 131.00 | 6.00 | 6.33 | 1.75 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 10,000.00 | 6.00 | 6.21 | 5.50 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 7,650.00 | 7.00 | 3.32 | 3.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 17,781.00 | 6.43 | 5.36 | 4.40 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 500.00 | 5.00 | 8.61 | 7.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 506-01020 | Geogrid Reinforce | | Sq Yard | | | |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 790.00 | 36.00 | 42.00 | 44.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1,290.00 | 23.98 | 25.74 | 29.66 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 29,187.00 | 6.71 | 4.17 | 3.34 |
| ========== | 507-00000 | Conc S and D Pave | | Cubic Yard | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 192.00 | 300.00 | 449.61 | 250.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 192.00 | 300.00 | 464.90 | 277.76 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 41.00 | 400.00 | 259.15 | 220.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 230.00 | 400.00 | 460.25 | 420.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 21.00 | 200.00 | 354.20 | 502.85 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 292.00 | 385.62 | 431.84 | 397.88 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 3.00 | 500.00 | 435.04 | 450.00 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 20.00 | 600.00 | 572.11 | 295.00 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 2.00 | 600.00 | 745.00 | 835.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 25.00 | 588.00 | 567.04 | 356.80 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 3.00 | 200.00 | 447.14 | 270.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 7.00 | 300.00 | 433.04 | 308.84 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 82.00 | 500.00 | 513.95 | 660.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 92.00 | 475.00 | 506.67 | 620.56 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 601.00 | 380.37 | 459.83 | 427.51 |
| ========== | 507-00100 | Conc S and D Pave (Reinf) | | Cubic Yard | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 192.00 | 400.00 | 398.09 | 444.49 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 192.00 | 400.00 | 398.09 | 444.49 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 507-00100 | Conc S and D Pave (Reinf) | | Cubic Yard | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 66.00 | 400.00 | 385.66 | 370.00 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 0.55 | 300.00 | 841.00 | 800.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 66.55 | 399.17 | 388.18 | 373.55 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 136.00 | 600.00 | 348.15 | 320.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 136.00 | 600.00 | 343.90 | 311.88 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 157.00 | 450.00 | 322.94 | 248.26 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 12.00 | 250.00 | 426.14 | 315.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 64.00 | 300.00 | 399.37 | 310.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 137.00 | 300.00 | 320.70 | 266.61 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 66.00 | 600.00 | 585.45 | 700.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 436.00 | 398.05 | 387.75 | 333.31 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 830.55 | 431.66 | 381.87 | 357.25 |
| ========== | 507-00105 | Conc S and D Pave (Reinf)(C) | | Cubic Yard | | | |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 19.00 | 500.00 | 404.06 | 310.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 19.00 | 500.00 | 404.06 | 310.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 19.00 | 500.00 | 404.06 | 310.00 |
| ========== | 507-00300 | Gr Rubble S and D Pave | | Cubic Yard | | | |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 15.00 | 200.00 | 360.49 | 516.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 15.00 | 200.00 | 360.49 | 516.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 15.00 | 200.00 | 360.49 | 516.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 507-00400 | Bitum S and D Pave (Asph) | | Ton | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 8.00 | 180.00 | 277.33 | 335.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 8.00 | 180.00 | 277.33 | 335.00 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 4.00 | 200.00 | 295.49 | 257.44 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 6.00 | 30.00 | 331.87 | 321.83 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 10.00 | 98.00 | 211.06 | 210.41 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 18.00 | 134.44 | 93.58 | 92.95 |
| ========== | 508-00100 | Tr Timber | | M Ft Bd Measure | | | |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 4.40 | 10800.00 | 7400.00 | 6100.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 4.40 | 10800.00 | 7400.00 | 6100.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4.40 | 10800.00 | 7400.00 | 6100.00 |
| ========== | 509-00000 | Str Steel | | Pound | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 82,304.00 | 2.00 | 1.68 | 1.55 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 82,304.00 | 2.00 | 1.68 | 1.55 |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 1,812.00 | 2.50 | 16.48 | 10.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1,812.00 | 2.50 | 16.48 | 10.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 384,578.00 | 1.85 | 1.91 | 1.95 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 489,961.00 | 1.85 | 1.70 | 1.60 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 874,539.00 | 1.85 | 1.81 | 1.75 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 958,655.00 | 1.86 | 1.82 | 1.75 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 509-00001 | Str Steel (Galv) | | Pound | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 22,960.00 | 5.00 | 2.45 | 1.53 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 22,960.00 | 5.00 | 2.67 | 1.74 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 22,960.00 | 5.00 | 2.67 | 1.74 |
| ========== | 509-08100 | Provide Temporary Support | | LUMP SUM | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 1.00 | 600000.00 | 288024.80 | 325000.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1.00 | 600000.00 | 288024.80 | 325000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 600000.00 | 288024.80 | 325000.00 |
| ========== | 509-08120 | Temporary Bridge Deck | | Sq Foot | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 1,938.00 | 50.00 | 109.03 | 1.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1,938.00 | 50.00 | 109.03 | 1.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,938.00 | 50.00 | 109.03 | 1.00 |
| ========== | 509-60000 | Refurb Architectural Steel | | LUMP SUM | | | |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 1.00 | 100000.00 | 39121.44 | 36000.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1.00 | 100000.00 | 39121.44 | 36000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 100000.00 | 39121.44 | 36000.00 |
| ========== | 509-90000 | Paint Existing Str(S) | | LUMP SUM | | | |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 1.00 | 230000.00 | 482501.46 | 554700.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1.00 | 230000.00 | 482501.46 | 554700.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 230000.00 | 482501.46 | 554700.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 509-90003 | Paint Structural Steel | | LUMP SUM | ========== | ========== | ========== |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1.00 | 50000.00 | 40614.29 | 55000.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 50000.00 | 40614.29 | 55000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 50000.00 | 40614.29 | 55000.00 |
| ========== | 512-00101 | Bearing Device (Type I) | | Each | ========== | ========== | ========== |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 4.00 | 1000.00 | 3778.54 | 3100.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 32.00 | 800.00 | 4567.23 | 3701.45 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 36.00 | 822.22 | 4540.45 | 3683.22 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 16.00 | 2000.00 | 1508.35 | 1100.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 16.00 | 2000.00 | 1508.35 | 1100.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 20.00 | 650.00 | 1188.57 | 1300.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 16.00 | 3750.00 | 2482.69 | 2238.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 36.00 | 2027.78 | 1659.16 | 1716.89 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 88.00 | 1529.55 | 2948.42 | 2364.17 |
| ========== | 512-00102 | Bearing Device (Type II) | | Each | ========== | ========== | ========== |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 8.00 | 3750.00 | 2705.74 | 2360.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 8.00 | 3750.00 | 2705.74 | 2360.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 8.00 | 3750.00 | 2705.74 | 2360.00 |
| ========== | 512-00103 | Bearing Device (Type III) | | Each | ========== | ========== | ========== |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 24.00 | 8000.00 | 5982.32 | 5500.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 512-00103 | Bearing Device (Type III) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 24.00 | 8000.00 | 5982.32 | 5500.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 24.00 | 8000.00 | 5982.32 | 5500.00 |
| ========== | 513-00600 | Bridge Drain | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 20.00 | 4000.00 | 12121.64 | 10500.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 20.00 | 4000.00 | 12121.64 | 10500.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 2.00 | 8000.00 | 4412.21 | 2800.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2.00 | 8000.00 | 4412.21 | 2800.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 22.00 | 4363.64 | 10993.43 | 9216.67 |
| ========== | 513-00606 | Bridge Drain (6 In) | | Each | | | |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 6.00 | 1000.00 | 1217.73 | 150.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 6.00 | 1000.00 | 1217.73 | 150.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 6.00 | 1000.00 | 1217.73 | 150.00 |
| ========== | 513-00690 | Bridge Drain (Spec) | | Each | | | |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 2.00 | 2200.00 | 3169.72 | 2400.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 4.00 | 6000.00 | 4335.83 | 1433.95 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 6.00 | 4733.33 | 3916.03 | 1755.97 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 4.00 | 3500.00 | 6465.28 | 6209.38 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 513-00690 | Bridge Drain (Spec) | | Each | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 4.00 | 2000.00 | 8494.29 | 9600.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 8.00 | 2750.00 | 7412.15 | 7904.69 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 14.00 | 3600.00 | 5823.01 | 5269.52 |
| ========== | 514-00000 | Pipe Railing | | Lin Foot | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 60.00 | 86.00 | 120.33 | 93.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 60.00 | 86.00 | 141.96 | 96.04 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1,374.00 | 90.00 | 94.86 | 74.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1,374.00 | 90.00 | 94.86 | 74.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,434.00 | 89.83 | 98.17 | 75.58 |
| ========== | 514-00200 | Pedestrian Railing (Steel) | | Lin Foot | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 361.00 | 180.00 | 69.36 | 55.74 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 361.00 | 180.00 | 69.36 | 55.74 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 237.00 | 160.00 | 124.77 | 120.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 237.00 | 160.00 | 124.77 | 120.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 522.00 | 100.00 | 192.12 | 226.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 372.00 | 60.00 | 135.35 | 137.88 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 894.00 | 83.36 | 161.88 | 189.33 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,492.00 | 118.91 | 129.43 | 146.00 |
| ========== | 514-00201 | Ped Railing (Steel) (Spec) | | Lin Foot | | | |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 517.00 | 250.00 | 199.86 | 180.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 517.00 | 250.00 | 199.86 | 180.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 514-00201 | Ped Railing (Steel) (Spec) | | Lin Foot | | | |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 350.00 | 120.00 | 208.82 | 165.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 350.00 | 120.00 | 208.82 | 165.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 867.00 | 197.52 | 202.52 | 173.94 |
| ========== | 515-00120 | Waterproofing (Membrane) | | Sq Yard | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 33,200.00 | 11.50 | 12.91 | 12.06 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 349.00 | 18.00 | 14.79 | 14.25 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 2,437.00 | 12.00 | 14.15 | 13.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 8,788.00 | 12.00 | 13.32 | 13.37 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 44,774.00 | 11.68 | 13.32 | 12.71 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 1,697.00 | 13.00 | 19.25 | 19.25 |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 1,055.00 | 14.00 | 12.53 | 12.05 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 6,561.00 | 12.00 | 13.63 | 12.58 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 1,388.00 | 13.00 | 14.18 | 16.00 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 8,385.00 | 13.00 | 16.46 | 14.50 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 194.00 | 20.00 | 25.83 | 23.20 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 2,071.00 | 4.00 | 16.67 | 16.50 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 1,095.00 | 13.00 | 14.13 | 12.30 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 5,837.00 | 12.00 | 13.67 | 15.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 3,398.00 | 13.00 | 13.23 | 12.44 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 31,681.00 | 12.10 | 14.70 | 14.42 |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 692.00 | 25.00 | 19.02 | 16.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 2,618.00 | 13.00 | 13.93 | 13.25 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 1,280.00 | 15.00 | 16.96 | 20.00 |
| BR2706-036 | | I-270 BRIDGE DECK REHABILITAT | 08/11/11 | 6,413.00 | 15.00 | 14.56 | 14.50 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 11,003.00 | 15.15 | 15.08 | 15.12 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 515-00120 | Waterproofing (Membrane) | | Sq Yard | | | |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 1,186.00 | 14.00 | 14.72 | 15.14 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 1,550.00 | 13.00 | 14.92 | 15.09 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 3,434.00 | 13.00 | 13.97 | 13.08 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 1,451.00 | 14.00 | 19.15 | 22.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 7,621.00 | 13.35 | 15.36 | 15.51 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 95,079.00 | 12.35 | 14.33 | 14.17 |
| ========== | 515-00300 | Waterproof Coating | | Sq Yard | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 510.00 | 15.00 | 103.46 | 8.20 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 510.00 | 15.00 | 103.46 | 8.20 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 510.00 | 15.00 | 103.46 | 8.20 |
| ========== | 515-00400 | Concrete Sealer | | Sq Yard | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 126.00 | 6.00 | 11.64 | 11.75 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 1,430.00 | 6.50 | 9.37 | 6.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 1,556.00 | 6.46 | 9.58 | 6.47 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 330.00 | 10.00 | 7.00 | 2.40 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 330.00 | 10.00 | 7.00 | 2.40 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 637.00 | 10.00 | 6.60 | 7.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 637.00 | 10.00 | 6.60 | 7.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,523.00 | 7.82 | 8.36 | 6.07 |
| ========== | 518-00010 | Rdwy Compress Joint Sealer | | Lin Foot | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 270.00 | 10.00 | 72.76 | 62.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 270.00 | 10.00 | 72.76 | 62.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 270.00 | 10.00 | 72.76 | 62.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 518-00112 | Waterstop (12 In) | | Lin Foot | | | |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 130.00 | 30.00 | 25.52 | 13.40 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 130.00 | 30.00 | 25.52 | 13.40 |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 84.00 | 28.00 | 25.87 | 23.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 84.00 | 28.00 | 25.87 | 23.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 214.00 | 29.21 | 27.68 | 22.34 |
| ========== | 518-01002 | Br Expan Device (0-2 In) | | Lin Foot | | | |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 894.40 | 180.00 | 188.68 | 207.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 894.40 | 180.00 | 188.68 | 207.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 894.40 | 180.00 | 188.68 | 207.00 |
| ========== | 518-01004 | Br Expan Device (0-4 In) | | Lin Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 850.00 | 200.00 | 244.23 | 160.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 80.00 | 160.00 | 188.87 | 150.00 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 684.00 | 250.00 | 177.56 | 260.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 468.00 | 200.00 | 171.31 | 155.79 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 2,082.00 | 214.89 | 189.24 | 211.11 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 58.00 | 200.00 | 454.00 | 433.00 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 343.00 | 180.00 | 170.30 | 173.37 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 468.00 | 150.00 | 197.98 | 140.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 291.00 | 180.00 | 215.19 | 140.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 234.00 | 150.00 | 201.72 | 231.01 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1,394.00 | 165.72 | 200.06 | 178.07 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 518-01004 | Br Expan Device (0-4 In) | | Lin Foot | | | |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 44.00 | 250.00 | 208.77 | 160.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 227.00 | 180.00 | 193.54 | 205.00 |
| BR2706-036 | | I-270 BRIDGE DECK REHABILITAT | 08/11/11 | 40.00 | 200.00 | 265.75 | 199.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 311.00 | 192.48 | 200.49 | 197.86 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 86.00 | 170.00 | 167.05 | 170.27 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 52.00 | 200.00 | 378.98 | 258.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 244.00 | 150.00 | 181.77 | 205.34 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 68.00 | 250.00 | 211.64 | 160.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 450.00 | 174.71 | 198.69 | 197.87 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4,237.00 | 192.80 | 195.44 | 194.88 |
| ========== | 518-01012 | Br Expan Device (0-12 In) | | Lin Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 144.00 | 2000.00 | 1888.33 | 1800.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 144.00 | 2000.00 | 1888.33 | 1800.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 144.00 | 2000.00 | 1888.33 | 1800.00 |
| ========== | 518-02010 | Elastomeric Conc End Dam | | Cubic Foot | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 257.00 | 550.00 | 420.10 | 280.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 257.00 | 550.00 | 424.53 | 290.61 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 30.00 | 500.00 | 486.33 | 464.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 139.00 | 500.00 | 387.64 | 180.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 169.00 | 500.00 | 397.25 | 230.41 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 426.00 | 530.16 | 414.65 | 268.20 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 518-03000 | Saw and Seal Br Joint | | Lin Foot | | | |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 391.00 | 12.00 | 6.58 | 6.25 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 143.00 | 17.00 | 14.33 | 10.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 534.00 | 13.34 | 10.15 | 7.25 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 80.00 | 20.00 | 14.72 | 12.61 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 80.00 | 20.00 | 14.72 | 12.61 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 614.00 | 14.21 | 14.06 | 8.82 |
| ========== | 519-01000 | Epoxy Resin (Injection) | | Lin Foot | | | |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 4.00 | 80.00 | 393.17 | 520.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 4.00 | 80.00 | 393.17 | 520.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4.00 | 80.00 | 652.89 | 128.47 |
| ========== | 519-01300 | Polyurethane Resin | | Pound | | | |
| NH5502-070 | | US 550 4 MILES SOUTH OF OURAY | 08/18/11 | 25,000.00 | 8.00 | 9.36 | 9.15 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 25,000.00 | 8.00 | 9.36 | 9.15 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 25,000.00 | 8.00 | 9.36 | 9.15 |
| ========== | 519-03000 | Thin Bonded Epoxy Overlay | | Sq Yard | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 440.00 | 50.00 | 87.12 | 80.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 440.00 | 50.00 | 87.12 | 80.00 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 7,343.00 | 40.00 | 34.46 | 37.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 519-03000 | Thin Bonded Epoxy Overlay | | Sq Yard | | | |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 753.00 | 45.00 | 41.05 | 43.75 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 8,096.00 | 40.47 | 35.07 | 37.63 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1,210.00 | 40.00 | 39.78 | 35.00 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 3,052.00 | 50.00 | 38.13 | 37.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 4,262.00 | 47.16 | 38.95 | 36.43 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 12,798.00 | 43.02 | 37.98 | 38.69 |
| ========== | 601-01000 | Conc CL B | | Cubic Yard | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 2.60 | 490.00 | 1702.83 | 1500.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 2.60 | 490.00 | 353.06 | 245.90 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 5.50 | 600.00 | 888.62 | 535.00 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 8.00 | 400.00 | 790.33 | 933.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 2.00 | 550.00 | 738.29 | 330.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 12.00 | 500.00 | 860.00 | 800.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 37.00 | 450.00 | 450.80 | 356.08 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 64.50 | 468.99 | 660.07 | 543.93 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 2.00 | 500.00 | 747.64 | 700.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 14.00 | 500.00 | 857.80 | 600.00 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 18.00 | 600.00 | 790.60 | 875.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 34.00 | 552.94 | 761.84 | 634.78 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1.00 | 100.00 | 626.29 | 395.00 |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 5.50 | 1200.00 | 675.00 | 500.00 |
| MC0504-065 | | US50B FROM MP 318 TO MP 359 | 12/01/11 | 83.00 | 350.00 | 300.00 | 255.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 89.50 | 399.44 | 324.00 | 271.62 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 190.60 | 451.59 | 468.45 | 383.74 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 601-01025 | Conc CL B (Misc) | | Cubic Yard | | | |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 41.70 | 410.00 | 492.64 | 355.59 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 8.00 | 800.00 | 423.51 | 525.00 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 0.70 | 1000.00 | 1806.68 | 1800.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 50.40 | 480.10 | 488.94 | 402.54 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 50.40 | 480.10 | 488.94 | 402.54 |
| ========== | 601-01030 | Conc CL B (Box) | | Cubic Yard | | | |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 71.00 | 350.00 | 357.99 | 318.45 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 71.00 | 350.00 | 357.99 | 318.45 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 71.00 | 350.00 | 357.99 | 318.45 |
| ========== | 601-01040 | Conc CL B (Bridge) | | Cubic Yard | | | |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 156.00 | 400.00 | 315.00 | 183.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 156.00 | 400.00 | 315.00 | 183.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 156.00 | 400.00 | 315.00 | 183.00 |
| ========== | 601-01050 | Conc CL B (Wall) | | Cubic Yard | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 8.50 | 410.00 | 665.06 | 552.45 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 8.50 | 410.00 | 665.06 | 552.45 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 33.00 | 600.00 | 663.09 | 625.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 33.00 | 600.00 | 663.09 | 625.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 41.50 | 561.08 | 788.40 | 786.95 |
| ========== | 601-03000 | Conc CL D | | Cubic Yard | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 1,160.00 | 300.00 | 373.28 | 325.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 601-03000 | Conc CL D | | Cubic Yard | ========== | ========== | ========== |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 34.90 | 830.00 | 876.10 | 900.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 484.00 | 410.00 | 417.34 | 285.11 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1,678.90 | 342.73 | 414.36 | 325.73 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 6.00 | 990.00 | 1205.23 | 3000.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 13.00 | 700.00 | 906.67 | 800.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 19.00 | 791.58 | 1071.39 | 1494.74 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 721.00 | 450.00 | 503.00 | 420.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 20.00 | 600.00 | 530.74 | 378.41 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 742.00 | 350.00 | 374.30 | 450.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1,483.00 | 401.99 | 434.84 | 434.45 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3,180.90 | 373.04 | 428.18 | 394.25 |
| ========== | 601-03020 | Conc CL D (Misc) | | Cubic Yard | ========== | ========== | ========== |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 9.00 | 500.00 | 1361.67 | 1625.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 9.00 | 500.00 | 1361.67 | 1625.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 9.00 | 500.00 | 1361.67 | 1625.00 |
| ========== | 601-03027 | Conc CL D (Spec) | | Cubic Yard | ========== | ========== | ========== |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 235.00 | 600.00 | 430.99 | 555.41 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 235.00 | 600.00 | 430.99 | 555.41 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 235.00 | 600.00 | 430.99 | 555.41 |
| ========== | 601-03030 | Conc CL D (Box) | | Cubic Yard | ========== | ========== | ========== |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 119.00 | 500.00 | 397.88 | 380.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 601-03030 | Conc CL D (Box) | | Cubic Yard | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 303.00 | 350.00 | 356.18 | 311.12 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 422.00 | 392.30 | 372.89 | 338.77 |
| C0091-038 | | SH 9 MM 81.9 BLUE RIVER EMERG | 08/24/11 | 9.50 | 800.00 | 1474.71 | 1760.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 15.00 | 800.00 | 929.60 | 835.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 24.50 | 800.00 | 1112.91 | 1193.67 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 8.90 | 430.00 | 579.59 | 428.20 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 461.00 | 450.00 | 513.86 | 510.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 469.90 | 449.62 | 514.75 | 508.45 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 916.40 | 432.59 | 410.87 | 402.39 |
| ========== | 601-03040 | Conc CL D (Bridge) | | Cubic Yard | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 13,740.00 | 350.00 | 515.64 | 350.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 285.00 | 600.00 | 466.68 | 400.00 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 1,388.00 | 500.00 | 440.52 | 360.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 1,995.00 | 500.00 | 569.19 | 392.05 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 17,408.00 | 383.24 | 512.93 | 366.72 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 2,404.00 | 325.00 | 454.91 | 463.01 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 1,618.00 | 450.00 | 436.00 | 430.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 716.00 | 600.00 | 584.00 | 472.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 2,851.00 | 350.00 | 350.46 | 320.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1,894.00 | 325.00 | 426.44 | 513.06 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 9,483.00 | 374.61 | 425.12 | 425.06 |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 262.00 | 500.00 | 797.96 | 730.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 601-03040 | Conc CL D (Bridge) | | Cubic Yard | | | |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 1,549.00 | 400.00 | 383.07 | 335.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 56.73 | 50.00 | 417.24 | 550.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1,867.73 | 403.40 | 441.01 | 409.06 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 548.00 | 450.00 | 447.29 | 439.03 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 499.00 | 440.00 | 643.57 | 545.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 246.00 | 500.00 | 524.40 | 497.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 967.00 | 500.00 | 462.99 | 463.92 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1,742.00 | 400.00 | 405.28 | 425.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 68.00 | 600.00 | 417.87 | 530.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 4,070.00 | 444.78 | 456.80 | 456.95 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 32,828.73 | 389.52 | 464.93 | 411.89 |
| ========== | 601-03041 | Conc CL D (Bridge) (Spec) | | Cubic Yard | | | |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 81.00 | 1200.00 | 700.33 | 605.00 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 243.90 | 680.00 | 1317.83 | 1310.00 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 27.00 | 1200.00 | 1042.00 | 526.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 351.90 | 839.59 | 1159.02 | 1087.57 |
| BR2706-036 | | I-270 BRIDGE DECK REHABILITAT | 08/11/11 | 786.00 | 1250.00 | 502.94 | 356.75 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 786.00 | 1250.00 | 502.94 | 356.75 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,137.90 | 1123.08 | 760.38 | 582.76 |
| ========== | 601-03050 | Conc CL D (Wall) | | Cubic Yard | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 5,125.00 | 450.00 | 465.50 | 350.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 5,125.00 | 450.00 | 465.50 | 350.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 601-03050 | Conc CL D (Wall) | | Cubic Yard | | | |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 22.00 | 500.00 | 617.84 | 614.66 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 2,017.00 | 500.00 | 402.69 | 410.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 3,017.00 | 425.00 | 300.43 | 280.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1,202.00 | 400.00 | 527.03 | 520.05 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 6,258.00 | 444.63 | 372.52 | 369.18 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 10.00 | 1000.00 | 848.93 | 850.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 10.00 | 1000.00 | 892.08 | 1075.00 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 4.10 | 500.00 | 684.99 | 390.41 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 33.00 | 350.00 | 715.86 | 460.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1,029.00 | 350.00 | 509.80 | 381.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 157.00 | 550.00 | 476.03 | 285.23 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 37.00 | 1000.00 | 615.72 | 910.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 1,260.10 | 394.49 | 516.11 | 386.70 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 12,653.10 | 442.25 | 408.79 | 371.14 |
| ========== | 601-03540 | Conc CL DT (Deck Topping) | | Cubic Yard | | | |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 21.20 | 600.00 | 1193.50 | 1596.50 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 434.00 | 400.00 | 598.33 | 475.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 455.20 | 409.31 | 612.52 | 527.23 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 455.20 | 409.31 | 619.96 | 527.40 |
| ========== | 601-04000 | Conc CL E | | Cubic Yard | | | |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 108.00 | 500.00 | 350.60 | 341.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 108.00 | 500.00 | 350.60 | 341.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 108.00 | 500.00 | 479.07 | 475.12 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 601-05000 | Conc CL H | | Cubic Yard | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 125.00 | 600.00 | 580.84 | 670.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 125.00 | 600.00 | 580.84 | 670.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 125.00 | 600.00 | 580.84 | 670.00 |
| ========== | 601-05001 | Conc CL H (Bridge) | | Cubic Yard | | | |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 477.00 | 600.00 | 570.40 | 541.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 477.00 | 600.00 | 570.40 | 541.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 477.00 | 600.00 | 570.40 | 541.00 |
| ========== | 601-05020 | Conc CL R | | Cubic Yard | | | |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 17.00 | 700.00 | 1200.00 | 1650.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 17.00 | 700.00 | 1200.00 | 1650.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 17.00 | 700.00 | 1200.00 | 1650.00 |
| ========== | 601-05050 | Conc CL S50 | | Cubic Yard | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 656.00 | 600.00 | 742.46 | 300.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 656.00 | 600.00 | 742.46 | 300.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 656.00 | 600.00 | 742.46 | 300.00 |
| ========== | 601-06100 | Conc (Patching) | | Cubic Yard | | | |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 7.20 | 1000.00 | 1797.31 | 2100.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 7.20 | 1000.00 | 1797.31 | 2100.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 7.20 | 1000.00 | 1380.40 | 1576.89 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 601-06150 | Conc (Patching) | | Sq Foot | | | |
| NH2872-018 | | US 287 RUSH CREEK NORTH | 07/21/11 | 100.00 | 75.00 | 85.77 | 105.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 100.00 | 75.00 | 85.77 | 105.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 100.00 | 75.00 | 85.77 | 105.00 |
| ========== | 601-06400 | Grout (Bridge)(Spec) | | Cubic Foot | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 11,925.00 | 60.00 | 43.76 | 12.56 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 11,925.00 | 60.00 | 43.76 | 12.56 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 11,925.00 | 60.00 | 43.76 | 12.56 |
| ========== | 601-21003 | Precast Wall Seg | | Sq Foot | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 1,704.00 | 26.20 | 44.92 | 42.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 1,704.00 | 26.20 | 44.92 | 42.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,704.00 | 26.20 | 44.92 | 42.00 |
| ========== | 601-40005 | Cut Stone Veneer | | Sq Foot | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 30,718.00 | 30.00 | 40.28 | 43.33 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 30,718.00 | 30.00 | 40.28 | 43.33 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 30,718.00 | 30.00 | 40.28 | 43.33 |
| ========== | 601-40250 | Bridge Deck Finish (Saw Grv) | | Sq Yard | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 266.00 | 10.00 | 5.12 | 3.70 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 266.00 | 10.00 | 5.12 | 3.70 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 266.00 | 10.00 | 5.12 | 3.70 |
| ========== | 601-40300 | Struct Conc Coating | | Sq Yard | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 18,622.00 | 8.00 | 8.75 | 9.90 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 18,622.00 | 8.00 | 8.75 | 9.90 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 601-40300 | Struct Conc Coating | | Sq Yard | | | |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 1,006.00 | 15.00 | 11.32 | 13.80 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1,006.00 | 15.00 | 11.32 | 13.80 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 8,427.00 | 10.00 | 8.50 | 7.13 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 7,352.00 | 9.00 | 6.74 | 8.61 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 15,779.00 | 9.53 | 7.48 | 7.82 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 35,407.00 | 8.88 | 8.32 | 9.08 |
| ========== | 601-40302 | Struct Conc Coating (Anti-Graf) | | Sq Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 570,760.00 | 1.00 | 0.70 | 0.85 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 570,760.00 | 1.00 | 0.70 | 0.85 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 570,760.00 | 1.00 | 0.70 | 0.85 |
| ========== | 601-40400 | Struct Conc Stain | | Sq Yard | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 85,538.00 | 7.55 | 6.43 | 7.20 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 2,730.00 | 6.00 | 10.59 | 9.50 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 88,268.00 | 7.50 | 6.83 | 7.42 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 2,689.00 | 6.00 | 7.77 | 8.55 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 11,149.00 | 8.00 | 6.45 | 7.50 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 601-40400 | Struct Conc Stain | | Sq Yard | | | |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 2,682.00 | 9.00 | 9.66 | 7.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1,659.00 | 10.00 | 7.78 | 7.69 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 18,179.00 | 8.03 | 7.32 | 7.60 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 1,113.00 | 10.00 | 7.85 | 5.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1,113.00 | 10.00 | 7.85 | 5.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 1,849.00 | 6.00 | 7.94 | 5.86 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1,849.00 | 6.00 | 7.94 | 5.86 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 109,409.00 | 7.59 | 7.04 | 7.37 |
| ========== | 602-00000 | Reinf Steel | | Pound | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 193,660.00 | 0.72 | 0.68 | 0.65 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 282.00 | 2.00 | 3.99 | 3.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 187,255.00 | 0.70 | 0.76 | 0.76 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 381,197.00 | 0.71 | 0.74 | 0.73 |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 1,500.00 | 1.00 | 3.15 | 3.00 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 42,365.00 | 0.80 | 0.79 | 0.77 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 85,265.00 | 0.70 | 0.74 | 0.65 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 360,986.00 | 0.70 | 0.65 | 0.68 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 1,683.00 | 1.00 | 1.67 | 1.50 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 70,717.00 | 1.00 | 0.75 | 0.82 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 562,516.00 | 0.75 | 0.71 | 0.72 |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 9,880.00 | 2.00 | 1.00 | 0.75 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 602-00000 | Reinf Steel | | Pound | | | |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 2,600.00 | 1.50 | 1.20 | 1.15 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 10,206.00 | 1.00 | 0.99 | 0.92 |
| C0091-038 | | SH 9 MM 81.9 BLUE RIVER EMERG | 08/24/11 | 1,018.00 | 3.00 | 2.36 | 2.70 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 580.00 | 3.00 | 2.54 | 2.40 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 203.00 | 2.00 | 2.00 | 3.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 24,487.00 | 1.60 | 1.07 | 0.98 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 2,977.00 | 3.00 | 1.25 | 1.06 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 61,243.00 | 0.80 | 0.76 | 0.75 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 60,819.00 | 0.80 | 0.75 | 0.70 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 46,895.00 | 0.80 | 0.86 | 0.77 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 9,404.00 | 0.80 | 0.72 | 0.80 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 181,338.00 | 0.84 | 0.79 | 0.75 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,149,538.00 | 0.77 | 0.74 | 0.74 |
| ========== | 602-00020 | Reinf Steel (Epoxy) | | Pound | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 5,122,048.00 | 0.70 | 0.78 | 0.70 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 38,318.00 | 1.00 | 0.93 | 0.82 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 417,463.00 | 0.80 | 0.77 | 0.74 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 222,804.00 | 0.80 | 0.99 | 1.01 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 5,800,633.00 | 0.72 | 0.80 | 0.77 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 1,939.00 | 1.50 | 1.92 | 1.75 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 580,592.00 | 0.80 | 0.84 | 0.82 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 565,349.00 | 0.85 | 0.82 | 0.79 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 9,430.00 | 1.20 | 1.90 | 2.10 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 115,338.00 | 1.50 | 1.03 | 0.98 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 726.00 | 2.00 | 1.88 | 2.20 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 624,249.00 | 0.80 | 0.87 | 0.80 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 251.00 | 2.00 | 2.37 | 2.50 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 492,241.00 | 0.80 | 0.88 | 0.95 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2,390,115.00 | 0.85 | 0.87 | 0.86 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 602-00020 | Reinf Steel (Epoxy) | | Pound | | | |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 63,006.00 | 2.10 | 1.13 | 0.90 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 334,950.00 | 0.85 | 0.91 | 0.90 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 3,300.00 | 3.00 | 2.22 | 1.05 |
| BR2706-036 | | I-270 BRIDGE DECK REHABILITAT | 08/11/11 | 6,100.00 | 2.00 | 3.24 | 1.70 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 696.00 | 3.00 | 2.50 | 2.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 408,052.00 | 1.08 | 0.98 | 0.92 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 153,602.00 | 1.00 | 0.92 | 0.82 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 249,841.00 | 1.00 | 0.88 | 0.95 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 266,817.00 | 1.00 | 0.90 | 0.85 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 158,269.00 | 0.90 | 1.03 | 0.83 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 481,359.00 | 0.85 | 0.83 | 0.90 |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 185.00 | 2.00 | 5.00 | 6.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 20,137.00 | 1.10 | 1.29 | 1.10 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 1,330,210.00 | 0.94 | 0.89 | 0.89 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 9,929,010.00 | 0.79 | 0.86 | 0.84 |
| ========== | 603-00001 | Annular Space Grouting | | Cubic Yard | | | |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 95.00 | 450.00 | 219.25 | 193.75 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 20.00 | 500.00 | 371.67 | 369.00 |
| C0241-055 | | SH 24 MP 148-152 | 05/26/11 | 36.00 | 700.00 | 392.14 | 470.00 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 5.00 | 500.00 | 465.65 | 366.30 |
| FSA 0502-064 | | US 50 EAST OF SARGENTS | 06/23/11 | 162.00 | 375.00 | 381.47 | 301.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 318.00 | 444.03 | 316.42 | 222.53 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 318.00 | 444.03 | 316.42 | 222.53 |
| ========== | 603-00024 | Prep Culvert Pipe (24 In) | | Lin Foot | | | |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 310.00 | 10.00 | 31.00 | 65.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 310.00 | 10.00 | 31.00 | 65.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 310.00 | 10.00 | 31.00 | 65.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 603-00025 | Culvert Lining (24 Inch)(Special) | | Lin Foot | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 495.00 | 250.00 | 184.87 | 190.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 495.00 | 250.00 | 184.87 | 190.00 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 49.00 | 170.00 | 179.92 | 195.75 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 49.00 | 170.00 | 179.92 | 195.75 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 310.00 | 250.00 | 264.33 | 332.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 310.00 | 250.00 | 264.33 | 332.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 854.00 | 245.41 | 202.95 | 241.88 |
| ========== | 603-00030 | Culvert Lining (30 In) | | Lin Foot | | | |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 172.00 | 200.00 | 208.83 | 224.50 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 172.00 | 200.00 | 208.83 | 224.50 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 172.00 | 200.00 | 208.83 | 224.50 |
| ========== | 603-00035 | Prep Culvert Pipe (36 In) | | Lin Foot | | | |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 75.00 | 10.00 | 63.33 | 25.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 75.00 | 10.00 | 63.33 | 25.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 75.00 | 10.00 | 63.33 | 25.00 |
| ========== | 603-00036 | Culvert Lining (36 In) | | Lin Foot | | | |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 120.00 | 300.00 | 285.00 | 215.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 120.00 | 300.00 | 272.83 | 235.50 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 120.00 | 300.00 | 272.83 | 235.50 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 603-00040 | Culvert Lining (40 In) | | Lin Foot | | | |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 152.00 | 275.00 | 288.76 | 249.51 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 152.00 | 275.00 | 288.76 | 249.51 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 152.00 | 275.00 | 288.76 | 249.51 |
| ========== | 603-00047 | Prepare Culvert Pipe (48 In) | | Lin Foot | | | |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 100.00 | 350.00 | 49.42 | 49.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 100.00 | 350.00 | 49.42 | 49.00 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 460.00 | 10.00 | 51.67 | 30.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 460.00 | 10.00 | 51.67 | 30.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 560.00 | 70.71 | 51.26 | 33.39 |
| ========== | 603-00048 | Culvert Lining (48 In) | | Lin Foot | | | |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 130.00 | 400.00 | 212.33 | 210.00 |
| C0241-055 | | SH 24 MP 148-152 | 05/26/11 | 145.00 | 560.00 | 537.53 | 325.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 275.00 | 484.36 | 383.80 | 270.64 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 460.00 | 400.00 | 310.00 | 250.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 460.00 | 400.00 | 310.00 | 250.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 735.00 | 431.56 | 337.61 | 257.72 |
| ========== | 603-00049 | Culvert Lining (48 Inch)(Special) | | Lin Foot | | | |
| C0241-055 | | SH 24 MP 148-152 | 05/26/11 | 35.00 | 600.00 | 713.11 | 480.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 35.00 | 600.00 | 713.11 | 480.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 35.00 | 600.00 | 713.11 | 480.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 603-00053 | Prep Culvert Pipe (54 In) | | Lin Foot | | | |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 354.00 | 10.00 | 65.00 | 40.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 354.00 | 10.00 | 65.00 | 40.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 354.00 | 10.00 | 65.00 | 40.00 |
| ========== | 603-00054 | Culvert Lining (54 In) | | Lin Foot | | | |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 354.00 | 400.00 | 345.00 | 275.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 354.00 | 400.00 | 345.00 | 275.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 354.00 | 400.00 | 345.00 | 275.00 |
| ========== | 603-00060 | Culvert Lining (60 In) | | Lin Foot | | | |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 333.00 | 550.00 | 618.74 | 580.72 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 333.00 | 550.00 | 618.74 | 580.72 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 333.00 | 550.00 | 532.47 | 483.93 |
| ========== | 603-00072 | Culvert Lining (72 In) | | Lin Foot | | | |
| FSA 0502-064 | | US 50 EAST OF SARGENTS | 06/23/11 | 250.00 | 800.00 | 930.05 | 808.96 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 250.00 | 800.00 | 930.05 | 808.96 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 250.00 | 800.00 | 930.05 | 808.96 |
| ========== | 603-01120 | 12 In RCP | | Lin Foot | | | |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 122.00 | 50.00 | 56.19 | 48.10 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 122.00 | 50.00 | 56.19 | 48.10 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 122.00 | 50.00 | 56.19 | 48.10 |
| ========== | 603-01125 | 12 In RCP (CIP) | | Lin Foot | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 18.00 | 220.01 | 58.73 | 37.59 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 18.00 | 220.01 | 58.73 | 37.59 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 18.00 | 220.01 | 58.73 | 37.59 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 603-01150 | 15 In RCP | | Lin Foot | ========== | ========== | ========== |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 242.00 | 50.00 | 60.24 | 58.50 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 242.00 | 50.00 | 60.24 | 58.50 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 60.00 | 50.00 | 59.20 | 63.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 60.00 | 50.00 | 59.20 | 63.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 302.00 | 50.00 | 59.97 | 59.39 |
| ========== | 603-01155 | 15 In RCP (CIP) | | Lin Foot | ========== | ========== | ========== |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 262.00 | 60.00 | 92.64 | 108.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 20.00 | 110.00 | 69.70 | 78.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 282.00 | 63.55 | 91.32 | 105.87 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 282.00 | 63.55 | 91.32 | 105.87 |
| ========== | 603-01180 | 18 In RCP | | Lin Foot | ========== | ========== | ========== |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 1,210.00 | 51.00 | 41.66 | 37.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 189.00 | 75.00 | 70.00 | 65.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1,399.00 | 54.24 | 46.84 | 41.75 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 825.00 | 45.00 | 50.32 | 48.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 818.00 | 60.00 | 58.64 | 60.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1,643.00 | 52.47 | 53.50 | 53.97 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3,042.00 | 53.28 | 50.33 | 48.12 |
| ========== | 603-01185 | 18 In RCP (CIP) | | Lin Foot | ========== | ========== | ========== |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 9,596.00 | 45.00 | 55.18 | 35.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 603-01185 | 18 In RCP (CIP) | | Lin Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 2,119.00 | 45.00 | 74.77 | 65.21 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 11,715.00 | 45.00 | 63.80 | 49.17 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 44.00 | 75.00 | 79.94 | 62.50 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 1,331.00 | 40.00 | 42.94 | 33.80 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 70.00 | 80.00 | 88.04 | 84.45 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 141.00 | 50.00 | 73.53 | 69.40 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 2,841.00 | 45.00 | 42.50 | 38.60 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 4,427.00 | 44.51 | 44.89 | 39.10 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1,398.00 | 45.00 | 65.86 | 61.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 505.00 | 70.00 | 76.43 | 98.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 451.00 | 40.00 | 59.00 | 47.93 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 433.00 | 38.00 | 63.04 | 58.35 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 16.00 | 150.00 | 94.67 | 95.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 210.00 | 50.00 | 75.95 | 110.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 3,013.00 | 48.34 | 66.47 | 68.46 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 19,155.00 | 45.41 | 58.01 | 49.63 |
| ========== | 603-01240 | 24 In RCP | | Lin Foot | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 270.00 | 80.00 | 135.60 | 108.00 |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 40.00 | 59.50 | 79.96 | 54.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 310.00 | 77.35 | 126.04 | 101.03 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 760.00 | 59.00 | 52.67 | 42.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 760.00 | 59.00 | 52.67 | 42.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 410.00 | 65.00 | 82.99 | 72.40 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 603-01240 | 24 In RCP | | Lin Foot | | | |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 600.00 | 65.00 | 70.20 | 75.25 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1,010.00 | 65.00 | 76.53 | 74.51 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,080.00 | 64.65 | 74.31 | 66.73 |
| ========== | 603-01245 | 24 In RCP (CIP) | | Lin Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 6,624.00 | 50.00 | 66.42 | 48.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 445.00 | 60.00 | 89.64 | 86.80 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 7,069.00 | 50.63 | 70.89 | 56.22 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 146.00 | 55.00 | 86.41 | 91.88 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 115.00 | 90.00 | 118.74 | 75.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 20.00 | 65.00 | 178.42 | 320.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 741.00 | 65.00 | 64.56 | 55.87 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1,022.00 | 66.38 | 78.24 | 68.34 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1,831.00 | 60.00 | 77.06 | 74.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 100.00 | 80.00 | 120.70 | 131.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 355.00 | 60.00 | 63.72 | 59.99 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1,070.00 | 55.00 | 81.58 | 62.38 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 293.00 | 60.00 | 83.44 | 100.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 3,649.00 | 59.08 | 78.50 | 72.88 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 11,740.00 | 54.63 | 75.79 | 67.02 |
| ========== | 603-01300 | 30 In RCP | | Lin Foot | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 1,800.00 | 72.00 | 63.57 | 63.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1,800.00 | 72.00 | 63.57 | 63.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 603-01300 | 30 In RCP | | Lin Foot | | | |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 100.00 | 75.00 | 89.80 | 116.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 100.00 | 75.00 | 89.80 | 116.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,900.00 | 72.16 | 64.73 | 65.79 |
| ========== | 603-01305 | 30 In RCP (CIP) | | Lin Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 2,540.00 | 65.00 | 90.82 | 85.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 71.00 | 98.00 | 99.53 | 88.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 282.00 | 90.00 | 97.32 | 79.45 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 2,893.00 | 68.25 | 93.17 | 83.63 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 2,007.00 | 85.00 | 90.43 | 89.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1,361.00 | 90.00 | 103.59 | 116.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 389.00 | 85.00 | 88.43 | 82.50 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 3,757.00 | 86.81 | 93.91 | 98.11 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 6,650.00 | 78.74 | 93.71 | 95.09 |
| ========== | 603-01360 | 36 In RCP | | Lin Foot | | | |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 633.00 | 95.00 | 149.78 | 96.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 155.00 | 75.00 | 108.59 | 140.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 788.00 | 91.07 | 144.31 | 104.65 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 788.00 | 91.07 | 144.31 | 104.65 |
| ========== | 603-01365 | 36 In RCP (CIP) | | Lin Foot | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 645.00 | 110.00 | 107.04 | 89.16 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 645.00 | 110.00 | 107.04 | 89.16 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 603-01365 | 36 In RCP (CIP) | | Lin Foot | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 738.00 | 100.00 | 89.16 | 93.46 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 738.00 | 100.00 | 89.16 | 93.46 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 866.00 | 110.00 | 112.43 | 121.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 376.00 | 80.00 | 103.39 | 88.51 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 217.00 | 90.00 | 112.28 | 140.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1,459.00 | 99.29 | 109.94 | 115.45 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,842.00 | 101.91 | 104.75 | 103.77 |
| ========== | 603-01420 | 42 In RCP | | Lin Foot | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 281.00 | 106.00 | 99.86 | 85.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 281.00 | 106.00 | 99.86 | 85.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 38.00 | 100.00 | 134.20 | 180.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 38.00 | 100.00 | 134.20 | 180.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 319.00 | 105.29 | 103.33 | 96.32 |
| ========== | 603-01425 | 42 In RCP (CIP) | | Lin Foot | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 13.00 | 150.00 | 229.71 | 160.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 13.00 | 150.00 | 229.71 | 160.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 13.00 | 150.00 | 229.71 | 160.00 |
| ========== | 603-01480 | 48 In RCP | | Lin Foot | | | |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 176.00 | 275.00 | 343.89 | 182.77 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 176.00 | 275.00 | 343.89 | 182.77 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 176.00 | 275.00 | 343.89 | 182.77 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 603-01485 | 48 In RCP (CIP) | | Lin Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 1,368.00 | 110.00 | 184.46 | 140.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 236.00 | 145.00 | 169.88 | 130.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1,604.00 | 115.15 | 178.51 | 135.92 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 181.00 | 120.00 | 146.88 | 180.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 181.00 | 120.00 | 146.88 | 180.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,785.00 | 115.64 | 170.97 | 146.43 |
| ========== | 603-01545 | 54 In RCP (CIP) | | Lin Foot | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 233.00 | 200.00 | 200.57 | 179.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 233.00 | 200.00 | 200.57 | 179.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 233.00 | 200.00 | 200.57 | 179.00 |
| ========== | 603-01665 | 66 In RCP (CIP) | | Lin Foot | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 422.00 | 230.00 | 255.86 | 240.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 422.00 | 230.00 | 255.86 | 240.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 422.00 | 230.00 | 255.86 | 240.00 |
| ========== | 603-01725 | 72 In RCP (CIP) | | Lin Foot | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 2,185.00 | 300.00 | 297.86 | 270.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2,185.00 | 300.00 | 297.86 | 270.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,185.00 | 300.00 | 297.86 | 270.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 603-02185 | 23x14 In RCP (CIP) | | Lin Foot | | | |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 303.00 | 75.00 | 58.61 | 67.59 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 303.00 | 75.00 | 58.61 | 67.59 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 93.00 | 70.00 | 102.83 | 65.28 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 93.00 | 70.00 | 102.83 | 65.28 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 396.00 | 73.83 | 68.99 | 67.05 |
| ========== | 603-02240 | 30x19 In RCP | | Lin Foot | | | |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 86.00 | 110.00 | 145.83 | 132.50 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 86.00 | 110.00 | 145.83 | 132.50 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 86.00 | 110.00 | 145.83 | 132.50 |
| ========== | 603-02245 | 30x19 In RCP (CIP) | | Lin Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 1,296.00 | 60.00 | 105.25 | 120.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1,296.00 | 60.00 | 105.25 | 120.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 47.00 | 100.00 | 85.04 | 102.30 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 287.00 | 85.00 | 86.32 | 100.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 334.00 | 87.11 | 86.01 | 100.32 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,630.00 | 65.56 | 98.65 | 110.01 |
| ========== | 603-02305 | 38x24 In RCP (CIP) | | Lin Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 920.00 | 110.00 | 124.46 | 105.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 603-02305 | 38x24 In RCP (CIP) | | Lin Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 920.00 | 110.00 | 124.46 | 105.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 117.00 | 170.00 | 154.86 | 245.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 523.00 | 110.00 | 122.72 | 139.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 256.00 | 110.00 | 103.01 | 95.58 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 896.00 | 117.83 | 120.16 | 140.44 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,816.00 | 113.87 | 121.34 | 133.20 |
| ========== | 603-02360 | 45x29 In RCP | | Lin Foot | | | |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 182.00 | 200.00 | 160.83 | 138.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 182.00 | 200.00 | 160.83 | 138.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 182.00 | 200.00 | 160.83 | 138.00 |
| ========== | 603-02365 | 45x29 In RCP (CIP) | | Lin Foot | | | |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 198.00 | 200.00 | 116.64 | 101.86 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 198.00 | 200.00 | 116.64 | 101.86 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 198.00 | 200.00 | 116.64 | 101.86 |
| ========== | 603-02485 | 60x30 In. RCP (CIP) | | Lin Foot | | | |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 100.00 | 180.00 | 407.59 | 280.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 100.00 | 180.00 | 407.59 | 280.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 100.00 | 180.00 | 407.59 | 280.00 |
| ========== | 603-02665 | 83X53 In RCP (CIP) | | Lin Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 2,116.00 | 300.00 | 381.03 | 210.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 603-02665 | 83X53 In RCP (CIP) | | Lin Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 2,116.00 | 300.00 | 381.03 | 210.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,116.00 | 300.00 | 381.03 | 210.00 |
| ========== | 603-05012 | 12 In RCES | | Each | | | |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 2.00 | 600.00 | 770.73 | 800.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 2.00 | 600.00 | 770.73 | 800.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 600.00 | 770.73 | 800.00 |
| ========== | 603-05018 | 18 In RCES | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 12.00 | 1200.00 | 1125.82 | 2100.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 12.00 | 1200.00 | 1125.82 | 2100.00 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 2.00 | 1100.00 | 1906.92 | 1953.84 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 2.00 | 800.00 | 609.68 | 484.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 1.00 | 1000.00 | 741.59 | 744.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 19.00 | 500.00 | 547.93 | 456.12 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 24.00 | 595.83 | 699.35 | 589.24 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 4.00 | 600.00 | 1406.16 | 1900.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 4.00 | 600.00 | 1277.30 | 1395.67 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1.00 | 1000.00 | 827.57 | 600.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 603-05018 | 18 In RCES | | Each | | | |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 4.00 | 1000.00 | 659.43 | 540.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 5.00 | 1000.00 | 686.80 | 552.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 45.00 | 802.22 | 820.00 | 824.74 |
| ========== | 603-05024 | 24 In RCES | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 4.00 | 1275.00 | 1360.86 | 2300.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 2.00 | 895.00 | 1024.04 | 995.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 6.00 | 1148.33 | 1155.84 | 1430.00 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 4.00 | 1350.00 | 2144.02 | 1584.19 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 2.00 | 1500.00 | 1202.96 | 1400.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 3.00 | 900.00 | 627.88 | 540.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 2.00 | 900.00 | 1003.89 | 790.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 2.00 | 600.00 | 842.37 | 904.12 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 13.00 | 1084.62 | 1300.81 | 1088.08 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 4.00 | 700.00 | 1004.35 | 1070.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 4.00 | 700.00 | 944.44 | 1016.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 4.00 | 1150.00 | 739.94 | 590.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 4.00 | 1150.00 | 739.94 | 590.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 27.00 | 1051.48 | 1118.59 | 1035.00 |
| ========== | 603-05030 | 30 In RCES | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 12.00 | 1600.00 | 1523.03 | 2500.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 603-05030 | 30 In RCES | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 12.00 | 1600.00 | 1523.03 | 2500.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1.00 | 2800.00 | 1434.58 | 1031.22 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 1.00 | 2800.00 | 1434.58 | 1031.22 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 13.00 | 1692.31 | 1502.81 | 2132.81 |
| ========== | 603-05036 | 36 In RCES | | Each | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1.00 | 800.00 | 1169.03 | 1076.82 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 1.00 | 800.00 | 1169.03 | 1076.82 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 3.00 | 1500.00 | 1594.98 | 2000.00 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 3.00 | 1500.00 | 1594.98 | 2000.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1.00 | 1300.00 | 1152.86 | 900.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 1.00 | 1800.00 | 1312.93 | 1739.71 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 2.00 | 1500.00 | 1177.63 | 1100.00 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 4.00 | 1525.00 | 1205.17 | 1209.93 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 8.00 | 1425.00 | 1309.43 | 1489.57 |
| ========== | 603-05042 | 42 In RCES | | Each | | | |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 1.00 | 850.00 | 1600.71 | 2000.00 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 1.00 | 850.00 | 1600.71 | 2000.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 1.00 | 850.00 | 1600.71 | 2000.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 603-05048 | 48 In RCES | | Each | | | |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 2.00 | 1800.00 | 2015.57 | 1800.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 1800.00 | 2015.57 | 1800.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 1800.00 | 2038.62 | 1998.33 |
| ========== | 603-05124 | 30x19 In RCES | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 4.00 | 1500.00 | 1533.84 | 2500.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 4.00 | 1500.00 | 1533.84 | 2500.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 1.00 | 1500.00 | 993.13 | 1936.31 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 1500.00 | 993.13 | 1936.31 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 5.00 | 1500.00 | 1279.39 | 2218.16 |
| ========== | 603-05136 | 45x29 In RCES | | Each | | | |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 2.00 | 2000.00 | 1567.57 | 1959.17 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 2000.00 | 1567.57 | 1959.17 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 2000.00 | 1567.57 | 1959.17 |
| ========== | 603-10120 | 12 In CSP | | Lin Foot | | | |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 86.00 | 50.00 | 56.82 | 30.63 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 163.00 | 50.00 | 68.50 | 44.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 249.00 | 50.00 | 65.46 | 39.38 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 249.00 | 50.00 | 65.46 | 39.38 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 603-10180 | 18 In CSP | | Lin Foot | ========== | ========== | ========== |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 338.00 | 50.00 | 61.72 | 51.60 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 48.00 | 45.00 | 51.42 | 89.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 386.00 | 49.38 | 59.62 | 56.25 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 16.00 | 70.00 | 113.75 | 49.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 16.00 | 70.00 | 113.75 | 49.00 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 62.00 | 80.00 | 120.90 | 112.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 62.00 | 80.00 | 120.90 | 112.00 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 210.00 | 7.00 | 43.29 | 19.22 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 46.00 | 110.00 | 118.25 | 59.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 347.00 | 45.00 | 45.67 | 62.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 603.00 | 36.72 | 46.89 | 46.87 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,067.00 | 44.32 | 53.36 | 54.08 |
| ========== | 603-10240 | 24 In CSP | | Lin Foot | ========== | ========== | ========== |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 30.00 | 70.00 | 153.50 | 44.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 861.00 | 80.00 | 101.98 | 81.40 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 5.00 | 100.00 | 83.79 | 47.07 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 896.00 | 79.78 | 102.37 | 79.96 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 111.00 | 50.00 | 107.63 | 105.79 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 20.00 | 90.00 | 163.15 | 170.00 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 4.00 | 100.00 | 213.67 | 190.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 135.00 | 57.41 | 116.46 | 117.80 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 603-10240 | 24 In CSP | | Lin Foot | | | |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 94.00 | 120.00 | 97.80 | 80.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 12.00 | 110.00 | 109.50 | 141.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 106.00 | 118.87 | 99.50 | 86.91 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,137.00 | 80.77 | 96.89 | 79.69 |
| ========== | 603-10300 | 30 In CSP | | Lin Foot | | | |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 3.00 | 100.00 | 284.27 | 296.86 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 40.00 | 60.00 | 98.33 | 105.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 43.00 | 62.79 | 111.31 | 118.39 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 50.00 | 65.00 | 121.41 | 117.05 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 50.00 | 65.00 | 121.41 | 117.05 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 93.00 | 63.98 | 117.88 | 117.67 |
| ========== | 603-10360 | 36 In CSP | | Lin Foot | | | |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 219.00 | 100.00 | 126.06 | 86.60 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 6.00 | 80.00 | 170.50 | 106.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 225.00 | 99.47 | 126.95 | 87.12 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 78.00 | 80.00 | 81.16 | 78.01 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 78.00 | 80.00 | 81.16 | 78.01 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 303.00 | 94.46 | 133.40 | 104.02 |
| ========== | 603-10480 | 48 In CSP | | Lin Foot | | | |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 30.00 | 120.00 | 143.33 | 142.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 603-10480 | 48 In CSP | | Lin Foot | ========== | ========== | ========== |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 86.00 | 200.00 | 284.92 | 138.84 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 116.00 | 179.31 | 236.28 | 139.66 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 234.00 | 120.00 | 113.58 | 180.00 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 234.00 | 120.00 | 113.58 | 180.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 350.00 | 139.66 | 127.16 | 166.63 |
| ========== | 603-10900 | 90 In CSP | | Lin Foot | ========== | ========== | ========== |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 152.00 | 400.00 | 199.06 | 158.16 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 152.00 | 400.00 | 199.06 | 158.16 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 152.00 | 400.00 | 199.06 | 158.16 |
| ========== | 603-15015 | 15 In Equiv CSPA | | Lin Foot | ========== | ========== | ========== |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 30.00 | 70.00 | 86.75 | 65.00 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 30.00 | 70.00 | 86.75 | 65.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 30.00 | 70.00 | 86.75 | 65.00 |
| ========== | 603-15018 | 18 In Equiv CSPA | | Lin Foot | ========== | ========== | ========== |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 38.00 | 65.00 | 159.25 | 170.00 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 38.00 | 65.00 | 159.25 | 170.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 38.00 | 65.00 | 159.25 | 170.00 |
| ========== | 603-15030 | 30 In Equiv CSPA | | Lin Foot | ========== | ========== | ========== |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 87.00 | 80.00 | 127.65 | 179.08 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 87.00 | 80.00 | 127.65 | 179.08 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 87.00 | 80.00 | 127.65 | 179.08 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 603-15036 | 36 In Equiv CSPA | | Lin Foot | | | |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 50.00 | 105.00 | 196.30 | 210.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 50.00 | 105.00 | 196.30 | 210.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 50.00 | 105.00 | 196.30 | 210.00 |
| ========== | 603-15042 | 42 In Equiv CSPA | | Lin Foot | | | |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 93.00 | 160.00 | 167.19 | 230.25 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 93.00 | 160.00 | 167.19 | 230.25 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 93.00 | 160.00 | 167.19 | 230.25 |
| ========== | 603-15084 | 84 In Equiv CSPA | | Lin Foot | | | |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 24.00 | 100.00 | 319.52 | 355.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 24.00 | 100.00 | 319.52 | 355.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 24.00 | 100.00 | 319.52 | 355.00 |
| ========== | 603-30018 | 18 In SES | | Each | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 1.00 | 500.00 | 299.46 | 255.00 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 2.00 | 300.00 | 356.46 | 420.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 3.00 | 366.67 | 344.07 | 365.00 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 2.00 | 500.00 | 486.00 | 400.01 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 2.00 | 500.00 | 486.00 | 400.01 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 3.00 | 385.00 | 625.70 | 270.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 3.00 | 385.00 | 625.70 | 270.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 8.00 | 406.88 | 450.71 | 338.13 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 603-30024 | 24 In SES | | Each | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 1.00 | 500.00 | 504.57 | 600.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1.00 | 500.00 | 306.68 | 282.14 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 16.00 | 300.00 | 352.69 | 145.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 1.00 | 250.00 | 422.66 | 532.12 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 17.00 | 297.06 | 354.81 | 167.77 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 10.00 | 300.00 | 366.54 | 647.70 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 2.00 | 415.00 | 859.50 | 330.00 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 1.00 | 150.00 | 560.00 | 475.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 13.00 | 306.15 | 440.70 | 585.54 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 3.00 | 450.00 | 487.08 | 449.27 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 3.00 | 500.00 | 454.46 | 380.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 2.00 | 320.00 | 335.29 | 235.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 8.00 | 436.25 | 439.96 | 369.73 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 39.00 | 333.85 | 365.78 | 323.06 |
| ========== | 603-30030 | 30 In SES | | Each | | | |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 1.00 | 600.00 | 512.90 | 712.48 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 2.00 | 600.00 | 809.71 | 815.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 3.00 | 600.00 | 710.77 | 780.83 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3.00 | 600.00 | 710.77 | 780.83 |
| ========== | 603-30036 | 36 In SES | | Each | | | |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 3.00 | 500.00 | 670.72 | 425.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 3.00 | 500.00 | 670.72 | 425.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 603-30036 | 36 In SES | | Each | | | |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 1.00 | 700.00 | 788.47 | 795.84 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 700.00 | 788.47 | 795.84 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4.00 | 550.00 | 667.15 | 528.47 |
| ========== | 603-30048 | 48 In SES | | Each | | | |
| C0241-055 | | SH 24 MP 148-152 | 05/26/11 | 1.00 | 1400.00 | 2182.23 | 2000.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 1.00 | 1400.00 | 2182.23 | 2000.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 2.00 | 1000.00 | 1733.87 | 1500.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 1000.00 | 1733.87 | 1500.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3.00 | 1133.33 | 1797.92 | 1666.67 |
| ========== | 603-31318 | 18 In Equiv Arch SES | | Each | | | |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 2.00 | 395.00 | 770.30 | 260.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 2.00 | 395.00 | 770.30 | 260.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 395.00 | 770.30 | 260.00 |
| ========== | 603-31330 | 30 In Equiv Arch SES | | Each | | | |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 2.00 | 500.00 | 917.70 | 1176.81 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 2.00 | 500.00 | 917.70 | 1176.81 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 500.00 | 917.70 | 1176.81 |
| ========== | 603-31336 | 36 In Equiv Arch SES | | Each | | | |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 2.00 | 525.00 | 1388.90 | 600.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 2.00 | 525.00 | 1388.90 | 600.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 525.00 | 1388.90 | 600.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 603-31342 | 42 In Equiv Arch SES | | Each | | | |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 2.00 | 800.00 | 2020.03 | 1893.13 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2.00 | 800.00 | 2020.03 | 1893.13 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 800.00 | 2020.03 | 1893.13 |
| ========== | 603-33030 | 30 In Pipe Safety End Treat | | Each | | | |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 2.00 | 2100.00 | 1620.67 | 1600.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 2.00 | 2100.00 | 1620.67 | 1600.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 2100.00 | 1620.67 | 1600.00 |
| ========== | 603-33048 | 48 In Pipe Safety End Treat | | Each | | | |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 4.00 | 3100.00 | 2232.78 | 2400.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 4.00 | 3100.00 | 2232.78 | 2400.00 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 2.00 | 4000.00 | 2177.13 | 2384.26 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2.00 | 4000.00 | 2177.13 | 2384.26 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 6.00 | 3400.00 | 2227.21 | 2394.75 |
| ========== | 603-50004 | 4 In Plastic Pipe | | Lin Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 3,004.00 | 15.00 | 19.51 | 12.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 3,004.00 | 15.00 | 19.51 | 12.00 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 16.00 | 20.00 | 21.33 | 20.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 603-50004 | 4 In Plastic Pipe | | Lin Foot | | | |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 64.00 | 20.00 | 26.47 | 18.30 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 80.00 | 20.00 | 25.90 | 18.64 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 3,084.00 | 15.13 | 19.89 | 12.64 |
| ========== | 603-50012 | 12 In Plastic Pipe | | Lin Foot | | | |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 308.00 | 45.00 | 32.51 | 49.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 308.00 | 45.00 | 32.51 | 49.00 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 70.00 | 50.00 | 42.71 | 12.00 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 70.00 | 50.00 | 42.71 | 12.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 79.00 | 50.00 | 106.45 | 110.00 |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 80.00 | 60.00 | 73.50 | 67.00 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 159.00 | 55.03 | 96.95 | 88.36 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 537.00 | 48.62 | 43.19 | 55.83 |
| ========== | 603-50015 | 15 In Plastic Pipe | | Lin Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 2,874.00 | 45.00 | 45.24 | 35.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 2,874.00 | 45.00 | 45.24 | 35.00 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 20.00 | 45.00 | 31.83 | 30.00 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 20.00 | 45.00 | 31.83 | 30.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 603-50015 | 15 In Plastic Pipe | | Lin Foot | | | |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 668.00 | 40.00 | 56.00 | 75.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 668.00 | 40.00 | 56.00 | 75.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 79.00 | 60.00 | 81.72 | 65.39 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 79.00 | 60.00 | 81.72 | 65.39 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3,641.00 | 44.41 | 51.42 | 53.52 |
| ========== | 603-50018 | 18 In Plastic Pipe | | Lin Foot | | | |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 60.00 | 50.00 | 48.00 | 46.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 103.00 | 50.00 | 101.57 | 73.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 163.00 | 50.00 | 89.49 | 63.06 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 163.00 | 50.00 | 89.49 | 63.06 |
| ========== | 603-50030 | 30 In Plastic Pipe | | Lin Foot | | | |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 137.00 | 300.00 | 838.24 | 925.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 137.00 | 300.00 | 838.24 | 925.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 141.00 | 55.00 | 104.29 | 96.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 141.00 | 55.00 | 104.29 | 96.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 278.00 | 175.74 | 490.46 | 504.54 |
| ========== | 603-61120 | 12 In Flexible Pipe | | Lin Foot | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 105.00 | 35.00 | 100.28 | 130.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 105.00 | 35.00 | 100.28 | 130.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 603-61120 | 12 In Flexible Pipe | | Lin Foot | | | |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 144.00 | 40.00 | 67.50 | 60.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 144.00 | 40.00 | 67.50 | 60.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 249.00 | 37.89 | 90.00 | 89.52 |
| ========== | 603-61240 | 24 In Flexible Pipe | | Lin Foot | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 688.00 | 50.00 | 106.90 | 140.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 688.00 | 50.00 | 106.90 | 140.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 688.00 | 50.00 | 106.90 | 140.00 |
| ========== | 603-70703 | 7x3 Ft CBC (Precast) | | Lin Foot | | | |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 172.00 | 950.00 | 612.33 | 546.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 172.00 | 950.00 | 612.33 | 546.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 96.00 | 500.00 | 714.20 | 800.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 96.00 | 500.00 | 714.20 | 800.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 268.00 | 788.81 | 661.43 | 636.99 |
| ========== | 603-70704 | 7x4 Ft CBC (Precast) | | Lin Foot | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1,107.00 | 500.00 | 397.86 | 400.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1,107.00 | 500.00 | 397.86 | 400.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,107.00 | 500.00 | 397.86 | 400.00 |
| ========== | 603-70804 | 8x4 Ft CBC (Precast) | | Lin Foot | | | |
| C0091-038 | | SH 9 MM 81.9 BLUE RIVER EMERG | 08/24/11 | 56.70 | 500.00 | 1115.47 | 694.23 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 56.70 | 500.00 | 1115.47 | 694.23 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 56.70 | 500.00 | 1115.47 | 694.23 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 603-70805 | 8x5 Ft CBC (Precast) | | Lin Foot | | | |
| C0091-038 | | SH 9 MM 81.9 BLUE RIVER EMERG | 08/24/11 | 56.70 | 500.00 | 1097.02 | 683.17 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 56.70 | 500.00 | 1097.02 | 683.17 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 56.70 | 500.00 | 1097.02 | 683.17 |
| ========== | 603-83008 | 8 In Sewer Pipe | | Lin Foot | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1,314.00 | 95.00 | 48.98 | 37.50 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1,314.00 | 95.00 | 48.98 | 37.50 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,314.00 | 95.00 | 48.98 | 37.50 |
| ========== | 603-83009 | 8 In Sewer Pipe (Spec) | | Lin Foot | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 232.00 | 100.00 | 78.83 | 62.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 232.00 | 100.00 | 78.83 | 62.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 232.00 | 100.00 | 78.83 | 62.00 |
| ========== | 604-00305 | Inlet Ty C (5 Ft) | | Each | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 2.00 | 3000.00 | 2656.92 | 2200.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 16.00 | 2500.00 | 2461.93 | 2100.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 18.00 | 2555.56 | 2504.32 | 2133.33 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 1.00 | 2500.00 | 2868.00 | 2832.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 1.00 | 2500.00 | 2480.06 | 2300.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 4.00 | 4000.00 | 2808.96 | 2030.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 1.00 | 2500.00 | 2571.83 | 2300.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 1.00 | 3000.00 | 3031.67 | 1620.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 604-00305 | Inlet Ty C (5 Ft) | | Each | | | |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 1.00 | 2500.00 | 3164.25 | 2100.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 4.00 | 3000.00 | 2419.84 | 2052.05 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 13.00 | 3153.85 | 2733.29 | 2114.30 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 3.00 | 2750.00 | 2467.21 | 2000.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 3.00 | 2750.00 | 2876.61 | 2652.36 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 3.00 | 3000.00 | 2777.99 | 2398.92 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 11.00 | 3000.00 | 2508.57 | 1660.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 3.00 | 2300.00 | 2584.74 | 2531.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 4.00 | 2500.00 | 2398.22 | 2012.15 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 2.00 | 3000.00 | 2459.62 | 2700.00 |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 1.00 | 3200.00 | 8500.00 | 11000.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 24.00 | 2837.50 | 2597.45 | 2395.77 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 58.00 | 2816.38 | 2661.75 | 2346.81 |
| ========== | 604-00310 | Inlet Ty C (10 Ft) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 4.00 | 3000.00 | 3552.26 | 2800.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 4.00 | 3000.00 | 3552.26 | 2800.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 1.00 | 4000.00 | 3384.14 | 2700.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1.00 | 4000.00 | 3384.14 | 2700.00 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 1.00 | 2000.00 | 7166.67 | 10400.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1.00 | 2000.00 | 7166.67 | 10400.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 604-00310 | Inlet Ty C (10 Ft) | | Each | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 2.00 | 4000.00 | 3634.29 | 2940.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 2.00 | 2500.00 | 2869.91 | 2755.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1.00 | 3500.00 | 3085.34 | 2877.37 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 5.00 | 3300.00 | 3258.18 | 2853.47 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 11.00 | 3136.36 | 3557.28 | 3770.92 |
| ========== | 604-00315 | Inlet Ty C (15 Ft) | | Each | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 1.00 | 4500.00 | 5296.12 | 4200.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 1.00 | 4500.00 | 5296.12 | 4200.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 2.00 | 5000.00 | 4217.14 | 3400.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1.00 | 4000.00 | 3868.12 | 3838.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 3.00 | 4666.67 | 4125.29 | 3546.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4.00 | 4625.00 | 4406.29 | 3709.50 |
| ========== | 604-00350 | Inlet Ty C (Spec) | | Each | | | |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 1.00 | 3000.00 | 3922.48 | 4700.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 2.00 | 4000.00 | 5628.29 | 6200.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 3.00 | 3666.67 | 4835.79 | 5262.87 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3.00 | 3666.67 | 4835.79 | 5262.87 |
| ========== | 604-00505 | Inlet Ty D (5 Ft) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 4.00 | 3500.00 | 3557.72 | 2900.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 604-00505 | Inlet Ty D (5 Ft) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 4.00 | 3500.00 | 3557.72 | 2900.00 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 1.00 | 3500.00 | 4018.96 | 3950.00 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 1.00 | 3500.00 | 3746.67 | 3090.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 1.00 | 4000.00 | 4197.00 | 3230.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 2.00 | 5000.00 | 3226.09 | 3032.36 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 5.00 | 4200.00 | 3506.70 | 3240.17 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 3.00 | 2000.00 | 3675.00 | 3725.00 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 1.00 | 3500.00 | 4376.87 | 3200.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 4.00 | 2375.00 | 3925.67 | 3593.75 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1.00 | 4000.00 | 3534.29 | 3700.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1.00 | 3000.00 | 3369.51 | 3018.22 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 1.00 | 4500.00 | 3483.96 | 3600.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 3.00 | 3833.33 | 3454.31 | 3439.41 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 16.00 | 3500.00 | 3578.72 | 3351.63 |
| ========== | 604-00510 | Inlet Ty D (10 Ft) | | Each | | | |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 3.00 | 6000.00 | 7170.84 | 10191.68 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1.00 | 8000.00 | 4011.72 | 3768.86 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 4.00 | 6500.00 | 5591.28 | 8585.98 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 2.00 | 4500.00 | 4431.43 | 4100.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 4500.00 | 4431.43 | 4100.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 6.00 | 5833.33 | 4966.74 | 7090.65 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 604-00550 | Inlet Ty D (Spec) | | Each | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 2.00 | 10000.00 | 9358.32 | 8300.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 2.00 | 10000.00 | 9358.32 | 8300.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 10000.00 | 9358.32 | 8300.00 |
| ========== | 604-13005 | Inlet Ty 13 (5 Ft) | | Each | | | |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 1.00 | 3000.00 | 2743.35 | 2285.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 1.00 | 3000.00 | 2743.35 | 2285.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1.00 | 4000.00 | 2642.86 | 2600.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 4000.00 | 2642.86 | 2600.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 3500.00 | 2696.45 | 2442.50 |
| ========== | 604-13010 | Inlet Ty 13 (10 Ft) | | Each | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 2.00 | 3000.00 | 3448.13 | 2883.27 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 2.00 | 3000.00 | 3448.13 | 2883.27 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 1.00 | 3750.00 | 3697.07 | 3000.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 1.00 | 3750.00 | 3697.07 | 3000.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1.00 | 4500.00 | 3610.00 | 2700.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 1.00 | 3750.00 | 3475.51 | 4792.01 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 4125.00 | 3538.27 | 3746.01 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 5.00 | 3600.00 | 3533.86 | 3251.71 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 604-13015 | Inlet Ty 13 (15 Ft) | | Each | | | |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 1.00 | 4500.00 | 4504.88 | 3100.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 1.00 | 4500.00 | 4504.88 | 3100.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 4500.00 | 4504.88 | 3100.00 |
| ========== | 604-16005 | Inlet Ty 16 (5 Ft) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 4.00 | 3000.00 | 3316.57 | 2800.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 2.00 | 3500.00 | 2885.68 | 2828.25 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 6.00 | 3166.67 | 3040.80 | 2818.83 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1.00 | 4000.00 | 2992.86 | 2750.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 7.00 | 2500.00 | 3060.45 | 2732.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1.00 | 3000.00 | 3073.87 | 2716.40 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 9.00 | 2722.22 | 3053.13 | 2732.27 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 15.00 | 2900.00 | 3049.02 | 2753.91 |
| ========== | 604-16010 | Inlet Ty 16 (10 Ft) | | Each | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 4.00 | 4000.00 | 3878.46 | 2979.79 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 4.00 | 4000.00 | 3878.46 | 2979.79 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1.00 | 4250.00 | 3624.29 | 2900.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 4250.00 | 3624.29 | 2900.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 5.00 | 4050.00 | 3832.84 | 2963.83 |
| ========== | 604-16015 | Inlet Ty 16 (15 Ft) | | Each | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 1.00 | 4500.00 | 4762.16 | 4483.23 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 1.00 | 4500.00 | 4762.16 | 4483.23 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 604-16015 | Inlet Ty 16 (15 Ft) | | Each | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 2.00 | 4250.00 | 4335.71 | 3600.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 4250.00 | 4335.71 | 3600.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3.00 | 4333.33 | 4490.79 | 3894.41 |
| ========== | 604-16050 | Inlet Ty 16 (S) (Spec) | | Each | | | |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 1.00 | 2500.00 | 3546.75 | 2400.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1.00 | 2500.00 | 3546.75 | 2400.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 2500.00 | 3546.75 | 2400.00 |
| ========== | 604-16505 | Inlet Ty 16 (D) (5 Ft) | | Each | | | |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 3.00 | 3500.00 | 4574.81 | 3600.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 3.00 | 3500.00 | 4574.81 | 3600.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3.00 | 3500.00 | 4574.81 | 3600.00 |
| ========== | 604-16510 | Inlet Ty 16 (D) (10 Ft) | | Each | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 4.00 | 5000.00 | 5375.24 | 4630.57 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 4.00 | 5000.00 | 5375.24 | 4630.57 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4.00 | 5000.00 | 5375.24 | 4630.57 |
| ========== | 604-16515 | Inlet Ty 16 (D) (15 Ft) | | Each | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 1.00 | 6000.00 | 6873.41 | 5776.77 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1.00 | 6000.00 | 6873.41 | 5776.77 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 6000.00 | 6873.41 | 5776.77 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 604-16605 | Inlet Ty 16 (T) (5 Ft) | | Each | | | |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1.00 | 5800.00 | 5546.96 | 6438.86 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 5800.00 | 5546.96 | 6438.86 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 5800.00 | 5546.96 | 6438.86 |
| ========== | 604-16610 | Inlet Ty 16 (T) (10 Ft) | | Each | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 1.00 | 7000.00 | 7424.10 | 5803.84 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 1.00 | 7000.00 | 7424.10 | 5803.84 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 2.00 | 7000.00 | 6308.05 | 5800.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 7000.00 | 6308.05 | 5800.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3.00 | 7000.00 | 6804.07 | 5801.28 |
| ========== | 604-19000 | Inlet Spec | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 4.00 | 4000.00 | 5979.04 | 3400.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 4.00 | 4000.00 | 5979.04 | 3400.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 1.00 | 3500.00 | 4929.17 | 3700.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 1.00 | 3500.00 | 4929.17 | 3700.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 1.00 | 5000.00 | 2737.00 | 1600.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 1.00 | 5000.00 | 2737.00 | 1600.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 6.00 | 4083.33 | 4853.57 | 2900.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 604-19105 | Inlet Ty R L5 (5 Ft) | | Each | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 2.00 | 3500.00 | 4453.77 | 4615.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 2.00 | 3500.00 | 4453.77 | 4615.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 1.00 | 3500.00 | 4323.17 | 3000.00 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 1.00 | 3500.00 | 4323.17 | 3000.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 2.00 | 4000.00 | 3637.03 | 4000.00 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 2.00 | 4000.00 | 3637.03 | 4000.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 2.00 | 3300.00 | 3408.57 | 3900.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 4.00 | 3000.00 | 3766.84 | 4819.59 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 6.00 | 3100.00 | 3657.80 | 4513.06 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 11.00 | 3372.73 | 3820.91 | 4300.76 |
| ========== | 604-19110 | Inlet Ty R L5 (10 Ft) | | Each | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 1.00 | 5000.00 | 6455.93 | 7580.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 1.00 | 5000.00 | 6455.93 | 7580.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 12.00 | 4000.00 | 4382.86 | 4330.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 2.00 | 3250.00 | 5053.43 | 5260.80 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 14.00 | 3892.86 | 4490.15 | 4462.97 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 15.00 | 3966.67 | 4583.76 | 4670.77 |
| ========== | 604-19115 | Inlet Ty R L5 (15 Ft) | | Each | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1.00 | 5500.00 | 5442.86 | 4700.00 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 1.00 | 5500.00 | 5442.86 | 4700.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 1.00 | 5500.00 | 5442.86 | 4700.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 604-19205 | Inlet Ty R L10 (5 Ft) | | Each | | | |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 1.00 | 4500.00 | 6492.00 | 4700.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1.00 | 3500.00 | 4933.91 | 4652.67 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 2.00 | 4000.00 | 5712.95 | 4676.34 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 5.00 | 4500.00 | 4890.58 | 5800.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 5.00 | 4500.00 | 4890.58 | 5800.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 8.00 | 4500.00 | 4910.00 | 5100.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 8.00 | 4500.00 | 4910.00 | 5100.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 15.00 | 4433.33 | 5008.39 | 5276.84 |
| ========== | 604-19210 | Inlet Ty R L10 (10 Ft) | | Each | | | |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 1.00 | 5200.00 | 7155.50 | 4900.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 5.00 | 4500.00 | 6382.79 | 5988.53 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 6.00 | 4616.67 | 6511.58 | 5807.11 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 2.00 | 5500.00 | 6436.05 | 6975.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 2.00 | 5500.00 | 6436.05 | 6975.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1.00 | 6200.00 | 5592.86 | 4829.15 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 6200.00 | 5592.86 | 4829.15 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 9.00 | 4988.89 | 6361.48 | 5957.98 |
| ========== | 604-19215 | Inlet Ty R L10 (15 Ft) | | Each | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1.00 | 5500.02 | 8980.52 | 7710.43 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 1.00 | 5500.02 | 8980.52 | 7710.43 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 604-19215 | Inlet Ty R L10 (15 Ft) | | Each | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 2.00 | 7000.00 | 8014.29 | 7400.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 7000.00 | 8014.29 | 7400.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3.00 | 6500.01 | 8304.16 | 7503.48 |
| ========== | 604-19305 | Inlet Ty R L15 (5 Ft) | | Each | | | |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 2.00 | 5500.00 | 6755.72 | 7300.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 2.00 | 5500.00 | 6755.72 | 7300.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 2.00 | 7500.00 | 6267.14 | 6200.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1.00 | 5000.00 | 6461.98 | 5885.52 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 3.00 | 6666.67 | 6337.99 | 6095.17 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 5.00 | 6200.00 | 6468.53 | 6577.10 |
| ========== | 604-19310 | Inlet Ty R L15 (10 Ft) | | Each | | | |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 1.00 | 5500.00 | 10075.16 | 10000.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1.00 | 5500.00 | 10075.16 | 10000.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 10.00 | 8000.00 | 8428.57 | 8200.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 10.00 | 8000.00 | 8428.57 | 8200.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 11.00 | 7772.73 | 8538.34 | 8363.64 |
| ========== | 604-19315 | Inlet Ty R L15 (15 Ft) | | Each | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 3.00 | 9500.00 | 11485.71 | 10000.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 3.00 | 9500.00 | 11485.71 | 10000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3.00 | 9500.00 | 11485.71 | 10000.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 604-19405 | Inlet Ty R Spec (5 Ft) | | Each | | | |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 1.00 | 6300.00 | 5185.29 | 3435.00 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 1.00 | 6300.00 | 5185.29 | 3435.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 6300.00 | 5185.29 | 3435.00 |
| ========== | 604-19410 | Inlet Ty R Spec (10 Ft) | | Each | | | |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 2.00 | 7300.00 | 6372.72 | 4030.00 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 2.00 | 7300.00 | 6372.72 | 4030.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 7300.00 | 6372.72 | 4030.00 |
| ========== | 604-19415 | Inlet Ty R Spec (15 Ft) | | Each | | | |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 1.00 | 8500.00 | 7763.95 | 6690.00 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 1.00 | 8500.00 | 7763.95 | 6690.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 8500.00 | 7763.95 | 6690.00 |
| ========== | 604-19510 | Inlet Ty R L20 (10 Ft) | | Each | | | |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 2.00 | 6000.00 | 11887.66 | 15000.00 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 2.00 | 6000.00 | 11887.66 | 15000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 6000.00 | 11887.66 | 15000.00 |
| ========== | 604-20000 | Outlet Structure | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 4.00 | 15000.00 | 28315.85 | 20000.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 4.00 | 15000.00 | 28315.85 | 20000.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 604-20000 | Outlet Structure | | Each | | | |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 1.00 | 20000.00 | 8955.07 | 10395.33 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1.00 | 8000.00 | 6907.09 | 5533.40 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 14000.00 | 7931.08 | 7964.37 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 6.00 | 14666.67 | 15269.60 | 11976.24 |
| ========== | 604-20010 | Settling Basin | | Each | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 2.00 | 80000.00 | 69585.71 | 77800.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 80000.00 | 69585.71 | 77800.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 80000.00 | 69585.71 | 77800.00 |
| ========== | 604-25000 | Vane Grate Inlet Spec | | Each | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 4.00 | 4000.00 | 4309.16 | 1568.84 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 4.00 | 4000.00 | 4309.16 | 1568.84 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 2.00 | 3308.00 | 3427.37 | 6700.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 4.00 | 5000.00 | 3512.44 | 3500.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 4.00 | 1000.00 | 4325.83 | 2077.45 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 10.00 | 3061.60 | 3801.51 | 3570.98 |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 12.00 | 200.00 | 1515.22 | 1400.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 12.00 | 200.00 | 1515.22 | 1400.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 2.00 | 1500.00 | 4330.10 | 4024.29 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 604-25000 | Vane Grate Inlet Spec | | Each | | | |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 2.00 | 3000.00 | 4391.69 | 6600.00 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 4.00 | 2250.00 | 4362.70 | 5312.15 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 30.00 | 1933.87 | 3161.47 | 2667.79 |
| ========== | 604-25005 | Vane Grate Inlet (5 Ft) | | Each | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 1.00 | 4000.00 | 3553.08 | 3089.84 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 1.00 | 4000.00 | 3553.08 | 3089.84 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 1.00 | 7000.00 | 3749.36 | 4850.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 2.00 | 3300.00 | 3549.88 | 2600.00 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 3.00 | 4533.33 | 3616.37 | 3350.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 2.00 | 3000.00 | 3621.88 | 4800.00 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 2.00 | 3000.00 | 3621.88 | 4800.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 6.00 | 3933.33 | 3604.80 | 3789.97 |
| ========== | 604-25006 | Vane Grate Inlet Spec (5 Ft) | | Each | | | |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 7.00 | 3500.00 | 6452.41 | 5600.00 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 7.00 | 3500.00 | 6452.41 | 5600.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 7.00 | 3500.00 | 6452.41 | 5600.00 |
| ========== | 604-25010 | Vane Grate Inlet (10 Ft) | | Each | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 4.00 | 4500.00 | 4277.47 | 3646.87 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 4.00 | 4500.00 | 4277.47 | 3646.87 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 604-25010 | Vane Grate Inlet (10 Ft) | | Each | | | |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 2.00 | 8000.00 | 4261.48 | 5050.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 2.00 | 4000.00 | 4320.70 | 3000.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 4.00 | 6000.00 | 4291.09 | 4025.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 8.00 | 5250.00 | 4283.83 | 3835.94 |
| ========== | 604-25011 | Vane Grate Inlet Spec (10 Ft) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 4.00 | 15000.00 | 5143.78 | 4100.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 4.00 | 15000.00 | 5143.78 | 4100.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 6.00 | 4000.00 | 8064.27 | 5700.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 6.00 | 4000.00 | 8064.27 | 5700.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 10.00 | 8400.00 | 7390.31 | 5471.43 |
| ========== | 604-25015 | Vane Grate Inlet (15 Ft) | | Each | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 1.00 | 6500.00 | 4138.01 | 4000.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1.00 | 6500.00 | 4138.01 | 4000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 6500.00 | 4138.01 | 4000.00 |
| ========== | 604-26005 | Vane Grate Inlet (D) (5 Ft) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 40.00 | 5500.00 | 4666.80 | 3700.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 604-26005 | Vane Grate Inlet (D) (5 Ft) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 1.00 | 5000.00 | 4415.83 | 3970.26 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 41.00 | 5487.80 | 4646.31 | 3724.57 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 8.00 | 5000.00 | 3819.83 | 3700.29 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 7.00 | 4250.00 | 3701.11 | 3900.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 4.00 | 5000.00 | 3894.42 | 3799.34 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 19.00 | 4723.68 | 3795.24 | 3794.72 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 60.00 | 5245.83 | 4161.05 | 3769.00 |
| ========== | 604-26006 | Vane Grate Inlet Spec (D) (5 Ft) | | Each | | | |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 1.00 | 5500.00 | 6190.93 | 4528.03 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1.00 | 5500.00 | 6190.93 | 4528.03 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 5500.00 | 6190.93 | 4528.03 |
| ========== | 604-26010 | Vane Grate Inlet (D) (10 Ft) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 52.00 | 6000.00 | 5543.26 | 4200.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 6.00 | 5500.00 | 5519.66 | 4813.70 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 58.00 | 5948.28 | 5536.39 | 4393.80 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 2.00 | 6000.00 | 4943.60 | 4964.48 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 2.00 | 5000.00 | 4497.11 | 4800.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 2.00 | 5500.00 | 5583.33 | 3800.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 2.00 | 8000.00 | 4420.98 | 4302.20 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 8.00 | 6125.00 | 4894.10 | 4466.67 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 66.00 | 5969.70 | 5378.02 | 4415.39 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 604-26011 | Vane Grate Inlet Special (D) (10 Ft) | | Each | | | |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 2.00 | 6500.00 | 10639.32 | 6605.94 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2.00 | 6500.00 | 10639.32 | 6605.94 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 6500.00 | 10639.32 | 6605.94 |
| ========== | 604-26015 | Vane Grate Inlet (D) (15 Ft) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 4.00 | 6250.00 | 6904.21 | 6000.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 4.00 | 6250.00 | 6904.21 | 6000.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 2.00 | 5500.00 | 5137.02 | 5200.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2.00 | 5500.00 | 5137.02 | 5200.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 6.00 | 6000.00 | 5894.39 | 5466.67 |
| ========== | 604-26020 | Vane Grate Inlet (D) (20 Ft.) | | Each | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 1.00 | 9533.00 | 6075.87 | 5800.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1.00 | 9533.00 | 6075.87 | 5800.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 9533.00 | 6075.87 | 5800.00 |
| ========== | 604-30000 | MH Slab Base (Spec) | | Each | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 2.00 | 7000.00 | 2868.57 | 3000.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 7000.00 | 2868.57 | 3000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 7000.00 | 2868.57 | 3000.00 |
| ========== | 604-30005 | MH Slab Base (5 Ft) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 8.00 | 2500.00 | 2676.28 | 2200.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 604-30005 | MH Slab Base (5 Ft) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 1.00 | 2200.00 | 3349.77 | 3200.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 9.00 | 2466.67 | 2844.65 | 2533.33 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 3.00 | 2377.00 | 2325.06 | 1900.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 1.00 | 2000.00 | 3518.00 | 2575.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 4.00 | 3500.00 | 2255.68 | 1676.18 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 8.00 | 2891.38 | 2439.49 | 1872.47 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 2.00 | 5000.00 | 2744.60 | 2335.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 2.00 | 5000.00 | 2744.60 | 2335.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1.00 | 3000.00 | 2610.00 | 2850.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1.00 | 3000.00 | 2169.22 | 1809.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 3.00 | 2500.00 | 2694.82 | 3711.75 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 6.00 | 2500.00 | 3034.91 | 2213.36 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 1.00 | 4000.00 | 3179.81 | 4900.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 12.00 | 2708.33 | 2865.76 | 2831.20 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 31.00 | 2833.26 | 2735.29 | 2448.97 |
| ========== | 604-30010 | MH Slab Base (10 Ft) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 16.00 | 3750.00 | 3321.13 | 2800.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 2.00 | 3000.00 | 3654.68 | 3300.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 4.00 | 3000.00 | 4440.21 | 3550.29 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 22.00 | 3545.45 | 3818.79 | 3200.12 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 604-30010 | MH Slab Base (10 Ft) | | Each | | | |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 5.00 | 3000.00 | 2727.15 | 2963.29 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 6.00 | 2750.00 | 2796.54 | 2400.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 2.00 | 3750.00 | 2948.36 | 2000.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 1.00 | 2500.00 | 4279.17 | 2750.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 3.00 | 4000.00 | 2670.60 | 2453.32 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 17.00 | 3147.06 | 2848.98 | 2548.61 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 1.00 | 3000.00 | 3227.95 | 3800.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 1.00 | 3000.00 | 3614.40 | 2829.33 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 22.00 | 3500.00 | 3424.29 | 3430.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 6.00 | 4000.00 | 2450.88 | 1843.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 3.00 | 3000.00 | 3104.15 | 3374.58 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 4.00 | 2750.00 | 3011.10 | 2817.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 35.00 | 3457.14 | 3215.50 | 3083.14 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 75.00 | 3406.67 | 3239.93 | 2949.62 |
| ========== | 604-30015 | MH Slab Base (15 Ft) | | Each | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 1.00 | 4000.00 | 5295.95 | 3500.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 2.00 | 4000.00 | 5000.86 | 3939.66 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 3.00 | 4000.00 | 5081.34 | 3793.11 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 1.00 | 3950.00 | 3356.62 | 3000.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 2.00 | 4500.00 | 3605.18 | 3926.33 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 3.00 | 4316.67 | 3522.33 | 3617.55 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 9.00 | 4000.00 | 5311.43 | 5200.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 604-30015 | MH Slab Base (15 Ft) | | Each | | | |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 1.00 | 4000.00 | 4536.88 | 3944.91 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 10.00 | 4000.00 | 5224.16 | 5074.49 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 16.00 | 4059.38 | 4919.88 | 4561.06 |
| ========== | 604-30020 | MH Slab Base (20 Ft) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 4.00 | 5000.00 | 5627.20 | 5200.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 1.00 | 5000.00 | 6339.54 | 4800.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 5.00 | 5000.00 | 5912.13 | 5000.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 2.00 | 5000.00 | 4960.34 | 4274.36 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 5000.00 | 4960.34 | 4274.36 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 7.00 | 5000.00 | 5420.88 | 4637.18 |
| ========== | 604-31010 | MH Box Base (10 Ft) | | Each | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 1.00 | 7000.00 | 8454.84 | 8279.05 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1.00 | 7000.00 | 8454.84 | 8279.05 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 7000.00 | 8454.84 | 8279.05 |
| ========== | 604-31015 | MH Box Base (15 Ft) | | Each | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 2.00 | 15000.00 | 12142.86 | 14200.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 15000.00 | 12142.86 | 14200.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 15000.00 | 12142.86 | 14200.00 |
| ========== | 604-31020 | MH Box Base (20 Ft) | | Each | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 1.00 | 8000.00 | 10296.77 | 9460.71 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1.00 | 8000.00 | 10296.77 | 9460.71 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 8000.00 | 10296.77 | 9460.71 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 604-32010 | MH T-Base (10 Ft) | | Each | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 4.00 | 5000.00 | 4347.14 | 4800.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 4.00 | 5000.00 | 4347.14 | 4800.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4.00 | 5000.00 | 4347.14 | 4800.00 |
| ========== | 604-32015 | MH T-Base (15 Ft) | | Each | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 3.00 | 4000.00 | 4908.57 | 5600.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 3.00 | 4000.00 | 4908.57 | 5600.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3.00 | 4000.00 | 4908.57 | 5600.00 |
| ========== | 604-39000 | MH Spec | | Each | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 1.00 | 75000.00 | 44533.07 | 14905.39 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1.00 | 75000.00 | 44533.07 | 14905.39 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 4.00 | 6000.00 | 2177.86 | 1875.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 1.00 | 36000.00 | 5703.83 | 7466.83 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 5.00 | 12000.00 | 2961.41 | 2993.37 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 6.00 | 22500.00 | 10519.89 | 4978.70 |
| ========== | 604-39005 | MH Spec (5 Ft) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 12.00 | 2500.00 | 3260.33 | 3400.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 12.00 | 2500.00 | 3260.33 | 3400.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 12.00 | 2500.00 | 3260.33 | 3400.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 604-39010 | MH Spec (10 Ft) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 8.00 | 3000.00 | 4082.68 | 4100.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 8.00 | 3000.00 | 4082.68 | 4100.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 2.00 | 6000.00 | 4157.21 | 3395.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 2.00 | 6000.00 | 4157.21 | 3395.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1.00 | 6000.00 | 3318.57 | 2500.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 6000.00 | 3318.57 | 2500.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 11.00 | 3818.18 | 3981.31 | 3498.00 |
| ========== | 604-39015 | MH Spec (15 Ft) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 4.00 | 10000.00 | 6751.44 | 6600.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 4.00 | 10000.00 | 6751.44 | 6600.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 2.00 | 10000.00 | 14159.37 | 8500.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 2.00 | 10000.00 | 14159.37 | 8500.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 2.00 | 10000.00 | 5544.85 | 8025.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 2.00 | 10000.00 | 5544.85 | 8025.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 8.00 | 10000.00 | 8915.68 | 7930.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 604-39020 | MH Spec (20 Ft) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 16.00 | 6000.00 | 11784.01 | 13000.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 16.00 | 6000.00 | 11784.01 | 13000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 16.00 | 6000.00 | 11784.01 | 13000.00 |
| ========== | 604-39025 | MH Spec (25 Ft) | | Each | | | |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 1.00 | 15000.00 | 9114.26 | 7325.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 1.00 | 15000.00 | 9114.26 | 7325.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1.00 | 300000.00 | 41800.23 | 35000.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 300000.00 | 41800.23 | 35000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 157500.00 | 21685.79 | 21162.50 |
| ========== | 604-39050 | MH (TMS) | | Each | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 2.00 | 4500.00 | 4145.22 | 6052.86 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 2.00 | 4500.00 | 4145.22 | 6052.86 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1.00 | 5000.00 | 3500.05 | 3285.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 5000.00 | 3500.05 | 3285.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3.00 | 4666.67 | 3991.61 | 5130.24 |
| ========== | 604-50062 | Grating and Frame | | Each | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 2.00 | 5000.00 | 3491.43 | 3350.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 5000.00 | 3491.43 | 3350.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 5000.00 | 3491.43 | 3350.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 604-50700 | Meter Vault | | Each | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 4.00 | 500.00 | 2965.62 | 3596.17 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 4.00 | 500.00 | 2965.62 | 3596.17 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1.00 | 5000.00 | 4982.56 | 3000.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 5000.00 | 4982.56 | 3000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 5.00 | 1400.00 | 3313.37 | 3476.94 |
| ========== | 605-00004 | 4 In Underdrain | | Lin Foot | | | |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 282.00 | 20.00 | 14.97 | 11.33 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 282.00 | 20.00 | 14.97 | 11.33 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 282.00 | 20.00 | 11.80 | 7.55 |
| ========== | 605-00040 | 4 In PP Underdrain | | Lin Foot | | | |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 344.00 | 50.00 | 16.57 | 8.13 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1,835.00 | 26.00 | 20.24 | 15.09 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2,179.00 | 29.79 | 19.50 | 13.99 |
| NH0403-053 | | US 40 RETAINING WALL REPAIR | 07/28/11 | 335.00 | 100.00 | 113.48 | 127.43 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 335.00 | 100.00 | 61.72 | 69.12 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,514.00 | 39.14 | 24.64 | 26.43 |
| ========== | 605-00041 | 4 In PP Underdrain (Special) | | Lin Foot | | | |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 411.00 | 65.00 | 83.35 | 115.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 411.00 | 65.00 | 83.35 | 115.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 411.00 | 65.00 | 83.35 | 115.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 605-00060 | 6 In PP Underdrain | | Lin Foot | ========== | ========== | ========== |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 410.00 | 30.00 | 30.49 | 45.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 410.00 | 30.00 | 13.27 | 17.73 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 2,089.00 | 15.00 | 19.51 | 12.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 309.00 | 15.00 | 23.14 | 12.53 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2,398.00 | 15.00 | 20.21 | 12.07 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,808.00 | 17.19 | 17.73 | 14.41 |
| ========== | 605-01030 | 3 In Hor Drain | | Lin Foot | ========== | ========== | ========== |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 2,000.00 | 30.00 | 29.23 | 25.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 2,000.00 | 30.00 | 25.14 | 23.50 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,000.00 | 30.00 | 25.14 | 23.50 |
| ========== | 605-82200 | French Drain | | Lin Foot | ========== | ========== | ========== |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 515.00 | 50.00 | 38.83 | 75.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 515.00 | 50.00 | 38.83 | 75.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1,000.00 | 10.00 | 18.85 | 12.07 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1,000.00 | 10.00 | 18.85 | 12.07 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,515.00 | 23.60 | 25.64 | 33.46 |
| ========== | 605-83002 | Geocomp Drain (w/ Pipe) | | Sq Yard | ========== | ========== | ========== |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 77.00 | 27.00 | 45.67 | 36.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 77.00 | 27.00 | 45.67 | 36.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 77.00 | 27.00 | 45.67 | 36.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 605-83580 | 8 In Pipe Underdrain | | Lin Foot | | | |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 132.00 | 75.00 | 25.24 | 15.84 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 132.00 | 75.00 | 25.24 | 15.84 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 80.00 | 35.00 | 22.01 | 25.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 80.00 | 35.00 | 22.01 | 25.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 212.00 | 59.91 | 24.35 | 19.30 |
| ========== | 605-84000 | Subsurface Drain Outlet | | Lin Foot | | | |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 234.00 | 20.00 | 37.32 | 45.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 234.00 | 20.00 | 37.32 | 45.00 |
| NH0403-053 | | US 40 RETAINING WALL REPAIR | 07/28/11 | 4.00 | 50.00 | 501.67 | 1035.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 4.00 | 50.00 | 501.67 | 1035.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 238.00 | 20.50 | 37.37 | 42.60 |
| ========== | 606-00301 | Gdrail Ty 3 (6-3) | | Lin Foot | | | |
| C0704-225 | | I-70 EAST OF BENNETT | 01/06/11 | 200.00 | 14.00 | 14.89 | 13.89 |
| ITS4701-121 | | C470 (SANTA FE TO I-25) AND R | 01/20/11 | 150.00 | 16.00 | 17.59 | 18.35 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 5,240.00 | 13.00 | 14.22 | 13.40 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 387.50 | 20.00 | 13.33 | 13.75 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 1,162.50 | 15.00 | 13.92 | 14.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 2,028.00 | 13.00 | 15.57 | 17.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 9,168.00 | 13.62 | 14.65 | 14.57 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 540.00 | 20.00 | 19.62 | 20.50 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 606-00301 | Gdrail Ty 3 (6-3) | | Lin Foot | | | |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 363.00 | 15.00 | 16.82 | 21.00 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 490.00 | 14.00 | 16.10 | 15.05 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 1,025.00 | 15.00 | 18.08 | 17.00 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 4,375.00 | 14.00 | 16.57 | 16.00 |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 375.00 | 15.00 | 15.42 | 14.85 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 1,242.00 | 14.00 | 14.35 | 15.50 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 1,207.00 | 14.00 | 14.42 | 13.68 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 1,155.00 | 14.00 | 17.36 | 18.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 8,563.00 | 15.00 | 17.15 | 17.75 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 993.00 | 20.00 | 17.76 | 17.15 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 5,892.00 | 13.00 | 13.34 | 13.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 4,351.00 | 20.00 | 18.00 | 17.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 5,566.00 | 13.00 | 14.72 | 13.06 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 29,089.00 | 12.00 | 15.57 | 14.90 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 3,613.00 | 16.00 | 16.00 | 15.14 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 68,839.00 | 13.76 | 15.79 | 15.22 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 925.00 | 14.00 | 16.62 | 17.11 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 150.00 | 15.50 | 14.94 | 12.75 |
| C0091-038 | | SH 9 MM 81.9 BLUE RIVER EMERG | 08/24/11 | 112.50 | 20.00 | 32.07 | 32.67 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 400.00 | 17.00 | 19.10 | 17.00 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 3,168.00 | 15.00 | 16.37 | 15.82 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 1,896.00 | 17.00 | 16.62 | 15.25 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 6,651.50 | 15.65 | 17.55 | 18.10 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 426.00 | 16.00 | 14.20 | 14.40 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 3,500.00 | 14.50 | 15.71 | 14.89 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 725.00 | 20.00 | 16.11 | 16.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 276.00 | 20.00 | 15.28 | 14.60 |
| ITSSW00-928 | | NB I-225 AT MM 2.28 | 11/03/11 | 150.00 | 17.00 | 17.13 | 16.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 244.00 | 15.00 | 18.63 | 16.66 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 750.00 | 20.00 | 21.06 | 23.00 |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 750.00 | 17.00 | 23.63 | 20.02 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 526.00 | 21.00 | 21.99 | 21.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 1,386.00 | 18.00 | 16.09 | 15.00 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 1,538.00 | 14.00 | 17.31 | 16.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 10,271.00 | 16.46 | 16.83 | 16.46 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 94,929.50 | 14.17 | 15.92 | 15.63 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 606-00350 | Gdrail Ty 3 (D) (6-3) | | Lin Foot | | | |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 800.00 | 20.00 | 22.98 | 22.50 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 38.00 | 21.00 | 24.79 | 27.27 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 838.00 | 20.05 | 23.03 | 22.72 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 838.00 | 20.05 | 21.60 | 19.93 |
| ========== | 606-00705 | Gdrail Ty 7 (Spec) | | Lin Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 34,836.00 | 40.00 | 42.42 | 12.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 34,836.00 | 40.00 | 42.42 | 12.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 282.00 | 117.00 | 193.54 | 150.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 282.00 | 117.00 | 193.54 | 150.00 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 13.00 | 100.00 | 475.80 | 582.00 |
| MC0504-065 | | US50B FROM MP 318 TO MP 359 | 12/01/11 | 108.00 | 125.00 | 176.83 | 263.50 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 121.00 | 122.31 | 199.04 | 297.72 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 35,239.00 | 40.90 | 46.28 | 20.06 |
| ========== | 606-00710 | Gdrail Ty 7 (Sty CA) | | Lin Foot | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 263.00 | 55.00 | 79.11 | 67.85 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 8,640.00 | 50.00 | 48.20 | 39.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 365.00 | 60.00 | 49.42 | 49.23 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 9,268.00 | 50.54 | 54.88 | 45.20 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 606-00710 | Gdrail Ty 7 (Sty CA) | | Lin Foot | | | |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 1,540.00 | 60.00 | 53.88 | 49.55 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 134.00 | 45.00 | 58.46 | 52.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 3,667.00 | 40.00 | 40.60 | 30.00 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 800.00 | 90.00 | 46.18 | 44.10 |
| ITS0703-370 | | EAST OF EJMT ON I-70 EB LANES | 06/16/11 | 222.50 | 65.00 | 104.62 | 118.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 895.00 | 45.00 | 63.50 | 41.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 7,258.50 | 51.23 | 50.65 | 49.10 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 80.00 | 65.00 | 87.54 | 125.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 80.00 | 65.00 | 54.65 | 54.65 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 696.00 | 50.00 | 48.08 | 47.50 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1,883.50 | 45.00 | 52.59 | 51.64 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 160.00 | 100.00 | 112.60 | 139.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2,739.50 | 49.48 | 53.77 | 55.69 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 19,346.00 | 50.71 | 52.67 | 49.72 |
| ========== | 606-00716 | Gdrail Ty 7 (Sty CA) (Spec) | | Lin Foot | | | |
| C006A-051 | | US 6 (LOVELAND PASS), CLEAR C | 07/14/11 | 1,015.00 | 80.00 | 106.00 | 91.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 13.00 | 175.00 | 199.40 | 140.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1,028.00 | 81.20 | 107.47 | 91.62 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 38.00 | 100.00 | 64.27 | 53.45 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 38.00 | 100.00 | 64.27 | 53.45 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,066.00 | 81.87 | 105.57 | 90.26 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 606-00720 | Gdrail Ty 7 (Sty CC) | | Lin Foot | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 1,911.00 | 40.00 | 51.41 | 46.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1,911.00 | 40.00 | 51.41 | 46.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 258.00 | 50.00 | 59.13 | 52.64 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 258.00 | 50.00 | 59.13 | 52.64 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,169.00 | 41.19 | 55.15 | 47.14 |
| ========== | 606-00721 | Gdrail Ty 7 (Sty CC)(Spec) | | Lin Foot | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 544.00 | 75.00 | 79.08 | 107.19 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 544.00 | 75.00 | 79.08 | 107.19 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 544.00 | 75.00 | 79.08 | 107.19 |
| ========== | 606-00725 | Gdrail Ty 7 (Sty CC)(Conc Glare Screen) | | Lin Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 2,220.00 | 100.00 | 70.10 | 91.50 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 2,220.00 | 100.00 | 70.10 | 91.50 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,220.00 | 100.00 | 70.10 | 91.50 |
| ========== | 606-00730 | Gdrail Ty 7 (Sty CD) | | Lin Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 3,564.00 | 50.00 | 55.80 | 51.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 3,564.00 | 50.00 | 55.80 | 51.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 606-00730 | Gdrail Ty 7 (Sty CD) | | Lin Foot | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 1,481.00 | 62.00 | 58.13 | 40.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1,481.00 | 62.00 | 58.13 | 40.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 117.00 | 70.00 | 96.31 | 89.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 117.00 | 70.00 | 96.31 | 89.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 90.00 | 100.00 | 92.00 | 80.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 138.00 | 65.00 | 59.94 | 65.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 228.00 | 78.82 | 75.24 | 70.92 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 5,390.00 | 54.95 | 60.20 | 48.31 |
| ========== | 606-00731 | Gdrail Ty 7 (Sty CD) (Spec) | | Lin Foot | | | |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1,914.00 | 50.00 | 63.55 | 62.87 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1,914.00 | 50.00 | 63.55 | 62.87 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,914.00 | 50.00 | 63.55 | 62.87 |
| ========== | 606-00740 | Gdrail Ty 7 (Sty CE) | | Lin Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 2,096.00 | 90.00 | 84.97 | 87.10 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 785.00 | 90.00 | 72.42 | 70.14 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 2,881.00 | 90.00 | 77.80 | 76.93 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 380.00 | 90.00 | 71.69 | 64.99 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 606-00740 | Gdrail Ty 7 (Sty CE) | | Lin Foot | ========== | ========== | ========== |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 1,698.00 | 70.00 | 75.33 | 73.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 239.00 | 100.00 | 107.34 | 83.25 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1,083.00 | 50.00 | 80.05 | 63.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 3,400.00 | 67.97 | 79.06 | 69.64 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 93.00 | 100.00 | 99.41 | 101.41 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 218.00 | 75.00 | 105.80 | 84.44 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 311.00 | 82.48 | 104.45 | 89.51 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 6,592.00 | 78.28 | 80.28 | 72.77 |
| ========== | 606-00741 | Gdrail Ty 7 (Sty CE) (Spec) | | Lin Foot | ========== | ========== | ========== |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 40.00 | 130.00 | 129.99 | 130.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 40.00 | 130.00 | 129.99 | 130.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 35.00 | 130.00 | 113.30 | 129.60 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 35.00 | 130.00 | 113.30 | 129.60 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 75.00 | 130.00 | 122.95 | 129.81 |
| ========== | 606-00745 | Gdrail Ty 7 (Sty CE)(Conc Glare Screen) | | Lin Foot | ========== | ========== | ========== |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 7,096.00 | 100.00 | 88.85 | 110.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 2,949.00 | 80.00 | 84.77 | 88.34 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 10,045.00 | 94.13 | 86.42 | 96.48 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 10,045.00 | 94.13 | 86.42 | 96.48 |
| ========== | 606-00900 | Gdrail (Spec) | | Lin Foot | ========== | ========== | ========== |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 416.00 | 100.00 | 189.68 | 160.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 416.00 | 100.00 | 189.68 | 160.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 416.00 | 100.00 | 189.68 | 160.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 606-01320 | End Anchor Ty 3B | | Each | | | |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 1.00 | 800.00 | 969.81 | 350.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 1.00 | 800.00 | 969.81 | 350.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 800.00 | 969.81 | 350.00 |
| ========== | 606-01340 | End Anchor Ty 3D | | Each | | | |
| C0704-225 | | I-70 EAST OF BENNETT | 01/06/11 | 1.00 | 700.00 | 712.50 | 594.00 |
| ITS4701-121 | | C470 (SANTA FE TO I-25) AND R | 01/20/11 | 1.00 | 700.00 | 800.81 | 878.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 16.00 | 600.00 | 555.78 | 503.65 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 1.00 | 800.00 | 716.57 | 733.07 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 19.00 | 621.05 | 638.27 | 622.98 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 1.00 | 700.00 | 809.87 | 660.00 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 4.00 | 600.00 | 703.55 | 650.70 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 1.00 | 600.00 | 803.00 | 803.00 |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 1.00 | 700.00 | 756.98 | 730.00 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 1.00 | 750.00 | 706.21 | 723.45 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 1.00 | 1500.00 | 790.93 | 741.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 2.00 | 600.00 | 601.48 | 670.00 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 28.00 | 650.00 | 600.60 | 645.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 8.00 | 300.00 | 534.22 | 508.99 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 47.00 | 605.32 | 730.54 | 672.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1.00 | 420.00 | 645.14 | 650.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1.00 | 750.00 | 635.38 | 600.00 |
| ITSSW00-928 | | NB I-225 AT MM 2.28 | 11/03/11 | 1.00 | 800.00 | 781.67 | 720.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 2.00 | 800.00 | 725.10 | 761.08 |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 5.00 | 700.00 | 817.75 | 748.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 3.00 | 750.00 | 762.79 | 810.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 13.00 | 716.92 | 752.28 | 743.24 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 79.00 | 627.47 | 725.25 | 715.66 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 606-01370 | Transition Ty 3G | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 4.00 | 1100.00 | 1393.07 | 1005.25 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 4.00 | 1300.00 | 971.93 | 1025.00 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 4.00 | 1200.00 | 1009.68 | 1100.00 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 35.00 | 1000.00 | 1339.18 | 1200.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 2.00 | 1100.00 | 1080.82 | 1115.88 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 49.00 | 1053.06 | 1237.93 | 1196.62 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 14.00 | 1100.00 | 1216.00 | 1154.00 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 16.00 | 1000.00 | 1196.33 | 1181.00 |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 1.00 | 1200.00 | 1147.89 | 1105.00 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 4.00 | 1100.00 | 1104.17 | 1124.78 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 2.00 | 1100.00 | 1368.02 | 1287.00 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 4.00 | 1100.00 | 4464.09 | 4430.00 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 1.00 | 1100.00 | 1378.28 | 1390.79 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 2.00 | 1500.00 | 1268.81 | 1350.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 2.00 | 1700.00 | 1263.38 | 1180.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 3.00 | 1100.00 | 1018.12 | 1000.00 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 25.00 | 1100.00 | 1032.13 | 965.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 6.00 | 400.00 | 988.07 | 939.58 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 80.00 | 1053.75 | 1284.75 | 1191.78 |
| C006A-051 | | US 6 (LOVELAND PASS), CLEAR C | 07/14/11 | 3.00 | 920.00 | 1577.50 | 1500.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 1.00 | 1200.00 | 1212.27 | 1040.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 4.00 | 990.00 | 1346.85 | 1318.77 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 4.00 | 1200.00 | 987.08 | 998.78 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1.00 | 1200.00 | 1154.29 | 1130.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1.00 | 1100.00 | 1117.48 | 1057.35 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 2.00 | 1300.00 | 1165.08 | 1147.14 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 1.00 | 1200.00 | 1272.17 | 1372.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 1.00 | 1350.00 | 1267.63 | 1220.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 606-01370 | Transition Ty 3G | | Each | | | |
| MC0504-065 | | US50B FROM MP 318 TO MP 359 | 12/01/11 | 18.00 | 1250.00 | 1022.33 | 975.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 4.00 | 1100.00 | 1168.30 | 1100.00 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 4.00 | 1100.00 | 1774.00 | 1332.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 36.00 | 1209.72 | 1131.33 | 1065.19 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 169.00 | 1085.27 | 1246.39 | 1176.44 |
| ========== | 606-01371 | Transition Ty 3G (Spec) | | Each | | | |
| ITS0703-370 | | EAST OF EJMT ON I-70 EB LANES | 06/16/11 | 1.00 | 920.00 | 2814.67 | 2800.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1.00 | 920.00 | 2814.67 | 2800.00 |
| C006A-051 | | US 6 (LOVELAND PASS), CLEAR C | 07/14/11 | 2.00 | 920.00 | 853.75 | 730.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 2.00 | 920.00 | 853.75 | 730.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3.00 | 920.00 | 1388.55 | 1420.00 |
| ========== | 606-01380 | Transition Ty 3H | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 12.00 | 600.00 | 870.21 | 534.40 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 2.00 | 750.00 | 638.53 | 655.47 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 14.00 | 621.43 | 728.89 | 690.46 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 1.00 | 600.00 | 663.50 | 639.00 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 1.00 | 625.00 | 641.33 | 654.80 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 3.00 | 600.00 | 780.67 | 745.00 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 4.00 | 750.00 | 1582.57 | 1619.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 2.00 | 800.00 | 681.14 | 656.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 5.00 | 600.00 | 609.48 | 660.00 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 12.00 | 600.00 | 568.12 | 540.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1.00 | 500.00 | 590.58 | 558.72 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 29.00 | 631.90 | 784.58 | 743.52 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 606-01380 | Transition Ty 3H | | Each | | | |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 2.00 | 700.00 | 718.74 | 766.60 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 700.00 | 718.74 | 766.60 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 45.00 | 631.67 | 762.60 | 733.00 |
| ========== | 606-01385 | Transition Ty 3J | | Each | | | |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 4.00 | 750.00 | 539.60 | 610.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 4.00 | 750.00 | 539.60 | 610.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 4.00 | 800.00 | 714.92 | 766.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 1.00 | 900.00 | 799.67 | 824.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 5.00 | 820.00 | 747.27 | 779.00 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 1.00 | 750.00 | 601.67 | 617.36 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 1.00 | 700.00 | 637.10 | 550.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 2.00 | 725.00 | 676.87 | 689.12 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 11.00 | 777.27 | 659.86 | 706.26 |
| ========== | 606-01390 | End Anchor Ty 3K | | Each | | | |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 4.00 | 1100.00 | 926.39 | 900.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 4.00 | 1100.00 | 926.39 | 900.00 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 5.00 | 1000.00 | 880.33 | 840.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 606-01390 | End Anchor Ty 3K | | Each | | | |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 4.00 | 1200.00 | 1023.99 | 1060.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 1.00 | 1000.00 | 1090.33 | 1040.00 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 3.00 | 1000.00 | 1034.48 | 815.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 13.00 | 1061.54 | 1025.90 | 937.86 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 1.00 | 1025.00 | 900.71 | 925.57 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 1.00 | 900.00 | 1019.30 | 1000.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 2.00 | 962.50 | 985.31 | 1041.86 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1.00 | 1500.00 | 950.43 | 1080.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 1.00 | 1200.00 | 853.54 | 820.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 1350.00 | 915.20 | 950.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 21.00 | 1086.90 | 985.23 | 945.89 |
| ========== | 606-01460 | Median Terminal | | Each | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 2.00 | 4000.00 | 3772.01 | 4500.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 2.00 | 4000.00 | 3155.41 | 3119.17 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 4.00 | 3500.00 | 3566.17 | 3625.00 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 48.00 | 3300.00 | 3075.82 | 2875.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 52.00 | 3315.38 | 3227.96 | 2990.74 |
| MC0504-065 | | US50B FROM MP 318 TO MP 359 | 12/01/11 | 9.00 | 2500.00 | 3328.33 | 3135.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 9.00 | 2500.00 | 3328.33 | 3135.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 63.00 | 3220.63 | 3213.44 | 3035.31 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 606-02003 | End Anchor (Nonflared) | | Each | | | |
| ITS4701-121 | | C470 (SANTA FE TO I-25) AND R | 01/20/11 | 1.00 | 2000.00 | 2392.50 | 2225.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 8.00 | 1700.00 | 1917.02 | 1816.90 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 3.00 | 1800.00 | 1858.88 | 1900.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 1.00 | 1800.00 | 2052.49 | 2164.95 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 13.00 | 1753.85 | 1994.98 | 1989.55 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 7.00 | 2000.00 | 1915.61 | 1908.05 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 1.00 | 1800.00 | 2076.35 | 1950.00 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 3.00 | 2000.00 | 2010.39 | 1896.25 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 4.00 | 2000.00 | 1925.67 | 1864.00 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 4.00 | 1600.00 | 1912.38 | 2066.00 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 1.00 | 1750.00 | 3280.81 | 2149.00 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 1.00 | 2000.00 | 2254.87 | 2274.85 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 2.00 | 1800.00 | 2014.00 | 2000.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 34.00 | 2000.00 | 1802.51 | 1875.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 3.00 | 2000.00 | 2013.06 | 1880.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 16.00 | 1750.00 | 1965.94 | 1974.99 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 26.00 | 1750.00 | 1822.97 | 1900.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 2.00 | 1500.00 | 1826.27 | 1733.84 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 104.00 | 1865.87 | 1869.33 | 1886.02 |
| C006A-051 | | US 6 (LOVELAND PASS), CLEAR C | 07/14/11 | 1.00 | 1995.00 | 2125.00 | 2100.00 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 4.00 | 1800.00 | 1763.70 | 1814.48 |
| C0091-038 | | SH 9 MM 81.9 BLUE RIVER EMERG | 08/24/11 | 3.00 | 2500.00 | 3031.27 | 2662.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 4.00 | 1800.00 | 2075.00 | 1900.00 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 6.00 | 2000.00 | 2013.05 | 1810.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 18.00 | 1994.17 | 2190.59 | 2268.06 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 4.00 | 2000.00 | 1815.53 | 1843.05 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 10.00 | 1800.00 | 1880.04 | 1775.64 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1.00 | 1500.00 | 2060.00 | 2020.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 606-02003 | End Anchor (Nonflared) | | Each | | | |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 2.00 | 2100.00 | 1982.75 | 1871.75 |
| ITSSW00-928 | | NB I-225 AT MM 2.28 | 11/03/11 | 1.00 | 2100.00 | 2010.50 | 1822.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 2.00 | 2000.00 | 1980.04 | 2007.49 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 3.00 | 2000.00 | 2108.73 | 2150.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 10.00 | 2000.00 | 1905.78 | 1800.00 |
| MC0504-065 | | US50B FROM MP 318 TO MP 359 | 12/01/11 | 1.00 | 2000.00 | 1876.67 | 1930.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 34.00 | 1935.29 | 1909.43 | 1856.15 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 169.00 | 1884.88 | 1941.26 | 1959.74 |
| ========== | 606-02005 | End Anchor (Flared) | | Each | | | |
| C0704-225 | | I-70 EAST OF BENNETT | 01/06/11 | 1.00 | 3500.00 | 3790.25 | 1511.00 |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 4.00 | 2000.00 | 1520.29 | 1520.00 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 3.00 | 2000.00 | 1540.67 | 1500.00 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 24.00 | 1500.00 | 1898.79 | 2000.00 |
| NH 0402-079 | | US40 MP 165.0 - 179.0 GRAND C | 03/31/11 | 2.00 | 1900.00 | 2160.00 | 2060.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 34.00 | 1685.29 | 1743.93 | 1734.04 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 1.00 | 1400.00 | 1629.15 | 1555.10 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 10.00 | 1700.00 | 1580.00 | 1504.00 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 8.00 | 1500.00 | 1526.67 | 1478.00 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 3.00 | 1450.00 | 1538.35 | 1504.98 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 1.00 | 1500.00 | 1862.10 | 1886.72 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 4.00 | 1500.00 | 1628.33 | 1600.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 1.00 | 1500.00 | 1435.51 | 1500.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 11.00 | 2000.00 | 1925.67 | 1600.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 2.00 | 1750.00 | 1538.36 | 1432.64 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 32.00 | 1400.00 | 1409.72 | 1350.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 8.00 | 1500.00 | 1406.76 | 1332.01 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 81.00 | 1556.17 | 1587.13 | 1457.20 |
| C006A-051 | | US 6 (LOVELAND PASS), CLEAR C | 07/14/11 | 2.00 | 1745.00 | 1662.50 | 1600.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 1.00 | 1600.00 | 1455.36 | 1500.00 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 1.00 | 2000.00 | 2114.54 | 1720.00 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 10.00 | 1500.00 | 1562.40 | 1500.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 14.00 | 1577.86 | 1585.52 | 1530.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 606-02005 | End Anchor (Flared) | | Each | | | |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 10.00 | 1750.00 | 1826.23 | 1816.00 |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 5.00 | 1700.00 | 2325.25 | 1606.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 11.00 | 2000.00 | 1746.98 | 1600.00 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 14.00 | 1900.00 | 1703.33 | 1590.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 40.00 | 1865.00 | 1809.51 | 1651.25 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 169.00 | 1657.04 | 1678.78 | 1574.04 |
| ========== | 606-10700 | Brdg Rail Ty 7 | | Lin Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 24,656.00 | 61.77 | 81.41 | 65.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 1,961.00 | 100.00 | 94.46 | 79.49 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 26,617.00 | 64.59 | 84.00 | 68.15 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 831.00 | 80.00 | 62.73 | 59.31 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 3,743.00 | 65.00 | 73.71 | 82.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 851.00 | 90.00 | 71.75 | 70.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 325.00 | 50.00 | 85.16 | 100.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 5,750.00 | 70.02 | 72.03 | 77.96 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 834.00 | 80.00 | 78.88 | 106.85 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 2,124.00 | 70.00 | 59.19 | 61.48 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2,958.00 | 72.82 | 64.74 | 74.27 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 35,325.00 | 66.16 | 77.57 | 72.36 |
| ========== | 606-10705 | Brdg Rail Ty 7 (Spec) | | Lin Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | . | 1,208.00 | 85.00 | 81.35 | . |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 606-10705 | Brdg Rail Ty 7 (Spec) | | Lin Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 51.00 | 150.00 | 127.44 | 62.17 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1,259.00 | 87.63 | 88.01 | 62.17 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 373.00 | 95.00 | 72.49 | 88.90 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 756.00 | 85.00 | 96.23 | 86.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 624.00 | 95.00 | 97.24 | 105.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1,753.00 | 90.69 | 90.27 | 93.38 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1,759.00 | 60.00 | 75.82 | 58.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1,759.00 | 60.00 | 75.82 | 58.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4,771.00 | 78.57 | 84.44 | 75.47 |
| ========== | 606-10742 | Bridge Rail Ty 7 (42") | | Lin Foot | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 1,598.00 | 90.00 | 95.28 | 120.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1,598.00 | 90.00 | 95.28 | 120.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,598.00 | 90.00 | 95.28 | 120.00 |
| ========== | 606-11005 | Brdg Rail Ty 10 (Spec) | | Lin Foot | | | |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 517.00 | 150.00 | 175.56 | 155.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 517.00 | 150.00 | 175.56 | 155.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 517.00 | 150.00 | 175.56 | 155.00 |
| ========== | 606-11010 | Brdg Rail Ty 10R | | Lin Foot | | | |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 845.00 | 80.00 | 89.17 | 84.50 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 606-11010 | Brdg Rail Ty 10R | | Lin Foot | ========== | ========== | ========== |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 2,860.00 | 100.00 | 87.92 | 87.00 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 104.00 | 90.00 | 164.65 | 166.00 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 923.00 | 80.00 | 95.01 | 92.27 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 4,732.00 | 92.31 | 90.98 | 89.32 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4,732.00 | 92.31 | 90.98 | 89.32 |
| ========== | 606-11015 | Brdg Rail Ty 10R (Spec) | | Lin Foot | ========== | ========== | ========== |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 248.00 | 150.00 | 160.96 | 120.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 248.00 | 150.00 | 160.96 | 120.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 780.00 | 125.00 | 167.30 | 170.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 780.00 | 125.00 | 167.30 | 170.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,028.00 | 131.03 | 170.83 | 171.27 |
| ========== | 606-11025 | Brdg Rail Ty 10H (Spec) | | Lin Foot | ========== | ========== | ========== |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 34.00 | 90.00 | 173.17 | 13.10 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 38.00 | 110.00 | 296.80 | 335.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 72.00 | 100.56 | 229.54 | 182.99 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 72.00 | 100.56 | 229.54 | 182.99 |
| ========== | 606-11030 | Brdg Rail Ty 10M | | Lin Foot | ========== | ========== | ========== |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 157.00 | 96.00 | 120.02 | 104.00 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 1,107.00 | 115.00 | 106.25 | 110.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 1,264.00 | 112.64 | 107.62 | 109.25 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 352.00 | 90.00 | 142.71 | 145.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 352.00 | 90.00 | 142.71 | 145.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 606-11030 | Brdg Rail Ty 10M | | Lin Foot | | | |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 537.00 | 110.00 | 120.15 | 101.64 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 537.00 | 110.00 | 120.15 | 101.64 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,153.00 | 108.28 | 116.78 | 114.23 |
| ========== | 606-11032 | Brdg Rail Ty 10M (Spec) | | Lin Foot | | | |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 324.00 | 110.00 | 217.50 | 77.50 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 324.00 | 110.00 | 217.50 | 77.50 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 522.00 | 150.00 | 198.71 | 216.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 522.00 | 150.00 | 198.71 | 216.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 846.00 | 134.68 | 203.81 | 162.96 |
| ========== | 606-20014 | Tensioned Cable Barrier (TL-4) | | Lin Foot | | | |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 4,465.00 | 14.00 | 11.34 | 10.07 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 341.00 | 15.00 | 25.05 | 23.48 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 4,806.00 | 14.07 | 13.16 | 11.02 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 13,823.00 | 12.00 | 11.39 | 8.49 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 13,823.00 | 12.00 | 13.06 | 10.25 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 18,629.00 | 12.53 | 13.07 | 10.33 |
| ========== | 606-21010 | End Anchor (Tens Cab Bar) | | Each | | | |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 10.00 | 2800.00 | 3300.40 | 2650.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 606-21010 | End Anchor (Tens Cab Bar) | | Each | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 2.00 | 50.00 | 4394.64 | 4177.97 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 12.00 | 2341.67 | 3613.04 | 2904.66 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 34.00 | 3200.00 | 3069.30 | 2795.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 34.00 | 3200.00 | 3239.86 | 1547.48 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 46.00 | 2976.09 | 3189.72 | 1906.88 |
| ========== | 606-99999 | Gdrail Ty 7 (Precast) | | Lin Foot | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 30,175.00 | 56.40 | 64.63 | 65.47 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 30,175.00 | 56.40 | 64.63 | 65.47 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 190.00 | 60.00 | 60.80 | 64.69 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 190.00 | 60.00 | 60.80 | 64.69 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 30,365.00 | 56.43 | 64.61 | 65.46 |
| ========== | 607-00005 | End Post | | Each | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 2.00 | 230.00 | 198.00 | 260.00 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 19.00 | 185.00 | 170.68 | 200.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 21.00 | 189.29 | 153.53 | 147.69 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 26.00 | 130.00 | 211.32 | 196.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 1.00 | 200.00 | 287.16 | 344.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 4.00 | 200.00 | 516.67 | 490.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1.00 | 400.00 | 148.72 | 135.72 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 32.00 | 149.38 | 256.31 | 258.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 607-00005 | End Post | | Each | | | |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 12.00 | 150.00 | 167.49 | 170.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 12.00 | 150.00 | 181.83 | 174.40 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 1.00 | 200.00 | 205.04 | 182.88 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 3.00 | 150.00 | 146.43 | 145.00 |
| SHE025A-013 | | I 25 BETWEEN MP 122 AND MP 12 | 11/03/11 | 21.00 | 205.00 | 313.37 | 320.00 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 4.00 | 200.00 | 151.37 | 150.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 2.00 | 400.00 | 433.88 | 440.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 31.00 | 211.45 | 294.54 | 284.45 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 96.00 | 178.23 | 223.76 | 214.32 |
| ========== | 607-00010 | Corner and Line Br Post | | Each | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 4.00 | 250.00 | 237.14 | 290.00 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 13.00 | 300.00 | 201.17 | 230.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 17.00 | 288.24 | 174.09 | 162.69 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 12.00 | 180.00 | 287.64 | 284.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 1.00 | 300.00 | 339.08 | 425.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 10.00 | 200.00 | 199.68 | 183.34 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 23.00 | 193.91 | 324.52 | 360.02 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 15.00 | 300.00 | 188.15 | 190.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 15.00 | 300.00 | 188.15 | 190.00 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 1.00 | 250.00 | 273.57 | 275.91 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 607-00010 | Corner and Line Br Post | | Each | | | |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 2.00 | 250.00 | 303.72 | 228.60 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 19.00 | 250.00 | 215.43 | 212.00 |
| SHE025A-013 | | I 25 BETWEEN MP 122 AND MP 12 | 11/03/11 | 173.00 | 240.00 | 485.13 | 465.00 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 53.00 | 240.00 | 173.05 | 170.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 248.00 | 240.89 | 426.62 | 379.90 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 303.00 | 242.90 | 368.61 | 326.23 |
| ========== | 607-00015 | End Post (Spec) | | Each | | | |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 48.00 | 300.00 | 612.33 | 570.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 48.00 | 300.00 | 612.33 | 570.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 48.00 | 300.00 | 612.33 | 570.00 |
| ========== | 607-00020 | Corner and Line Br Post (Spec) | | Each | | | |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 57.00 | 400.00 | 788.33 | 750.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 57.00 | 400.00 | 788.33 | 750.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 8.00 | 200.00 | 570.08 | 520.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 8.00 | 200.00 | 570.08 | 520.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 65.00 | 375.38 | 723.67 | 721.69 |
| ========== | 607-01000 | Fence BW MP | | Lin Foot | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 605.00 | 1.50 | 2.51 | 2.40 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 6,665.00 | 1.10 | 1.72 | 1.70 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 7,270.00 | 1.13 | 1.22 | 1.03 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 2,226.00 | 7.00 | 1.30 | 1.26 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2,226.00 | 7.00 | 1.30 | 1.26 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 607-01000 | Fence BW MP | | Lin Foot | | | |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 12,820.00 | 1.50 | 1.04 | 1.05 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 12,820.00 | 1.50 | 1.14 | 1.12 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 1,896.00 | 1.50 | 1.75 | 1.77 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 656.00 | 3.00 | 1.87 | 1.28 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 2,404.00 | 1.50 | 1.50 | 1.50 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 775.00 | 5.00 | 2.70 | 3.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 5,731.00 | 2.15 | 1.71 | 1.77 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 28,047.00 | 1.97 | 1.27 | 1.11 |
| ========== | 607-01010 | Fence BW MP (Spec) | | Lin Foot | | | |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 272.00 | 2.25 | 3.07 | 3.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 272.00 | 2.25 | 1.81 | 1.38 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 272.00 | 2.25 | 1.81 | 1.38 |
| ========== | 607-01050 | Fence Wire MP | | Lin Foot | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1,606.00 | 1.50 | 1.80 | 1.70 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1,606.00 | 1.50 | 1.80 | 1.70 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,606.00 | 1.50 | 1.80 | 1.70 |
| ========== | 607-01100 | Fence BW TWP | | Lin Foot | | | |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 10,850.00 | 2.20 | 2.99 | 3.20 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 10,850.00 | 2.20 | 2.99 | 3.20 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 10,850.00 | 2.20 | 2.99 | 3.20 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 607-11300 | Fence CW TWP | | Lin Foot | | | |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 1,303.00 | 3.00 | 2.85 | 2.50 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 35.00 | 20.00 | 17.31 | 10.60 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1,338.00 | 3.44 | 3.18 | 2.71 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,338.00 | 3.44 | 3.18 | 2.71 |
| ========== | 607-11350 | Fence Deer | | Lin Foot | | | |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 11,115.00 | 10.00 | 11.47 | 11.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 11,115.00 | 10.00 | 11.19 | 9.59 |
| SHE025A-013 | | I 25 BETWEEN MP 122 AND MP 12 | 11/03/11 | 55,319.00 | 7.00 | 8.84 | 6.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 2,270.00 | 17.00 | 8.18 | 9.50 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 57,589.00 | 7.39 | 8.81 | 6.14 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 68,704.00 | 7.82 | 9.10 | 6.94 |
| ========== | 607-11525 | Fence (Plastic) | | Lin Foot | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 500.00 | 2.50 | 3.39 | 3.50 |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 250.00 | 3.35 | 2.96 | 4.00 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 1,000.00 | 3.25 | 2.23 | 2.60 |
| NH 0241-056 | | US 24 BUENA VISTA NORTH | 03/03/11 | 200.00 | 1.00 | 2.50 | 2.00 |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 120.00 | 3.00 | 4.16 | 3.95 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 460.00 | 3.00 | 5.02 | 8.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 5,000.00 | 3.00 | 2.63 | 2.18 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 7,530.00 | 2.96 | 2.74 | 2.76 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 2,390.00 | 3.00 | 2.98 | 2.38 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 400.00 | 4.00 | 5.22 | 4.70 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 6,560.00 | 2.00 | 2.00 | 2.00 |
| C0241-055 | | SH 24 MP 148-152 | 05/26/11 | 508.00 | 3.00 | 2.93 | 1.90 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 607-11525 | Fence (Plastic) | | Lin Foot | | | |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 1,399.00 | 1.60 | 1.96 | 1.15 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 1,100.00 | 4.00 | 2.46 | 3.18 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 1,042.00 | 4.00 | 1.97 | 1.24 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 2,560.00 | 2.00 | 3.25 | 2.40 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 2,000.00 | 3.00 | 2.70 | 2.50 |
| FSA 0502-064 | | US 50 EAST OF SARGENTS | 06/23/11 | 1,200.00 | 4.00 | 3.08 | 3.32 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1,169.00 | 6.00 | 2.83 | 3.02 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 120.00 | 3.00 | 6.35 | 3.20 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 20,448.00 | 2.81 | 2.92 | 2.43 |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 200.00 | 2.50 | 3.03 | 1.60 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 300.00 | 3.50 | 2.12 | 2.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 1,940.00 | 2.00 | 2.76 | 3.30 |
| NH0403-053 | | US 40 RETAINING WALL REPAIR | 07/28/11 | 1,000.00 | 2.50 | 2.96 | 3.29 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 400.00 | 3.00 | 3.01 | 3.00 |
| NH5502-070 | | US 550 4 MILES SOUTH OF OURAY | 08/18/11 | 500.00 | 5.00 | 4.33 | 6.00 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 260.00 | 4.00 | 4.06 | 4.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 200.00 | 4.00 | 2.81 | 3.00 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 200.00 | 2.00 | 3.32 | 2.45 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 100.00 | 5.00 | 2.83 | 2.50 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 1,200.00 | 2.50 | 3.06 | 1.50 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 6,300.00 | 2.76 | 2.95 | 3.01 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 418.00 | 4.00 | 2.88 | 3.31 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 2,000.00 | 2.50 | 3.72 | 4.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 2,050.00 | 3.00 | 3.50 | 4.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 1,300.00 | 3.00 | 3.83 | 4.03 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 100.00 | 6.00 | 11.50 | 3.00 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 200.00 | 4.00 | 3.19 | 3.00 |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 400.00 | 5.00 | 4.50 | 6.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 1,000.00 | 3.00 | 2.37 | 2.30 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 7,468.00 | 3.10 | 3.43 | 3.81 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 41,746.00 | 2.88 | 2.98 | 2.80 |
| ========== | 607-11530 | Fence (Spec) | | Lin Foot | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 624.00 | 100.00 | 220.76 | 208.47 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 624.00 | 100.00 | 220.76 | 208.47 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 607-11530 | Fence (Spec) | | Lin Foot | | | |
| IM0703-368 | | GEORGETOWN HILL CHUTES 6,7,9, | 12/01/11 | 995.00 | 550.00 | 557.34 | 440.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 995.00 | 550.00 | 557.34 | 440.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,619.00 | 376.56 | 370.07 | 350.76 |
| ========== | 607-11580 | Fence (Temp) | | Lin Foot | | | |
| ITS4701-121 | | C470 (SANTA FE TO I-25) AND R | 01/20/11 | 100.00 | 3.00 | 7.00 | 2.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 900.00 | 3.00 | 7.55 | 5.34 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 1,000.00 | 3.00 | 7.52 | 5.01 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 1,000.00 | 3.00 | 3.53 | 2.00 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 1,000.00 | 5.00 | 2.29 | 1.29 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 2,000.00 | 4.00 | 3.04 | 1.65 |
| C006A-051 | | US 6 (LOVELAND PASS), CLEAR C | 07/14/11 | 250.00 | 8.00 | 4.08 | 8.50 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 250.00 | 8.00 | 3.69 | 4.27 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 363.00 | 2.50 | 10.57 | 12.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 363.00 | 2.50 | 10.57 | 12.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3,613.00 | 3.85 | 5.43 | 3.85 |
| ========== | 607-13064 | Fence Msnry (Sound) (64 In) | | Lin Foot | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 510.00 | 100.00 | 161.08 | 170.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 510.00 | 100.00 | 161.08 | 170.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 510.00 | 100.00 | 161.08 | 170.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 607-13088 | Fence Msnry (Sound)(88 In) | | Lin Foot | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 44.00 | 135.00 | 208.55 | 170.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 44.00 | 135.00 | 208.55 | 170.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 44.00 | 135.00 | 208.55 | 170.00 |
| ========== | 607-13096 | Fence Msnry (Sound) (96 In) | | Lin Foot | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 56.00 | 145.00 | 219.61 | 190.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 56.00 | 145.00 | 219.61 | 190.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 56.00 | 145.00 | 219.61 | 190.00 |
| ========== | 607-13104 | Fence Msnry (Sound) (104 In) | | Lin Foot | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 112.00 | 155.00 | 227.40 | 200.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 112.00 | 155.00 | 227.40 | 200.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 112.00 | 155.00 | 227.40 | 200.00 |
| ========== | 607-13112 | Fence Msnry (Sound) (112 In) | | Lin Foot | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 44.00 | 170.00 | 242.71 | 220.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 44.00 | 170.00 | 242.71 | 220.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 44.00 | 170.00 | 242.71 | 220.00 |
| ========== | 607-13144 | Fence Msnry (Sound) (144 In) | | Lin Foot | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 948.00 | 215.00 | 263.56 | 270.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 948.00 | 215.00 | 263.56 | 270.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 948.00 | 215.00 | 263.56 | 270.00 |
| ========== | 607-14000 | Fence Comp (Sound) | | Sq Foot | | | |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 2,615.00 | 30.00 | 42.00 | 30.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 2,615.00 | 30.00 | 42.00 | 30.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,615.00 | 30.00 | 42.00 | 30.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 607-20124 | Glare Screen (24 In) | | Lin Foot | | | |
| C2854-125 | | US 285, ASPEN PARK TO MORRISO | 12/08/11 | 9,948.00 | 17.00 | 16.25 | 17.75 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 9,948.00 | 17.00 | 16.25 | 17.75 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 9,948.00 | 17.00 | 16.25 | 17.75 |
| ========== | 607-53001 | Fence CL (PVC) | | Lin Foot | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 685.00 | 66.00 | 29.14 | 29.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 685.00 | 66.00 | 29.14 | 29.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 685.00 | 66.00 | 29.14 | 29.00 |
| ========== | 607-53005 | Fence CL (Spec) | | Lin Foot | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 467.00 | 30.00 | 221.19 | 220.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 467.00 | 30.00 | 221.19 | 220.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 467.00 | 30.00 | 221.19 | 220.00 |
| ========== | 607-53137 | Fence CL (Spec) (36 In) | | Lin Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 11,134.00 | 21.86 | 24.52 | 22.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 11,134.00 | 21.86 | 24.52 | 22.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 2,489.00 | 35.00 | 28.74 | 30.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 851.00 | 30.00 | 20.87 | 25.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 325.00 | 25.00 | 21.14 | 19.51 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 3,665.00 | 32.95 | 26.04 | 27.91 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 404.00 | 25.00 | 30.00 | 29.18 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 404.00 | 25.00 | 30.00 | 29.18 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 15,203.00 | 24.62 | 25.40 | 25.04 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 607-53142 | Fence CL (42 In) | | Lin Foot | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 2,037.00 | 60.00 | 23.79 | 24.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2,037.00 | 60.00 | 23.79 | 24.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,037.00 | 60.00 | 23.79 | 24.00 |
| ========== | 607-53143 | Fence CL (Spec) (42 In) | | Lin Foot | | | |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1,967.00 | 18.00 | 18.00 | 21.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1,967.00 | 18.00 | 18.00 | 21.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,967.00 | 18.00 | 18.00 | 21.00 |
| ========== | 607-53160 | Fence CL (60 In) | | Lin Foot | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 285.00 | 60.00 | 46.14 | 55.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 285.00 | 60.00 | 46.14 | 55.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 200.00 | 30.00 | 23.38 | 20.62 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 200.00 | 30.00 | 23.38 | 20.62 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 485.00 | 47.63 | 35.14 | 40.82 |
| ========== | 607-53161 | Fence CL (Spec) (60 In) | | Lin Foot | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 400.00 | 30.00 | 23.04 | 17.61 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 400.00 | 30.00 | 23.04 | 17.61 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 916.00 | 25.00 | 23.03 | 25.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 916.00 | 25.00 | 23.03 | 25.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,316.00 | 26.52 | 23.03 | 22.75 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 607-53172 | Fence CL (72 In) | | Lin Foot | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 725.00 | 12.00 | 22.64 | 24.21 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 725.00 | 12.00 | 22.64 | 24.21 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 605.00 | 35.00 | 19.80 | 25.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 605.00 | 35.00 | 19.80 | 25.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 38.00 | 25.00 | 37.74 | 35.75 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 38.00 | 25.00 | 37.74 | 35.75 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,368.00 | 22.53 | 21.74 | 24.88 |
| ========== | 607-53173 | Fence CL (Spec) (72 In) | | Lin Foot | | | |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 396.00 | 25.00 | 26.53 | 31.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 392.00 | 35.00 | 31.82 | 27.69 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 788.00 | 29.97 | 29.77 | 29.35 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 788.00 | 29.97 | 29.77 | 29.35 |
| ========== | 607-53196 | Fence CL (96 In) | | Lin Foot | | | |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 390.00 | 30.00 | 44.63 | 55.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 390.00 | 30.00 | 44.63 | 55.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 390.00 | 30.00 | 44.63 | 55.00 |
| ========== | 607-55030 | Mesh Post | | Each | | | |
| SHE0402-081 | | US 40 - MP 113 TO 120 ROUTT C | 10/27/11 | 46.00 | 1340.00 | 2589.13 | 3030.78 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 607-55030 | Mesh Post | | Each | | | |
| IM0703-368 | | GEORGETOWN HILL CHUTES 6,7,9, | 12/01/11 | 6.00 | 5200.00 | 5272.85 | 4800.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 52.00 | 1785.38 | 2753.44 | 3234.92 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 52.00 | 1785.38 | 2753.44 | 3234.92 |
| ========== | 607-55031 | Mesh Post (Spec) | | Each | | | |
| SHE0402-081 | | US 40 - MP 113 TO 120 ROUTT C | 10/27/11 | 28.00 | 1800.00 | 2691.85 | 3285.78 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 28.00 | 1800.00 | 2691.85 | 3285.78 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 28.00 | 1800.00 | 2691.85 | 3285.78 |
| ========== | 607-55040 | Mesh Anchor | | Each | | | |
| NH5502-070 | | US 550 4 MILES SOUTH OF OURAY | 08/18/11 | 20.00 | 200.00 | 607.20 | 610.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 20.00 | 200.00 | 607.20 | 610.00 |
| IM0703-368 | | GEORGETOWN HILL CHUTES 6,7,9, | 12/01/11 | 18.00 | 238.00 | 500.36 | 575.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 18.00 | 238.00 | 500.36 | 575.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 38.00 | 218.00 | 556.59 | 593.42 |
| ========== | 607-55060 | Mesh Pin | | Each | | | |
| SHE0402-081 | | US 40 - MP 113 TO 120 ROUTT C | 10/27/11 | 150.00 | 100.00 | 257.40 | 122.38 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 150.00 | 100.00 | 257.40 | 122.38 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 150.00 | 100.00 | 257.40 | 122.38 |
| ========== | 607-55100 | Wire Mesh | | Sq Foot | | | |
| SHE0402-081 | | US 40 - MP 113 TO 120 ROUTT C | 10/27/11 | 195,500.00 | 3.90 | 3.75 | 2.74 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 195,500.00 | 3.90 | 3.75 | 2.74 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 195,500.00 | 3.90 | 3.75 | 2.74 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 607-55101 | Cable Net (1/2 In) | | Sq Foot | | | |
| IM0703-368 | | GEORGETOWN HILL CHUTES 6,7,9, | 12/01/11 | 19,200.00 | 15.00 | 13.32 | 11.70 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 19,200.00 | 15.00 | 13.32 | 11.70 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 19,200.00 | 15.00 | 13.32 | 11.70 |
| ========== | 607-55102 | Cable Net (5/16 In) | | Sq Foot | | | |
| NH5502-070 | | US 550 4 MILES SOUTH OF OURAY | 08/18/11 | 16,000.00 | 6.00 | 8.49 | 8.40 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 16,000.00 | 6.00 | 8.49 | 8.40 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 16,000.00 | 6.00 | 8.49 | 8.40 |
| ========== | 607-60001 | Pedest Gate (Spec) | | Each | | | |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 11.00 | 550.00 | 520.00 | 500.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 11.00 | 550.00 | 598.21 | 487.19 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 11.00 | 550.00 | 598.21 | 487.19 |
| ========== | 607-60002 | Game Ramp | | Each | | | |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 7.00 | 7000.00 | 8187.00 | 7700.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 7.00 | 7000.00 | 7958.85 | 6524.58 |
| SHE025A-013 | | I 25 BETWEEN MP 122 AND MP 12 | 11/03/11 | 11.00 | 7000.00 | 9538.95 | 7650.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 11.00 | 7000.00 | 9538.95 | 7650.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 18.00 | 7000.00 | 9026.11 | 7087.29 |
| ========== | 607-60113 | 12 Ft Gate (Spec) | | Each | | | |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 5.00 | 400.00 | 363.57 | 280.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 5.00 | 400.00 | 363.57 | 280.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 607-60113 | 12 Ft Gate (Spec) | | Each | | | |
| SHE025A-013 | | I 25 BETWEEN MP 122 AND MP 12 | 11/03/11 | 2.00 | 280.00 | 1670.41 | 1370.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 280.00 | 1670.41 | 1370.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 7.00 | 365.71 | 673.67 | 591.43 |
| ========== | 607-60116 | 16 Ft Gate | | Each | | | |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 6.00 | 300.00 | 740.34 | 734.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 6.00 | 300.00 | 740.34 | 734.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 6.00 | 300.00 | 740.34 | 734.00 |
| ========== | 607-60117 | 16 Ft Gate (Spec) | | Each | | | |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 1.00 | 2000.00 | 1021.34 | 1100.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 2000.00 | 1021.34 | 1100.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 2000.00 | 1021.34 | 1100.00 |
| ========== | 607-60121 | 20 Ft Gate (Spec) | | Each | | | |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 2.00 | 600.00 | 698.52 | 440.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 2.00 | 600.00 | 698.52 | 440.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 600.00 | 698.52 | 440.00 |
| ========== | 607-60212 | 12 Ft Gate S (CL) | | Each | | | |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 1.00 | 500.00 | 520.39 | 510.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 1.00 | 500.00 | 520.39 | 510.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 500.00 | 520.39 | 510.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 607-60266 | 16 Ft Gate D (CL) | | Each | | | |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 13.00 | 900.00 | 1287.33 | 1200.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 13.00 | 900.00 | 1287.33 | 1200.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 13.00 | 900.00 | 1287.33 | 1200.00 |
| ========== | 607-60620 | Road Closure Gate | | Each | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 1.00 | 11000.00 | 10384.10 | 10200.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1.00 | 11000.00 | 10384.10 | 10200.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 11000.00 | 10384.10 | 10200.00 |
| ========== | 608-00000 | Conc Sidewalk | | Sq Yard | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 245.00 | 30.00 | 42.74 | 45.35 |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 123.00 | 40.00 | 32.72 | 35.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 368.00 | 33.34 | 35.53 | 34.52 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 14.00 | 50.00 | 57.50 | 50.00 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 2,047.00 | 30.00 | 27.91 | 19.35 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 6.00 | 40.00 | 43.97 | 51.60 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 163.00 | 45.00 | 32.75 | 31.50 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 18.00 | 40.00 | 57.75 | 48.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2,248.00 | 31.32 | 29.55 | 22.88 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 16.00 | 30.00 | 47.20 | 34.30 |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 120.00 | 50.00 | 35.42 | 35.10 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 41.00 | 50.00 | 52.05 | 34.78 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 3,882.00 | 30.00 | 27.71 | 17.00 |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 36.00 | 50.00 | 62.00 | 64.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 4,095.00 | 30.96 | 28.54 | 18.39 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 608-00000 | Conc Sidewalk | | Sq Yard | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 13,089.00 | 25.00 | 22.69 | 21.20 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 381.00 | 30.00 | 30.00 | 31.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 1,037.00 | 32.00 | 28.46 | 28.68 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 32.00 | 100.00 | 92.70 | 93.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 14,539.00 | 25.80 | 23.34 | 22.15 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 21,250.00 | 27.51 | 25.23 | 22.09 |
| ========== | 608-00006 | Conc Sidewalk (6 In) | | Sq Yard | | | |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 37.00 | 40.00 | 42.75 | 56.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 37.00 | 40.00 | 42.75 | 56.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 433.00 | 37.00 | 28.92 | 30.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 476.00 | 35.00 | 38.83 | 47.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1,591.00 | 40.00 | 30.30 | 27.57 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 82.00 | 50.00 | 50.40 | 52.80 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2,582.00 | 38.89 | 32.99 | 33.39 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 108.00 | 45.00 | 53.67 | 60.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 1,577.00 | 35.00 | 33.44 | 32.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1,685.00 | 35.64 | 34.34 | 34.37 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1,839.00 | 25.00 | 31.03 | 27.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 749.00 | 35.00 | 33.14 | 30.44 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 129.60 | 40.00 | 38.68 | 31.28 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2,717.60 | 28.47 | 32.30 | 28.15 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 7,021.60 | 34.08 | 33.17 | 31.79 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 608-00010 | Conc Curb Ramp | | Sq Yard | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 40.00 | 100.00 | 91.64 | 76.10 |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 173.00 | 110.00 | 70.70 | 48.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 213.00 | 108.12 | 79.69 | 59.40 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 88.00 | 75.00 | 71.82 | 55.00 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 656.00 | 75.00 | 84.68 | 65.00 |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 12.00 | 100.00 | 103.02 | 94.50 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 63.00 | 90.00 | 94.48 | 56.80 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 6.00 | 100.00 | 162.00 | 157.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 118.00 | 100.00 | 100.50 | 75.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 221.00 | 65.00 | 103.76 | 112.31 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 40.00 | 110.00 | 133.50 | 142.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1,204.00 | 77.94 | 90.29 | 76.70 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 216.00 | 80.00 | 107.72 | 94.00 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 77.00 | 100.00 | 102.67 | 115.00 |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 48.00 | 80.00 | 109.80 | 108.00 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 107.00 | 100.00 | 122.40 | 112.35 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 96.00 | 120.00 | 108.91 | 115.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 267.00 | 80.00 | 75.65 | 40.00 |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 11.00 | 80.00 | 119.00 | 88.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 822.00 | 89.15 | 99.67 | 85.12 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 524.00 | 125.00 | 102.71 | 160.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 163.00 | 100.00 | 91.30 | 57.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 24.00 | 125.00 | 105.10 | 98.72 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 31.90 | 100.00 | 111.73 | 105.11 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 65.00 | 120.00 | 133.42 | 134.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 807.90 | 118.57 | 102.21 | 133.14 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3,046.90 | 93.84 | 95.02 | 91.79 |
| ========== | 608-00011 | Curb Ramp (Fast Track) | | Sq Yard | | | |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 75.00 | 110.00 | 92.02 | 92.61 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 75.00 | 110.00 | 92.02 | 92.61 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 75.00 | 110.00 | 92.02 | 92.61 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 608-00015 | Detectable Warnings | | Sq Foot | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 96.00 | 40.00 | 29.61 | 19.30 |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 424.00 | 35.00 | 33.68 | 25.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 520.00 | 35.92 | 33.03 | 23.95 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 162.00 | 28.00 | 39.84 | 44.00 |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 12.00 | 50.00 | 67.61 | 70.35 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 304.00 | 40.00 | 51.36 | 39.20 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 576.00 | 40.00 | 36.55 | 38.27 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 80.00 | 75.00 | 43.33 | 34.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1,134.00 | 40.86 | 42.33 | 38.79 |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 40.00 | 80.00 | 52.50 | 53.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 40.00 | 80.00 | 52.50 | 53.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 88.00 | 50.00 | 49.64 | 33.50 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 40.00 | 60.00 | 43.16 | 13.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 201.60 | 42.00 | 45.39 | 50.76 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 329.60 | 46.32 | 46.28 | 41.57 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,023.60 | 41.25 | 40.86 | 35.95 |
| ========== | 608-00026 | Conc Bikeway (6 In) | | Sq Yard | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 1,282.00 | 35.00 | 43.32 | 45.10 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1,282.00 | 35.00 | 43.32 | 45.10 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,282.00 | 35.00 | 43.32 | 45.10 |
| ========== | 608-00350 | Conc Sidewalk (C) | | Sq Yard | | | |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 356.00 | 45.00 | 47.05 | 51.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 608-00350 | Conc Sidewalk (C) | | Sq Yard | | | |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 344.00 | 55.00 | 72.75 | 76.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 700.00 | 49.91 | 58.69 | 63.29 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 700.00 | 49.91 | 58.69 | 63.29 |
| ========== | 608-01000 | Bitum Sidewalk | | Ton | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 12.00 | 150.00 | 184.95 | 165.08 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 12.00 | 150.00 | 184.95 | 165.08 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 12.00 | 150.00 | 184.95 | 165.08 |
| ========== | 608-10010 | Sidewalk Drain | | Each | | | |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 2.00 | 1000.00 | 2032.84 | 2165.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2.00 | 1000.00 | 2032.84 | 2165.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 1000.00 | 2286.30 | 2498.00 |
| ========== | 609-20010 | Curb Ty 2 B | | Lin Foot | | | |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 32.00 | 20.00 | 19.77 | 25.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 32.00 | 20.00 | 19.77 | 25.00 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 24.00 | 20.00 | 33.62 | 35.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 221.00 | 18.00 | 21.42 | 14.50 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 245.00 | 18.20 | 22.43 | 16.51 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 109.00 | 18.00 | 18.36 | 8.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 52.00 | 20.00 | 16.93 | 12.13 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 685.00 | 15.00 | 24.73 | 33.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 846.00 | 15.69 | 23.62 | 28.50 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,123.00 | 16.36 | 23.35 | 25.78 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 609-21010 | C and G Ty 2 I-B | | Lin Foot | ========== | ========== | ========== |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 2,394.00 | 14.00 | 13.94 | 13.60 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 33.00 | 20.00 | 19.17 | 13.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 383.00 | 18.00 | 19.33 | 20.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 631.00 | 12.00 | 11.28 | 9.34 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 3,441.00 | 14.14 | 14.10 | 13.53 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 536.00 | 11.00 | 14.12 | 14.95 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 189.00 | 30.00 | 23.50 | 26.00 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 388.00 | 20.00 | 18.64 | 16.05 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 1,665.00 | 13.00 | 12.15 | 13.00 |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 282.00 | 25.00 | 19.50 | 16.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 3,060.00 | 15.69 | 13.70 | 14.96 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 6,060.00 | 12.00 | 10.00 | 9.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 65.00 | 20.00 | 15.50 | 24.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 700.00 | 15.00 | 15.48 | 15.12 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 1,929.00 | 16.00 | 18.55 | 19.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 8,754.00 | 13.18 | 12.75 | 11.80 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 15,255.00 | 13.90 | 13.19 | 12.83 |
| ========== | 609-21011 | C and G Ty 2 I-M | | Lin Foot | ========== | ========== | ========== |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 1,420.00 | 13.00 | 13.31 | 13.04 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1,420.00 | 13.00 | 13.74 | 11.43 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 3,865.00 | 12.00 | 12.72 | 10.98 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 3,865.00 | 12.00 | 12.72 | 10.98 |
| MC0504-065 | | US50B FROM MP 318 TO MP 359 | 12/01/11 | 44.00 | 13.00 | 22.33 | 21.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 44.00 | 13.00 | 22.33 | 21.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 5,329.00 | 12.27 | 13.47 | 11.31 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 609-21020 | C and G Ty 2 II-B | | Lin Foot | ========== | ========== | ========== |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 571.00 | 15.00 | 23.12 | 15.75 |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 2,389.00 | 13.00 | 14.93 | 15.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 868.00 | 18.00 | 17.16 | 21.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 575.00 | 15.00 | 15.64 | 14.77 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 4,403.00 | 14.51 | 16.34 | 15.47 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 351.00 | 18.00 | 18.60 | 18.00 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 13,093.00 | 12.00 | 10.59 | 11.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 528.00 | 18.00 | 17.09 | 12.00 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 774.00 | 18.00 | 16.15 | 15.50 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 361.00 | 20.00 | 22.13 | 19.00 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 174.00 | 20.00 | 14.13 | 13.65 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 100.00 | 15.00 | 22.50 | 20.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 822.00 | 15.00 | 23.08 | 24.50 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 3,523.00 | 12.00 | 12.91 | 11.03 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 117.00 | 20.00 | 21.25 | 22.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 19,843.00 | 12.90 | 12.26 | 12.21 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 403.00 | 13.00 | 15.52 | 16.05 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 240.00 | 20.00 | 28.83 | 32.00 |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 240.00 | 14.00 | 18.84 | 19.50 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 120.00 | 25.00 | 22.10 | 18.73 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 1,570.00 | 16.00 | 13.64 | 13.50 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 7,950.00 | 20.00 | 12.77 | 12.25 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 18.00 | 50.00 | 27.70 | 30.00 |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 44.00 | 30.00 | 25.00 | 25.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 10,585.00 | 19.15 | 13.67 | 13.52 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 17,959.00 | 12.00 | 11.29 | 11.50 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1,002.00 | 15.00 | 14.17 | 18.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 1,320.00 | 14.00 | 15.42 | 14.56 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 609-21020 | C and G Ty 2 II-B | | Lin Foot | | | |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1,308.00 | 16.00 | 16.43 | 16.66 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 40.00 | 50.00 | 30.02 | 30.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 2,586.00 | 17.00 | 23.39 | 24.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 24,215.00 | 13.05 | 13.54 | 13.58 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 59,046.00 | 14.20 | 13.34 | 13.23 |
| ========== | 609-21021 | C and G Ty 2 II-M | | Lin Foot | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 1,795.00 | 16.00 | 20.24 | 14.90 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 2,555.00 | 15.00 | 15.10 | 15.41 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 4,350.00 | 15.41 | 16.67 | 15.20 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 850.00 | 19.00 | 17.52 | 16.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 302.00 | 18.00 | 24.92 | 28.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 1,152.00 | 18.74 | 19.46 | 19.15 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 19.00 | 22.00 | 24.41 | 19.30 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 130.00 | 50.00 | 31.60 | 32.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 149.00 | 46.43 | 28.95 | 30.38 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 5,651.00 | 16.91 | 17.34 | 16.40 |
| ========== | 609-21110 | C & G Ty 2 I-B (Spec) | | Lin Foot | | | |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 590.00 | 16.00 | 21.17 | 22.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 590.00 | 16.00 | 21.17 | 22.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 848.00 | 20.00 | 24.50 | 30.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 848.00 | 20.00 | 24.50 | 30.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,438.00 | 18.36 | 23.23 | 26.72 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 609-23000 | Gutter (Special) | | Lin Foot | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 271.00 | 33.00 | 47.14 | 55.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 271.00 | 33.00 | 47.14 | 55.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 52.00 | 40.00 | 19.98 | 16.77 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 52.00 | 40.00 | 19.98 | 16.77 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 323.00 | 34.13 | 41.61 | 48.85 |
| ========== | 609-24002 | Gutter Ty 2 (2 Ft) | | Lin Foot | | | |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 10.00 | 30.00 | 24.01 | 38.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 131.00 | 12.00 | 17.24 | 18.73 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 141.00 | 13.28 | 17.61 | 20.10 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 15.00 | 30.00 | 24.57 | 41.30 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 1,882.00 | 12.00 | 17.40 | 17.00 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 442.00 | 12.00 | 17.08 | 16.80 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 2,800.00 | 15.00 | 20.25 | 27.57 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 5,139.00 | 13.69 | 18.94 | 22.81 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 605.00 | 18.00 | 13.61 | 9.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1,296.00 | 15.00 | 18.69 | 16.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 156.00 | 12.00 | 23.49 | 23.16 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2,057.00 | 15.65 | 17.39 | 14.48 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 7,337.00 | 14.23 | 18.49 | 20.43 |
| ========== | 609-24004 | Gutter Ty 2 (4 Ft) | | Lin Foot | | | |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 98.00 | 24.00 | 36.67 | 35.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 98.00 | 24.00 | 36.67 | 35.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 609-24004 | Gutter Ty 2 (4 Ft) | | Lin Foot | | | |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 402.00 | 20.00 | 22.92 | 23.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 402.00 | 20.00 | 22.92 | 23.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 528.00 | 15.00 | 22.30 | 16.30 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 181.00 | 20.00 | 31.53 | 32.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 709.00 | 16.28 | 24.11 | 20.31 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,209.00 | 18.14 | 24.53 | 22.39 |
| ========== | 609-24005 | Gutter Ty 2 (5 Ft) | | Lin Foot | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 38.00 | 16.00 | 31.84 | 20.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 38.00 | 16.00 | 31.84 | 20.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 38.00 | 16.00 | 31.84 | 20.00 |
| ========== | 609-24006 | Gutter Ty 2 (6 Ft) | | Lin Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 512.00 | 25.00 | 36.58 | 33.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 512.00 | 25.00 | 36.58 | 33.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 624.00 | 75.00 | 31.62 | 34.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 624.00 | 75.00 | 31.62 | 34.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,136.00 | 52.46 | 32.96 | 33.83 |
| ========== | 609-24008 | Gutter Ty 2 (8 Ft) | | Lin Foot | | | |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 32.00 | 50.00 | 45.34 | 61.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 32.00 | 50.00 | 45.34 | 61.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 32.00 | 50.00 | 45.34 | 61.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 609-24100 | Gutter Ty 2 Variable | | Lin Foot | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 217.00 | 36.00 | 35.49 | 40.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 217.00 | 36.00 | 35.49 | 40.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 217.00 | 36.00 | 35.49 | 40.00 |
| ========== | 609-31010 | C and G Ty 2 I-B (Fast Track) | | Lin Foot | | | |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 1,235.00 | 15.00 | 14.52 | 16.06 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 1,235.00 | 15.00 | 14.52 | 16.06 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,235.00 | 15.00 | 14.52 | 16.06 |
| ========== | 609-31020 | C and G Ty 2 II-B (Fast Track) | | Lin Foot | | | |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 250.00 | 20.00 | 19.57 | 18.87 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 250.00 | 20.00 | 19.57 | 18.87 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 250.00 | 20.00 | 19.57 | 18.87 |
| ========== | 609-40010 | Curb Ty 4 B | | Lin Foot | | | |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 287.00 | 40.00 | 14.26 | 35.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 287.00 | 40.00 | 14.26 | 35.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 287.00 | 40.00 | 14.26 | 35.00 |
| ========== | 609-40011 | Curb Ty 4 M | | Lin Foot | | | |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 290.00 | 9.00 | 15.52 | 15.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 290.00 | 9.00 | 15.52 | 15.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 6.00 | 40.00 | 25.27 | 10.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 6.00 | 40.00 | 25.27 | 10.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 296.00 | 9.63 | 15.63 | 14.90 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 609-60011 | Curb Ty 6 M | | Lin Foot | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 84.00 | 11.50 | 29.82 | 30.00 |
| NH 0241-056 | | US 24 BUENA VISTA NORTH | 03/03/11 | 1,110.00 | 7.00 | 8.25 | 9.00 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 594.00 | 8.00 | 13.50 | 18.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 10.00 | 15.00 | 67.42 | 22.01 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1,798.00 | 7.59 | 10.80 | 11.24 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 1,560.00 | 10.00 | 7.70 | 9.50 |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 375.00 | 8.00 | 10.16 | 6.20 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 650.00 | 8.00 | 8.19 | 13.40 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 1,124.00 | 7.00 | 6.97 | 7.39 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 222.00 | 9.00 | 18.71 | 32.50 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 190.00 | 12.00 | 13.65 | 21.00 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 12.00 | 20.00 | 30.25 | 26.25 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 621.00 | 8.00 | 9.56 | 9.50 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 2,743.00 | 8.00 | 10.60 | 16.00 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 674.00 | 10.00 | 16.05 | 15.75 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 792.00 | 10.00 | 9.09 | 7.04 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 8,963.00 | 8.68 | 8.90 | 10.69 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 302.00 | 13.00 | 10.01 | 11.87 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 302.00 | 13.00 | 11.88 | 9.81 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 702.00 | 6.00 | 6.17 | 6.25 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 4,812.00 | 7.00 | 7.54 | 5.85 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 472.00 | 10.00 | 10.61 | 12.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 5,986.00 | 7.12 | 7.48 | 6.38 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 17,049.00 | 8.09 | 8.91 | 9.60 |
| ========== | 610-00020 | Median Cover (Pattern Conc) | | Sq Foot | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 11,318.00 | 6.00 | 6.81 | 5.25 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 610-00020 | Median Cover (Pattern Conc) | | Sq Foot | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 7,065.00 | 7.00 | 5.84 | 6.41 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 18,383.00 | 6.38 | 6.11 | 4.85 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 8,429.00 | 6.00 | 5.54 | 5.15 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 1,745.00 | 6.00 | 7.48 | 7.44 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 1,101.00 | 8.00 | 8.39 | 8.70 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 11,275.00 | 6.20 | 6.04 | 5.85 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 793.00 | 4.00 | 9.73 | 6.05 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 856.00 | 8.00 | 8.78 | 8.03 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 2,877.00 | 8.00 | 6.09 | 9.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 4,526.00 | 7.30 | 6.87 | 8.30 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 23,558.00 | 5.00 | 5.15 | 5.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 23,558.00 | 5.00 | 5.15 | 5.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 57,742.00 | 5.85 | 5.88 | 5.21 |
| ========== | 610-00024 | Median Cover (4 In Pattern Conc) | | Sq Foot | | | |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 4,130.00 | 9.00 | 6.00 | 6.75 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 4,130.00 | 9.00 | 6.00 | 6.75 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 14,199.00 | 6.00 | 5.38 | 4.67 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 14,199.00 | 6.00 | 5.38 | 4.67 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 18,329.00 | 6.68 | 5.44 | 5.14 |
| ========== | 610-00026 | Median Cover (6 In Pattern Conc) | | Sq Foot | | | |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 1,351.00 | 20.00 | 9.00 | 10.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1,351.00 | 20.00 | 9.00 | 10.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 610-00026 | Median Cover (6 In Pattern Conc) | | Sq Foot | | | |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 31,648.00 | 8.00 | 7.45 | 6.50 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 31,648.00 | 8.00 | 7.45 | 6.50 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 32,999.00 | 8.49 | 7.46 | 6.64 |
| ========== | 610-00030 | Median Cover Matl (Conc) | | Sq Foot | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 558.00 | 8.00 | 6.80 | 5.50 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 3,022.00 | 8.00 | 7.26 | 6.64 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 3,580.00 | 8.00 | 7.19 | 6.46 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 3,813.00 | 6.00 | 5.44 | 6.75 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 3,813.00 | 6.00 | 5.44 | 6.75 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 3,793.00 | 8.00 | 5.45 | 6.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 100.00 | 7.00 | 9.63 | 8.82 |
| MC0504-065 | | US50B FROM MP 318 TO MP 359 | 12/01/11 | 112.00 | 7.00 | 8.92 | 9.75 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 4,005.00 | 7.95 | 5.67 | 6.18 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 11,398.00 | 7.31 | 6.02 | 6.46 |
| ========== | 610-00110 | Median Edging | | Lin Foot | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 2,642.00 | 100.00 | 13.48 | 9.19 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2,642.00 | 100.00 | 13.48 | 9.19 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,642.00 | 100.00 | 13.48 | 9.19 |
| ========== | 611-00016 | 16 Ft Cattle Gd | | Each | | | |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 1.00 | 8000.00 | 7616.90 | 9000.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1.00 | 8000.00 | 7616.90 | 9000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 8000.00 | 7616.90 | 9000.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 611-00017 | 16 Ft Deer Gd | | Each | | | |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 8.00 | 24000.00 | 25570.67 | 24000.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 8.00 | 24000.00 | 25026.95 | 24946.51 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 8.00 | 24000.00 | 25026.95 | 24946.51 |
| ========== | 611-00019 | 18 Ft Deer Gd | | Each | | | |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 2.00 | 25000.00 | 26752.67 | 25000.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2.00 | 25000.00 | 26752.67 | 25000.00 |
| SHE025A-013 | | I 25 BETWEEN MP 122 AND MP 12 | 11/03/11 | 5.00 | 21000.00 | 36914.41 | 32000.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 5.00 | 21000.00 | 36914.41 | 32000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 7.00 | 22142.86 | 35427.32 | 30000.00 |
| ========== | 611-00025 | 24 Ft Deer Gd | | Each | | | |
| SHE025A-013 | | I 25 BETWEEN MP 122 AND MP 12 | 11/03/11 | 3.00 | 35000.00 | 40623.20 | 42355.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 3.00 | 35000.00 | 40623.20 | 42355.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3.00 | 35000.00 | 41028.94 | 44355.47 |
| ========== | 611-00026 | 26 Ft Cattle Gd | | Each | | | |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 2.00 | 8000.00 | 11705.25 | 9750.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2.00 | 8000.00 | 11705.25 | 9750.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 8000.00 | 11705.25 | 9750.00 |
| ========== | 612-00001 | Delin (Ty I) | | Each | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 56.00 | 18.00 | 19.13 | 17.55 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 612-00001 | Delin (Ty I) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 304.00 | 20.00 | 28.05 | 26.55 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 5.00 | 19.50 | 26.68 | 13.00 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 44.00 | 15.00 | 16.94 | 15.00 |
| NH 2852-017 | | US 285 PONCHA PASS SOUTH RESU | 03/03/11 | 146.00 | 20.00 | 27.73 | 62.00 |
| NH 0241-056 | | US 24 BUENA VISTA NORTH | 03/03/11 | 246.00 | 19.00 | 16.67 | 22.00 |
| STA0504-061 | | US 50 M.P.369.9 -M.P.373.2 | 03/03/11 | 125.00 | 15.00 | 23.51 | 15.97 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 64.00 | 17.00 | 24.62 | 24.21 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 990.00 | 18.59 | 22.06 | 26.89 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 248.00 | 20.00 | 23.10 | 23.00 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 4.00 | 20.00 | 26.21 | 22.00 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 180.00 | 20.00 | 28.33 | 31.00 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 7.00 | 20.00 | 26.63 | 32.90 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 14.00 | 20.00 | 20.07 | 19.00 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 170.00 | 20.00 | 26.97 | 25.00 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 127.00 | 16.00 | 21.50 | 22.00 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 60.00 | 20.00 | 21.51 | 17.25 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 26.00 | 20.00 | 16.54 | 18.75 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 4.00 | 25.00 | 28.37 | 27.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 8.00 | 20.00 | 18.65 | 17.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 140.00 | 10.00 | 22.33 | 24.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 500.00 | 20.00 | 16.19 | 15.35 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 154.00 | 20.00 | 25.11 | 24.14 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1,642.00 | 18.85 | 21.78 | 20.68 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 150.00 | 17.50 | 17.24 | 16.19 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 47.00 | 16.00 | 21.39 | 19.90 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 15.00 | 20.00 | 37.09 | 19.36 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 144.00 | 20.00 | 14.06 | 12.60 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 40.00 | 40.00 | 22.16 | 24.00 |
| STR096A-040 | | SH 96 MP 193 TO MP 201 | 09/01/11 | 120.00 | 30.00 | 23.46 | 21.37 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 38.00 | 16.00 | 22.89 | 21.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 554.00 | 22.32 | 19.88 | 18.47 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 14.00 | 30.00 | 21.19 | 13.57 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 612-00001 | Delin (Ty I) | | Each | | | |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 56.00 | 19.00 | 19.75 | 16.42 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 28.00 | 20.00 | 21.86 | 19.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 2.00 | 24.00 | 19.16 | 17.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 3.00 | 18.00 | 26.82 | 27.58 |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 5.00 | 15.00 | 47.65 | 73.60 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 24.00 | 25.00 | 24.40 | 26.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 10.00 | 17.00 | 25.83 | 18.00 |
| MC0504-065 | | US50B FROM MP 318 TO MP 359 | 12/01/11 | 11.00 | 30.00 | 33.67 | 20.00 |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 516.00 | 25.00 | 18.02 | 15.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 195.00 | 30.00 | 17.75 | 16.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 864.00 | 25.55 | 18.65 | 16.22 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4,050.00 | 20.69 | 20.95 | 20.89 |
| ========== | 612-00002 | Delin (Ty II) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 56.00 | 22.00 | 33.51 | 22.19 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| NH 0241-056 | | US 24 BUENA VISTA NORTH | 03/03/11 | 40.00 | 20.00 | 18.18 | 24.00 |
| STA0504-061 | | US 50 M.P.369.9 -M.P.373.2 | 03/03/11 | 187.00 | 16.00 | 24.70 | 18.10 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 14.00 | 18.00 | 25.64 | 25.31 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 297.00 | 17.76 | 24.29 | 19.88 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 65.00 | 21.00 | 24.14 | 24.00 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 47.00 | 21.00 | 24.81 | 23.00 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 6.00 | 20.00 | 28.49 | 32.90 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 6.00 | 22.00 | 21.08 | 20.00 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 180.00 | 22.00 | 27.16 | 25.00 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 135.00 | 17.00 | 22.50 | 23.00 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 20.00 | 22.00 | 22.30 | 18.33 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 2.00 | 22.00 | 17.61 | 20.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 18.00 | 27.00 | 19.09 | 28.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 29.00 | 22.00 | 20.24 | 18.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 62.00 | 15.00 | 22.33 | 24.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 140.00 | 22.00 | 17.26 | 16.37 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 8.00 | 20.00 | 49.50 | 28.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 21.00 | 30.00 | 25.63 | 24.14 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 739.00 | 20.66 | 23.67 | 22.52 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 612-00002 | Delin (Ty II) | | Each | | | |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 50.00 | 17.50 | 19.22 | 18.35 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 47.00 | 17.00 | 22.91 | 21.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 12.00 | 20.00 | 19.23 | 18.80 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 3.00 | 18.00 | 23.91 | 21.00 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 2.00 | 50.00 | 25.92 | 20.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 114.00 | 18.14 | 21.04 | 19.59 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 86.00 | 20.00 | 21.94 | 18.61 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 26.00 | 21.00 | 22.71 | 18.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 8.00 | 25.00 | 20.94 | 19.00 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 9.00 | 28.00 | 25.68 | 27.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 55.00 | 35.00 | 19.67 | 18.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 184.00 | 25.23 | 21.16 | 18.77 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,334.00 | 20.43 | 23.18 | 21.28 |
| ========== | 612-00003 | Delin (Ty III) | | Each | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 4.00 | 20.00 | 93.86 | 350.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 16.00 | 25.00 | 55.24 | 23.74 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 7.00 | 23.00 | 29.41 | 15.00 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 4.00 | 18.00 | 20.30 | 17.00 |
| NH 2852-017 | | US 285 PONCHA PASS SOUTH RESU | 03/03/11 | 35.00 | 25.00 | 30.42 | 68.00 |
| NH 0241-056 | | US 24 BUENA VISTA NORTH | 03/03/11 | 66.00 | 21.00 | 20.87 | 26.00 |
| STA0504-061 | | US 50 M.P.369.9 -M.P.373.2 | 03/03/11 | 34.00 | 17.00 | 26.69 | 20.23 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 2.00 | 20.00 | 26.94 | 26.41 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 168.00 | 21.38 | 26.71 | 36.38 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 48.00 | 22.00 | 25.19 | 25.00 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 10.00 | 22.00 | 26.90 | 24.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 612-00003 | Delin (Ty III) | | Each | | | |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 20.00 | 20.00 | 37.67 | 41.00 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 16.00 | 25.00 | 20.33 | 19.00 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 4.00 | 25.00 | 31.35 | 32.90 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 35.00 | 18.00 | 23.50 | 24.00 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 20.00 | 24.00 | 25.22 | 19.41 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 34.00 | 24.00 | 19.69 | 22.50 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 7.00 | 30.00 | 26.73 | 30.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 4.00 | 24.00 | 22.12 | 20.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 43.00 | 20.00 | 23.33 | 24.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 86.00 | 24.00 | 18.31 | 17.40 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 1.00 | 25.00 | 50.25 | 28.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 23.00 | 40.00 | 26.33 | 24.14 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 351.00 | 23.58 | 25.92 | 23.08 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 25.00 | 20.00 | 20.67 | 19.43 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 56.00 | 19.00 | 24.47 | 21.10 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 10.00 | 20.00 | 20.67 | 20.40 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 4.00 | 50.00 | 26.08 | 28.00 |
| STR096A-040 | | SH 96 MP 193 TO MP 201 | 09/01/11 | 6.00 | 35.00 | 25.79 | 21.37 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 12.00 | 20.00 | 24.47 | 21.00 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 14.00 | 50.00 | 32.67 | 39.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 127.00 | 24.52 | 25.95 | 23.39 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 2.00 | 42.00 | 24.90 | 15.88 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 6.00 | 23.00 | 26.36 | 22.99 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 19.00 | 21.00 | 24.57 | 20.00 |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 15.00 | 17.00 | 63.97 | 75.87 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 8.00 | 30.00 | 26.85 | 28.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 10.00 | 20.00 | 31.88 | 20.00 |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 2.00 | 40.00 | 65.00 | 100.00 |
| MC0504-065 | | US50B FROM MP 318 TO MP 359 | 12/01/11 | 11.00 | 30.00 | 38.00 | 25.00 |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 134.00 | 30.00 | 21.20 | 19.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 9.00 | 40.00 | 22.12 | 21.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 216.00 | 28.27 | 25.41 | 24.64 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 862.00 | 24.47 | 26.00 | 26.16 |
| ========== | 612-00021 | Delin (Ty I) (Barrier) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 824.00 | 11.00 | 19.19 | 15.87 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 612-00021 | Delin (Ty I) (Barrier) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 149.00 | 20.00 | 13.82 | 16.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 973.00 | 12.38 | 17.44 | 15.92 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 51.00 | 16.00 | 15.76 | 14.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 51.00 | 16.00 | 16.98 | 14.19 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 23.00 | 11.00 | 17.92 | 30.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 23.00 | 11.00 | 17.92 | 30.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,047.00 | 12.52 | 17.41 | 16.46 |
| ========== | 612-00022 | Delin (Ty II) (Barrier) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 124.00 | 12.00 | 21.01 | 13.27 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| C0703-363 | | CLEAR CREEK AND JEFFERSON COU | 02/17/11 | 3,285.00 | 15.00 | 11.16 | 13.50 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 234.00 | 24.00 | 15.73 | 19.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 28.00 | 20.00 | 14.50 | 11.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 3,671.00 | 15.51 | 11.61 | 13.84 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 7.00 | 16.00 | 17.14 | 15.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 7.00 | 16.00 | 17.14 | 15.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 49.00 | 11.00 | 19.52 | 35.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 49.00 | 11.00 | 19.52 | 35.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3,727.00 | 15.45 | 11.71 | 14.13 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 612-00031 | Delin (Ty I) (Extra Ht) | | Each | | | |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 325.00 | 25.00 | 31.33 | 28.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 325.00 | 25.00 | 31.33 | 28.00 |
| C006A-051 | | US 6 (LOVELAND PASS), CLEAR C | 07/14/11 | 8.00 | 45.00 | 40.20 | 36.80 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 8.00 | 45.00 | 35.57 | 34.53 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 333.00 | 25.48 | 31.53 | 28.23 |
| ========== | 612-00032 | Delin (Ty II) (Extra Ht) | | Each | | | |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 30.00 | 25.00 | 34.17 | 30.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 30.00 | 25.00 | 34.17 | 30.00 |
| C006A-051 | | US 6 (LOVELAND PASS), CLEAR C | 07/14/11 | 2.00 | 45.00 | 38.40 | 38.60 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 2.00 | 45.00 | 38.40 | 38.60 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 32.00 | 26.25 | 34.51 | 30.54 |
| ========== | 612-00033 | Delin (Ty III) (Extra Ht) | | Each | | | |
| C006A-051 | | US 6 (LOVELAND PASS), CLEAR C | 07/14/11 | 2.00 | 45.00 | 40.94 | 41.75 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 2.00 | 45.00 | 40.94 | 41.75 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 45.00 | 40.94 | 41.75 |
| ========== | 612-00041 | Delin (Flex) (Ty I) | | Each | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 2.00 | 50.00 | 52.13 | 88.00 |
| C0703-363 | | CLEAR CREEK AND JEFFERSON COU | 02/17/11 | 1,999.00 | 22.00 | 50.27 | 41.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 612-00041 | Delin (Flex) (Ty I) | | Each | | | |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 120.00 | 30.00 | 32.71 | 34.05 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 2,121.00 | 22.48 | 49.43 | 40.65 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 24.00 | 30.00 | 53.45 | 36.00 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 11.00 | 30.00 | 39.10 | 29.57 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 35.00 | 30.00 | 47.38 | 33.98 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 9.00 | 50.00 | 101.67 | 78.00 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 9.00 | 50.00 | 101.67 | 78.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 2,165.00 | 22.72 | 49.51 | 40.70 |
| ========== | 612-00042 | Delin (Flex) (Ty II) | | Each | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 1.00 | 90.00 | 53.13 | 88.00 |
| C0703-363 | | CLEAR CREEK AND JEFFERSON COU | 02/17/11 | 249.00 | 40.00 | 52.35 | 42.00 |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 15.00 | 35.00 | 33.97 | 34.05 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 265.00 | 39.91 | 51.48 | 41.72 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 11.00 | 33.00 | 40.87 | 31.68 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 11.00 | 33.00 | 40.87 | 31.68 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 276.00 | 39.63 | 50.92 | 41.32 |
| ========== | 612-00043 | Delin (Flex) (Ty III) | | Each | | | |
| C0703-363 | | CLEAR CREEK AND JEFFERSON COU | 02/17/11 | 305.00 | 41.00 | 54.61 | 43.00 |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 30.00 | 35.00 | 34.38 | 34.05 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 335.00 | 40.46 | 53.07 | 42.20 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 612-00043 | Delin (Flex) (Ty III) | | Each | | | |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 7.00 | 36.00 | 41.88 | 33.80 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 7.00 | 36.00 | 41.88 | 33.80 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 342.00 | 40.37 | 52.77 | 42.03 |
| ========== | 612-00060 | Reflector (Median Barrier) | | Each | | | |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 19.00 | 25.00 | 14.71 | 16.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 19.00 | 25.00 | 14.71 | 16.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 19.00 | 25.00 | 14.71 | 16.00 |
| ========== | 612-00065 | Reflector Strip (1-1/2 In) | | Each | | | |
| C0703-363 | | CLEAR CREEK AND JEFFERSON COU | 02/17/11 | 965.00 | 8.15 | 21.97 | 29.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 965.00 | 8.15 | 21.97 | 29.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 965.00 | 8.15 | 21.97 | 29.00 |
| ========== | 612-00075 | Reflector Strip (6 In) | | Each | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 20,781.00 | 20.00 | 15.63 | 14.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 20,781.00 | 20.00 | 15.63 | 14.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 20,781.00 | 20.00 | 15.63 | 14.00 |
| ========== | 612-00081 | Delin (PM) (Ty I) | | Each | | | |
| C0703-363 | | CLEAR CREEK AND JEFFERSON COU | 02/17/11 | 1,314.00 | 18.00 | 24.50 | 18.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1,314.00 | 18.00 | 24.50 | 18.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,314.00 | 18.00 | 24.50 | 18.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 612-00082 | Delin (PM)(Ty II) | | Each | | | |
| C0703-363 | | CLEAR CREEK AND JEFFERSON COU | 02/17/11 | 172.00 | 19.00 | 27.25 | 20.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 172.00 | 19.00 | 27.25 | 20.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 172.00 | 19.00 | 27.25 | 20.00 |
| ========== | 612-00083 | Delin (PM)(Ty III) | | Each | | | |
| C0703-363 | | CLEAR CREEK AND JEFFERSON COU | 02/17/11 | 24.00 | 20.00 | 29.84 | 21.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 24.00 | 20.00 | 29.84 | 21.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 24.00 | 20.00 | 29.84 | 21.00 |
| ========== | 612-00101 | Delin (Drv Conc Inst) (Ty I) | | Each | | | |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 920.00 | 72.00 | 99.84 | 90.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 920.00 | 72.00 | 103.18 | 88.22 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 920.00 | 72.00 | 103.18 | 88.22 |
| ========== | 612-00102 | Delin (Drv Conc Inst) (Ty II) | | Each | | | |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 130.00 | 75.00 | 101.21 | 90.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 130.00 | 75.00 | 112.25 | 85.53 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 130.00 | 75.00 | 112.25 | 85.53 |
| ========== | 612-00103 | Delin (Drv Conc Inst) (Ty III) | | Each | | | |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 40.00 | 80.00 | 106.99 | 90.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 40.00 | 80.00 | 123.03 | 84.39 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 40.00 | 80.00 | 123.03 | 84.39 |
| ========== | 612-00104 | Delin (Drv Conc Inst) (Ty I) (Fr Only) | | Each | | | |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 180.00 | 33.00 | 34.99 | 40.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 180.00 | 33.00 | 37.13 | 40.14 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 180.00 | 33.00 | 37.13 | 40.14 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 612-00105 | Delin (Drv Conc Inst) (Ty II) (Fr Only) | | Each | | | |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 80.00 | 35.00 | 35.81 | 40.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 80.00 | 35.00 | 40.09 | 40.55 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 80.00 | 35.00 | 40.09 | 40.55 |
| ========== | 612-00106 | Delin (Drv Conc Inst) (Ty III) (Fr Only) | | Each | | | |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 40.00 | 35.00 | 36.93 | 40.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 40.00 | 35.00 | 44.26 | 41.29 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 40.00 | 35.00 | 44.26 | 41.29 |
| ========== | 612-00107 | Delin (Mounted) (Ty III) | | Each | | | |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 57.00 | 25.00 | 53.06 | 60.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 57.00 | 25.00 | 53.06 | 60.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 57.00 | 25.00 | 53.06 | 60.00 |
| ========== | 612-00108 | Delin (Mounted) (Ty III) (Fr Only) | | Each | | | |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 20.00 | 20.00 | 18.31 | 20.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 20.00 | 20.00 | 18.31 | 20.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 20.00 | 20.00 | 18.31 | 20.00 |
| ========== | 612-00260 | Loc Mark (Fib Opt)(Dome) | | Each | | | |
| C0704-225 | | I-70 EAST OF BENNETT | 01/06/11 | 5.00 | 100.00 | 112.25 | 40.00 |
| ITS4701-121 | | C470 (SANTA FE TO I-25) AND R | 01/20/11 | 46.00 | 80.00 | 87.50 | 41.00 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 4.00 | 80.00 | 70.61 | 80.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 8.00 | 100.00 | 120.57 | 165.08 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 63.00 | 84.13 | 92.09 | 57.60 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 612-00260 | Loc Mark (Fib Opt)(Dome) | | Each | | | |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 12.00 | 100.00 | 47.06 | 47.00 |
| ITS0703-370 | | EAST OF EJMT ON I-70 EB LANES | 06/16/11 | 5.00 | 90.00 | 103.67 | 110.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 17.00 | 97.06 | 74.85 | 40.35 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 2.00 | 150.00 | 65.18 | 65.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 12.00 | 75.00 | 119.02 | 100.61 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 14.00 | 85.71 | 113.94 | 95.52 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 94.00 | 86.70 | 83.86 | 47.20 |
| ========== | 612-00266 | Loc Mark (Electronic)(Ball) | | Each | | | |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 14.00 | 100.00 | 127.17 | 20.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 14.00 | 100.00 | 127.17 | 20.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 14.00 | 100.00 | 127.17 | 20.00 |
| ========== | 612-00270 | Loc Mark (Util)(Flat Slat) | | Each | | | |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 20.00 | 70.00 | 73.00 | 70.00 |
| ITS0703-370 | | EAST OF EJMT ON I-70 EB LANES | 06/16/11 | 8.00 | 88.00 | 86.00 | 99.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 28.00 | 75.14 | 96.96 | 68.41 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 2.00 | 100.00 | 61.88 | 65.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 100.00 | 61.88 | 65.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 30.00 | 76.80 | 95.86 | 68.33 |
| ========== | 613-00075 | 3/4 In Elec Cond | | Lin Foot | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 43.00 | 8.00 | 16.99 | 17.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 613-00075 | 3/4 In Elec Cond | | Lin Foot | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 360.00 | 4.00 | 1.59 | 1.51 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 403.00 | 4.43 | 10.45 | 15.24 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 16.00 | 20.00 | 11.15 | 7.00 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 16.00 | 20.00 | 11.15 | 7.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 419.00 | 5.02 | 10.46 | 15.12 |
| ========== | 613-00100 | 1 In Elec Cond | | Lin Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 1,904.00 | 10.00 | 9.17 | 9.10 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 2,762.00 | 8.00 | 7.00 | 5.50 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 4,666.00 | 8.82 | 7.36 | 5.76 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 745.00 | 8.00 | 13.34 | 8.45 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 242.00 | 10.00 | 18.97 | 19.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 610.00 | 9.00 | 15.37 | 15.00 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 1,597.00 | 8.69 | 15.24 | 14.34 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 147.00 | 5.00 | 4.18 | 4.15 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 147.00 | 5.00 | 4.18 | 4.15 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 494.00 | 9.00 | 4.28 | 2.10 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 382.00 | 6.00 | 15.41 | 12.07 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 876.00 | 7.69 | 10.44 | 6.45 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 7,286.00 | 8.58 | 9.77 | 8.53 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 613-00125 | 1-1/4 In Elec Cond | | Lin Foot | | | |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 60.00 | 5.00 | 24.50 | 26.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 60.00 | 5.00 | 24.50 | 26.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 60.00 | 5.00 | 24.50 | 26.00 |
| ========== | 613-00128 | 1 1/4 Inch Elec Cond (Multi)(Jacked) | | Lin Foot | | | |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 780.00 | 30.00 | 24.56 | 20.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 780.00 | 30.00 | 24.56 | 20.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 780.00 | 30.00 | 24.56 | 20.00 |
| ========== | 613-00150 | 1-1/2 In Elec Cond | | Lin Foot | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 20.00 | 10.00 | 28.60 | 55.02 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 20.00 | 10.00 | 28.60 | 55.02 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 604.00 | 5.00 | 4.23 | 4.02 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 604.00 | 5.00 | 16.84 | 26.23 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 624.00 | 5.16 | 17.20 | 26.65 |
| ========== | 613-00151 | 1-1/2 In Elec Cond (Jacked) | | Lin Foot | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 200.00 | 11.00 | 14.80 | 14.08 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 200.00 | 11.00 | 14.80 | 14.08 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 200.00 | 11.00 | 14.80 | 14.08 |
| ========== | 613-00200 | 2 In Elec Cond | | Lin Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 77,674.00 | 7.38 | 7.83 | 7.65 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 613-00200 | 2 In Elec Cond | | Lin Foot | ========== | ========== | ========== |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 4,702.00 | 9.00 | 4.10 | 6.60 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 82,376.00 | 7.47 | 6.55 | 6.50 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 1,490.00 | 8.00 | 8.74 | 8.45 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 10,406.00 | 8.00 | 7.11 | 7.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 702.00 | 12.00 | 3.91 | 2.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 1,702.00 | 8.00 | 3.58 | 3.20 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1,264.00 | 3.00 | 7.41 | 7.04 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 15,564.00 | 7.77 | 7.36 | 8.51 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 9,850.00 | 7.00 | 8.92 | 9.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 1,677.00 | 8.00 | 4.70 | 4.70 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 11,527.00 | 7.15 | 7.61 | 8.39 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 299.00 | 10.00 | 8.01 | 4.35 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 784.00 | 8.00 | 5.36 | 5.52 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 6,135.00 | 8.00 | 5.11 | 4.02 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 4,000.00 | 11.00 | 12.18 | 12.00 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 100.00 | 10.00 | 12.33 | 11.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 11,318.00 | 9.13 | 6.77 | 7.01 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 120,785.00 | 7.64 | 6.80 | 7.26 |
| ========== | 613-00201 | 2 In Elec Cond (Jacked) | | Lin Foot | ========== | ========== | ========== |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 130.00 | 15.00 | 16.82 | 15.94 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 130.00 | 15.00 | 16.82 | 15.94 |
| ITSSW00-928 | | NB I-225 AT MM 2.28 | 11/03/11 | 450.00 | 12.00 | 11.01 | 7.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 450.00 | 12.00 | 11.01 | 7.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 580.00 | 12.67 | 12.81 | 10.05 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 613-00203 | 2 Inch Elec Cond (Multi)(Jacked) | | Lin Foot | | | |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 390.00 | 30.00 | 27.44 | 20.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 390.00 | 30.00 | 27.44 | 20.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 390.00 | 30.00 | 27.44 | 20.00 |
| ========== | 613-00206 | 2 In Elec Cond (Bored) | | Lin Foot | | | |
| C0704-225 | | I-70 EAST OF BENNETT | 01/06/11 | 600.00 | 8.00 | 9.54 | 7.00 |
| ITS4701-121 | | C470 (SANTA FE TO I-25) AND R | 01/20/11 | 6,050.00 | 8.00 | 11.58 | 12.70 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 2,000.00 | 10.00 | 49.16 | 48.42 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 8,650.00 | 8.46 | 25.58 | 20.56 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 4,700.00 | 9.00 | 8.84 | 9.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 135.00 | 12.00 | 27.14 | 27.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 1,500.00 | 9.00 | 8.35 | 7.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 8,034.00 | 10.00 | 14.45 | 7.26 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 2,676.00 | 25.00 | 50.67 | 53.00 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 440.00 | 12.00 | 14.98 | 8.95 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 17,485.00 | 12.01 | 13.18 | 11.63 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 2,050.00 | 20.00 | 18.58 | 22.00 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 4,020.00 | 11.00 | 13.02 | 14.21 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 6,070.00 | 14.04 | 14.98 | 15.27 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 217.00 | 9.00 | 8.86 | 8.51 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1,630.00 | 20.00 | 9.25 | 9.30 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 8,408.00 | 9.00 | 10.00 | 7.04 |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 1,500.00 | 20.00 | 47.40 | 43.61 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 840.00 | 30.00 | 25.80 | 20.00 |
| C2854-125 | | US 285, ASPEN PARK TO MORRISO | 12/08/11 | 330.00 | 20.00 | 51.00 | 31.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 12,925.00 | 13.31 | 13.57 | 13.05 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 45,130.00 | 11.97 | 14.68 | 12.92 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 613-00300 | 3 In Elec Cond | | Lin Foot | ========== | ========== | ========== |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 9,400.00 | 10.00 | 11.06 | 9.10 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 237.00 | 12.00 | 9.23 | 11.50 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 9,637.00 | 10.05 | 10.92 | 9.32 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 745.00 | 10.00 | 9.54 | 9.51 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 280.00 | 9.00 | 9.31 | 9.50 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 851.00 | 10.00 | 7.19 | 7.50 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 896.00 | 20.00 | 12.75 | 12.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 2,772.00 | 13.13 | 15.85 | 28.71 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 50.00 | 25.00 | 19.00 | 10.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 50.00 | 25.00 | 19.00 | 10.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1,615.00 | 10.00 | 8.38 | 3.50 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 392.00 | 10.00 | 6.44 | 6.62 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 2,007.00 | 10.00 | 7.84 | 4.11 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 14,466.00 | 10.68 | 12.11 | 15.86 |
| ========== | 613-00306 | 3 In Elec Cond (Bored) | | Lin Foot | ========== | ========== | ========== |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 1,500.00 | 12.00 | 12.32 | 11.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 227.00 | 14.00 | 68.00 | 62.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 1,394.00 | 13.00 | 16.12 | 9.11 |
| ITS0703-370 | | EAST OF EJMT ON I-70 EB LANES | 06/16/11 | 110.00 | 33.00 | 61.83 | 34.50 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 150.00 | 15.00 | 18.98 | 17.85 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 880.00 | 12.00 | 17.60 | 10.20 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 4,261.00 | 13.08 | 21.85 | 19.62 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 613-00306 | 3 In Elec Cond (Bored) | | Lin Foot | | | |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 2,300.00 | 20.00 | 18.50 | 17.50 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 3,100.00 | 12.00 | 14.38 | 14.04 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 655.00 | 12.00 | 16.71 | 16.50 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 6,055.00 | 15.04 | 15.99 | 15.07 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 575.00 | 15.00 | 11.86 | 11.99 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1,550.00 | 11.00 | 10.97 | 8.05 |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 1,700.00 | 22.00 | 48.87 | 33.49 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 3,825.00 | 16.49 | 22.76 | 19.95 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 14,141.00 | 14.84 | 19.93 | 17.75 |
| ========== | 613-00400 | 4 In Elec Cond | | Lin Foot | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1,896.00 | 11.00 | 17.17 | 16.34 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 1,896.00 | 11.00 | 17.17 | 16.34 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,896.00 | 11.00 | 17.17 | 16.34 |
| ========== | 613-00402 | Inst 4 In Elec Cond | | Lin Foot | | | |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 3,540.00 | 10.00 | 2.02 | 1.25 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 3,540.00 | 10.00 | 2.02 | 1.25 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3,540.00 | 10.00 | 2.02 | 1.25 |
| ========== | 613-00408 | 4 In Elec Cond (Bored) | | Lin Foot | | | |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 2,700.00 | 15.00 | 18.08 | 18.30 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 2,700.00 | 15.00 | 18.08 | 18.30 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,700.00 | 15.00 | 18.08 | 18.30 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 613-00602 | Inst 6 In Elec Cond | | Lin Foot | | | |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1,180.00 | 15.00 | 2.73 | 1.50 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1,180.00 | 15.00 | 2.73 | 1.50 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,180.00 | 15.00 | 2.73 | 1.50 |
| ========== | 613-01100 | 1 In Elec Cond (P) | | Lin Foot | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 1,050.00 | 8.00 | 4.89 | 6.60 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1,050.00 | 8.00 | 4.89 | 6.60 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 250.00 | 10.00 | 10.08 | 10.56 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 250.00 | 10.00 | 10.08 | 10.56 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,300.00 | 8.38 | 5.89 | 7.36 |
| ========== | 613-01150 | 1-1/2 In Elec Cond (P) | | Lin Foot | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 4,100.00 | 6.00 | 6.63 | 6.39 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 4,100.00 | 6.00 | 6.63 | 6.39 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4,100.00 | 6.00 | 6.63 | 6.39 |
| ========== | 613-01200 | 2 In Elec Cond (P) | | Lin Foot | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 194.00 | 10.00 | 16.33 | 11.70 |
| C0704-225 | | I-70 EAST OF BENNETT | 01/06/11 | 3,700.00 | 5.00 | 4.70 | 2.24 |
| ITS4701-121 | | C470 (SANTA FE TO I-25) AND R | 01/20/11 | 3,035.00 | 7.00 | 6.63 | 4.40 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 14,360.00 | 9.00 | 5.76 | 5.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 4,290.00 | 12.00 | 10.08 | 12.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 6,000.00 | 9.00 | 7.54 | 7.70 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 31,579.00 | 8.75 | 7.31 | 6.79 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 613-01200 | 2 In Elec Cond (P) | | Lin Foot | | | |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 100.00 | 7.00 | 13.56 | 6.65 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 3,080.00 | 7.00 | 11.37 | 10.56 |
| SHE074A-001 | | SH 74 - EVERGREEN - JEFFERSON | 04/28/11 | 100.00 | 6.00 | 13.75 | 6.75 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 2,850.00 | 8.00 | 8.65 | 8.50 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 6,400.00 | 8.00 | 4.50 | 4.10 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 64,400.00 | 6.00 | 4.15 | 4.79 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 1,984.00 | 15.00 | 13.88 | 13.75 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 3,970.00 | 7.00 | 7.06 | 6.79 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 200.00 | 6.00 | 7.53 | 6.80 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 83,084.00 | 6.52 | 5.93 | 4.06 |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 750.00 | 9.00 | 11.53 | 7.00 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 2,250.00 | 8.00 | 8.62 | 10.17 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 1,539.00 | 7.00 | 9.97 | 10.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 4,756.00 | 10.00 | 7.67 | 7.35 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 9,295.00 | 8.94 | 8.88 | 8.46 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 497.00 | 9.00 | 8.86 | 8.51 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 815.00 | 10.00 | 14.29 | 7.55 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 4,600.00 | 8.00 | 12.08 | 12.95 |
| ITSSW00-928 | | NB I-225 AT MM 2.28 | 11/03/11 | 800.00 | 6.00 | 7.82 | 6.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 100.00 | 8.00 | 5.99 | 5.52 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1,200.00 | 9.00 | 9.29 | 7.04 |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 550.00 | 8.00 | 12.21 | 11.83 |
| C2854-125 | | US 285, ASPEN PARK TO MORRISO | 12/08/11 | 1,130.00 | 10.00 | 12.92 | 11.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 7,800.00 | 10.00 | 10.58 | 8.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 17,492.00 | 9.12 | 10.85 | 9.44 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 141,450.00 | 7.50 | 6.78 | 4.79 |
| ========== | 613-01250 | 2-1/2 In Elec Cond (P) | | Lin Foot | | | |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 2,811.00 | 11.00 | 8.27 | 8.40 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 2,811.00 | 11.00 | 8.27 | 8.40 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,811.00 | 11.00 | 8.27 | 8.40 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 613-01300 | 3 In Elec Cond (P) | | Lin Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 13,160.00 | 10.00 | 7.36 | 6.50 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 572.00 | 12.00 | 9.42 | 2.40 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 650.00 | 12.00 | 15.19 | 13.21 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 14,382.00 | 10.17 | 8.67 | 7.18 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 200.00 | 8.00 | 14.82 | 10.00 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 1,420.00 | 11.00 | 16.12 | 12.67 |
| SHE074A-001 | | SH 74 - EVERGREEN - JEFFERSON | 04/28/11 | 100.00 | 7.00 | 15.25 | 8.25 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 440.00 | 10.00 | 10.10 | 10.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 4,873.00 | 11.50 | 15.10 | 14.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 400.00 | 11.00 | 20.27 | 5.88 |
| ITS0703-370 | | EAST OF EJMT ON I-70 EB LANES | 06/16/11 | 4,120.00 | 7.50 | 11.46 | 7.85 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 3,410.00 | 8.00 | 8.44 | 8.05 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 400.00 | 11.00 | 8.60 | 7.70 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 15,363.00 | 9.46 | 12.80 | 10.88 |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 600.00 | 11.00 | 13.88 | 9.00 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 250.00 | 12.00 | 12.31 | 16.09 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 850.00 | 11.29 | 13.51 | 10.52 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1,630.00 | 12.00 | 15.17 | 8.70 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 85.00 | 10.00 | 16.21 | 16.45 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 860.00 | 10.00 | 10.16 | 8.05 |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 450.00 | 9.00 | 12.60 | 8.40 |
| MC0504-065 | | US50B FROM MP 318 TO MP 359 | 12/01/11 | 1,020.00 | 10.00 | 6.17 | 7.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 2,300.00 | 12.00 | 12.37 | 9.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 6,345.00 | 11.17 | 12.37 | 8.53 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 36,940.00 | 10.07 | 11.72 | 9.83 |
| ========== | 613-01400 | 4 In Elec Cond (P) | | Lin Foot | | | |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 1,402.00 | 13.00 | 16.25 | 10.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1,402.00 | 13.00 | 16.25 | 10.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 613-01400 | 4 In Elec Cond (P) | | Lin Foot | | | |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 150.00 | 15.00 | 25.78 | 28.68 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 150.00 | 15.00 | 25.78 | 28.68 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,552.00 | 13.19 | 17.29 | 11.81 |
| ========== | 613-01600 | 6 In Elec Cond (P) | | Lin Foot | | | |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 30.00 | 15.00 | 26.01 | 18.25 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 30.00 | 15.00 | 26.01 | 18.25 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 30.00 | 15.00 | 26.01 | 18.25 |
| ========== | 613-04130 | 1-1/2 In Elec Cond (Liquidtight Flx Met) | | Lin Foot | | | |
| C0704-225 | | I-70 EAST OF BENNETT | 01/06/11 | 50.00 | 10.00 | 13.86 | 11.25 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 50.00 | 10.00 | 13.86 | 11.25 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 50.00 | 10.00 | 13.86 | 11.25 |
| ========== | 613-05151 | Wildlife Detection System | | Each | | | |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 2.00 | 80100.00 | 67400.00 | 64000.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2.00 | 80100.00 | 65448.29 | 63569.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 80100.00 | 65448.29 | 63569.00 |
| ========== | 613-06000 | Meter Pole | | Each | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 3.00 | 3000.00 | 1807.41 | 2100.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 3.00 | 3000.00 | 1807.41 | 2100.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 2.00 | 2575.00 | 2277.39 | 2300.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2.00 | 2575.00 | 2277.39 | 2300.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 613-06000 | Meter Pole | | Each | | | |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 3.00 | 2000.00 | 2388.08 | 1777.33 |
| C2854-125 | | US 285, ASPEN PARK TO MORRISO | 12/08/11 | 1.00 | 2500.00 | 2666.67 | 3600.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 4.00 | 2125.00 | 2443.80 | 2233.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 9.00 | 2516.67 | 2144.87 | 2203.55 |
| ========== | 613-07000 | Pull Box (Spec) | | Each | | | |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 4.00 | 225.00 | 305.40 | 280.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 12.00 | 250.00 | 674.79 | 700.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 16.00 | 243.75 | 500.96 | 460.00 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 22.00 | 500.00 | 96.50 | 165.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 5.00 | 858.00 | 722.13 | 720.00 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 4.00 | 850.00 | 840.29 | 810.00 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 15.00 | 850.00 | 276.79 | 323.44 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 11.00 | 500.00 | 726.07 | 779.76 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 2.00 | 1000.00 | 3652.00 | 3000.00 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 16.00 | 300.00 | 533.50 | 342.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 75.00 | 583.20 | 491.07 | 471.61 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 24.00 | 300.00 | 462.32 | 475.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 24.00 | 300.00 | 502.21 | 550.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 16.00 | 600.00 | 629.67 | 301.82 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 2.00 | 250.00 | 343.33 | 300.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 18.00 | 561.11 | 616.85 | 301.62 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 133.00 | 488.27 | 520.50 | 465.54 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 613-07016 | Pull Box (16"x16"x6") | | Each | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 1.00 | 418.00 | 686.77 | 690.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 1.00 | 750.00 | 446.08 | 700.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2.00 | 584.00 | 557.17 | 695.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 584.00 | 557.17 | 695.00 |
| ========== | 613-07018 | Pull Box (18"x12"x8") | | Each | | | |
| C2854-125 | | US 285, ASPEN PARK TO MORRISO | 12/08/11 | 6.00 | 250.00 | 546.67 | 630.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 6.00 | 250.00 | 546.67 | 630.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 6.00 | 250.00 | 546.67 | 630.00 |
| ========== | 613-07023 | Pull Box (24"x36"x24") | | Each | | | |
| C0704-225 | | I-70 EAST OF BENNETT | 01/06/11 | 5.00 | 750.00 | 913.50 | 784.00 |
| ITS4701-121 | | C470 (SANTA FE TO I-25) AND R | 01/20/11 | 46.00 | 800.00 | 948.75 | 855.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 16.00 | 700.00 | 975.84 | 900.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 8.00 | 950.00 | 980.03 | 1000.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 75.00 | 791.33 | 954.90 | 870.63 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 4.00 | 775.00 | 715.44 | 702.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 10.00 | 813.00 | 1026.85 | 1000.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 12.00 | 900.00 | 1073.20 | 1100.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 71.00 | 900.00 | 1037.29 | 961.91 |
| ITS0703-370 | | EAST OF EJMT ON I-70 EB LANES | 06/16/11 | 13.00 | 750.00 | 665.00 | 975.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 110.00 | 869.82 | 995.91 | 972.20 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 38.00 | 800.00 | 832.37 | 686.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 38.00 | 800.00 | 832.37 | 686.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 613-07023 | Pull Box (24"x36"x24") | | Each | | | |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 8.00 | 1000.00 | 980.21 | 981.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 21.00 | 1400.00 | 1030.84 | 1120.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 29.00 | 1289.66 | 1014.51 | 1081.66 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 252.00 | 884.25 | 963.59 | 913.94 |
| ========== | 613-07026 | Pull Box (16"x24"x12") | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 52.00 | 300.00 | 657.82 | 600.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 52.00 | 300.00 | 473.05 | 435.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 3.00 | 418.00 | 759.98 | 760.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 3.00 | 418.00 | 759.98 | 760.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 4.00 | 750.00 | 621.17 | 626.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 4.00 | 750.00 | 621.17 | 626.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 59.00 | 336.51 | 531.34 | 494.98 |
| ========== | 613-07034 | Pull Box (24"x36"x18") | | Each | | | |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 24.00 | 750.00 | 665.15 | 672.00 |
| SHE074A-001 | | SH 74 - EVERGREEN - JEFFERSON | 04/28/11 | 4.00 | 900.00 | 1038.33 | 905.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 16.00 | 700.00 | 948.46 | 926.10 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 44.00 | 745.45 | 767.93 | 785.58 |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 4.00 | 700.00 | 733.00 | 425.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 613-07034 | Pull Box (24"x36"x18") | | Each | | | |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 24.00 | 700.00 | 773.45 | 633.00 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 1.00 | 200.00 | 806.67 | 900.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 29.00 | 682.76 | 777.53 | 638.45 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 5.00 | 500.00 | 496.13 | 478.47 |
| ITSSW00-928 | | NB I-225 AT MM 2.28 | 11/03/11 | 4.00 | 800.00 | 932.38 | 720.00 |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 17.00 | 800.00 | 1386.93 | 1317.71 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 26.00 | 742.31 | 1103.34 | 1064.36 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 99.00 | 726.26 | 855.47 | 812.19 |
| ========== | 613-07038 | Pull Box (36"x48"x18") | | Each | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 2.00 | 900.00 | 1250.17 | 1100.53 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 2.00 | 900.00 | 1250.17 | 1100.53 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 8.00 | 900.00 | 1255.15 | 1006.07 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 8.00 | 900.00 | 1255.15 | 1006.07 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 10.00 | 900.00 | 1254.15 | 1024.96 |
| ========== | 613-07039 | Pull Box (30"x48"x18") | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 28.00 | 950.00 | 1224.84 | 1165.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 28.00 | 950.00 | 1224.84 | 1165.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 6.00 | 1100.00 | 1394.58 | 1400.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 6.00 | 1100.00 | 1394.58 | 1400.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 613-07039 | Pull Box (30"x48"x18") | | Each | | | |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 1.00 | 800.00 | 932.00 | 745.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1.00 | 800.00 | 1189.53 | 1206.76 |
| MC0504-065 | | US50B FROM MP 318 TO MP 359 | 12/01/11 | 2.00 | 1200.00 | 1310.00 | 1230.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 1200.00 | 1310.00 | 1230.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 37.00 | 983.78 | 1266.61 | 1248.29 |
| ========== | 613-07040 | Pull Box (30"x48"x24") | | Each | | | |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 1.00 | 1000.00 | 1065.86 | 1100.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 10.00 | 1000.00 | 1349.29 | 1192.16 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 11.00 | 1000.00 | 1257.17 | 1175.69 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 4.00 | 1050.00 | 1085.32 | 857.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 4.00 | 1050.00 | 1085.32 | 857.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 15.00 | 1013.33 | 1165.74 | 1135.95 |
| ========== | 613-07050 | Pull Box (13"x24"x18") Deep | | Each | | | |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 12.00 | 700.00 | 960.17 | 1000.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 12.00 | 700.00 | 960.17 | 1000.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 4.00 | 700.00 | 362.58 | 360.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 4.00 | 700.00 | 362.58 | 360.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 16.00 | 700.00 | 776.29 | 840.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 613-07199 | Inst Pull Box | | Each | ========== | ========== | ========== |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 9.00 | 400.00 | 500.04 | 520.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 9.00 | 400.00 | 500.04 | 520.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 9.00 | 400.00 | 500.04 | 520.00 |
| ========== | 613-10000 | Wiring | | LUMP SUM | ========== | ========== | ========== |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 1.00 | 4000.00 | 2028.84 | 2340.00 |
| C0704-225 | | I-70 EAST OF BENNETT | 01/06/11 | 1.00 | 5000.00 | 9326.50 | 11966.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 1.00 | 135000.00 | 86356.57 | 83600.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 1.00 | 10000.00 | 26089.11 | 31000.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 1.00 | 50000.00 | 33375.09 | 6052.86 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 5.00 | 76125.00 | 30433.89 | 21268.98 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 1.00 | 12500.00 | 5424.09 | 6039.00 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 1.00 | 15000.00 | 29323.07 | 15841.92 |
| SHE074A-001 | | SH 74 - EVERGREEN - JEFFERSON | 04/28/11 | 1.00 | 6500.00 | 6333.33 | 4200.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 1.00 | 25000.00 | 67178.27 | 67300.00 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 1.00 | 3000.00 | 1603.52 | 1048.00 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 1.00 | 5000.00 | 4194.74 | 3234.38 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 1.00 | 25000.00 | 26996.31 | 28000.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 1.00 | 100000.00 | 22076.88 | 9854.50 |
| ITS0703-370 | | EAST OF EJMT ON I-70 EB LANES | 06/16/11 | 1.00 | 25000.00 | 60208.33 | 52975.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 1.00 | 8000.00 | 6703.67 | 2250.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1.00 | 25000.00 | 38226.19 | 36924.57 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 1.00 | 8000.00 | 13267.50 | 8835.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 12.00 | 21500.00 | 38926.81 | 52595.96 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 1.00 | 10000.00 | 7143.33 | 4530.00 |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 1.00 | 5000.00 | 6965.20 | 7500.00 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 1.00 | 40000.00 | 37249.57 | 36773.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 1.00 | 15000.00 | 9170.66 | 7235.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 613-10000 | Wiring | | LUMP SUM | ========== | ========== | ========== |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 1.00 | 60000.00 | 28984.49 | 42000.00 |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 1.00 | 20000.00 | 6840.00 | 7080.00 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 1.00 | 5000.00 | 1081.67 | 250.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 7.00 | 22142.86 | 17049.56 | 17769.65 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 1.00 | 6000.00 | 4961.24 | 4784.65 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1.00 | 20000.00 | 14314.29 | 16900.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1.00 | 40000.00 | 24748.26 | 17068.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 1.00 | 3800.00 | 3012.31 | 3172.27 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1.00 | 40000.00 | 22901.72 | 11569.83 |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 1.00 | 20000.00 | 56244.00 | 39976.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 1.00 | 22000.00 | 13663.10 | 12880.00 |
| C2854-125 | | US 285, ASPEN PARK TO MORRISO | 12/08/11 | 1.00 | 3000.00 | 5733.33 | 7000.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 1.00 | 40000.00 | 75415.03 | 85900.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 9.00 | 21644.44 | 27011.76 | 22138.97 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 33.00 | 33800.00 | 29720.92 | 32067.55 |
| ========== | 613-10010 | Wiring (Spec) | | LUMP SUM | ========== | ========== | ========== |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 1.00 | 18000.00 | 5434.33 | 5200.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1.00 | 18000.00 | 6809.00 | 5150.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 18000.00 | 6809.00 | 5150.00 |
| ========== | 613-16000 | Luminaire (Spec) | | Each | ========== | ========== | ========== |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 4.00 | 1300.00 | 2303.89 | 1901.03 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 10.00 | 1300.00 | 1024.50 | 990.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 8.00 | 1500.00 | 2180.50 | 2400.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 22.00 | 1372.73 | 1667.36 | 1668.37 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 9.00 | 1000.00 | 824.29 | 780.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 3.00 | 1000.00 | 691.69 | 398.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 613-16000 | Luminaire (Spec) | | Each | | | |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 3.00 | 1500.00 | 905.22 | 945.28 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 32.00 | 2800.00 | 877.45 | 900.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 47.00 | 2257.45 | 863.43 | 847.87 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 69.00 | 1975.36 | 1086.74 | 1109.48 |
| ========== | 613-30005 | Light Std + Lumin (Pedest) | | Each | | | |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 2.00 | 3500.00 | 3346.02 | 3584.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 3500.00 | 3346.02 | 3584.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 3500.00 | 3346.02 | 3584.00 |
| ========== | 613-32300 | Light Std Steel (30 Ft) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 4.00 | 3500.00 | 4479.82 | 4200.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 4.00 | 3500.00 | 3557.53 | 3400.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4.00 | 3500.00 | 2362.49 | 2043.75 |
| ========== | 613-32350 | Light Std Steel (35 Ft) | | Each | | | |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 2.00 | 3500.00 | 5745.50 | 5266.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2.00 | 3500.00 | 5745.50 | 5266.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 13.00 | 3750.00 | 3561.10 | 3219.43 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 13.00 | 3750.00 | 3561.10 | 3219.43 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 15.00 | 3716.67 | 3642.01 | 3492.31 |
| ========== | 613-32352 | Light Std Steel (35 Ft) (2) | | Each | | | |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1.00 | 4500.00 | 3833.60 | 3219.43 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 4500.00 | 3833.60 | 3219.43 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 4500.00 | 3833.60 | 3219.43 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 613-32400 | Light Std Steel (40 Ft) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 208.00 | 3000.00 | 3844.66 | 3680.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 208.00 | 3000.00 | 3844.66 | 3680.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 21.00 | 4000.00 | 3510.44 | 3500.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 21.00 | 4000.00 | 3510.44 | 3500.00 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 4.00 | 2500.00 | 2078.85 | 1993.61 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1.00 | 4000.00 | 3925.48 | 3219.43 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 5.00 | 2800.00 | 2606.46 | 2238.77 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 234.00 | 3085.47 | 3721.22 | 3539.15 |
| ========== | 613-34180 | Light Std Metal (18 Ft) | | Each | | | |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 8.00 | 2500.00 | 3057.50 | 3300.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 8.00 | 2500.00 | 3057.50 | 3300.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 8.00 | 2500.00 | 3057.50 | 3300.00 |
| ========== | 613-34250 | Light Std Metal (25 Ft) | | Each | | | |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 18.00 | 4250.00 | 1537.58 | 1400.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 18.00 | 4250.00 | 1537.58 | 1400.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 18.00 | 4250.00 | 1537.58 | 1400.00 |
| ========== | 613-34300 | Light Std Metal (30 Ft) | | Each | | | |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 18.00 | 3500.00 | 1695.17 | 1700.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 613-34300 | Light Std Metal (30 Ft) | | Each | | | |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 36.00 | 3500.00 | 1504.27 | 1410.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 54.00 | 3500.00 | 1589.12 | 1506.67 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 54.00 | 3500.00 | 1589.12 | 1506.67 |
| ========== | 613-34350 | Light Std Metal (35 Ft) | | Each | | | |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 9.00 | 3000.00 | 2803.32 | 2534.71 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 6.00 | 2500.00 | 2685.72 | 3100.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 15.00 | 2800.00 | 2759.99 | 2760.83 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 9.00 | 2500.00 | 4221.70 | 4134.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 9.00 | 2500.00 | 4221.70 | 4134.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 24.00 | 2687.50 | 3173.68 | 3275.77 |
| ========== | 613-34400 | Light Std Metal (40 Ft) | | Each | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 35.00 | 3500.00 | 2973.23 | 2861.36 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 35.00 | 3500.00 | 2973.23 | 2861.36 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 13.00 | 3000.00 | 3162.93 | 2957.16 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 13.00 | 3000.00 | 1722.39 | 1639.30 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 26.00 | 3000.00 | 2545.56 | 2298.23 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 12.00 | 3000.00 | 3897.37 | 3707.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 14.00 | 4500.00 | 2191.91 | 1900.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 26.00 | 3807.69 | 2742.06 | 2734.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 87.00 | 3442.53 | 2786.76 | 2655.01 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 613-34700 | Light Std Metal (70 Ft) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 24.00 | 7500.00 | 11528.63 | 9900.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 24.00 | 7500.00 | 11528.63 | 9900.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 3.00 | 10000.00 | 5468.27 | 5080.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 3.00 | 10000.00 | 5468.27 | 5080.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 27.00 | 7777.78 | 10211.16 | 8293.33 |
| ========== | 613-40000 | Conc Foundation Pad | | Each | | | |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 1.00 | 500.00 | 632.41 | 570.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 2.00 | 400.00 | 1064.45 | 1012.75 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 3.00 | 433.33 | 905.28 | 865.17 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 2.00 | 1000.00 | 994.22 | 1500.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 1000.00 | 994.22 | 1500.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 5.00 | 660.00 | 948.55 | 1119.10 |
| ========== | 613-40010 | Light Std Foundation | | Each | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 3.00 | 750.00 | 1288.63 | 1170.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 204.00 | 800.00 | 1080.48 | 970.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 23.00 | 950.00 | 952.78 | 825.39 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 230.00 | 814.35 | 1021.69 | 908.34 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 613-40010 | Light Std Foundation | | Each | | | |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 18.00 | 800.00 | 1036.83 | 739.29 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 12.00 | 1025.00 | 1084.02 | 1100.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 6.00 | 900.00 | 817.37 | 750.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 8.00 | 800.00 | 919.50 | 815.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 7.00 | 400.00 | 1064.80 | 1013.75 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 2.00 | 1000.00 | 1100.00 | 955.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 53.00 | 816.98 | 1027.86 | 960.95 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 16.00 | 950.00 | 821.92 | 820.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 36.00 | 500.00 | 497.39 | 840.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 52.00 | 638.46 | 632.26 | 833.85 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 4.00 | 850.00 | 829.54 | 797.44 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 16.00 | 950.00 | 978.46 | 1018.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 15.00 | 850.00 | 870.09 | 603.64 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 2.00 | 1100.00 | 1271.01 | 1344.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 32.00 | 900.00 | 1063.72 | 1200.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 69.00 | 903.62 | 999.60 | 1008.99 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 404.00 | 807.30 | 955.89 | 932.24 |
| ========== | 613-50010 | Photoel Cell | | Each | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 2.00 | 632.00 | 618.61 | 620.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 2.00 | 632.00 | 618.61 | 620.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 2.00 | 45.00 | 195.09 | 195.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 2.00 | 45.00 | 195.09 | 195.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4.00 | 338.50 | 376.60 | 407.50 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 613-50100 | Lighting Ctrl Center | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 4.00 | 10000.00 | 5033.91 | 4450.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 1.00 | 6000.00 | 1584.14 | 3851.82 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 5.00 | 9200.00 | 2746.71 | 3267.27 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 1.00 | 6000.00 | 5026.50 | 4700.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 1.00 | 6800.00 | 6211.17 | 7600.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 2.00 | 1500.00 | 8053.91 | 7648.41 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 4.00 | 3950.00 | 6763.97 | 6899.21 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 2.00 | 5000.00 | 5716.66 | 6800.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 2.00 | 5000.00 | 5716.66 | 6800.00 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 3.00 | 6000.00 | 1662.08 | 1594.88 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 2.00 | 4500.00 | 9656.39 | 15500.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 5.00 | 5400.00 | 6022.61 | 7156.93 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 16.00 | 6175.00 | 5281.13 | 6198.81 |
| ========== | 613-50105 | Lighting Ctrl Center (Pedestal Only) | | Each | | | |
| ITS4701-121 | | C470 (SANTA FE TO I-25) AND R | 01/20/11 | 12.00 | 2400.00 | 1614.00 | 1571.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 12.00 | 2400.00 | 1614.00 | 1571.00 |
| ITSSW00-928 | | NB I-225 AT MM 2.28 | 11/03/11 | 1.00 | 2000.00 | 1584.67 | 1500.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 613-50105 | Lighting Ctrl Center (Pedestal Only) | | Each | | | |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 2.00 | 2700.00 | 5070.85 | 1509.11 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 3.00 | 2466.67 | 4120.07 | 1506.07 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 15.00 | 2413.33 | 2401.62 | 1558.01 |
| ========== | 613-50150 | Secondary Serv Pedestal | | Each | | | |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 2.00 | 1500.00 | 1684.81 | 1584.19 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 2.00 | 500.00 | 1207.00 | 1100.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 4.00 | 1000.00 | 1707.34 | 1181.05 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4.00 | 1000.00 | 1707.34 | 1181.05 |
| ========== | 613-50210 | Temporary Lighting | | LUMP SUM | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 1.00 | 30000.00 | 36984.04 | 22010.41 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1.00 | 30000.00 | 36984.04 | 22010.41 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1.00 | 10000.00 | 20607.38 | 19973.36 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1.00 | 10000.00 | 20607.38 | 19973.36 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 1.00 | 10000.00 | 6490.96 | 5225.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1.00 | 10000.00 | 6490.96 | 5225.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3.00 | 16666.67 | 23787.97 | 15736.26 |
| ========== | 613-70100 | Lumin HPS (100 W) | | Each | | | |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 4.00 | 1600.00 | 1413.83 | 1318.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 4.00 | 1600.00 | 1413.83 | 1318.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4.00 | 1600.00 | 1413.83 | 1318.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 613-70150 | Lumin HPS (150 W) | | Each | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 12.00 | 1000.00 | 2273.18 | 1540.73 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 12.00 | 1000.00 | 2273.18 | 1540.73 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 4.00 | 1000.00 | 2225.38 | 2137.13 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 4.00 | 1000.00 | 2225.38 | 2137.13 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 8.00 | 1800.00 | 2359.41 | 2436.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 12.00 | 1000.00 | 1314.02 | 1810.93 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 20.00 | 1320.00 | 1621.49 | 2060.96 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 36.00 | 1177.78 | 1922.49 | 1896.01 |
| ========== | 613-70250 | Lumin HPS (250 W) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 208.00 | 400.00 | 760.10 | 720.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 208.00 | 400.00 | 612.18 | 551.38 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 4.00 | 450.00 | 368.01 | 332.00 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 9.00 | 500.00 | 385.84 | 316.84 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 36.00 | 450.00 | 409.02 | 410.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 5.00 | 400.00 | 479.11 | 420.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 2.00 | 450.00 | 547.55 | 863.68 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 39.00 | 700.00 | 372.42 | 353.00 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 8.00 | 450.00 | 845.00 | 490.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 103.00 | 546.60 | 409.42 | 393.62 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 4.00 | 300.00 | 393.33 | 400.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 613-70250 | Lumin HPS (250 W) | | Each | | | |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 4.00 | 460.00 | 355.80 | 269.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 18.00 | 450.00 | 292.53 | 295.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 36.00 | 500.00 | 332.09 | 425.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 62.00 | 470.00 | 319.49 | 375.58 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 19.00 | 500.00 | 1107.51 | 1225.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 9.00 | 450.00 | 437.56 | 402.43 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 28.00 | 483.93 | 818.67 | 960.60 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 401.00 | 454.34 | 502.04 | 488.58 |
| ========== | 613-70400 | Lumin HPS (400 W) | | Each | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 35.00 | 1500.00 | 927.76 | 385.18 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 35.00 | 1500.00 | 927.76 | 385.18 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 13.00 | 475.00 | 407.84 | 316.84 |
| SHE074A-001 | | SH 74 - EVERGREEN - JEFFERSON | 04/28/11 | 2.00 | 750.00 | 536.67 | 780.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 1.00 | 1500.00 | 1113.87 | 5200.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 9.00 | 700.00 | 427.22 | 407.31 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 25.00 | 619.00 | 447.38 | 581.79 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 9.00 | 450.00 | 379.38 | 331.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 9.00 | 450.00 | 377.86 | 324.64 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 4.00 | 400.00 | 318.32 | 307.28 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 6.00 | 750.00 | 1873.05 | 1827.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 8.00 | 400.00 | 880.06 | 402.43 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 18.00 | 516.67 | 1042.82 | 856.14 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 87.00 | 934.77 | 773.39 | 528.17 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 613-71000 | Lumin HPS (1000 W) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 64.00 | 1200.00 | 1122.68 | 1080.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 64.00 | 1200.00 | 1122.68 | 1080.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 64.00 | 1200.00 | 1122.68 | 1080.00 |
| ========== | 613-72150 | Lumin HPS (WT) (150 W) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 60.00 | 600.00 | 3063.54 | 3125.33 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 60.00 | 600.00 | 3063.54 | 3125.33 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 12.00 | 1000.00 | 594.69 | 600.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 12.00 | 1000.00 | 594.69 | 600.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 4.00 | 400.00 | 403.73 | 400.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 4.00 | 400.00 | 403.73 | 400.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 76.00 | 652.63 | 1963.66 | 1796.13 |
| ========== | 614-00011 | Sign Panel (CL I) | | Sq Foot | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 70.00 | 20.00 | 17.07 | 17.55 |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 34.00 | 20.00 | 24.20 | 21.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 1,132.00 | 18.00 | 16.13 | 15.42 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-00011 | Sign Panel (CL I) | | Sq Foot | | | |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 5.00 | 15.00 | 18.07 | 17.00 |
| STA0504-061 | | US 50 M.P.369.9 -M.P.373.2 | 03/03/11 | 184.00 | 20.00 | 14.47 | 14.91 |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 59.25 | 15.00 | 18.47 | 20.65 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 1.50 | 20.00 | 54.52 | 60.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 35.00 | 18.00 | 16.41 | 15.96 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1,520.75 | 18.25 | 17.47 | 16.22 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 112.00 | 18.00 | 20.04 | 20.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 198.00 | 18.00 | 19.26 | 20.00 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 24.00 | 16.00 | 14.50 | 15.00 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 143.00 | 18.00 | 17.85 | 17.25 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 425.00 | 20.00 | 15.30 | 16.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 75.00 | 15.00 | 17.73 | 20.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 45.00 | 16.00 | 28.41 | 18.42 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 12.50 | 18.00 | 24.75 | 22.00 |
| ITS0703-370 | | EAST OF EJMT ON I-70 EB LANES | 06/16/11 | 3.00 | 18.00 | 23.67 | 28.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 78.00 | 15.00 | 19.18 | 22.60 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 306.00 | 20.00 | 20.05 | 20.11 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 195.00 | 18.00 | 32.00 | 27.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1,616.50 | 18.54 | 23.22 | 19.59 |
| C006A-051 | | US 6 (LOVELAND PASS), CLEAR C | 07/14/11 | 100.00 | 17.50 | 20.95 | 23.80 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 30.00 | 20.00 | 27.87 | 25.60 |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 39.00 | 14.00 | 30.95 | 20.80 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 198.00 | 16.00 | 23.41 | 17.03 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 16.00 | 18.00 | 16.14 | 15.50 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 192.00 | 15.00 | 14.47 | 16.20 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 38.00 | 15.00 | 13.14 | 18.00 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 18.00 | 15.00 | 15.96 | 12.00 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 37.00 | 17.00 | 16.74 | 14.00 |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 90.00 | 20.00 | 21.50 | 18.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 758.00 | 16.49 | 19.22 | 17.79 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 103.00 | 18.00 | 17.10 | 17.01 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 624.00 | 20.00 | 17.93 | 19.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 107.00 | 16.00 | 17.87 | 16.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-00011 | Sign Panel (CL I) | | Sq Foot | | | |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 214.00 | 18.00 | 16.51 | 15.09 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 7.50 | 20.00 | 19.74 | 21.00 |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 54.00 | 35.00 | 44.96 | 102.83 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 5.00 | 18.00 | 15.78 | 17.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 10.00 | 20.00 | 17.94 | 17.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 34.00 | 15.00 | 16.30 | 15.00 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 90.00 | 15.00 | 21.67 | 19.50 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 1,248.50 | 19.29 | 18.36 | 21.45 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 5,143.75 | 18.34 | 19.48 | 18.81 |
| ========== | 614-00012 | Sign Panel (CL II) | | Sq Foot | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 90.00 | 22.00 | 19.77 | 20.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 3,380.00 | 20.00 | 20.81 | 22.17 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 61.00 | 18.00 | 22.26 | 23.00 |
| STA0504-061 | | US 50 M.P.369.9 -M.P.373.2 | 03/03/11 | 780.00 | 22.00 | 16.01 | 15.97 |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 350.00 | 18.00 | 19.73 | 20.65 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 160.00 | 20.00 | 27.89 | 22.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 237.00 | 20.00 | 23.25 | 24.21 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 5,058.00 | 20.18 | 18.83 | 19.40 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 56.25 | 20.00 | 17.89 | 15.00 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 18.00 | 20.00 | 23.10 | 23.00 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 12.00 | 20.00 | 24.68 | 22.00 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 36.00 | 20.00 | 18.33 | 19.00 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 9.00 | 20.00 | 25.81 | 28.20 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 50.00 | 20.00 | 20.97 | 18.78 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 314.00 | 20.00 | 25.42 | 27.00 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 96.00 | 22.00 | 30.56 | 29.50 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 21.00 | 20.00 | 22.51 | 22.64 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 316.00 | 23.00 | 18.42 | 21.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 72.00 | 17.00 | 23.14 | 26.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 86.00 | 20.00 | 18.07 | 17.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 302.00 | 20.00 | 18.77 | 16.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 140.00 | 18.00 | 23.79 | 28.25 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 121.00 | 21.00 | 23.79 | 23.13 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 1,649.25 | 20.46 | 21.42 | 20.91 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-00012 | Sign Panel (CL II) | | Sq Foot | | | |
| C006A-051 | | US 6 (LOVELAND PASS), CLEAR C | 07/14/11 | 38.00 | 19.00 | 25.68 | 26.70 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 15.00 | 18.00 | 22.86 | 19.43 |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 77.50 | 18.00 | 33.18 | 23.40 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 9.00 | 22.00 | 27.98 | 16.45 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 170.00 | 20.00 | 22.77 | 22.75 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 516.00 | 18.00 | 19.04 | 18.30 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 40.00 | 16.00 | 17.62 | 22.00 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 628.00 | 18.00 | 21.04 | 16.00 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 91.00 | 20.00 | 19.33 | 16.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 1,584.50 | 18.33 | 20.06 | 19.25 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 328.00 | 20.00 | 19.39 | 19.14 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 136.00 | 25.00 | 24.14 | 23.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 107.00 | 25.00 | 23.57 | 24.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 152.00 | 20.00 | 20.66 | 22.13 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 16.00 | 20.00 | 25.71 | 26.00 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 57.00 | 22.00 | 19.10 | 19.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 59.00 | 24.00 | 24.00 | 23.00 |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 18.00 | 40.00 | 25.30 | 17.25 |
| C2854-125 | | US 285, ASPEN PARK TO MORRISO | 12/08/11 | 24.00 | 25.00 | 27.67 | 22.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 495.00 | 18.00 | 20.59 | 19.00 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 68.00 | 17.00 | 27.67 | 25.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 1,460.00 | 20.58 | 21.23 | 20.64 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 9,751.75 | 19.99 | 19.94 | 19.81 |
| ========== | 614-00013 | Sign Panel (CL III) | | Sq Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 13,872.00 | 22.00 | 23.73 | 23.17 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 1,340.00 | 35.00 | 30.30 | 30.81 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 15,212.00 | 23.15 | 25.43 | 25.58 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 420.00 | 22.00 | 26.28 | 25.60 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-00013 | Sign Panel (CL III) | | Sq Foot | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 1,688.00 | 22.00 | 25.80 | 24.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 648.00 | 22.00 | 23.70 | 20.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 966.00 | 22.00 | 34.19 | 35.20 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 3,722.00 | 22.00 | 27.51 | 26.39 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 216.00 | 30.00 | 30.10 | 30.00 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 216.00 | 30.00 | 30.10 | 30.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 551.00 | 35.00 | 30.10 | 33.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 350.00 | 22.00 | 24.86 | 30.18 |
| C2854-125 | | US 285, ASPEN PARK TO MORRISO | 12/08/11 | 70.00 | 30.00 | 26.00 | 27.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 1,491.00 | 20.00 | 24.33 | 23.00 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 2,462.00 | 23.93 | 25.26 | 26.37 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 21,612.00 | 23.11 | 26.05 | 26.10 |
| ========== | 614-00035 | Sign Panel (Spec) | | Sq Foot | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 6.00 | 300.00 | 125.25 | 165.08 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 6.00 | 300.00 | 125.25 | 165.08 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 30.00 | 30.00 | 29.33 | 28.00 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 30.00 | 30.00 | 30.72 | 26.28 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 36.00 | 75.00 | 51.30 | 42.15 |
| ========== | 614-00037 | Sign Panel (Spec) | | Each | | | |
| ITS0703-370 | | EAST OF EJMT ON I-70 EB LANES | 06/16/11 | 1.00 | 27500.00 | 58866.00 | 56550.00 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 1.00 | 27500.00 | 58866.00 | 56550.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 1.00 | 27500.00 | 58866.00 | 56550.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-00040 | Sign Post (Spec) | | Lin Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 76.00 | 70.00 | 81.67 | 93.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 76.00 | 70.00 | 81.67 | 93.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 30.00 | 88.00 | 64.75 | 68.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 30.00 | 88.00 | 64.75 | 68.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 8.00 | 100.00 | 52.28 | 46.50 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 8.00 | 100.00 | 52.28 | 46.50 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 28.00 | 80.00 | 66.68 | 75.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 28.00 | 80.00 | 66.68 | 75.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 142.00 | 77.46 | 69.01 | 73.87 |
| ========== | 614-00200 | Steel Sign Post (U-2) | | Lin Foot | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 56.00 | 15.00 | 10.70 | 9.60 |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 99.00 | 12.00 | 17.83 | 10.30 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 155.00 | 13.08 | 14.28 | 10.05 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 155.00 | 13.08 | 14.28 | 10.05 |
| ========== | 614-00216 | Steel Sign Post (2x2 In T) | | Lin Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 1,968.00 | 14.00 | 13.30 | 15.38 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-00216 | Steel Sign Post (2x2 In T) | | Lin Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 1,968.00 | 14.00 | 13.30 | 15.38 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 177.00 | 12.00 | 14.31 | 12.50 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 177.00 | 12.00 | 14.31 | 12.50 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 595.00 | 12.00 | 14.14 | 10.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 268.00 | 15.00 | 10.87 | 12.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 36.00 | 15.00 | 12.36 | 12.07 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 899.00 | 13.01 | 13.30 | 10.68 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 3,044.00 | 13.59 | 13.42 | 12.36 |
| ========== | 614-00612 | Steel Sign Post (W 6x12) | | Lin Foot | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 15.00 | 50.00 | 56.35 | 77.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 34.00 | 42.00 | 39.75 | 42.92 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 49.00 | 44.45 | 43.42 | 54.46 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 49.00 | 44.45 | 43.42 | 54.46 |
| ========== | 614-00615 | Steel Sign Post (W 6x15) | | Lin Foot | | | |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 54.00 | 45.00 | 41.74 | 44.79 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 237.00 | 40.00 | 47.26 | 41.23 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 291.00 | 40.93 | 45.98 | 41.89 |
| C2854-125 | | US 285, ASPEN PARK TO MORRISO | 12/08/11 | 30.00 | 50.00 | 47.67 | 47.00 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 30.00 | 50.00 | 47.67 | 47.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 321.00 | 41.78 | 46.05 | 42.37 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-00818 | Steel Sign Post (W 8x18) | | Lin Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 140.00 | 80.00 | 52.64 | 49.26 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 140.00 | 80.00 | 52.64 | 49.26 |
| ITS0703-370 | | EAST OF EJMT ON I-70 EB LANES | 06/16/11 | 13.00 | 50.00 | 73.12 | 85.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 13.00 | 50.00 | 73.12 | 85.00 |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 28.00 | 80.00 | 139.09 | 362.36 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 206.00 | 50.00 | 48.42 | 46.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 234.00 | 53.59 | 53.59 | 83.86 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 387.00 | 63.02 | 53.78 | 79.61 |
| ========== | 614-00821 | Steel Sign Post (W 8x21) | | Lin Foot | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 33.00 | 55.00 | 61.38 | 70.43 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 33.00 | 55.00 | 61.38 | 70.43 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 33.00 | 55.00 | 61.38 | 70.43 |
| ========== | 614-01022 | Steel Sign Post (W 10x22) | | Lin Foot | | | |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 33.00 | 50.00 | 64.80 | 80.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 33.00 | 50.00 | 64.80 | 80.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 33.00 | 50.00 | 64.80 | 80.00 |
| ========== | 614-01026 | Steel Sign Post (W 10x26) | | Lin Foot | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 49.00 | 60.00 | 72.55 | 85.40 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 49.00 | 60.00 | 72.55 | 85.40 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-01026 | Steel Sign Post (W 10x26) | | Lin Foot | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 36.00 | 62.00 | 66.10 | 68.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 36.00 | 62.00 | 66.10 | 68.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 85.00 | 60.85 | 70.26 | 78.03 |
| ========== | 614-01226 | Steel Sign Post (W 12x26) | | Lin Foot | | | |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 212.00 | 60.00 | 57.57 | 53.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 212.00 | 60.00 | 57.57 | 53.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 212.00 | 60.00 | 57.57 | 53.00 |
| ========== | 614-01502 | Steel Sign Supp (2-In Rd)(Po&Sock) | | Lin Foot | | | |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 19.00 | 30.00 | 17.26 | 18.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 275.00 | 10.00 | 16.15 | 13.07 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 294.00 | 11.29 | 16.23 | 13.39 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 15.00 | 20.00 | 21.42 | 20.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 15.00 | 20.00 | 21.42 | 20.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 309.00 | 11.72 | 16.60 | 13.71 |
| ========== | 614-01503 | Steel Sign Supp (2-In Rd)(Po&Sock) | | Each | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 4.00 | 250.00 | 136.82 | 120.00 |
| STA0504-061 | | US 50 M.P.369.9 -M.P.373.2 | 03/03/11 | 12.00 | 18.00 | 138.73 | 117.14 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 16.00 | 76.00 | 173.47 | 106.97 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 9.00 | 30.00 | 46.79 | 20.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 9.00 | 30.00 | 46.79 | 20.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-01503 | Steel Sign Supp (2-In Rd)(Po&Sock) | | Each | | | |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 6.00 | 150.00 | 160.51 | 159.49 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 6.00 | 78.00 | 144.96 | 140.00 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 12.00 | 120.00 | 227.00 | 160.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 24.00 | 117.00 | 173.46 | 154.87 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 49.00 | 87.63 | 153.42 | 141.04 |
| ========== | 614-01512 | Steel Sign Supp (2-In Rd)(Post) | | Lin Foot | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 46.00 | 15.00 | 10.91 | 5.50 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 46.00 | 15.00 | 17.35 | 18.92 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 21.00 | 325.00 | 6.84 | 9.00 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 44.00 | 11.00 | 9.25 | 9.50 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 660.00 | 15.00 | 7.17 | 6.50 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 24.00 | 15.00 | 25.13 | 11.50 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 28.00 | 8.00 | 9.22 | 11.30 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 777.00 | 22.90 | 8.08 | 7.06 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 282.00 | 9.00 | 10.00 | 5.25 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 98.00 | 17.00 | 10.89 | 9.00 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 10.00 | 12.00 | 10.01 | 5.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 390.00 | 11.09 | 10.19 | 6.19 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 219.00 | 10.00 | 7.10 | 8.90 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 8.00 | 9.00 | 7.55 | 8.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 227.00 | 9.96 | 7.11 | 8.87 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,440.00 | 17.41 | 9.27 | 8.01 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-01522 | Steel Sign Supp (2-In Rd)(Sock) | | Each | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 4.00 | 75.00 | 134.62 | 71.53 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 4.00 | 75.00 | 111.96 | 73.74 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 2.00 | 326.00 | 59.66 | 46.00 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 4.00 | 70.00 | 102.50 | 105.00 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 60.00 | 60.00 | 58.67 | 37.00 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 3.00 | 60.00 | 162.75 | 12.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 4.00 | 65.00 | 73.42 | 110.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 73.00 | 68.11 | 67.06 | 43.95 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 23.00 | 60.00 | 40.55 | 32.00 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 19.00 | 200.00 | 80.00 | 110.00 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 2.00 | 46.00 | 103.19 | 72.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 44.00 | 119.82 | 83.16 | 71.41 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 29.00 | 70.00 | 82.57 | 100.00 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 2.00 | 100.00 | 122.65 | 84.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 31.00 | 71.94 | 83.72 | 98.97 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 152.00 | 84.04 | 80.35 | 65.12 |
| ========== | 614-01572 | Steel Sign Supp (2-1/2 Rd NP40)(Po&Silp) | | Lin Foot | | | |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 117.00 | 40.00 | 29.69 | 25.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 117.00 | 40.00 | 29.69 | 25.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 117.00 | 40.00 | 29.69 | 25.00 |
| ========== | 614-01573 | Steel Sign Supp (2-1/2 Rd NP40)(Po&Slip) | | Each | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 14.00 | 260.00 | 289.92 | 350.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-01573 | Steel Sign Supp (2-1/2 Rd NP40)(Po&Slip) | | Each | | | |
| STA0504-061 | | US 50 M.P.369.9 -M.P.373.2 | 03/03/11 | 51.00 | 320.00 | 312.48 | 351.41 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 65.00 | 307.08 | 347.92 | 350.58 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 1.00 | 300.00 | 545.22 | 765.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 9.00 | 400.00 | 94.92 | 50.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 5.00 | 400.00 | 370.48 | 390.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 15.00 | 150.00 | 144.61 | 62.35 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 30.00 | 271.67 | 174.11 | 136.68 |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 3.00 | 300.00 | 522.00 | 520.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 3.00 | 300.00 | 387.62 | 378.00 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 21.00 | 350.00 | 364.53 | 345.56 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 9.00 | 380.00 | 404.59 | 350.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 15.00 | 360.00 | 341.78 | 330.90 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 54.00 | 245.00 | 329.78 | 310.00 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 6.00 | 350.00 | 411.00 | 378.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 105.00 | 300.00 | 342.59 | 327.41 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 203.00 | 298.08 | 341.30 | 338.49 |
| ========== | 614-01575 | Steel Sign Supp (2-1/2 In Rd NP40)(Po) | | Lin Foot | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 144.00 | 25.00 | 18.91 | 13.21 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 144.00 | 25.00 | 18.91 | 13.21 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 304.00 | 30.00 | 17.00 | 21.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 287.00 | 10.00 | 12.83 | 17.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 591.00 | 20.29 | 14.28 | 19.06 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-01575 | Steel Sign Supp (2-1/2 In Rd NP40)(Po) | | Lin Foot | | | |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 541.00 | 25.00 | 17.05 | 14.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 541.00 | 25.00 | 17.05 | 14.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 98.00 | 25.00 | 17.29 | 18.00 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 12.00 | 25.00 | 17.67 | 18.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 110.00 | 25.00 | 17.30 | 18.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,386.00 | 22.99 | 16.36 | 16.39 |
| ========== | 614-01578 | Steel Sign Supp (2-1/2 In Rd NP40)(Slip) | | Each | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 14.00 | 250.00 | 269.45 | 192.59 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 14.00 | 250.00 | 269.45 | 192.59 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 25.00 | 250.00 | 191.33 | 190.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 25.00 | 25.00 | 312.67 | 238.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 50.00 | 137.50 | 272.22 | 214.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 43.00 | 200.00 | 216.65 | 200.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 43.00 | 200.00 | 243.34 | 204.24 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 7.00 | 250.00 | 286.43 | 230.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1.00 | 250.00 | 307.25 | 350.00 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 1.00 | 200.00 | 319.38 | 350.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 9.00 | 244.44 | 289.46 | 256.67 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 116.00 | 182.54 | 260.76 | 209.81 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-01582 | Steel Sign Supp (2-1/2 In Rd)(Po&Slip) | | Lin Foot | | | |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 86.00 | 45.00 | 54.55 | 43.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 86.00 | 45.00 | 54.55 | 43.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 8.00 | 140.00 | 72.25 | 68.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 8.00 | 140.00 | 72.25 | 68.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 94.00 | 53.09 | 55.25 | 45.13 |
| ========== | 614-01583 | Stl Sign Supp (2-1/2 In Rd 80)(Po&Slip) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 144.00 | 400.00 | 400.53 | 439.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| STA0504-061 | | US 50 M.P.369.9 -M.P.373.2 | 03/03/11 | 13.00 | 360.00 | 407.80 | 409.98 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 13.00 | 300.00 | 350.53 | 300.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 170.00 | 389.29 | 393.19 | 403.77 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 4.00 | 500.00 | 524.31 | 350.00 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 4.00 | 250.00 | 387.67 | 371.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 13.00 | 450.00 | 439.47 | 450.00 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 10.00 | 450.00 | 298.07 | 388.13 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 31.00 | 430.65 | 410.17 | 406.95 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 4.00 | 450.00 | 446.89 | 425.30 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 16.00 | 450.00 | 418.26 | 352.13 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 20.00 | 450.00 | 422.13 | 366.76 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 221.00 | 400.59 | 416.61 | 412.03 |
| ========== | 614-01585 | Steel Sign Supp (2-1/2 In Rd 80) (Post) | | Lin Foot | | | |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 68.00 | 20.00 | 18.45 | 18.55 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 68.00 | 20.00 | 24.47 | 25.50 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-01585 | Steel Sign Supp (2-1/2 In Rd 80) (Post) | | Lin Foot | ========== | ========== | ========== |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 72.00 | 30.00 | 16.37 | 12.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 188.00 | 21.00 | 12.40 | 9.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 260.00 | 23.49 | 16.46 | 14.58 |
| C006A-051 | | US 6 (LOVELAND PASS), CLEAR C | 07/14/11 | 158.00 | 26.00 | 30.23 | 35.90 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 18.00 | 20.00 | 19.83 | 2.16 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 31.00 | 25.00 | 38.55 | 17.23 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 566.00 | 20.00 | 17.14 | 15.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 773.00 | 21.43 | 20.73 | 19.06 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 57.00 | 11.00 | 16.23 | 10.00 |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 24.00 | 35.00 | 31.98 | 28.50 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 81.00 | 18.11 | 22.73 | 15.48 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,182.00 | 21.57 | 19.46 | 17.71 |
| ========== | 614-01588 | Steel Sign Supp (2-1/2 In Rd 80)(Slip) | | Each | ========== | ========== | ========== |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 5.00 | 300.00 | 271.22 | 309.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 5.00 | 300.00 | 431.70 | 246.38 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 6.00 | 300.00 | 221.60 | 200.01 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 7.00 | 300.00 | 353.28 | 223.72 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 13.00 | 230.00 | 335.00 | 300.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 26.00 | 265.00 | 271.74 | 240.09 |
| C006A-051 | | US 6 (LOVELAND PASS), CLEAR C | 07/14/11 | 13.00 | 160.00 | 259.50 | 273.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-01588 | Steel Sign Supp (2-1/2 In Rd 80)(Slip) | | Each | | | |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 2.00 | 215.00 | 225.44 | 172.72 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 3.00 | 250.00 | 373.95 | 183.00 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 9.00 | 250.00 | 227.24 | 177.00 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 66.00 | 220.00 | 165.89 | 20.00 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 93.00 | 215.38 | 193.08 | 79.10 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 8.00 | 180.00 | 300.20 | 250.00 |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 2.00 | 200.00 | 410.60 | 310.00 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 10.00 | 184.00 | 332.67 | 262.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 134.00 | 225.82 | 275.72 | 166.50 |
| ========== | 614-03001 | Conc Footing (Ty 1) | | Each | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 1.00 | 1500.00 | 1221.00 | 1800.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 2.00 | 1000.00 | 1042.74 | 1045.50 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 3.00 | 1166.67 | 909.14 | 1082.33 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 6.00 | 1000.00 | 1137.05 | 1055.99 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 6.00 | 1000.00 | 1137.05 | 1055.99 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 9.00 | 1055.56 | 982.40 | 1071.80 |
| ========== | 614-03002 | Conc Footing (Ty 2) | | Each | | | |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 2.00 | 1300.00 | 1161.31 | 1408.55 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 6.00 | 1200.00 | 1323.00 | 1156.57 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 8.00 | 1225.00 | 1273.25 | 1219.57 |
| C2854-125 | | US 285, ASPEN PARK TO MORRISO | 12/08/11 | 2.00 | 1500.00 | 2683.33 | 3500.00 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 2.00 | 1500.00 | 2683.33 | 3500.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 10.00 | 1280.00 | 1419.12 | 1675.65 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-03003 | Conc Footing (Ty 3) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 8.00 | 1250.00 | 1524.74 | 1182.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 8.00 | 1250.00 | 1524.74 | 1182.00 |
| ITS0703-370 | | EAST OF EJMT ON I-70 EB LANES | 06/16/11 | 1.00 | 1275.00 | 1255.67 | 1105.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 1.00 | 1275.00 | 1255.67 | 1105.00 |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 2.00 | 1500.00 | 1476.63 | 931.50 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 12.00 | 1200.00 | 1126.68 | 1000.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 14.00 | 1242.86 | 1150.82 | 990.21 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 23.00 | 1246.74 | 1202.24 | 1019.53 |
| ========== | 614-03004 | Conc Footing (Ty 4) | | Each | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 2.00 | 1250.00 | 1826.05 | 2201.04 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 2.00 | 1250.00 | 1826.05 | 2201.04 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 1250.00 | 1826.05 | 2201.04 |
| ========== | 614-03005 | Conc Footing (Ty 5) | | Each | | | |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 2.00 | 2350.00 | 1668.36 | 2500.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 2350.00 | 1668.36 | 2500.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 2350.00 | 1668.36 | 2500.00 |
| ========== | 614-03006 | Conc Footing (Ty 6) | | Each | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 2.00 | 1750.00 | 2316.31 | 2641.25 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 2.00 | 1750.00 | 2316.31 | 2641.25 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| | 614-03006 | Conc Footing (Ty 6) | | Each | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 2.00 | 1900.00 | 1905.75 | 1900.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 2.00 | 1900.00 | 1905.75 | 1900.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4.00 | 1825.00 | 2140.36 | 2270.63 |
| | 614-03007 | Conc Footing (Ty 7) | | Each | | | |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 10.00 | 1500.00 | 1364.91 | 1200.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 10.00 | 1500.00 | 1364.91 | 1200.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 10.00 | 1500.00 | 1364.91 | 1200.00 |
| | 614-03100 | Conc Footing (Sig Pole) | | Each | | | |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 4.00 | 2500.00 | 3165.46 | 2481.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 4.00 | 2500.00 | 3165.46 | 2481.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4.00 | 2500.00 | 3165.46 | 2481.00 |
| | 614-07000 | Mask Sign Legend | | Each | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 2.00 | 300.00 | 483.81 | 330.06 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 2.00 | 300.00 | 483.81 | 330.06 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 1.00 | 100.00 | 628.67 | 750.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 1.00 | 100.00 | 628.67 | 750.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3.00 | 233.33 | 506.68 | 470.04 |
| | 614-10115 | Dyn Mesg Sign (Color LED)(O/H) | | Each | | | |
| ITS0703-370 | | EAST OF EJMT ON I-70 EB LANES | 06/16/11 | 1.00 | 220000.00 | 289662.33 | 275000.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 1.00 | 220000.00 | 289662.33 | 275000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 220000.00 | 289662.33 | 275000.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-10120 | Var Mesg Sign | | Each | | | |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 1.00 | 100000.00 | 95302.00 | 80408.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 100000.00 | 95302.00 | 80408.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 100000.00 | 101008.00 | 94098.00 |
| ========== | 614-10125 | Var Mesg Sign (Grnd Mtd) | | Each | | | |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 8.00 | 100000.00 | 112396.03 | 103284.13 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 8.00 | 100000.00 | 112396.03 | 103284.13 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 8.00 | 100000.00 | 112396.03 | 103284.13 |
| ========== | 614-10128 | Blankout Sign (Fib Opt) | | Each | | | |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 4.00 | 15000.00 | 9660.00 | 9000.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 4.00 | 15000.00 | 9463.93 | 8912.16 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4.00 | 15000.00 | 9463.93 | 8912.16 |
| ========== | 614-10130 | Illuminated Sign | | Each | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 2.00 | 2700.00 | 2684.80 | 2700.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2.00 | 2700.00 | 2684.80 | 2700.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 2700.00 | 2684.80 | 2700.00 |
| ========== | 614-10139 | Radar Speed Disp Sgn (LED) | | Each | | | |
| C2854-125 | | US 285, ASPEN PARK TO MORRISO | 12/08/11 | 2.00 | 10000.00 | 11066.67 | 11000.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 10000.00 | 11066.67 | 11000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 10000.00 | 11066.67 | 11000.00 |
| ========== | 614-10147 | VMS LED (Overhead) | | Each | | | |
| C0704-225 | | I-70 EAST OF BENNETT | 01/06/11 | 1.00 | 115000.00 | 127266.50 | 125465.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-10147 | VMS LED (Overhead) | | Each | | | |
| ITS4701-121 | | C470 (SANTA FE TO I-25) AND R | 01/20/11 | 1.00 | 120000.00 | 100537.25 | 124498.00 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 1.00 | 140000.00 | 148119.12 | 170000.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 3.00 | 125000.00 | 128566.41 | 139987.67 |
| ITSSW00-928 | | NB I-225 AT MM 2.28 | 11/03/11 | 1.00 | 125000.00 | 136042.17 | 125000.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 125000.00 | 136042.17 | 125000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4.00 | 125000.00 | 126453.84 | 123095.43 |
| ========== | 614-10148 | VMS LED (Speed Radar) | | Each | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 1.00 | 20000.00 | 26717.29 | 31000.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 1.00 | 20000.00 | 26717.29 | 31000.00 |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 2.00 | 22000.00 | 25220.25 | 24181.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 22000.00 | 25220.25 | 24181.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3.00 | 21333.33 | 25861.84 | 26454.00 |
| ========== | 614-10160 | Sig Head B-Plates | | Each | | | |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 65.00 | 200.00 | 171.00 | 177.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 65.00 | 200.00 | 171.00 | 177.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 65.00 | 200.00 | 171.00 | 177.00 |
| ========== | 614-30110 | Btrfly Str | | Each | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 2.00 | 30000.00 | 23314.78 | 22356.28 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 2.00 | 30000.00 | 23314.78 | 22356.28 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-30110 | Btrfly Str | | Each | | | |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 1.00 | 2500.00 | 26231.60 | 29000.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 1.00 | 2500.00 | 26231.60 | 29000.00 |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 4.00 | 25000.00 | 25570.00 | 19780.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 4.00 | 25000.00 | 25570.00 | 19780.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 7.00 | 23214.29 | 24763.53 | 21833.22 |
| ========== | 614-31800 | Monotube Overhead Sign Cant (18 In Dia) | | Each | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 1.00 | 30000.00 | 24154.09 | 22200.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 1.00 | 30000.00 | 24154.09 | 22200.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 30000.00 | 24154.09 | 22200.00 |
| ========== | 614-32000 | Monotube Overhead Sign Cant (20 In Dia) | | Each | | | |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 1.00 | 25000.00 | 29315.86 | 28300.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 1.00 | 25000.00 | 29315.86 | 28300.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 2.00 | 2200.00 | 26902.61 | 24700.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 2.00 | 2200.00 | 26902.61 | 24700.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3.00 | 9800.00 | 27637.08 | 25900.00 |
| ========== | 614-32400 | Monotube Overhead Sign Cant (24 In Dia) | | Each | | | |
| C0704-225 | | I-70 EAST OF BENNETT | 01/06/11 | 1.00 | 32000.00 | 34961.75 | 34228.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-32400 | Monotube Overhead Sign Cant (24 In Dia) | | Each | | | |
| ITS4701-121 | | C470 (SANTA FE TO I-25) AND R | 01/20/11 | 1.00 | 33500.00 | 35366.25 | 35315.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 4.00 | 35000.00 | 37338.38 | 30000.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 1.00 | 33000.00 | 51409.52 | 57000.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 1.00 | 40000.00 | 40267.27 | 34232.97 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 8.00 | 34812.50 | 40256.54 | 38155.19 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 2.00 | 30000.00 | 33905.98 | 33796.10 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 1.00 | 30000.00 | 36684.97 | 35600.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 3.00 | 30000.00 | 34839.53 | 34199.05 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1.00 | 35000.00 | 40722.22 | 35000.00 |
| ITSSW00-928 | | NB I-225 AT MM 2.28 | 11/03/11 | 1.00 | 35000.00 | 45682.00 | 33100.00 |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 5.00 | 40000.00 | 50329.05 | 44216.20 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 7.00 | 38571.43 | 47880.13 | 41311.57 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 18.00 | 35472.22 | 41567.40 | 38860.28 |
| ========== | 614-41400 | Monotube Overhead Sign Brdg (14 In Dia) | | Each | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 1.00 | 40000.00 | 42173.45 | 37300.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 1.00 | 40000.00 | 42173.45 | 37300.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 40000.00 | 42173.45 | 37300.00 |
| ========== | 614-41800 | Monotube Overhead Sign Brdg (18 In Dia) | | Each | | | |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1.00 | 52500.00 | 54613.16 | 45000.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 52500.00 | 54613.16 | 45000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 52500.00 | 54613.16 | 45000.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-42000 | Monotube Overhead Sign Brdg (20 In Dia) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 12.00 | 42500.00 | 57455.72 | 52000.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 12.00 | 42500.00 | 57455.72 | 52000.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 2.00 | 45000.00 | 52119.40 | 47400.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 2.00 | 45000.00 | 52119.40 | 47400.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 14.00 | 42857.14 | 55813.77 | 50160.00 |
| ========== | 614-42400 | Monotube Overhead Sign Brdg (24 In Dia) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 4.00 | 65000.00 | 76832.74 | 70000.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 1.00 | 65000.00 | 65140.96 | 65423.96 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 5.00 | 65000.00 | 71330.72 | 67711.98 |
| ITS0703-370 | | EAST OF EJMT ON I-70 EB LANES | 06/16/11 | 1.00 | 65000.00 | 66523.25 | 66486.75 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 1.00 | 65000.00 | 66523.25 | 66486.75 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1.00 | 70000.00 | 72568.70 | 70000.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 70000.00 | 72568.70 | 70000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 7.00 | 65714.29 | 71001.42 | 67977.68 |
| ========== | 614-70117 | Ped Sig Face (16) | | Each | | | |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 2.00 | 525.00 | 420.04 | 478.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-70117 | Ped Sig Face (16) | | Each | | | |
| SHE074A-001 | | SH 74 - EVERGREEN - JEFFERSON | 04/28/11 | 8.00 | 450.00 | 628.33 | 545.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 16.00 | 700.00 | 472.67 | 451.56 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 26.00 | 609.62 | 496.19 | 482.34 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 26.00 | 609.62 | 496.19 | 482.34 |
| ========== | 614-70150 | Ped Sig Face (16) (Countdown) | | Each | | | |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 8.00 | 500.00 | 482.36 | 532.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 8.00 | 600.00 | 706.99 | 634.45 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 16.00 | 750.00 | 633.50 | 512.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 32.00 | 650.00 | 589.72 | 547.61 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 8.00 | 500.00 | 630.33 | 516.00 |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 8.00 | 500.00 | 535.80 | 459.00 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 32.00 | 575.00 | 528.47 | 476.00 |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 2.00 | 600.00 | 798.00 | 826.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 50.00 | 552.00 | 546.94 | 492.04 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 17.00 | 550.00 | 585.43 | 500.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 8.00 | 500.00 | 563.27 | 544.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 10.00 | 550.00 | 627.59 | 603.64 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 35.00 | 538.57 | 595.83 | 539.67 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 117.00 | 574.79 | 573.36 | 513.76 |
| ========== | 614-70216 | Traf Sig Face (8-8) | | Each | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 4.00 | 500.00 | 650.08 | 650.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 4.00 | 500.00 | 650.08 | 650.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4.00 | 500.00 | 650.08 | 650.00 |
| ========== | 614-70328 | Traf Sig Face (12-8-8) | | Each | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 4.00 | 600.00 | 774.97 | 780.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 4.00 | 600.00 | 774.97 | 780.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4.00 | 600.00 | 774.97 | 780.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-70336 | Traf Sig Face (12-12-12) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 84.00 | 400.00 | 836.42 | 800.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 84.00 | 400.00 | 789.14 | 638.92 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 16.00 | 600.00 | 697.97 | 705.00 |
| SHE074A-001 | | SH 74 - EVERGREEN - JEFFERSON | 04/28/11 | 10.00 | 600.00 | 735.00 | 655.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 19.00 | 744.00 | 1026.51 | 1000.00 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 1.00 | 700.00 | 985.51 | 1078.13 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 10.00 | 700.00 | 850.85 | 784.88 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 27.00 | 800.00 | 708.70 | 678.85 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 30.00 | 650.00 | 814.00 | 688.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 113.00 | 695.01 | 805.74 | 749.79 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 13.00 | 650.00 | 763.67 | 681.00 |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 8.00 | 600.00 | 678.60 | 560.00 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 78.00 | 650.00 | 645.54 | 507.00 |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 8.00 | 600.00 | 912.00 | 944.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 107.00 | 642.52 | 668.91 | 564.48 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 30.00 | 800.00 | 760.14 | 620.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 16.00 | 650.00 | 730.88 | 711.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 30.00 | 1000.00 | 725.84 | 603.64 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 5.00 | 750.00 | 2065.25 | 2100.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 81.00 | 841.36 | 764.73 | 723.27 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 385.00 | 646.85 | 755.18 | 669.65 |
| ========== | 614-70448 | Traf Sig Face (12-12-12-12) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 4.00 | 750.00 | 1237.09 | 1180.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-70448 | Traf Sig Face (12-12-12-12) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 4.00 | 750.00 | 761.22 | 703.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 1.00 | 1210.00 | 1128.70 | 1100.00 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 1.00 | 1210.00 | 1128.70 | 1100.00 |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 4.00 | 700.00 | 854.40 | 675.00 |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 82.00 | 650.00 | 1026.00 | 1062.00 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 86.00 | 652.33 | 1007.35 | 1044.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 4.00 | 1000.00 | 981.14 | 866.00 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 1.00 | 1200.00 | 1606.77 | 1600.00 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 5.00 | 1040.00 | 1022.85 | 1012.80 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 96.00 | 682.40 | 939.74 | 1009.59 |
| ========== | 614-70560 | Traf Sig Face (12-12-12-12-12) | | Each | | | |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 4.00 | 1100.00 | 1080.88 | 1120.00 |
| SHE074A-001 | | SH 74 - EVERGREEN - JEFFERSON | 04/28/11 | 8.00 | 900.00 | 1127.67 | 1108.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 8.00 | 1200.00 | 1341.70 | 1362.03 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 6.00 | 1000.00 | 1177.90 | 1113.32 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 26.00 | 1046.15 | 1192.62 | 1189.24 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 8.00 | 900.00 | 1136.67 | 1100.00 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 10.00 | 1000.00 | 851.38 | 729.00 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 18.00 | 955.56 | 964.77 | 896.70 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-70560 | Traf Sig Face (12-12-12-12-12) | | Each | | | |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 2.00 | 600.00 | 965.87 | 804.86 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 600.00 | 965.87 | 804.86 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 46.00 | 991.30 | 1089.20 | 1030.58 |
| ========== | 614-72830 | Communications Cabinet | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 4.00 | 5000.00 | 10908.73 | 11400.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 4.00 | 5000.00 | 10908.73 | 11400.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4.00 | 5000.00 | 5025.38 | 1833.33 |
| ========== | 614-72831 | Comm Cabinet (Type 1) | | Each | | | |
| ITS4701-121 | | C470 (SANTA FE TO I-25) AND R | 01/20/11 | 18.00 | 2250.00 | 4451.50 | 4391.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 18.00 | 2250.00 | 4451.50 | 4391.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 18.00 | 2250.00 | 4451.50 | 4391.00 |
| ========== | 614-72832 | Comm Cabinet (Type 2) | | Each | | | |
| ITS4701-121 | | C470 (SANTA FE TO I-25) AND R | 01/20/11 | 2.00 | 2550.00 | 4978.75 | 4620.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 2.00 | 2550.00 | 4978.75 | 4620.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1.00 | 5000.00 | 10532.89 | 11066.79 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 5000.00 | 10532.89 | 11066.79 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3.00 | 3366.67 | 7755.82 | 6768.93 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-72855 | Traf Sig Ctrl Cabinet | | Each | | | |
| ITS4701-121 | | C470 (SANTA FE TO I-25) AND R | 01/20/11 | 6.00 | 10000.00 | 3869.25 | 1647.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 8.00 | 1500.00 | 10606.05 | 10150.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 14.00 | 5142.86 | 6756.45 | 3772.75 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 1.00 | 10800.00 | 10485.12 | 10300.00 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 2.00 | 12500.00 | 14885.00 | 16870.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 3.00 | 11933.33 | 12245.07 | 14680.00 |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 1.00 | 13000.00 | 19925.20 | 18500.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 1.00 | 13000.00 | 19925.20 | 18500.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1.00 | 12500.00 | 12126.31 | 11271.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 2.00 | 11000.00 | 17022.98 | 20121.45 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 3.00 | 11500.00 | 15857.11 | 17171.30 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 21.00 | 7395.24 | 10754.45 | 9615.73 |
| ========== | 614-72858 | Ped Pole (3.5 In) | | Each | | | |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 1.00 | 1000.00 | 1779.00 | 1000.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 1.00 | 1000.00 | 1779.00 | 1000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 1000.00 | 1779.00 | 1000.00 |
| ========== | 614-72860 | Ped Push Button | | Each | | | |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 10.00 | 160.00 | 120.05 | 95.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-72860 | Ped Push Button | | Each | | | |
| SHE074A-001 | | SH 74 - EVERGREEN - JEFFERSON | 04/28/11 | 8.00 | 150.00 | 201.33 | 94.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 16.00 | 300.00 | 171.06 | 162.93 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 16.00 | 200.00 | 309.50 | 219.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 50.00 | 216.00 | 180.94 | 156.26 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 8.00 | 170.00 | 210.33 | 96.00 |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 8.00 | 150.00 | 151.20 | 149.00 |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 2.00 | 150.00 | 228.00 | 236.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 18.00 | 158.89 | 181.00 | 136.80 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 17.00 | 200.00 | 275.43 | 500.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 8.00 | 150.00 | 233.26 | 214.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 25.00 | 184.00 | 264.82 | 408.48 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 93.00 | 196.34 | 209.02 | 205.77 |
| ========== | 614-72866 | Fire Preempt Unit + Timer | | Each | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 4.00 | 5000.00 | 2085.36 | 2100.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 8.00 | 400.00 | 2288.08 | 2204.51 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 2.00 | 7000.00 | 7755.00 | 7510.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 14.00 | 2657.14 | 2511.79 | 2932.58 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 2.00 | 4000.00 | 5481.43 | 7000.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 2.00 | 5000.00 | 4468.13 | 3347.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 4.00 | 4500.00 | 5059.22 | 5173.50 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 18.00 | 3066.67 | 3226.21 | 3447.19 |
| ========== | 614-72871 | Loop Detect Wire (Prefab) Spec | | Lin Foot | | | |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 14,868.00 | 7.00 | 2.65 | 4.45 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-72871 | Loop Detect Wire (Prefab) Spec | | Lin Foot | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 580.00 | 12.00 | 13.56 | 14.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 15,448.00 | 7.19 | 3.05 | 4.81 |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 300.00 | 10.00 | 11.50 | 12.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 300.00 | 10.00 | 11.50 | 12.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 15,748.00 | 7.24 | 3.11 | 4.95 |
| ========== | 614-72875 | Loop Detect Wire | | Lin Foot | | | |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 2,184.00 | 3.00 | 2.85 | 3.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 5,840.00 | 3.00 | 3.28 | 3.30 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 8,024.00 | 3.00 | 3.06 | 3.12 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 720.00 | 5.00 | 2.95 | 3.00 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 2,184.00 | 4.00 | 5.27 | 4.90 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 6,552.00 | 4.00 | 3.00 | 3.02 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 5,828.00 | 3.00 | 3.34 | 2.71 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 15,284.00 | 3.67 | 3.54 | 3.16 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 1,700.00 | 2.50 | 7.58 | 6.50 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 14,370.00 | 3.00 | 3.47 | 2.69 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 16,070.00 | 2.95 | 3.81 | 3.09 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 5,580.00 | 3.50 | 4.02 | 4.00 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 504.00 | 6.00 | 8.52 | 7.80 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 6,084.00 | 3.71 | 4.56 | 4.31 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 45,462.00 | 3.30 | 3.64 | 3.30 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-72876 | Detect Amp (Loop) (2) | | Each | | | |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 6.00 | 500.00 | 618.94 | 559.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 6.00 | 500.00 | 618.94 | 559.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 6.00 | 500.00 | 618.94 | 559.00 |
| ========== | 614-72878 | Detect Amp (Loop) (4) | | Each | | | |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 4.00 | 850.00 | 805.77 | 715.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 4.00 | 850.00 | 805.77 | 715.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4.00 | 850.00 | 805.77 | 715.00 |
| ========== | 614-72882 | Detect (Micro) | | Each | | | |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 6.00 | 350.00 | 497.56 | 500.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 6.00 | 350.00 | 497.56 | 500.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 6.00 | 350.00 | 497.56 | 500.00 |
| ========== | 614-72884 | Detect (Micro Wave) | | Each | | | |
| ITS4701-121 | | C470 (SANTA FE TO I-25) AND R | 01/20/11 | 9.00 | 7000.00 | 8814.75 | 8609.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 9.00 | 7000.00 | 8814.75 | 8609.00 |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 9.00 | 5500.00 | 8550.00 | 8850.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 9.00 | 5500.00 | 8550.00 | 8850.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 2.00 | 1000.00 | 10171.12 | 7545.54 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 1000.00 | 10171.12 | 7545.54 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 20.00 | 5725.00 | 9056.70 | 8611.10 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-72886 | Intersection Detect Sys (Camera) | | Each | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 5.00 | 6000.00 | 4995.86 | 5000.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 10.00 | 1000.00 | 6952.75 | 6642.70 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 2.00 | 5000.00 | 15897.50 | 14795.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 17.00 | 2941.18 | 6708.84 | 7118.65 |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 4.00 | 4000.00 | 7148.60 | 6400.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 4.00 | 4000.00 | 6624.54 | 6036.14 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 2.00 | 6000.00 | 6809.50 | 6241.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 4.00 | 2500.00 | 6522.70 | 5533.40 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 6.00 | 3666.67 | 6590.98 | 5769.27 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 27.00 | 3259.26 | 6586.58 | 6347.31 |
| ========== | 614-72887 | Detect (Microwave Veh) | | Each | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 2.00 | 10000.00 | 6021.54 | 6000.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2.00 | 10000.00 | 6021.54 | 6000.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 12.00 | 8000.00 | 8212.86 | 7450.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1.00 | 10000.00 | 12826.65 | 13329.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 13.00 | 8153.85 | 8472.06 | 7902.23 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 15.00 | 8400.00 | 8180.91 | 7648.60 |
| ========== | 614-72889 | Detect (Micro) (Non-Invasive) | | Each | | | |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 26.00 | 650.00 | 891.61 | 668.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-72889 | Detect (Micro) (Non-Invasive) | | Each | | | |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 2.00 | 1300.00 | 3161.09 | 2587.51 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 9.00 | 700.00 | 1047.96 | 760.32 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 37.00 | 697.30 | 1010.53 | 794.21 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 24.00 | 950.00 | 759.31 | 515.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 24.00 | 950.00 | 759.31 | 515.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 61.00 | 796.72 | 929.05 | 684.36 |
| ========== | 614-72900 | WL Magnet Vehicle Det Sys | | Each | | | |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1.00 | 30000.00 | 19440.08 | 20168.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 2.00 | 27500.00 | 6328.40 | 6036.44 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 3.00 | 28333.33 | 9450.23 | 10746.96 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3.00 | 28333.33 | 9450.23 | 10746.96 |
| ========== | 614-80000 | Flash Beacon | | Each | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 1.00 | 2000.00 | 2937.89 | 3510.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 16.00 | 2500.00 | 2764.11 | 2695.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 17.00 | 2470.59 | 2785.30 | 2858.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 3.00 | 2500.00 | 2981.57 | 3000.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 3.00 | 2500.00 | 2981.57 | 3000.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 3.00 | 1500.00 | 2951.64 | 2820.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 3.00 | 1500.00 | 2951.64 | 2820.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-80000 | Flash Beacon | | Each | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1.00 | 1400.00 | 1932.14 | 2035.00 |
| C2854-125 | | US 285, ASPEN PARK TO MORRISO | 12/08/11 | 1.00 | 2000.00 | 2966.67 | 2500.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 1700.00 | 2242.50 | 2267.50 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 25.00 | 2296.00 | 2792.44 | 2791.15 |
| ========== | 614-80001 | Flash Beacon (Solar Pwred) | | Each | | | |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 2.00 | 5000.00 | 5281.56 | 4641.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 2.00 | 5000.00 | 5281.56 | 4641.00 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 4.00 | 5000.00 | 3866.67 | 3400.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 4.00 | 5000.00 | 3866.67 | 3400.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 6.00 | 5000.00 | 4509.80 | 3813.67 |
| ========== | 614-80006 | Surface Condition Analyzer | | Each | | | |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 3.00 | 1000.00 | 6040.03 | 5000.14 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 2.00 | 6500.00 | 7193.85 | 6710.89 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 5.00 | 3200.00 | 6441.36 | 5684.44 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 5.00 | 3200.00 | 6441.36 | 5684.44 |
| ========== | 614-80010 | Travel Time Indicator | | Each | | | |
| C0704-225 | | I-70 EAST OF BENNETT | 01/06/11 | 1.00 | 3000.00 | 7362.75 | 5943.00 |
| ITS4701-121 | | C470 (SANTA FE TO I-25) AND R | 01/20/11 | 15.00 | 4000.00 | 7281.25 | 6225.00 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 1.00 | 6000.00 | 8393.32 | 7000.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 17.00 | 4058.82 | 7381.23 | 6254.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-80010 | Travel Time Indicator | | Each | | | |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 2.00 | 1500.00 | 7725.00 | 5927.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 2.00 | 1500.00 | 7725.00 | 5927.00 |
| ITSSW00-928 | | NB I-225 AT MM 2.28 | 11/03/11 | 1.00 | 7000.00 | 8649.50 | 10000.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 2.00 | 1500.00 | 10750.90 | 6036.44 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 3.00 | 3333.33 | 10177.79 | 7357.63 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 22.00 | 3727.27 | 8023.97 | 6374.77 |
| ========== | 614-80321 | Barricade (Ty 3 M-A) | | Each | | | |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 6.00 | 300.00 | 165.00 | 100.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 6.00 | 300.00 | 165.00 | 100.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 6.00 | 300.00 | 165.00 | 100.00 |
| ========== | 614-80385 | Rumble Strip | | Lin Foot | | | |
| STA0504-061 | | US 50 M.P.369.9 -M.P.373.2 | 03/03/11 | 9,724.00 | 0.20 | 0.49 | 0.54 |
| NH 0402-079 | | US40 MP 165.0 - 179.0 GRAND C | 03/31/11 | 73,920.00 | 0.20 | 0.17 | 0.25 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 83,644.00 | 0.20 | 0.23 | 0.33 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 66,000.00 | 0.25 | 0.13 | 0.08 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 37,030.00 | 0.25 | 0.19 | 0.25 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 27,700.00 | 0.25 | 0.25 | 0.30 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 11,230.00 | 0.25 | 0.50 | 0.50 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 73,938.00 | 0.20 | 0.16 | 0.09 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 215,898.00 | 0.23 | 0.18 | 0.16 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 257,097.00 | 0.12 | 0.26 | 0.33 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-80385 | Rumble Strip | | Lin Foot | ========== | ========== | ========== |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 20,600.00 | 0.25 | 0.39 | 0.35 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 277,697.00 | 0.13 | 0.29 | 0.35 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 10,398.00 | 0.25 | 0.54 | 0.79 |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 57.00 | 40.00 | 59.21 | 26.50 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 95,040.00 | 0.35 | 0.18 | 0.20 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 105,495.00 | 0.36 | 0.28 | 0.27 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 682,734.00 | 0.21 | 0.24 | 0.28 |
| ========== | 614-80387 | Rumble Strip (Grind) | | Lin Foot | ========== | ========== | ========== |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 3,400.00 | 0.30 | 1.99 | 1.88 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 3,400.00 | 0.30 | 1.99 | 1.88 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3,400.00 | 0.30 | 1.99 | 1.88 |
| ========== | 614-80391 | Rumble Strip (Grind)(Asphalt) | | Lin Foot | ========== | ========== | ========== |
| MC0504-065 | | US50B FROM MP 318 TO MP 359 | 12/01/11 | 146,520.00 | 0.10 | 0.30 | 0.40 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 146,520.00 | 0.10 | 0.30 | 0.40 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 146,520.00 | 0.10 | 0.18 | 0.23 |
| ========== | 614-80392 | Rumble Strip (Grind)(Conc) | | Lin Foot | ========== | ========== | ========== |
| C2854-125 | | US 285, ASPEN PARK TO MORRISO | 12/08/11 | 68,471.00 | 0.50 | 0.50 | 0.45 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 68,471.00 | 0.50 | 0.50 | 0.45 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 68,471.00 | 0.50 | 0.50 | 0.45 |
| ========== | 614-81010 | Sig-Light Pole Steel (1) | | Each | ========== | ========== | ========== |
| SHE074A-001 | | SH 74 - EVERGREEN - JEFFERSON | 04/28/11 | 2.00 | 13200.00 | 13141.67 | 14325.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2.00 | 13200.00 | 13141.67 | 14325.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 13200.00 | 13141.67 | 14325.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-81125 | Sig-Light Pole Steel (1-25 Ft) | | Each | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 2.00 | 10000.00 | 13271.43 | 13000.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 10000.00 | 13271.43 | 13000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 10000.00 | 13271.43 | 13000.00 |
| ========== | 614-81130 | Sig-Light Pole Steel (1-30 Ft) | | Each | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 2.00 | 10500.00 | 13442.32 | 13500.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2.00 | 10500.00 | 13442.32 | 13500.00 |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 1.00 | 12000.00 | 12416.40 | 10500.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1.00 | 12000.00 | 12416.40 | 10500.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3.00 | 11000.00 | 12913.04 | 12467.25 |
| ========== | 614-81135 | Sig-Light Pole Steel (1-35 Ft) | | Each | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 3.00 | 12000.00 | 14446.67 | 14500.00 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 2.00 | 14000.00 | 18985.00 | 17970.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 5.00 | 12800.00 | 15271.82 | 15888.00 |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 1.00 | 13000.00 | 12867.60 | 11675.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1.00 | 13000.00 | 12867.60 | 11675.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1.00 | 13000.00 | 17661.05 | 15493.51 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 13000.00 | 17661.05 | 15493.51 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 7.00 | 12857.14 | 14732.21 | 14371.85 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-81140 | Sig-Light Pole Steel (1-40 Ft) | | Each | | | |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 2.00 | 14500.00 | 19348.50 | 18297.00 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 2.00 | 14500.00 | 19348.50 | 18297.00 |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 1.00 | 15000.00 | 14364.80 | 13500.00 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 2.00 | 14500.00 | 13551.44 | 13243.00 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 3.00 | 14666.67 | 13864.27 | 13328.67 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1.00 | 12000.00 | 15257.14 | 15500.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1.00 | 13500.00 | 18677.39 | 16097.16 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 2.00 | 12750.00 | 17081.27 | 15798.58 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 7.00 | 14071.43 | 16057.77 | 15453.88 |
| ========== | 614-81145 | Sig-Light Pole Steel (1-45 Ft) | | Each | | | |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 1.00 | 15000.00 | 22586.00 | 21372.00 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 1.00 | 15000.00 | 22586.00 | 21372.00 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 2.00 | 15000.00 | 13609.51 | 13243.00 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 2.00 | 15000.00 | 13609.51 | 13243.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 3.00 | 12500.00 | 15385.71 | 15700.00 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 3.00 | 12500.00 | 15385.71 | 15700.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 6.00 | 13750.00 | 15391.87 | 15826.33 |
| ========== | 614-81150 | Sig-Light Pole Steel (1-50 Ft) | | Each | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1.00 | 16000.00 | 11759.47 | 11196.55 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 1.00 | 16000.00 | 11759.47 | 11196.55 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-81150 | Sig-Light Pole Steel (1-50 Ft) | | Each | | | |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 2.00 | 13000.00 | 14724.67 | 13444.00 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 1.00 | 15500.00 | 13945.52 | 13369.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 3.00 | 13833.33 | 14413.01 | 13419.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1.00 | 12500.00 | 16071.43 | 16000.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 2.00 | 14500.00 | 21946.59 | 19115.38 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 3.00 | 13833.33 | 20158.49 | 18076.92 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 7.00 | 14142.86 | 17393.13 | 15097.76 |
| ========== | 614-81155 | Sig-Light Pole Steel (1-55 Ft) | | Each | | | |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 2.00 | 16000.00 | 17031.12 | 14000.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 2.00 | 16000.00 | 11888.71 | 11304.16 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 1.00 | 16000.00 | 23221.50 | 21943.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 5.00 | 16000.00 | 15133.88 | 14510.26 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 1.00 | 16000.00 | 14230.73 | 13522.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 1.00 | 16000.00 | 16590.43 | 16913.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 2.00 | 13000.00 | 16285.71 | 16700.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 13000.00 | 16285.71 | 16700.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 8.00 | 15250.00 | 15730.51 | 15530.81 |
| ========== | 614-81160 | Sig-Light Pole Steel (1-60 Ft) | | Each | | | |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 2.00 | 16000.00 | 21258.33 | 19795.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-81160 | Sig-Light Pole Steel (1-60 Ft) | | Each | | | |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 1.00 | 16000.00 | 21388.80 | 18990.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 3.00 | 16000.00 | 21317.64 | 19526.67 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 2.00 | 19000.00 | 25853.43 | 23139.66 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 19000.00 | 25853.43 | 23139.66 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 5.00 | 17200.00 | 24005.51 | 20971.86 |
| ========== | 614-81165 | Sig-Light Pole Steel (1-65 Ft) | | Each | | | |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 2.00 | 19000.00 | 24566.25 | 20000.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1.00 | 25000.00 | 23534.79 | 22629.44 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 3.00 | 21000.00 | 24222.43 | 20876.48 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 1.00 | 18500.00 | 20412.17 | 19025.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1.00 | 18500.00 | 20412.17 | 19025.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4.00 | 20375.00 | 23529.66 | 20413.61 |
| ========== | 614-81170 | Sig-Light Pole Steel (1-70 Ft) | | Each | | | |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 2.00 | 20000.00 | 23777.44 | 21982.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 2.00 | 20000.00 | 23777.44 | 21982.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 20000.00 | 23777.44 | 21982.00 |
| ========== | 614-81175 | Sig-Light Pole Steel (1-75 Ft) | | Each | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 3.00 | 32000.00 | 23453.11 | 22252.30 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 3.00 | 32000.00 | 23453.11 | 22252.30 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3.00 | 32000.00 | 23453.11 | 22252.30 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-81230 | Sig-Light Pole Steel (2-30 Ft) | | Each | | | |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 2.00 | 25000.00 | 22531.59 | 21064.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 25000.00 | 22531.59 | 21064.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 25000.00 | 22531.59 | 21064.00 |
| ========== | 614-81255 | Sig-Light Pole Steel (2-55 Ft) | | Each | | | |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 2.00 | 25000.00 | 32596.30 | 33413.21 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 2.00 | 25000.00 | 32596.30 | 33413.21 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 25000.00 | 31959.65 | 32141.47 |
| ========== | 614-82010 | Sig Pole Steel (1) | | Each | | | |
| SHE074A-001 | | SH 74 - EVERGREEN - JEFFERSON | 04/28/11 | 2.00 | 13500.00 | 12185.00 | 11505.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 2.00 | 13500.00 | 12185.00 | 11505.00 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 7.00 | 12500.00 | 12804.54 | 12422.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 7.00 | 12500.00 | 12804.54 | 12422.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 9.00 | 12722.22 | 12695.21 | 12218.22 |
| ========== | 614-82020 | Sig Pole Steel (2) | | Each | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 2.00 | 20000.00 | 20495.75 | 19486.60 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 2.00 | 20000.00 | 20495.75 | 19486.60 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 20000.00 | 20495.75 | 19486.60 |
| ========== | 614-84000 | Traf Sig Ped Pole Steel | | Each | | | |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 1.00 | 1250.00 | 1235.52 | 1078.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-84000 | Traf Sig Ped Pole Steel | | Each | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 6.00 | 1240.00 | 1730.43 | 1700.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 4.00 | 1700.00 | 1560.00 | 1500.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 6.00 | 1300.00 | 802.59 | 766.35 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 17.00 | 1370.00 | 1329.40 | 1283.74 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 3.00 | 1000.00 | 1306.67 | 860.00 |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 3.00 | 1150.00 | 1288.80 | 1075.00 |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 8.00 | 1200.00 | 912.00 | 944.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 14.00 | 1146.43 | 1142.10 | 954.07 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 2.00 | 1500.00 | 4450.34 | 4163.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 1500.00 | 4450.34 | 4163.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 33.00 | 1283.03 | 1454.47 | 1283.30 |
| ========== | 614-84100 | Traf Sig Ped Pole Alum | | Each | | | |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 2.00 | 1100.00 | 1357.35 | 851.40 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2.00 | 1100.00 | 1357.35 | 851.40 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1.00 | 1500.00 | 1497.02 | 1006.07 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 1500.00 | 1497.02 | 1006.07 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3.00 | 1233.33 | 1285.62 | 797.97 |
| ========== | 614-85001 | Impact Atten | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 12.00 | 30000.00 | 23792.34 | 20000.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-85001 | Impact Atten | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 1.00 | 25000.00 | 24351.99 | 20174.25 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 13.00 | 29615.38 | 23920.26 | 20043.56 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 1.00 | 30000.00 | 22288.23 | 21300.00 |
| ITS0703-370 | | EAST OF EJMT ON I-70 EB LANES | 06/16/11 | 1.00 | 22750.00 | 26121.67 | 24450.00 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 2.00 | 26375.00 | 23438.26 | 22875.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 2.00 | 21000.00 | 19297.03 | 18750.00 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 2.00 | 21000.00 | 20032.69 | 20441.50 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 2.00 | 20000.00 | 29021.43 | 31000.00 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 2.00 | 20000.00 | 29021.43 | 31000.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 19.00 | 27355.26 | 23686.55 | 22474.19 |
| ========== | 614-85003 | Impact Atten (LM) | | Each | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 2.00 | 20000.00 | 18676.67 | 22000.00 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 5.00 | 20000.00 | 22667.77 | 21135.00 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 7.00 | 20000.00 | 20893.94 | 21382.14 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 2.00 | 22000.00 | 24009.06 | 25000.00 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 2.00 | 22000.00 | 24009.06 | 25000.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 9.00 | 20444.44 | 22053.06 | 22186.11 |
| ========== | 614-85130 | Impact Atten (Quadguard II) | | Each | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 1.00 | 20000.00 | 26516.98 | 28000.90 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 1.00 | 20000.00 | 26516.98 | 28000.90 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-85130 | Impact Atten (Quadguard II) | | Each | | | |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 2.00 | 2500.00 | 17293.33 | 16500.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2.00 | 2500.00 | 17293.33 | 16500.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3.00 | 8333.33 | 21905.15 | 20333.63 |
| ========== | 614-85312 | Span Wire Pole (12 In) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 8.00 | 3500.00 | 5769.33 | 5800.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 8.00 | 3500.00 | 5769.33 | 5800.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 8.00 | 3500.00 | 5769.33 | 5800.00 |
| ========== | 614-85362 | Sig-Light Span Wire Pole (12 In) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 12.00 | 7000.00 | 8063.56 | 8300.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 12.00 | 7000.00 | 8063.56 | 8300.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 12.00 | 7000.00 | 8063.56 | 8300.00 |
| ========== | 614-85366 | Sig-Light Span Wire Pole (16 In) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 8.00 | 10000.00 | 9426.00 | 10100.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 8.00 | 10000.00 | 9426.00 | 10100.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 8.00 | 10000.00 | 9426.00 | 10100.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-86002 | Spread Spectrum Radio | | Each | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 1.00 | 2500.00 | 2473.49 | 2500.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 1.00 | 2500.00 | 2473.49 | 2500.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 2500.00 | 2473.49 | 2500.00 |
| ========== | 614-86004 | Spread Spectrum Radio (Install) | | Each | | | |
| ITS4701-121 | | C470 (SANTA FE TO I-25) AND R | 01/20/11 | 6.00 | 200.00 | 766.00 | 434.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 6.00 | 200.00 | 766.00 | 434.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 6.00 | 200.00 | 766.00 | 434.00 |
| ========== | 614-86007 | Serial to IP Converter | | Each | | | |
| C0704-225 | | I-70 EAST OF BENNETT | 01/06/11 | 1.00 | 1000.00 | 1695.00 | 1465.00 |
| ITS4701-121 | | C470 (SANTA FE TO I-25) AND R | 01/20/11 | 3.00 | 2000.00 | 2174.00 | 1826.00 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 2.00 | 3000.00 | 5090.03 | 3000.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 6.00 | 2166.67 | 3355.30 | 2157.17 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 6.00 | 2166.67 | 3355.30 | 2157.17 |
| ========== | 614-86105 | Telemetry (Field) | | Each | | | |
| ITS4701-121 | | C470 (SANTA FE TO I-25) AND R | 01/20/11 | 5.00 | 1000.00 | 1791.25 | 1350.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 5.00 | 1000.00 | 1878.04 | 1503.43 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 2.00 | 3300.00 | 2773.00 | 396.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 2.00 | 3300.00 | 2183.88 | 589.67 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 2.00 | 2500.00 | 2590.71 | 1725.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-86105 | Telemetry (Field) | | Each | | | |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 2.00 | 2000.00 | 4147.95 | 3018.22 |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 8.00 | 1500.00 | 3123.97 | 1037.88 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 12.00 | 1750.00 | 3267.81 | 1482.46 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 19.00 | 1715.79 | 3078.76 | 1808.94 |
| ========== | 614-86106 | Telemetry (Field)(Install Only) | | Each | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 4.00 | 4500.00 | 885.46 | 843.79 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 4.00 | 4500.00 | 885.46 | 843.79 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4.00 | 4500.00 | 885.46 | 843.79 |
| ========== | 614-86238 | Ctrler (S-S) (F-A) (8) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 8.00 | 15000.00 | 4244.04 | 2695.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 8.00 | 15000.00 | 4244.04 | 2695.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 1.00 | 6420.00 | 6107.55 | 6100.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 1.00 | 6420.00 | 6107.55 | 6100.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 9.00 | 14046.67 | 4709.92 | 3830.00 |
| ========== | 614-86239 | Ctrler (S-S) (F-A) (12) | | Each | | | |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 2.00 | 2500.00 | 5401.50 | 2603.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 2.00 | 2500.00 | 5401.50 | 2603.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1.00 | 2500.00 | 9105.38 | 8836.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-86239 | Ctrler (S-S) (F-A) (12) | | Each | | | |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 2.00 | 2500.00 | 5589.90 | 3521.26 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 3.00 | 2500.00 | 6426.92 | 5292.84 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 5.00 | 2500.00 | 6262.85 | 4216.90 |
| ========== | 614-86246 | Ctrler (Ty 170E-HC11) | | Each | | | |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 1.00 | 24000.00 | 18933.79 | 20922.65 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 3.00 | 15000.00 | 20055.41 | 19184.89 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 4.00 | 17250.00 | 19851.47 | 19619.33 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 1.00 | 20000.00 | 24478.00 | 23044.00 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 3.00 | 23000.00 | 23607.22 | 21182.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 4.00 | 22250.00 | 22423.78 | 20702.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 8.00 | 19750.00 | 21057.92 | 20152.48 |
| ========== | 614-86250 | Ctrler (Ramp Metering) | | Each | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 2.00 | 9000.00 | 10452.80 | 10500.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2.00 | 9000.00 | 10452.80 | 10500.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 9000.00 | 10452.80 | 10500.00 |
| ========== | 614-86710 | Traffic Sig Equip | | LUMP SUM | | | |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 1.00 | 25000.00 | 29640.00 | 30680.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1.00 | 25000.00 | 29640.00 | 30680.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 25000.00 | 29640.00 | 30680.00 |
| ========== | 614-86735 | Weather Sensor | | LUMP SUM | | | |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 1.00 | 25000.00 | 14867.17 | 15000.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 25000.00 | 14867.17 | 15000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 25000.00 | 16946.87 | 15000.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-86741 | Weather Monitor System | | Each | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 1.00 | 40000.00 | 52253.52 | 52824.98 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1.00 | 40000.00 | 52253.52 | 52824.98 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 40000.00 | 59066.47 | 59662.49 |
| ========== | 614-86748 | Ctrler (Ty 2070) | | Each | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 2.00 | 17000.00 | 19785.71 | 21000.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 17000.00 | 19785.71 | 21000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 17000.00 | 19785.71 | 21000.00 |
| ========== | 614-86752 | Fold-Over Tower (ITS) | | Each | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 1.00 | 10000.00 | 12173.07 | 8804.16 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1.00 | 10000.00 | 12173.07 | 8804.16 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 10000.00 | 13355.32 | 8302.08 |
| ========== | 614-86800 | Uninterrupted Power Supply | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 8.00 | 6500.00 | 5324.02 | 5000.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 8.00 | 6500.00 | 5550.35 | 5576.50 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 1.00 | 6600.00 | 8417.12 | 8400.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 3.00 | 6000.00 | 7501.05 | 7148.57 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 4.00 | 6150.00 | 7730.07 | 7461.43 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 12.00 | 6383.33 | 6625.87 | 6459.19 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-87006 | Fiber Optic Termination Panel - 6 Fiber | | Each | | | |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 3.00 | 300.00 | 1267.25 | 3076.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 3.00 | 300.00 | 1267.25 | 3076.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3.00 | 300.00 | 1267.25 | 3076.00 |
| ========== | 614-87010 | Fiber Optic Cable (S Mode) (12 Fiber) | | Lin Foot | | | |
| C0704-225 | | I-70 EAST OF BENNETT | 01/06/11 | 2,000.00 | 2.50 | 2.25 | 1.18 |
| ITS4701-121 | | C470 (SANTA FE TO I-25) AND R | 01/20/11 | 12,000.00 | 2.00 | 2.92 | 2.35 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 2,081.00 | 3.00 | 4.14 | 3.50 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 1,000.00 | 3.00 | 3.72 | 3.08 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 17,081.00 | 2.24 | 3.13 | 2.40 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 2,730.00 | 2.50 | 1.34 | 1.09 |
| ITS0703-370 | | EAST OF EJMT ON I-70 EB LANES | 06/16/11 | 4,331.00 | 3.30 | 2.13 | 2.50 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 4,960.00 | 6.00 | 2.49 | 1.70 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 12,021.00 | 4.23 | 2.17 | 1.85 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 8,450.00 | 1.70 | 1.80 | 1.25 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 405.00 | 3.00 | 3.22 | 1.30 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 1,650.00 | 3.00 | 3.12 | 3.10 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 10,505.00 | 1.95 | 2.29 | 1.54 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 480.00 | 3.00 | 2.22 | 2.30 |
| ITSSW00-928 | | NB I-225 AT MM 2.28 | 11/03/11 | 300.00 | 3.00 | 7.66 | 4.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 3,590.00 | 2.00 | 2.29 | 2.01 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 4,370.00 | 2.18 | 2.58 | 2.18 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 43,977.00 | 2.71 | 2.62 | 2.02 |
| ========== | 614-87020 | Optical Transceiver | | Each | | | |
| C0704-225 | | I-70 EAST OF BENNETT | 01/06/11 | 2.00 | 2000.00 | 2584.00 | 2411.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-87020 | Optical Transceiver | | Each | | | |
| ITS4701-121 | | C470 (SANTA FE TO I-25) AND R | 01/20/11 | 40.00 | 2000.00 | 2166.25 | 2480.00 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 6.00 | 2000.00 | 3357.36 | 3200.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 1.00 | 2000.00 | 5265.19 | 2476.17 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 49.00 | 2000.00 | 2501.22 | 2565.27 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 4.00 | 1940.00 | 3113.04 | 3100.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 10.00 | 2000.00 | 2113.32 | 2558.28 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 14.00 | 1982.86 | 2223.27 | 2087.73 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 7.00 | 2200.00 | 3155.00 | 2665.00 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 1.00 | 3000.00 | 2688.15 | 2891.00 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 8.00 | 2300.00 | 3080.30 | 2693.25 |
| ITSSW00-928 | | NB I-225 AT MM 2.28 | 11/03/11 | 2.00 | 3500.00 | 2547.42 | 2040.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 4.00 | 2600.00 | 2456.62 | 2515.18 |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 2.00 | 2000.00 | 3066.63 | 2234.50 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 8.00 | 2675.00 | 2571.42 | 2326.22 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 79.00 | 2095.70 | 2461.66 | 2392.29 |
| ========== | 614-87028 | Video Optic Transceiver | | Each | | | |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 4.00 | 2500.00 | 2876.19 | 3325.77 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 4.00 | 2500.00 | 2769.35 | 2598.85 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 4.00 | 2500.00 | 2456.66 | 2353.00 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 4.00 | 2500.00 | 2456.66 | 2353.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 8.00 | 2500.00 | 2726.22 | 2571.53 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-87310 | TMS Building Equip | | LUMP SUM | ========== | ========== | ========== |
| ITS4701-121 | | C470 (SANTA FE TO I-25) AND R | 01/20/11 | 1.00 | 9000.00 | 7523.00 | 10642.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1.00 | 9000.00 | 7523.00 | 10642.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 9000.00 | 14585.14 | 6406.00 |
| ========== | 614-87320 | CCTV | | Each | ========== | ========== | ========== |
| C0704-225 | | I-70 EAST OF BENNETT | 01/06/11 | 1.00 | 5000.00 | 5079.50 | 3623.00 |
| ITS4701-121 | | C470 (SANTA FE TO I-25) AND R | 01/20/11 | 16.00 | 3000.00 | 3879.25 | 3667.00 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 2.00 | 3000.00 | 5114.31 | 5500.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 19.00 | 3105.26 | 4276.19 | 3939.75 |
| ITS0703-370 | | EAST OF EJMT ON I-70 EB LANES | 06/16/11 | 1.00 | 5500.00 | 4137.67 | 4150.00 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 6.00 | 3000.00 | 3738.00 | 3126.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 7.00 | 3357.14 | 3817.93 | 3272.29 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 1.00 | 6000.00 | 5071.52 | 4067.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1.00 | 6000.00 | 5820.88 | 4832.96 |
| ITSSW00-928 | | NB I-225 AT MM 2.28 | 11/03/11 | 1.00 | 3500.00 | 3738.17 | 4071.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 2.00 | 4000.00 | 4294.35 | 4024.29 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 3.00 | 3833.33 | 4142.66 | 4039.86 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 30.00 | 3333.33 | 4295.19 | 3858.95 |
| ========== | 614-87325 | CCTV Pole | | Each | ========== | ========== | ========== |
| ITS4701-121 | | C470 (SANTA FE TO I-25) AND R | 01/20/11 | 21.00 | 2000.00 | 2555.25 | 2096.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-87325 | CCTV Pole | | Each | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 2.00 | 3000.00 | 2873.22 | 2600.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 23.00 | 2086.96 | 2595.00 | 2139.83 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 2.00 | 3000.00 | 5692.65 | 5700.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2.00 | 3000.00 | 5692.65 | 5700.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1.00 | 3000.00 | 3809.86 | 3780.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 3000.00 | 3809.86 | 3780.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 26.00 | 2192.31 | 2977.71 | 2476.77 |
| ========== | 614-87333 | CCTV Camera (Traf Surveil) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 4.00 | 6000.00 | 7905.39 | 7800.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 4.00 | 6000.00 | 7905.39 | 7800.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 2.00 | 8000.00 | 3726.64 | 3700.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2.00 | 8000.00 | 3636.44 | 3700.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 6.00 | 6666.67 | 4246.29 | 3941.18 |
| ========== | 614-87350 | Test Fiber Optic Cable | | LUMP SUM | | | |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 1.00 | 3500.00 | 15745.32 | 3172.27 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1.00 | 3500.00 | 17752.61 | 4311.14 |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 1.00 | 2000.00 | 1101.00 | 880.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-87350 | Test Fiber Optic Cable | | LUMP SUM | ========== | ========== | ========== |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 1.00 | 15000.00 | 2807.25 | 4100.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 1.00 | 3000.00 | 1682.63 | 1165.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 3.00 | 6666.67 | 1827.23 | 2064.19 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4.00 | 5875.00 | 5808.57 | 2813.17 |
| ========== | 614-87360 | Control Center Upgrade | | LUMP SUM | ========== | ========== | ========== |
| IM0702-306 | | HANGING LAKE TUNNEL | 10/27/11 | 1.00 | 610000.00 | 663101.83 | 523311.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 610000.00 | 663101.83 | 523311.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 610000.00 | 663101.83 | 523311.00 |
| ========== | 614-87406 | Fiber Optic Cable (S Mode) (6 S) | | Lin Foot | ========== | ========== | ========== |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 200.00 | 5.00 | 4.41 | 1.12 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 200.00 | 5.00 | 4.41 | 1.12 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 200.00 | 5.00 | 4.41 | 1.12 |
| ========== | 614-87412 | Fiber Optic Cable (S Mode) (12 S) (Inst) | | Lin Foot | ========== | ========== | ========== |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 1,900.00 | 2.00 | 6.91 | 7.50 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1,900.00 | 2.00 | 6.91 | 7.50 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 530.00 | 2.00 | 3.51 | 0.82 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 530.00 | 2.00 | 2.10 | 1.77 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,430.00 | 2.00 | 3.43 | 2.60 |
| ========== | 614-87424 | Fiber Optic Cable (S Mode) (24 S) | | Lin Foot | ========== | ========== | ========== |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 1,520.00 | 3.00 | 6.63 | 6.50 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1,520.00 | 3.00 | 4.14 | 2.97 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-87424 | Fiber Optic Cable (S Mode) (24 S) | | Lin Foot | | | |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 150.00 | 5.00 | 2.62 | 3.00 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 150.00 | 5.00 | 2.62 | 3.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,670.00 | 3.18 | 3.79 | 2.89 |
| ========== | 614-87448 | Fiber Optic Cable (S Mode) (48 S) | | Lin Foot | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 2,000.00 | 3.00 | 4.67 | 4.24 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 2,000.00 | 3.00 | 4.67 | 4.24 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1,350.00 | 4.50 | 3.69 | 3.10 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 1,350.00 | 4.50 | 3.69 | 3.10 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3,350.00 | 3.60 | 4.38 | 3.78 |
| ========== | 614-87496 | Fiber Optic Cable (S Mode) (96 S) | | Lin Foot | | | |
| ITS4701-121 | | C470 (SANTA FE TO I-25) AND R | 01/20/11 | 2,000.00 | 3.00 | 3.20 | 2.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 8,400.00 | 4.00 | 6.98 | 7.60 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 10,400.00 | 3.81 | 5.86 | 4.87 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 79,600.00 | 1.50 | 1.53 | 1.53 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 79,600.00 | 1.50 | 1.80 | 1.40 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 90,000.00 | 1.77 | 1.91 | 1.45 |
| ========== | 614-87498 | Fiber Optic Cable (S Mode) (144 S) | | Lin Foot | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 2,000.00 | 5.00 | 8.41 | 4.40 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 2,000.00 | 5.00 | 8.41 | 4.40 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-87498 | Fiber Optic Cable (S Mode) (144 S) | | Lin Foot | | | |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1,350.00 | 5.00 | 5.04 | 5.45 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 2,600.00 | 2.00 | 4.19 | 3.02 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 3,950.00 | 3.03 | 4.40 | 3.85 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 5,950.00 | 3.69 | 5.87 | 4.04 |
| ========== | 614-87506 | Splice FO Cable (6 Strand) | | Each | | | |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 8.00 | 200.00 | 390.40 | 315.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 8.00 | 200.00 | 592.34 | 310.99 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 8.00 | 200.00 | 301.80 | 173.60 |
| ========== | 614-87660 | Video Decoder | | Each | | | |
| C0704-225 | | I-70 EAST OF BENNETT | 01/06/11 | 1.00 | 5000.00 | 8574.50 | 10668.00 |
| ITS4701-121 | | C470 (SANTA FE TO I-25) AND R | 01/20/11 | 3.00 | 4500.00 | 3825.25 | 3791.00 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 2.00 | 7000.00 | 5638.96 | 7000.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 6.00 | 5416.67 | 5281.02 | 6006.83 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 1.00 | 7500.00 | 2069.52 | 2100.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 4.00 | 1600.00 | 7036.50 | 4150.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 5.00 | 2780.00 | 6033.87 | 4885.71 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 11.00 | 4218.18 | 5704.49 | 5403.15 |
| ========== | 614-87661 | Video Encoder | | Each | | | |
| C0704-225 | | I-70 EAST OF BENNETT | 01/06/11 | 1.00 | 5000.00 | 6815.50 | 3632.00 |
| ITS4701-121 | | C470 (SANTA FE TO I-25) AND R | 01/20/11 | 2.00 | 4500.00 | 4772.75 | 3791.00 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 2.00 | 7000.00 | 6180.63 | 7000.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 5.00 | 5600.00 | 5817.15 | 5042.80 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 614-87661 | Video Encoder | | Each | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 1.00 | 7500.00 | 2069.52 | 2100.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 1.00 | 5800.00 | 8226.17 | 12200.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2.00 | 6650.00 | 5010.56 | 5572.50 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 7.00 | 5900.00 | 5471.47 | 5278.22 |
| ========== | 614-87690 | Ethernet Switch | | Each | | | |
| SHE074A-001 | | SH 74 - EVERGREEN - JEFFERSON | 04/28/11 | 4.00 | 2700.00 | 4536.67 | 3310.00 |
| ITS0703-370 | | EAST OF EJMT ON I-70 EB LANES | 06/16/11 | 2.00 | 4000.00 | 3303.00 | 3115.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 2.00 | 14960.00 | 23614.17 | 27600.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 8.00 | 6090.00 | 14127.40 | 12820.77 |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 1.00 | 20000.00 | 22590.00 | 2500.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1.00 | 20000.00 | 22590.00 | 2500.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 9.00 | 7635.56 | 14973.66 | 12083.57 |
| ========== | 615-00030 | Emb Prot Ty 3 | | Each | | | |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 4.00 | 1200.00 | 1297.98 | 1300.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 4.00 | 1200.00 | 1297.98 | 1300.00 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 2.00 | 300.00 | 1750.01 | 1500.04 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 1.00 | 750.00 | 3270.45 | 3540.89 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 8.00 | 1500.00 | 1890.00 | 1250.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 6.00 | 2000.00 | 1189.94 | 1508.56 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 17.00 | 1491.18 | 1475.09 | 1415.29 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 6.00 | 3000.00 | 1358.55 | 1026.28 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 615-00030 | Emb Prot Ty 3 | | Each | | | |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 6.00 | 1200.00 | 458.69 | 360.81 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 4.00 | 2200.00 | 1007.41 | 760.00 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 16.00 | 2125.00 | 1010.86 | 710.16 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 37.00 | 1733.78 | 1245.25 | 1175.63 |
| ========== | 615-00050 | Emb Prot Ty 5 | | Each | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 2.00 | 2500.00 | 1450.52 | 500.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 2.00 | 2500.00 | 1450.52 | 500.00 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 2.00 | 300.00 | 1718.01 | 2000.06 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 1.00 | 2300.00 | 1373.73 | 1056.13 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 3.00 | 3000.00 | 1017.04 | 1257.14 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 6.00 | 1983.33 | 1614.39 | 1344.83 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 2.00 | 1500.00 | 1400.73 | 1700.00 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 2.00 | 1500.00 | 1400.73 | 1700.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 4.00 | 2500.00 | 1140.10 | 370.00 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 4.00 | 2500.00 | 1140.10 | 370.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 14.00 | 2135.71 | 1446.38 | 1123.08 |
| ========== | 615-10024 | 24 In Auto Drain Gate | | Each | | | |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 1.00 | 2500.00 | 3882.08 | 2206.03 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 1.00 | 2500.00 | 3882.08 | 2206.03 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 1.00 | 2500.00 | 3882.08 | 2206.03 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 615-10036 | 36 In Auto Drain Gate | | Each | | | |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 1.00 | 5000.00 | 6018.79 | 3309.05 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 5000.00 | 6018.79 | 3309.05 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 5000.00 | 6018.79 | 3309.05 |
| ========== | 615-10048 | 48 In Auto Drain Gate | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 4.00 | 1000.00 | 9025.39 | 11000.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 4.00 | 1000.00 | 9025.39 | 11000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4.00 | 1000.00 | 9025.39 | 11000.00 |
| ========== | 615-21899 | 18 In Sl Hdgate Spec | | Each | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1.00 | 1500.00 | 6747.14 | 5800.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 1500.00 | 6747.14 | 5800.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 1500.00 | 6747.14 | 5800.00 |
| ========== | 616-00150 | 15 In Conc Siphon Pipe | | Lin Foot | | | |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 77.00 | 100.00 | 327.33 | 226.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 77.00 | 100.00 | 327.33 | 226.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 77.00 | 100.00 | 327.33 | 226.00 |
| ========== | 616-00180 | 18 In Conc Siphon Pipe | | Lin Foot | | | |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 20.00 | 120.00 | 392.33 | 281.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 20.00 | 120.00 | 392.33 | 281.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 20.00 | 120.00 | 392.33 | 281.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 616-30030 | 30 In Trash Guard | | Each | | | |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 1.00 | 1500.00 | 2576.67 | 1725.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1.00 | 1500.00 | 2576.67 | 1725.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 1500.00 | 1130.86 | 1041.86 |
| ========== | 616-30066 | 66 In Trash Guard | | Each | | | |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 1.00 | 2500.00 | 4238.67 | 2175.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1.00 | 2500.00 | 4238.67 | 2175.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 2500.00 | 4238.67 | 2175.00 |
| ========== | 616-30499 | Trash Guard Spec | | Each | | | |
| C0241-055 | | SH 24 MP 148-152 | 05/26/11 | 1.00 | 10000.00 | 9289.13 | 7700.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1.00 | 10000.00 | 9289.13 | 7700.00 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 1.00 | 15000.00 | 27389.86 | 25000.00 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 1.00 | 10000.00 | 6087.30 | 7556.52 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 2.00 | 12500.00 | 18513.79 | 16278.26 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 2.00 | 3000.00 | 5642.86 | 6200.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 3000.00 | 5642.86 | 6200.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 5.00 | 8200.00 | 11345.96 | 10531.30 |
| ========== | 618-00002 | Prestress Steel Strand | | M Kip Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 74,886.00 | 27.50 | 25.61 | 17.58 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 618-00002 | Prestress Steel Strand | | M Kip Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 5,086.00 | 100.00 | 59.92 | 40.16 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 79,972.00 | 32.11 | 31.41 | 22.86 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 79,972.00 | 32.11 | 31.41 | 22.86 |
| ========== | 618-00005 | Prestress Steel Bar | | M Kip Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 32,698.00 | 100.00 | 14.41 | 17.58 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 32,698.00 | 100.00 | 14.41 | 17.58 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 32,698.00 | 100.00 | 14.41 | 17.58 |
| ========== | 618-00142 | Prestress Conc I (BT42) | | Lin Foot | | | |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 4,403.00 | 150.00 | 158.27 | 144.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 4,403.00 | 150.00 | 158.27 | 144.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4,403.00 | 150.00 | 158.27 | 144.00 |
| ========== | 618-00163 | Prestress Conc I (BT63) | | Lin Foot | | | |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 5,304.00 | 170.00 | 200.43 | 170.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 5,304.00 | 170.00 | 200.43 | 170.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 4,270.00 | 175.00 | 175.22 | 175.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 4,270.00 | 175.00 | 175.22 | 175.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 9,574.00 | 172.23 | 188.35 | 172.23 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 618-00172 | Prestress Conc I (BT72) | | Lin Foot | | | |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 903.00 | 275.00 | 241.62 | 280.04 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 903.00 | 275.00 | 241.62 | 280.04 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 903.00 | 275.00 | 241.62 | 280.04 |
| ========== | 618-00184 | Prestress Conc I (BT84) | | Lin Foot | | | |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 3,021.00 | 200.00 | 249.83 | 240.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 3,021.00 | 200.00 | 249.83 | 240.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 668.00 | 200.00 | 346.62 | 310.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 668.00 | 200.00 | 346.62 | 310.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3,689.00 | 200.00 | 264.03 | 252.68 |
| ========== | 618-01994 | Prestress Conc Box (Depth 32" Thru 48") | | Sq Foot | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 1,128.00 | 55.00 | 70.67 | 61.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1,128.00 | 55.00 | 70.67 | 61.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 7,791.00 | 50.00 | 55.47 | 63.12 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 7,791.00 | 50.00 | 55.47 | 63.12 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 8,919.00 | 50.63 | 56.95 | 62.85 |
| ========== | 618-06032 | Prestress Conc Slab (Depth Less Than 6") | | Sq Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 87,716.00 | 9.00 | 9.29 | 9.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 618-06032 | Prestress Conc Slab (Depth Less Than 6") | | Sq Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 87,716.00 | 9.00 | 9.29 | 9.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 87,716.00 | 9.00 | 9.29 | 9.00 |
| ========== | 618-06034 | Prestress Conc Slab (Depth 6" Thru 13") | | Sq Foot | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 67,602.00 | 50.00 | 30.33 | 26.27 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 67,602.00 | 50.00 | 30.33 | 26.27 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 67,602.00 | 50.00 | 30.33 | 26.27 |
| ========== | 618-10000 | Precast Conc U Girder (Pre-Ten) | | Lin Foot | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 2,136.00 | 450.00 | 437.62 | 365.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2,136.00 | 450.00 | 437.62 | 365.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,136.00 | 450.00 | 437.62 | 365.00 |
| ========== | 618-10060 | Precast Conc U Girder (U60)(Pre-Ten) | | Lin Foot | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 696.00 | 380.00 | 473.59 | 410.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 696.00 | 380.00 | 473.59 | 410.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 696.00 | 380.00 | 473.59 | 410.00 |
| ========== | 618-10072 | Precast Conc U Girder (U72)(Pre-Ten) | | Lin Foot | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 2,920.00 | 450.00 | 620.28 | 552.53 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 2,920.00 | 450.00 | 620.28 | 552.53 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 3,291.00 | 350.00 | 463.56 | 405.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 3,291.00 | 350.00 | 463.56 | 405.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 6,211.00 | 397.01 | 537.24 | 474.36 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 618-10200 | Precast Conc U Girder (Pre and Post-Ten) | | Lin Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | . | 8,488.00 | 750.00 | 572.91 | . |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 8,488.00 | 750.00 | 572.91 | . |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 8,488.00 | 750.00 | 572.91 | . |
| ========== | 618-10372 | Precast Concrete U Girder (U72)(Curved) | | Lin Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 6,878.00 | 660.00 | 611.02 | 600.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 6,878.00 | 660.00 | 611.02 | 600.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 6,878.00 | 660.00 | 611.02 | 600.00 |
| ========== | 619-00000 | Water Meter and Vault | | Each | | | |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 9.00 | 10000.00 | 4338.44 | 5100.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 9.00 | 10000.00 | 4338.44 | 5100.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1.00 | 20000.00 | 3280.00 | 4000.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 20000.00 | 3280.00 | 4000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 10.00 | 11000.00 | 4195.96 | 4990.00 |
| ========== | 619-00002 | Water Service | | Each | | | |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 3.00 | 2500.00 | 2514.17 | 2000.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 3.00 | 2500.00 | 2514.17 | 2000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3.00 | 2500.00 | 2514.17 | 2000.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 619-00007 | Connect To Existing Waterline | | Each | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 22.00 | 1500.00 | 1627.14 | 1050.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 22.00 | 1500.00 | 1627.14 | 1050.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 22.00 | 1500.00 | 1627.14 | 1050.00 |
| ========== | 619-10000 | Temp Water Line | | Lin Foot | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 11,000.00 | 12.00 | 9.08 | 10.75 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 11,000.00 | 12.00 | 9.08 | 10.75 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 11,000.00 | 12.00 | 9.08 | 10.75 |
| ========== | 619-10120 | 12 In Weld Steel Pipe | | Lin Foot | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 91.00 | 110.00 | 127.37 | 132.06 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 91.00 | 110.00 | 127.37 | 132.06 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 91.00 | 110.00 | 127.37 | 132.06 |
| ========== | 619-10200 | 20 In Weld Steel Pipe | | Lin Foot | | | |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 143.00 | 150.00 | 305.88 | 380.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 143.00 | 150.00 | 305.88 | 380.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 32.00 | 250.00 | 192.86 | 185.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 32.00 | 250.00 | 192.86 | 185.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 175.00 | 168.29 | 278.92 | 344.34 |
| ========== | 619-10240 | 24 In Weld Steel Pipe | | Lin Foot | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 32.00 | 350.00 | 200.71 | 170.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 619-10240 | 24 In Weld Steel Pipe | | Lin Foot | ========== | ========== | ========== |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 42.00 | 300.00 | 595.00 | 590.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 74.00 | 321.62 | 308.25 | 408.38 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 74.00 | 321.62 | 308.25 | 408.38 |
| ========== | 619-10300 | 30 In Weld Steel Pipe | | Lin Foot | ========== | ========== | ========== |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 22.00 | 300.00 | 3796.15 | 3489.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 22.00 | 300.00 | 3796.15 | 3489.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 22.00 | 300.00 | 3796.15 | 3489.00 |
| ========== | 619-10360 | 36 In Weld Steel Pipe | | Lin Foot | ========== | ========== | ========== |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 58.00 | 400.00 | 670.00 | 690.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 58.00 | 400.00 | 670.00 | 690.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 58.00 | 400.00 | 670.00 | 690.00 |
| ========== | 619-10425 | 42 In Weld Steel Pipe (Spec) | | Lin Foot | ========== | ========== | ========== |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 133.00 | 600.00 | 498.57 | 580.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 133.00 | 600.00 | 498.57 | 580.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 133.00 | 600.00 | 498.57 | 580.00 |
| ========== | 619-10600 | 60 In Weld Steel Pipe | | Lin Foot | ========== | ========== | ========== |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 686.00 | 500.00 | 769.57 | 749.28 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 686.00 | 500.00 | 769.57 | 749.28 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 686.00 | 500.00 | 769.57 | 749.28 |
| ========== | 619-30000 | 60 In Internal Joint Seals | | Each | ========== | ========== | ========== |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 6.00 | 800.00 | 2298.86 | 2095.89 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 6.00 | 800.00 | 2298.86 | 2095.89 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 6.00 | 800.00 | 2298.86 | 2095.89 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 619-40060 | 3/4 In Copper Pipe | | Lin Foot | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 35.00 | 55.00 | 37.43 | 34.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 35.00 | 55.00 | 37.43 | 34.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 35.00 | 55.00 | 37.43 | 34.00 |
| ========== | 619-40080 | 1 In Copper Pipe | | Lin Foot | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 110.00 | 37.00 | 48.22 | 60.95 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 110.00 | 37.00 | 48.22 | 60.95 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 218.00 | 70.00 | 36.43 | 34.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 218.00 | 70.00 | 36.43 | 34.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 328.00 | 58.93 | 39.99 | 43.04 |
| ========== | 619-40120 | 1-1/2 In Copper Pipe | | Lin Foot | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 44.00 | 200.00 | 46.29 | 50.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 44.00 | 200.00 | 46.29 | 50.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 44.00 | 200.00 | 46.29 | 50.00 |
| ========== | 619-40160 | 2 In Copper Pipe | | Lin Foot | | | |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 851.00 | 25.00 | 41.88 | 50.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 851.00 | 25.00 | 41.88 | 50.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 851.00 | 25.00 | 41.88 | 50.00 |
| ========== | 619-50080 | 1 In Plastic Pipe | | Lin Foot | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 10,520.00 | 3.00 | 1.04 | 0.31 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 10,520.00 | 3.00 | 1.04 | 0.31 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 10,520.00 | 3.00 | 1.04 | 0.31 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 619-50100 | 1-1/4 In Plastic Pipe | | Lin Foot | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 500.00 | 2.50 | 1.27 | 0.62 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 500.00 | 2.50 | 1.27 | 0.62 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 500.00 | 2.50 | 1.27 | 0.62 |
| ========== | 619-50120 | 1-1/2 In Plastic Pipe | | Lin Foot | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 4,240.00 | 2.50 | 4.50 | 1.04 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 4,240.00 | 2.50 | 4.50 | 1.04 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4,240.00 | 2.50 | 4.50 | 1.04 |
| ========== | 619-50200 | 2-1/2 In Plastic Pipe | | Lin Foot | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 280.00 | 4.00 | 2.11 | 1.14 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 280.00 | 4.00 | 2.11 | 1.14 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 280.00 | 4.00 | 2.11 | 1.14 |
| ========== | 619-50240 | 3 In Plastic Pipe | | Lin Foot | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 700.00 | 6.50 | 3.19 | 1.97 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 700.00 | 6.50 | 3.19 | 1.97 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 700.00 | 6.50 | 3.19 | 1.97 |
| ========== | 619-50320 | 4 In Plastic Pipe | | Lin Foot | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1,622.00 | 18.00 | 28.82 | 25.40 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1,622.00 | 18.00 | 28.82 | 25.40 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 177.00 | 50.00 | 38.79 | 27.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 177.00 | 50.00 | 38.79 | 27.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,799.00 | 21.15 | 29.95 | 25.56 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 619-50480 | 6 In Plastic Pipe | | Lin Foot | | | |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 18.00 | 40.00 | 47.36 | 67.00 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 18.00 | 40.00 | 47.36 | 67.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 641.00 | 65.00 | 52.14 | 46.00 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 641.00 | 65.00 | 52.14 | 46.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 659.00 | 64.32 | 52.03 | 46.57 |
| ========== | 619-50640 | 8 In Plastic Pipe | | Lin Foot | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 130.00 | 80.00 | 129.73 | 104.68 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 130.00 | 80.00 | 129.73 | 104.68 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1,300.00 | 35.00 | 37.90 | 36.57 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 1,300.00 | 35.00 | 37.90 | 36.57 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 5,689.00 | 35.00 | 65.92 | 75.20 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 5,689.00 | 35.00 | 65.92 | 75.20 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 797.00 | 75.00 | 105.57 | 90.00 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 797.00 | 75.00 | 105.57 | 90.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 7,916.00 | 39.77 | 67.53 | 70.83 |
| ========== | 619-50800 | 10 In Plastic Pipe | | Lin Foot | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1,944.00 | 35.00 | 49.95 | 43.68 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 1,944.00 | 35.00 | 49.95 | 43.68 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 1,944.00 | 35.00 | 49.95 | 43.68 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 619-50960 | 12 In Plastic Pipe | | Lin Foot | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 3,086.00 | 85.00 | 69.81 | 61.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 3,086.00 | 85.00 | 69.81 | 61.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3,086.00 | 85.00 | 69.81 | 61.00 |
| ========== | 619-51280 | 16 In Plastic Pipe | | Lin Foot | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 353.00 | 110.00 | 134.42 | 111.81 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 353.00 | 110.00 | 134.42 | 111.81 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 353.00 | 110.00 | 134.42 | 111.81 |
| ========== | 619-71508 | 1 In Air and Vacuum Valve | | Each | | | |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 1.00 | 4000.00 | 4687.41 | 5040.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1.00 | 4000.00 | 4687.41 | 5040.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 4000.00 | 4687.41 | 5040.00 |
| ========== | 619-71516 | 2 In Air and Vacuum Valve | | Each | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1.00 | 7500.00 | 6465.71 | 5400.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 7500.00 | 6465.71 | 5400.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 7500.00 | 6465.71 | 5400.00 |
| ========== | 619-71548 | 6 In Air and Vacuum Valve | | Each | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1.00 | 8999.00 | 5375.28 | 5826.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1.00 | 8999.00 | 5375.28 | 5826.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 8999.00 | 5375.28 | 5826.00 |
| ========== | 619-71596 | 12 In Air and Vacuum Valve | | Each | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1.00 | 9999.00 | 6861.90 | 6430.44 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1.00 | 9999.00 | 6861.90 | 6430.44 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 9999.00 | 6861.90 | 6430.44 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 619-73050 | 6 In Blow Off and Vault | | Each | | | |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 1.00 | 12500.00 | 12499.18 | 13099.34 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 12500.00 | 12499.18 | 13099.34 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 12500.00 | 12499.18 | 13099.34 |
| ========== | 619-73051 | 6 In Air Val Accs Mnhle Assm | | Each | | | |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 2.00 | 10000.00 | 17711.52 | 20434.97 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 10000.00 | 17711.52 | 20434.97 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 10000.00 | 17711.52 | 20434.97 |
| ========== | 619-75000 | Cast Iron Valve Box | | Each | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 22.00 | 250.00 | 180.34 | 89.40 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 22.00 | 250.00 | 180.34 | 89.40 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 22.00 | 250.00 | 180.34 | 89.40 |
| ========== | 619-75032 | 4 In Gate Valve | | Each | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 11.00 | 800.00 | 610.48 | 519.11 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 11.00 | 800.00 | 610.48 | 519.11 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 11.00 | 800.00 | 610.48 | 519.11 |
| ========== | 619-75048 | 6 In Gate Valve | | Each | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 3.00 | 1180.00 | 1275.71 | 1300.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 1.00 | 1500.00 | 1566.55 | 1721.59 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 4.00 | 1260.00 | 1355.94 | 1405.40 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4.00 | 1260.00 | 1355.94 | 1405.40 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 619-75064 | 8 In Gate Valve | | Each | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 4.00 | 2000.00 | 1215.55 | 1026.03 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 4.00 | 2000.00 | 1215.55 | 1026.03 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 16.00 | 1300.00 | 1632.46 | 2000.00 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 16.00 | 1300.00 | 1632.46 | 2000.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 14.00 | 1700.00 | 1702.86 | 1750.00 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 14.00 | 1700.00 | 1702.86 | 1750.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 34.00 | 1547.06 | 1617.08 | 1782.47 |
| ========== | 619-75096 | 12 In Gate Valve | | Each | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 12.00 | 3100.00 | 2865.71 | 3000.00 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 12.00 | 3100.00 | 2865.71 | 3000.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 12.00 | 3100.00 | 2865.71 | 3000.00 |
| ========== | 619-76096 | 12 In Eccentric Plug Valve | | Each | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 7.00 | 5999.00 | 4541.40 | 3108.55 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 7.00 | 5999.00 | 4541.40 | 3108.55 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 7.00 | 5999.00 | 4541.40 | 3108.55 |
| ========== | 619-77210 | Restrained Plug (Spec) | | Each | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 5.00 | 2500.00 | 1243.71 | 1200.00 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 5.00 | 2500.00 | 1243.71 | 1200.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 5.00 | 2500.00 | 1243.71 | 1200.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 619-77300 | Corporation Stop | | Each | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 2.00 | 1750.00 | 513.60 | 387.05 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2.00 | 1750.00 | 513.60 | 387.05 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 8.00 | 1800.00 | 811.43 | 430.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 8.00 | 1800.00 | 811.43 | 430.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 10.00 | 1790.00 | 758.87 | 421.41 |
| ========== | 619-78048 | 6 In Fire Hydrant | | Each | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1.00 | 4000.00 | 4325.97 | 2956.17 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1.00 | 4000.00 | 4325.97 | 2956.17 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 6.00 | 4000.00 | 5455.17 | 6330.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 6.00 | 4000.00 | 5455.17 | 6330.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 7.00 | 4000.00 | 5266.97 | 5848.02 |
| ========== | 619-78049 | Inst 6 In Fire Hydrant | | Each | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 14.00 | 1500.00 | 2622.86 | 1900.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 14.00 | 1500.00 | 2622.86 | 1900.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 14.00 | 1500.00 | 2622.86 | 1900.00 |
| ========== | 620-00001 | Field Office (CL 1) | | Each | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 1.00 | 10000.00 | 10724.76 | 4565.00 |
| NH 0241-056 | | US 24 BUENA VISTA NORTH | 03/03/11 | 1.00 | 12000.00 | 10650.02 | 12000.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 2.00 | 11000.00 | 10683.99 | 8282.50 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 620-00001 | Field Office (CL 1) | | Each | | | |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 1.00 | 10000.00 | 15108.21 | 28000.00 |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 1.00 | 6000.00 | 11515.62 | 5630.00 |
| C0241-055 | | SH 24 MP 148-152 | 05/26/11 | 1.00 | 10000.00 | 7832.80 | 3000.00 |
| FSA 0502-064 | | US 50 EAST OF SARGENTS | 06/23/11 | 1.00 | 12000.00 | 8722.55 | 12413.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 4.00 | 9500.00 | 10966.53 | 13134.71 |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 1.00 | 15000.00 | 22782.13 | 33600.00 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 1.00 | 15000.00 | 21091.33 | 3399.00 |
| BR2706-036 | | I-270 BRIDGE DECK REHABILITAT | 08/11/11 | 1.00 | 5000.00 | 11230.00 | 13870.00 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 1.00 | 10000.00 | 9200.00 | 6400.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 4.00 | 11250.00 | 15794.34 | 13453.80 |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 1.00 | 15000.00 | 13588.70 | 12000.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 15000.00 | 13588.70 | 12000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 11.00 | 10909.09 | 12406.52 | 12518.47 |
| ========== | 620-00002 | Field Office (CL 2) | | Each | | | |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 1.00 | 5000.00 | 12430.70 | 6300.00 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 1.00 | 15000.00 | 26596.89 | 29500.00 |
| NH 2852-017 | | US 285 PONCHA PASS SOUTH RESU | 03/03/11 | 1.00 | 10000.00 | 11249.17 | 14000.00 |
| STA0504-061 | | US 50 M.P.369.9 -M.P.373.2 | 03/03/11 | 1.00 | 12000.00 | 12430.32 | 7951.58 |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 1.00 | 12000.00 | 13003.04 | 11000.00 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 1.00 | 20000.00 | 18965.78 | 15000.00 |
| NH 0402-079 | | US40 MP 165.0 - 179.0 GRAND C | 03/31/11 | 1.00 | 12000.00 | 12857.14 | 14000.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 7.00 | 12285.71 | 18677.43 | 19957.72 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 1.00 | 21000.00 | 24964.29 | 20000.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 620-00002 | Field Office (CL 2) | | Each | | | |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 1.00 | 10000.00 | 15583.33 | 16750.00 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 1.00 | 15000.00 | 13135.00 | 18110.00 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 1.00 | 50000.00 | 51755.89 | 21232.14 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 1.00 | 54000.00 | 41219.54 | 33300.00 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 1.00 | 13500.00 | 24984.67 | 33373.00 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 1.00 | 9000.00 | 16360.08 | 17000.00 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 1.00 | 15000.00 | 10000.00 | 11000.00 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 1.00 | 10000.00 | 21137.95 | 9563.00 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 1.00 | 28000.00 | 15666.67 | 15000.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 1.00 | 11000.00 | 23868.11 | 14400.00 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 1.00 | 20000.00 | 7535.35 | 9500.70 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 1.00 | 15000.00 | 30400.00 | 33300.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 1.00 | 36000.00 | 25145.77 | 8237.67 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 1.00 | 12000.00 | 12577.33 | 9500.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 15.00 | 21300.00 | 22233.44 | 16256.12 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 1.00 | 25000.00 | 18599.51 | 14597.57 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 1.00 | 20000.00 | 23880.14 | 24200.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 1.00 | 58000.00 | 52071.08 | 40000.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 1.00 | 40000.00 | 24834.63 | 40000.00 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 1.00 | 20000.00 | 9485.00 | 10000.00 |
| STR096A-040 | | SH 96 MP 193 TO MP 201 | 09/01/11 | 1.00 | 14000.00 | 13596.19 | 9788.58 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 1.00 | 22000.00 | 20612.99 | 25000.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 7.00 | 28428.57 | 21966.24 | 18808.87 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 1.00 | 30000.00 | 21225.05 | 15127.22 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 1.00 | 19000.00 | 19017.18 | 16192.65 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 1.00 | 50000.00 | 45118.28 | 27667.26 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1.00 | 50000.00 | 54456.11 | 71451.55 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 1.00 | 15000.00 | 14300.00 | 8600.00 |
| IM0703-368 | | GEORGETOWN HILL CHUTES 6,7,9, | 12/01/11 | 1.00 | 16728.00 | 20415.50 | 11600.00 |
| FBR0252-415 | | NB I-25 SOUTH OF FOUNTAIN, MP | 12/15/11 | 1.00 | 12000.00 | 13252.27 | 9036.35 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 1.00 | 20000.00 | 19373.25 | 27500.00 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 1.00 | 12000.00 | 10500.00 | 9000.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 9.00 | 24969.78 | 25588.94 | 18743.18 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 38.00 | 21821.79 | 22184.78 | 18034.08 |
| ========== | 620-00005 | Field Office (Spec) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 4.00 | 100000.00 | 128719.65 | 125000.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 620-00005 | Field Office (Spec) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 1.00 | 55000.00 | 102719.58 | 65957.20 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 5.00 | 91000.00 | 116484.32 | 95478.60 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 1.00 | 45000.00 | 40893.11 | 33500.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1.00 | 40000.00 | 62835.08 | 108926.34 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2.00 | 42500.00 | 52863.11 | 80808.78 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1.00 | 65000.00 | 86000.00 | 40000.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1.00 | 75000.00 | 90915.90 | 100000.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 70000.00 | 88048.29 | 70000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 9.00 | 75555.56 | 83552.56 | 81911.93 |
| ========== | 620-00011 | Field Lab (CL 1) | | Each | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 1.00 | 12000.00 | 7369.76 | 5090.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1.00 | 12000.00 | 7369.76 | 5090.00 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 1.00 | 10000.00 | 10766.07 | 18000.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1.00 | 10000.00 | 7088.36 | 10000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 11000.00 | 7594.53 | 8149.75 |
| ========== | 620-00012 | Field Lab (CL 2) | | Each | | | |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 1.00 | 5000.00 | 8349.13 | 3200.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 4.00 | 100000.00 | 44995.30 | 30000.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 620-00012 | Field Lab (CL 2) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 1.00 | 20000.00 | 12272.29 | 12000.00 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 1.00 | 15000.00 | 21595.65 | 18600.00 |
| NH 2852-017 | | US 285 PONCHA PASS SOUTH RESU | 03/03/11 | 1.00 | 10000.00 | 10250.00 | 14000.00 |
| NH 0241-056 | | US 24 BUENA VISTA NORTH | 03/03/11 | 1.00 | 15000.00 | 10158.33 | 12000.00 |
| STA0504-061 | | US 50 M.P.369.9 -M.P.373.2 | 03/03/11 | 1.00 | 12000.00 | 10435.77 | 7578.87 |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 1.00 | 15000.00 | 9644.38 | 9500.00 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 1.00 | 18000.00 | 18245.44 | 15000.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 1.00 | 55000.00 | 38411.37 | 23491.07 |
| NH 0402-079 | | US40 MP 165.0 - 179.0 GRAND C | 03/31/11 | 1.00 | 12000.00 | 12500.00 | 14000.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 14.00 | 41214.29 | 19925.10 | 16719.30 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 1.00 | 12000.00 | 12390.07 | 12000.33 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 1.00 | 21000.00 | 14734.69 | 15000.00 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 1.00 | 10000.00 | 17700.00 | 17100.00 |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 1.00 | 6000.00 | 9282.83 | 6271.00 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 1.00 | 50000.00 | 31255.84 | 16162.73 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 1.00 | 54000.00 | 27048.61 | 18000.00 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 1.00 | 13500.00 | 17665.28 | 14035.00 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 1.00 | 9000.00 | 11387.60 | 6000.00 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 1.00 | 13000.00 | 11500.00 | 14000.00 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 1.00 | 10000.00 | 17056.78 | 12344.57 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 1.00 | 20000.00 | 17666.67 | 17000.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 1.00 | 12000.00 | 21256.79 | 16000.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 1.00 | 15000.00 | 26858.71 | 16400.00 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 1.00 | 17000.00 | 13106.60 | 14313.20 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 1.00 | 45000.00 | 22431.85 | 17100.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 1.00 | 15000.00 | 31966.67 | 34400.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 1.00 | 36000.00 | 19054.67 | 8595.83 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 1.00 | 8000.00 | 11355.33 | 10500.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1.00 | 35000.00 | 28134.58 | 17294.94 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 19.00 | 21131.58 | 18971.39 | 15857.35 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 1.00 | 17000.00 | 13414.97 | 14811.84 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 1.00 | 15000.00 | 17408.24 | 23200.00 |
| NH2872-018 | | US 287 RUSH CREEK NORTH | 07/21/11 | 1.00 | 15000.00 | 11988.00 | 12000.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 1.00 | 58000.00 | 30586.74 | 40000.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 1.00 | 40000.00 | 22289.75 | 30000.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 620-00012 | Field Lab (CL 2) | | Each | | | |
| BR2706-036 | | I-270 BRIDGE DECK REHABILITAT | 08/11/11 | 1.00 | 5000.00 | 10400.00 | 12800.00 |
| STR096A-040 | | SH 96 MP 193 TO MP 201 | 09/01/11 | 1.00 | 15000.00 | 11885.98 | 8157.95 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 1.00 | 22000.00 | 20947.87 | 25000.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 8.00 | 23375.00 | 18012.97 | 18034.77 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 1.00 | 16000.00 | 15099.78 | 11152.42 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 1.00 | 15000.00 | 15214.42 | 11068.81 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1.00 | 20000.00 | 35857.14 | 32000.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1.00 | 75000.00 | 39832.63 | 40000.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 1.00 | 30000.00 | 27391.78 | 18873.23 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1.00 | 30000.00 | 26647.69 | 7692.01 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 1.00 | 15000.00 | 17800.00 | 15600.00 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 1.00 | 20000.00 | 13215.33 | 20000.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 1.00 | 10000.00 | 9662.04 | 9688.00 |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 1.00 | 20000.00 | 15093.09 | 11000.00 |
| FBR0252-415 | | NB I-25 SOUTH OF FOUNTAIN, MP | 12/15/11 | 1.00 | 12000.00 | 11458.25 | 10446.25 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 1.00 | 18000.00 | 16054.53 | 14800.00 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 1.00 | 14000.00 | 11066.67 | 10000.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 13.00 | 22692.31 | 20047.84 | 14888.05 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 54.00 | 27046.30 | 19279.07 | 16149.80 |
| ========== | 620-00015 | Field Lab (State Furn) | | Each | | | |
| STR096A-040 | | SH 96 MP 193 TO MP 201 | 09/01/11 | 1.00 | 1200.00 | 4554.78 | 2664.35 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1.00 | 1200.00 | 4554.78 | 2664.35 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 1200.00 | 4554.78 | 2664.35 |
| ========== | 620-00020 | Sanitary Facility | | Each | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 1.00 | 800.00 | 944.00 | 630.00 |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 1.00 | 500.00 | 751.38 | 600.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 4.00 | 10000.00 | 5345.54 | 3000.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 1.00 | 800.00 | 743.07 | 300.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 620-00020 | Sanitary Facility | | Each | | | |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 1.00 | 1200.00 | 1873.24 | 1700.00 |
| NH 2852-017 | | US 285 PONCHA PASS SOUTH RESU | 03/03/11 | 1.00 | 1000.00 | 1541.67 | 2000.00 |
| NH 0241-056 | | US 24 BUENA VISTA NORTH | 03/03/11 | 1.00 | 1500.00 | 1820.83 | 2000.00 |
| STA0504-061 | | US 50 M.P.369.9 -M.P.373.2 | 03/03/11 | 1.00 | 1000.00 | 2135.25 | 2236.24 |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 1.00 | 1500.00 | 1588.98 | 1000.00 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 1.00 | 2500.00 | 2429.76 | 2000.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 2.00 | 5500.00 | 2741.29 | 2860.50 |
| NH 0402-079 | | US40 MP 165.0 - 179.0 GRAND C | 03/31/11 | 1.00 | 1000.00 | 1725.00 | 2000.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 16.00 | 3925.00 | 2070.01 | 2128.04 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 1.00 | 1000.00 | 2025.01 | 2500.07 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 1.00 | 750.00 | 904.13 | 900.00 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 1.00 | 2100.00 | 3406.82 | 4000.00 |
| STA0343-032 | | US 34 EAST OF AKRON | 04/07/11 | 1.00 | 800.00 | 300.00 | 250.00 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 1.00 | 1000.00 | 2316.67 | 950.00 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 1.00 | 1000.00 | 1112.67 | 1016.00 |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 1.00 | 600.00 | 1060.76 | 505.00 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 1.00 | 1500.00 | 339.25 | 147.00 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 2.00 | 5000.00 | 1805.79 | 1689.80 |
| SHE074A-001 | | SH 74 - EVERGREEN - JEFFERSON | 04/28/11 | 1.00 | 1000.00 | 421.67 | 115.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 3.00 | 5400.00 | 1817.86 | 1100.00 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 1.00 | 1350.00 | 1421.49 | 1398.00 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 1.00 | 900.00 | 1438.79 | 861.00 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 1.00 | 1800.00 | 3050.00 | 1600.00 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 1.00 | 1000.00 | 1637.24 | 485.15 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 1.00 | 1500.00 | 3500.00 | 2000.00 |
| C0241-055 | | SH 24 MP 148-152 | 05/26/11 | 1.00 | 2000.00 | 577.27 | 325.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 1.00 | 2500.00 | 3814.53 | 4600.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 1.00 | 2000.00 | 1375.15 | 1200.00 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 1.00 | 1200.00 | 439.50 | 594.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 2.00 | 4500.00 | 1661.39 | 1200.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 1.00 | 1500.00 | 4901.30 | 2700.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 1.00 | 3600.00 | 3169.75 | 2046.63 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 1.00 | 1500.00 | 407.00 | 400.00 |
| ITS0703-370 | | EAST OF EJMT ON I-70 EB LANES | 06/16/11 | 1.00 | 1000.00 | 1009.00 | 1365.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 1.00 | 1500.00 | 768.33 | 500.00 |
| FSA 0502-064 | | US 50 EAST OF SARGENTS | 06/23/11 | 1.00 | 300.00 | 849.80 | 575.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 2.00 | 800.00 | 1446.31 | 1501.93 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 1.00 | 2100.00 | 832.50 | 565.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 34.00 | 2126.47 | 1644.25 | 1608.73 |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 1.00 | 1500.00 | 2040.05 | 530.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 620-00020 | Sanitary Facility | | Each | | | |
| C006A-051 | | US 6 (LOVELAND PASS), CLEAR C | 07/14/11 | 1.00 | 1000.00 | 783.50 | 244.00 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 2.00 | 500.00 | 333.71 | 300.00 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 2.00 | 1500.00 | 803.65 | 539.76 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 1.00 | 1500.00 | 2062.50 | 1825.00 |
| NH2872-018 | | US 287 RUSH CREEK NORTH | 07/21/11 | 1.00 | 1600.00 | 785.50 | 850.00 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 1.00 | 600.00 | 473.00 | 234.00 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 2.00 | 2000.00 | 466.25 | 635.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 1.00 | 5800.00 | 3251.42 | 1625.00 |
| NH0403-053 | | US 40 RETAINING WALL REPAIR | 07/28/11 | 1.00 | 2000.00 | 592.67 | 543.01 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 4.00 | 1500.00 | 1458.78 | 1900.00 |
| BR2706-036 | | I-270 BRIDGE DECK REHABILITAT | 08/11/11 | 1.00 | 500.00 | 570.75 | 283.00 |
| NH5502-070 | | US 550 4 MILES SOUTH OF OURAY | 08/18/11 | 1.00 | 1500.00 | 1427.93 | 1200.00 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 1.00 | 1500.00 | 3025.00 | 3000.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 2.00 | 1000.00 | 308.40 | 300.00 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 1.00 | 1500.00 | 846.30 | 500.00 |
| STR096A-040 | | SH 96 MP 193 TO MP 201 | 09/01/11 | 1.00 | 1800.00 | 3533.03 | 3599.10 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 1.00 | 2000.00 | 2367.96 | 1000.00 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 1.00 | 1000.00 | 956.67 | 535.00 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 1.00 | 3000.00 | 778.60 | 300.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 27.00 | 1585.19 | 1341.51 | 990.06 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 2.00 | 1500.00 | 1415.56 | 2648.69 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 1.00 | 1500.00 | 2505.34 | 3284.51 |
| NH0501-060 | | US50 MP 74.0 TO 81, 94.2 TO 1 | 10/20/11 | 1.00 | 1000.00 | 1009.56 | 100.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 2.00 | 2000.00 | 3280.00 | 4500.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 2.00 | 7500.00 | 2607.27 | 2600.00 |
| SHE0402-081 | | US 40 - MP 113 TO 120 ROUTT C | 10/27/11 | 1.00 | 2500.00 | 930.67 | 883.99 |
| SHE025A-013 | | I 25 BETWEEN MP 122 AND MP 12 | 11/03/11 | 1.00 | 1200.00 | 1927.13 | 1500.00 |
| STA0343-033 | | SH 34 ECKLEY | 11/10/11 | 1.00 | 1000.00 | 654.75 | 500.00 |
| R600-395 | | REGION 6; VARIOUS LOCATIONS | 11/10/11 | 1.00 | 900.00 | 1335.00 | 1675.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 2.00 | 3000.00 | 2034.21 | 2068.15 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1.00 | 3000.00 | 3288.50 | 131.39 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 2.00 | 1000.00 | 1750.00 | 1500.00 |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 2.00 | 1000.00 | 816.25 | 990.00 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 1.00 | 2000.00 | 913.33 | 1100.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 1.00 | 1200.00 | 899.50 | 1344.00 |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 1.00 | 1500.00 | 750.00 | 1000.00 |
| MC0504-065 | | US50B FROM MP 318 TO MP 359 | 12/01/11 | 1.00 | 1000.00 | 1093.33 | 2000.00 |
| IM0703-368 | | GEORGETOWN HILL CHUTES 6,7,9, | 12/01/11 | 1.00 | 1422.00 | 1832.29 | 1500.00 |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 4.00 | 2000.00 | 1246.47 | 1325.00 |
| FBR0252-415 | | NB I-25 SOUTH OF FOUNTAIN, MP | 12/15/11 | 2.00 | 12000.00 | 1068.89 | 1122.57 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 2.00 | 2500.00 | 1395.51 | 730.00 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 1.00 | 2000.00 | 2000.00 | 1000.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 33.00 | 2703.70 | 1650.21 | 1522.67 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 110.00 | 2428.38 | 1654.55 | 1528.12 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 621-00202 | Haul Road (Spec) | | Sq Yard | | | |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 8,488.00 | 10.00 | 12.14 | 12.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 8,488.00 | 10.00 | 12.14 | 12.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 8,488.00 | 10.00 | 12.14 | 12.00 |
| ========== | 621-00425 | Detour | | LUMP SUM | | | |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 1.00 | 150000.00 | 211144.10 | 207060.62 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 150000.00 | 211144.10 | 207060.62 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 150000.00 | 221171.36 | 241030.31 |
| ========== | 621-00430 | Detour | | Sq Yard | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 86,324.00 | 5.00 | 30.35 | 30.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 86,324.00 | 5.00 | 30.35 | 30.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 86,324.00 | 5.00 | 30.35 | 30.00 |
| ========== | 621-00450 | Detour Pvmt | | Sq Yard | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 500.00 | 40.00 | 50.01 | 43.78 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 500.00 | 40.00 | 50.01 | 43.78 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 848.00 | 40.00 | 46.33 | 45.40 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 2,144.00 | 35.00 | 34.49 | 28.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 10,548.00 | 20.00 | 45.75 | 40.17 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 13,540.00 | 23.63 | 42.23 | 37.36 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 3,360.00 | 38.00 | 31.29 | 28.50 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 3,360.00 | 38.00 | 33.77 | 32.13 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 621-00450 | Detour Pvmt | | Sq Yard | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 10,000.00 | 45.00 | 27.68 | 27.25 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 918.00 | 50.00 | 65.10 | 65.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1,900.00 | 30.00 | 37.92 | 32.35 |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 1,461.00 | 55.00 | 31.00 | 32.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 14,279.00 | 44.35 | 31.31 | 30.84 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 31,679.00 | 34.75 | 37.02 | 34.16 |
| ========== | 621-00500 | Temp Brdg | | LUMP SUM | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 1.00 | 143750.00 | 211124.33 | 125000.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 1.00 | 143750.00 | 211124.33 | 125000.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1.00 | 200000.00 | 217282.22 | 234510.86 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 200000.00 | 217282.22 | 234510.86 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 155000.00 | 214022.16 | 179755.43 |
| ========== | 622-00010 | Bicycle Rack | | Each | | | |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 28.00 | 1000.00 | 674.70 | 589.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 28.00 | 1000.00 | 674.70 | 589.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 28.00 | 1000.00 | 674.70 | 589.00 |
| ========== | 622-00100 | Shade Shelter | | Each | | | |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 1.00 | 22500.00 | 32635.00 | 28000.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 1.00 | 22500.00 | 32635.00 | 28000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 22500.00 | 32635.00 | 28000.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| | 622-00270 | Bollard | | Each | | | |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 2.00 | 200.00 | 481.14 | 500.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 2.00 | 200.00 | 481.14 | 500.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 200.00 | 481.14 | 500.00 |
| | 622-01025 | Pond Lining | | Sq Yard | | | |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 7,944.00 | 3.70 | 4.47 | 4.10 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 7,944.00 | 3.70 | 4.47 | 4.10 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 7,944.00 | 3.70 | 4.47 | 4.10 |
| | 623-00162 | Drip Emit Tubing | | Lin Foot | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 65,900.00 | 2.00 | 0.47 | 0.43 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 65,900.00 | 2.00 | 0.47 | 0.43 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 65,900.00 | 2.00 | 0.47 | 0.43 |
| | 623-00168 | 1 In Emit Valve Assembly | | Each | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 27.00 | 150.00 | 231.93 | 184.55 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 27.00 | 150.00 | 231.93 | 184.55 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 27.00 | 150.00 | 231.93 | 184.55 |
| | 623-00186 | 3/4 In Flush Unit | | Each | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 163.00 | 25.00 | 44.78 | 27.48 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 163.00 | 25.00 | 44.78 | 27.48 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 163.00 | 25.00 | 44.78 | 27.48 |
| | 623-01708 | 1 Inch Backflow Preventer | | Each | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 2.00 | 2600.00 | 1638.51 | 1787.47 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 2.00 | 2600.00 | 1638.51 | 1787.47 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 2600.00 | 1638.51 | 1787.47 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| | 623-03004 | 3/4 In Drip Zone Crtl Valve | | Each | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 75.00 | 200.00 | 74.93 | 64.28 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 75.00 | 200.00 | 74.93 | 64.28 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 75.00 | 200.00 | 74.93 | 64.28 |
| | 623-03108 | 1 In Auto Ctrl Valve | | Each | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 2.00 | 250.00 | 207.30 | 103.69 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 2.00 | 250.00 | 207.30 | 103.69 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 250.00 | 207.30 | 103.69 |
| | 623-04000 | Ctrl Wire 24 Volt | | Lin Foot | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 18,500.00 | 0.15 | 0.22 | 0.21 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 18,500.00 | 0.15 | 0.22 | 0.21 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 18,500.00 | 0.15 | 0.22 | 0.21 |
| | 623-04008 | 1 In Quick-Coupler | | Each | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 15.00 | 275.00 | 166.28 | 155.52 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 15.00 | 275.00 | 166.28 | 155.52 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 15.00 | 275.00 | 166.28 | 155.52 |
| | 623-05012 | 1-1/2 In Gate Valve | | Each | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 8.00 | 100.00 | 105.94 | 68.43 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 8.00 | 100.00 | 105.94 | 68.43 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 8.00 | 100.00 | 105.94 | 68.43 |
| | 623-06900 | Valve Box | | Each | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 27.00 | 250.00 | 69.01 | 82.94 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 27.00 | 250.00 | 69.01 | 82.94 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 27.00 | 250.00 | 69.01 | 82.94 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 623-08118 | 18 Station Auto Ctrler | | Each | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 2.00 | 5500.00 | 1300.72 | 2521.53 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 2.00 | 5500.00 | 1300.72 | 2521.53 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 5500.00 | 1300.72 | 2521.53 |
| ========== | 623-09900 | Sprinkler System | | LUMP SUM | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1.00 | 5000.00 | 30371.43 | 36000.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1.00 | 40000.00 | 30672.01 | 26875.00 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 2.00 | 22500.00 | 30496.67 | 31437.50 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 22500.00 | 30496.67 | 31437.50 |
| ========== | 624-20012 | 12 In Drainage Pipe (CL 0) | | Lin Foot | | | |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 112.00 | 40.00 | 28.63 | 30.67 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 112.00 | 40.00 | 28.63 | 30.67 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 112.00 | 40.00 | 37.83 | 40.13 |
| ========== | 624-20013 | 12 In Drainage Pipe (CL 0) (CIP) | | Lin Foot | | | |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 4.00 | 50.00 | 175.50 | 79.00 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 4.00 | 50.00 | 175.50 | 79.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4.00 | 50.00 | 175.50 | 79.00 |
| ========== | 624-20018 | 18 In Drainage Pipe (CL 0) | | Lin Foot | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 103.00 | 60.00 | 50.76 | 45.71 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 103.00 | 60.00 | 62.10 | 56.64 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 210.00 | 60.00 | 62.94 | 51.00 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 210.00 | 60.00 | 62.94 | 51.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 624-20018 | 18 In Drainage Pipe (CL 0) | | Lin Foot | | | |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 928.00 | 45.00 | 34.09 | 29.63 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 928.00 | 45.00 | 34.09 | 29.63 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,241.00 | 48.78 | 51.45 | 44.77 |
| ========== | 624-20019 | 18 In Drainage Pipe (CL 0) (CIP) | | Lin Foot | | | |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 30.00 | 60.00 | 76.00 | 50.00 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 30.00 | 60.00 | 76.00 | 50.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 30.00 | 60.00 | 76.00 | 50.00 |
| ========== | 624-20024 | 24 In Drainage Pipe (CL 0) | | Lin Foot | | | |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 708.00 | 70.00 | 73.90 | 67.00 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 708.00 | 70.00 | 73.90 | 67.00 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 941.00 | 50.00 | 44.37 | 39.02 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 941.00 | 50.00 | 44.37 | 39.02 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,649.00 | 58.59 | 67.62 | 64.10 |
| ========== | 624-20025 | 24 In Drainage Pipe (CL 0) (CIP) | | Lin Foot | | | |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 340.00 | 40.00 | 80.00 | 49.00 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 340.00 | 40.00 | 80.00 | 49.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 340.00 | 40.00 | 80.00 | 49.00 |
| ========== | 624-20036 | 36 In Drainage Pipe (CL 0) | | Lin Foot | | | |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 194.00 | 100.00 | 100.98 | 81.00 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 194.00 | 100.00 | 100.98 | 81.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 194.00 | 100.00 | 102.63 | 98.26 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 624-20048 | 48 In Drainage Pipe (CL 0) | | Lin Foot | | | |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 107.00 | 120.00 | 133.33 | 109.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 107.00 | 120.00 | 133.33 | 109.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 107.00 | 120.00 | 124.74 | 100.02 |
| ========== | 624-20072 | 72 In Drainage Pipe (CL 0) | | Lin Foot | | | |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 122.00 | 200.00 | 214.73 | 139.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 122.00 | 200.00 | 214.73 | 139.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 122.00 | 200.00 | 214.73 | 139.00 |
| ========== | 624-20108 | 108 In Drainage Pipe (CL 0) | | Lin Foot | | | |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 146.00 | 350.00 | 392.52 | 315.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 146.00 | 350.00 | 392.52 | 315.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 146.00 | 350.00 | 392.52 | 315.00 |
| ========== | 624-20300 | Detour Drainage Pipe (CL 0) | | Lin Foot | | | |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1,000.00 | 48.00 | 40.07 | 43.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1,000.00 | 48.00 | 40.07 | 43.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,000.00 | 48.00 | 40.07 | 43.00 |
| ========== | 624-20301 | Detour Drainage Pipe (CL 0) | | LUMP SUM | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 1.00 | 50000.00 | 80429.91 | 35000.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1.00 | 50000.00 | 80429.91 | 35000.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 624-20301 | Detour Drainage Pipe (CL 0) | | LUMP SUM | ========== | ========== | ========== |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 1.00 | 30000.00 | 27248.45 | 15967.48 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 30000.00 | 27248.45 | 15967.48 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 46000.00 | 57582.71 | 25322.49 |
| ========== | 624-22018 | 18 In Drainage Pipe (CL 2) | | Lin Foot | ========== | ========== | ========== |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 158.00 | 60.00 | 54.51 | 55.40 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 158.00 | 60.00 | 54.51 | 55.40 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 158.00 | 60.00 | 54.51 | 55.40 |
| ========== | 624-22024 | 24 In Drainage Pipe (CL 2) | | Lin Foot | ========== | ========== | ========== |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 70.00 | 100.00 | 72.61 | 73.10 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 70.00 | 100.00 | 72.61 | 73.10 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 70.00 | 100.00 | 72.61 | 73.10 |
| ========== | 624-22036 | 36 In Drainage Pipe (CL 2) | | Lin Foot | ========== | ========== | ========== |
| C0091-038 | | SH 9 MM 81.9 BLUE RIVER EMERG | 08/24/11 | 80.00 | 150.00 | 163.49 | 164.96 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 80.00 | 150.00 | 163.49 | 164.96 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 80.00 | 150.00 | 163.49 | 164.96 |
| ========== | 624-23024 | 24 In Drainage Pipe (CL 3) | | Lin Foot | ========== | ========== | ========== |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 238.00 | 90.00 | 63.65 | 67.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 238.00 | 90.00 | 67.38 | 72.25 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 238.00 | 90.00 | 67.38 | 72.25 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 624-24018 | 18 In Drainage Pipe (CL 4) | | Lin Foot | | | |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 531.00 | 94.00 | 96.00 | 69.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 31.00 | 70.00 | 63.18 | 51.81 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 562.00 | 92.68 | 80.24 | 63.30 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 562.00 | 92.68 | 80.24 | 63.30 |
| ========== | 624-24024 | 24 In Drainage Pipe (CL 4) | | Lin Foot | | | |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 260.00 | 98.00 | 129.00 | 96.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 260.00 | 98.00 | 101.59 | 97.69 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 260.00 | 98.00 | 101.59 | 97.69 |
| ========== | 624-24030 | 30 In Drainage Pipe (CL 4) | | Lin Foot | | | |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 338.00 | 102.00 | 162.67 | 146.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 338.00 | 102.00 | 162.67 | 146.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 338.00 | 102.00 | 162.67 | 146.00 |
| ========== | 624-24036 | 36 In Drainage Pipe (CL 4) | | Lin Foot | | | |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 749.00 | 105.00 | 177.00 | 165.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 749.00 | 105.00 | 177.00 | 165.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 749.00 | 105.00 | 177.00 | 165.00 |
| ========== | 624-24042 | 42 In Drainage Pipe (CL 4) | | Lin Foot | | | |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 134.00 | 110.00 | 278.20 | 193.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 134.00 | 110.00 | 278.20 | 193.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 134.00 | 110.00 | 278.20 | 193.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 624-26036 | 36 In Drainage Pipe (CL 6) | | Lin Foot | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 152.00 | 300.00 | 116.46 | 128.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 152.00 | 300.00 | 116.46 | 128.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 152.00 | 300.00 | 116.46 | 128.00 |
| ========== | 624-27018 | 18 In Drainage Pipe (CL 7) | | Lin Foot | | | |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 1,321.00 | 40.00 | 43.45 | 48.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1,321.00 | 40.00 | 43.45 | 48.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 149.00 | 60.00 | 57.21 | 51.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 149.00 | 60.00 | 57.21 | 51.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,470.00 | 42.03 | 44.85 | 48.30 |
| ========== | 624-27024 | 24 In Drainage Pipe (CL 7) | | Lin Foot | | | |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 45.00 | 80.00 | 76.73 | 83.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 45.00 | 80.00 | 76.73 | 83.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 45.00 | 80.00 | 76.73 | 83.00 |
| ========== | 624-27025 | 24 In Drainage Pipe (CL 7) (CIP) | | Lin Foot | | | |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 220.00 | 125.00 | 151.67 | 145.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 220.00 | 125.00 | 151.67 | 145.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 220.00 | 125.00 | 151.67 | 145.00 |
| ========== | 624-27036 | 36 In Drainage Pipe (CL 7) | | Lin Foot | | | |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 100.00 | 175.00 | 132.35 | 110.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 100.00 | 175.00 | 132.35 | 110.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 100.00 | 175.00 | 132.35 | 110.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 625-00000 | Const Surveying | | LUMP SUM | ========== | ========== | ========== |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 1.00 | 10000.00 | 12672.00 | 32760.00 |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 1.00 | 3000.00 | 2856.25 | 3000.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 1.00 | 270000.00 | 244092.53 | 250000.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 1.00 | 40000.00 | 6363.00 | 7200.00 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 1.00 | 35000.00 | 30230.16 | 20700.00 |
| STA0504-061 | | US 50 M.P.369.9 -M.P.373.2 | 03/03/11 | 1.00 | 10400.00 | 6310.70 | 4653.50 |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 1.00 | 15000.00 | 12905.92 | 7000.00 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 1.00 | 45000.00 | 12428.51 | 15000.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 1.00 | 180000.00 | 119144.91 | 34676.29 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 9.00 | 118200.00 | 50571.41 | 33454.21 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 1.00 | 10000.00 | 4303.62 | 3500.00 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 1.00 | 35000.00 | 35773.78 | 10000.00 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 1.00 | 5000.00 | 3102.53 | 3388.50 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 1.00 | 125000.00 | 38173.25 | 30099.65 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 1.00 | 80000.00 | 61107.78 | 49200.00 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 1.00 | 40000.00 | 36500.00 | 35000.00 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 1.00 | 7500.00 | 3612.11 | 3342.19 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 1.00 | 10000.00 | 6061.67 | 12000.00 |
| C0241-055 | | SH 24 MP 148-152 | 05/26/11 | 1.00 | 7000.00 | 2509.07 | 2400.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 1.00 | 70000.00 | 67960.65 | 73000.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 1.00 | 30000.00 | 17430.54 | 16000.00 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 1.00 | 20000.00 | 3975.31 | 4535.61 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 1.00 | 110000.00 | 80563.58 | 160000.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 1.00 | 60000.00 | 50533.33 | 42000.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 1.00 | 80000.00 | 70656.31 | 80227.72 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 1.00 | 25000.00 | 28061.67 | 19505.00 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 1.00 | 5000.00 | 2356.50 | 2400.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 1.00 | 10000.00 | 13582.17 | 9000.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1.00 | 100000.00 | 103867.55 | 102145.74 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 19.00 | 43657.89 | 28684.75 | 28817.57 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 1.00 | 4000.00 | 3274.36 | 4000.00 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 1.00 | 10000.00 | 5316.65 | 5699.77 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 1.00 | 3000.00 | 3713.33 | 5210.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 625-00000 | Const Surveying | | LUMP SUM | | | |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 1.00 | 3500.00 | 3579.20 | 4465.00 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 1.00 | 4000.00 | 3772.50 | 3600.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 1.00 | 125000.00 | 29534.54 | 28300.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 1.00 | 45000.00 | 54449.65 | 54000.00 |
| NH5502-070 | | US 550 4 MILES SOUTH OF OURAY | 08/18/11 | 1.00 | 8000.00 | 13048.52 | 15000.00 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 1.00 | 25000.00 | 19710.83 | 18000.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 1.00 | 10000.00 | 4649.00 | 3000.00 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 1.00 | 10000.00 | 9491.08 | 13000.00 |
| STR096A-040 | | SH 96 MP 193 TO MP 201 | 09/01/11 | 1.00 | 15000.00 | 12269.27 | 6857.80 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 1.00 | 40000.00 | 59506.17 | 50000.00 |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 1.00 | 5000.00 | 2850.00 | 2950.00 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 1.00 | 10000.00 | 10843.34 | 10000.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 15.00 | 21166.67 | 17654.58 | 14155.40 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 1.00 | 20000.00 | 14450.57 | 10718.37 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 1.00 | 40000.00 | 21640.74 | 16888.76 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1.00 | 150000.00 | 91782.60 | 87000.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1.00 | 100000.00 | 60876.82 | 65000.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 1.00 | 80000.00 | 33357.79 | 38478.71 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1.00 | 100000.00 | 43580.19 | 38632.18 |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 1.00 | 10000.00 | 11185.50 | 14742.00 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 1.00 | 25000.00 | 16922.00 | 16000.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 1.00 | 6000.00 | 7307.55 | 4500.00 |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 1.00 | 8000.00 | 11000.00 | 10000.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 1.00 | 90000.00 | 57274.23 | 50900.00 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 1.00 | 20000.00 | 5233.33 | 3500.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 12.00 | 54083.33 | 37334.56 | 29696.67 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 55.00 | 55420.69 | 31793.94 | 25569.90 |
| ========== | 625-00001 | Const Surveying (Hour) | | Hour | | | |
| NH 0402-079 | | US40 MP 165.0 - 179.0 GRAND C | 03/31/11 | 10.00 | 100.00 | 142.86 | 150.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 10.00 | 100.00 | 148.28 | 142.86 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 100.00 | 125.00 | 108.87 | 100.33 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 168.00 | 140.00 | 121.67 | 130.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 625-00001 | Const Surveying (Hour) | | Hour | | | |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 100.00 | 100.00 | 106.09 | 100.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 100.00 | 100.00 | 110.67 | 100.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 144.00 | 120.00 | 128.17 | 135.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 612.00 | 119.77 | 116.06 | 116.81 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 40.00 | 125.00 | 105.99 | 105.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 20.00 | 200.00 | 109.12 | 110.00 |
| C0091-038 | | SH 9 MM 81.9 BLUE RIVER EMERG | 08/24/11 | 40.00 | 100.00 | 149.90 | 82.00 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 20.00 | 125.00 | 138.33 | 135.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 120.00 | 129.17 | 137.00 | 157.04 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 100.00 | 100.00 | 101.52 | 84.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 100.00 | 100.00 | 103.23 | 95.58 |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 20.00 | 150.00 | 233.59 | 125.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 40.00 | 125.00 | 150.05 | 140.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 260.00 | 107.69 | 119.73 | 100.22 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,002.00 | 117.56 | 121.03 | 121.97 |
| ========== | 626-00000 | Mobilization | | LUMP SUM | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 1.00 | 50000.00 | 82291.47 | 70000.00 |
| C0704-225 | | I-70 EAST OF BENNETT | 01/06/11 | 1.00 | 20000.00 | 16115.25 | 15201.00 |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 1.00 | 22000.00 | 54206.56 | 49000.00 |
| ITS4701-121 | | C470 (SANTA FE TO I-25) AND R | 01/20/11 | 1.00 | 20000.00 | 63469.00 | 11876.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 1.00 | 3000000.00 | 2626750.37 | 2000000.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 1.00 | 90000.00 | 81201.72 | 60000.00 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 1.00 | 450000.00 | 458509.78 | 509258.10 |
| C0703-363 | | CLEAR CREEK AND JEFFERSON COU | 02/17/11 | 1.00 | 20000.00 | 35746.67 | 15000.00 |
| NH 2852-017 | | US 285 PONCHA PASS SOUTH RESU | 03/03/11 | 1.00 | 100000.00 | 162983.33 | 132000.00 |
| NH 0241-056 | | US 24 BUENA VISTA NORTH | 03/03/11 | 1.00 | 150000.00 | 165243.67 | 110000.00 |
| STA0504-061 | | US 50 M.P.369.9 -M.P.373.2 | 03/03/11 | 1.00 | 100000.00 | 130258.76 | 41393.81 |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 1.00 | 180000.00 | 146335.90 | 60008.82 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 1.00 | 1100000.00 | 898210.79 | 505000.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 626-00000 | Mobilization | | LUMP SUM | ========== | ========== | ========== |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 1.00 | 1500000.00 | 1190138.40 | 1037000.00 |
| NH 0402-079 | | US40 MP 165.0 - 179.0 GRAND C | 03/31/11 | 1.00 | 250000.00 | 256831.37 | 271000.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 15.00 | 891777.78 | 442101.52 | 266330.72 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 1.00 | 320000.00 | 233390.80 | 119000.00 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 1.00 | 100000.00 | 79729.07 | 90000.00 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 1.00 | 250000.00 | 327181.72 | 379300.26 |
| STA0343-032 | | US 34 EAST OF AKRON | 04/07/11 | 1.00 | 65000.00 | 84607.77 | 70881.73 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 1.00 | 260000.00 | 404550.00 | 421650.00 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 1.00 | 220000.00 | 160978.55 | 75000.00 |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 1.00 | 36000.00 | 48456.56 | 9500.00 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 1.00 | 25000.00 | 41851.11 | 21710.00 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 1.00 | 460000.00 | 568096.60 | 620000.00 |
| SHE074A-001 | | SH 74 - EVERGREEN - JEFFERSON | 04/28/11 | 1.00 | 12000.00 | 12795.00 | 7985.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 1.00 | 720000.00 | 626393.46 | 491642.38 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 1.00 | 80000.00 | 451143.47 | 205740.00 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 1.00 | 25000.00 | 54828.74 | 20411.00 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 1.00 | 120000.00 | 134400.30 | 97600.00 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 1.00 | 60000.00 | 67278.91 | 38165.30 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 1.00 | 175000.00 | 235000.00 | 145000.00 |
| C0241-055 | | SH 24 MP 148-152 | 05/26/11 | 1.00 | 25000.00 | 30496.09 | 25000.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 1.00 | 370000.00 | 624176.54 | 582000.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 1.00 | 240000.00 | 332980.35 | 388300.00 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 1.00 | 50000.00 | 70462.31 | 68235.52 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 1.00 | 600000.00 | 661012.31 | 847792.57 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 1.00 | 350000.00 | 415666.67 | 264000.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 1.00 | 450000.00 | 429992.63 | 205000.00 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 1.00 | 90702.25 | 102598.33 | 109950.00 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 1.00 | 15000.00 | 25986.06 | 23000.00 |
| ITS0703-370 | | EAST OF EJMT ON I-70 EB LANES | 06/16/11 | 1.00 | 36000.00 | 57133.33 | 60000.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 1.00 | 50000.00 | 132500.00 | 82000.00 |
| FSA 0502-064 | | US 50 EAST OF SARGENTS | 06/23/11 | 1.00 | 35000.00 | 41828.51 | 84495.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1.00 | 1500000.40 | 1199000.20 | 1475000.00 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 1.00 | 50000.00 | 28978.00 | 15656.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 30.00 | 226323.42 | 262781.76 | 207122.81 |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 1.00 | 150000.00 | 183353.78 | 198670.51 |
| C006A-051 | | US 6 (LOVELAND PASS), CLEAR C | 07/14/11 | 1.00 | 18000.00 | 42000.00 | 34000.00 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 1.00 | 30000.00 | 32785.43 | 44998.00 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 1.00 | 100000.80 | 123295.52 | 71165.87 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 626-00000 | Mobilization | | LUMP SUM | ========== | ========== | ========== |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 1.00 | 150000.75 | 80933.53 | 113954.80 |
| NH2872-018 | | US 287 RUSH CREEK NORTH | 07/21/11 | 1.00 | 100000.00 | 102478.50 | 65000.00 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 1.00 | 30000.00 | 29639.58 | 39790.00 |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 1.00 | 15000.00 | 12072.20 | 8558.00 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 1.00 | 40000.00 | 46001.41 | 83984.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 1.00 | 360000.00 | 423835.98 | 240000.00 |
| NH0403-053 | | US 40 RETAINING WALL REPAIR | 07/28/11 | 1.00 | 54000.00 | 39889.14 | 36667.43 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 1.00 | 360000.50 | 522607.00 | 445000.00 |
| BR2706-036 | | I-270 BRIDGE DECK REHABILITAT | 08/11/11 | 1.00 | 150000.00 | 229232.75 | 142054.00 |
| NH5502-070 | | US 550 4 MILES SOUTH OF OURAY | 08/18/11 | 1.00 | 50000.00 | 78273.31 | 80000.00 |
| C0091-038 | | SH 9 MM 81.9 BLUE RIVER EMERG | 08/24/11 | 1.00 | 12000.00 | 33354.73 | 24609.00 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 1.00 | 90000.00 | 122871.13 | 86000.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 1.00 | 30000.20 | 37540.00 | 44000.00 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 1.00 | 50000.36 | 66381.97 | 50627.36 |
| STR096A-040 | | SH 96 MP 193 TO MP 201 | 09/01/11 | 1.00 | 140000.00 | 270353.19 | 178559.58 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 1.00 | 225000.00 | 516166.67 | 293000.00 |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 1.00 | 35000.00 | 91500.00 | 65000.00 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 1.00 | 40000.00 | 91666.67 | 60000.00 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 1.00 | 90000.00 | 49772.20 | 65000.00 |
| | | | | --- | --- | --- | --- |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 23.00 | 100826.20 | 156498.60 | 103892.01 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 1.00 | 100000.00 | 162446.96 | 126694.55 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 1.00 | 80000.00 | 381918.06 | 195025.59 |
| NH0501-060 | | US50 MP 74.0 TO 81, 94.2 TO 1 | 10/20/11 | 1.00 | 120000.00 | 84807.23 | 5128.40 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1.00 | 1270000.80 | 1073857.14 | 800000.00 |
| IM0702-306 | | HANGING LAKE TUNNEL | 10/27/11 | 1.00 | 50000.00 | 56885.17 | 26257.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1.00 | 1000000.00 | 1142885.70 | 967500.00 |
| SHE0402-081 | | US 40 - MP 113 TO 120 ROUTT C | 10/27/11 | 1.00 | 100000.00 | 62659.86 | 17959.17 |
| SHE025A-013 | | I 25 BETWEEN MP 122 AND MP 12 | 11/03/11 | 1.00 | 30000.00 | 84694.91 | 27700.00 |
| ITSSW00-928 | | NB I-225 AT MM 2.28 | 11/03/11 | 1.00 | 20000.00 | 17571.25 | 1950.50 |
| STA0343-033 | | SH 34 ECKLEY | 11/10/11 | 1.00 | 80000.00 | 99362.74 | 30351.45 |
| R600-395 | | REGION 6; VARIOUS LOCATIONS | 11/10/11 | 1.00 | 60000.00 | 42407.60 | 18375.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 1.00 | 330000.00 | 470695.85 | 215100.77 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1.00 | 485000.00 | 752199.85 | 800969.36 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 1.00 | 450000.00 | 389500.00 | 265000.00 |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 1.00 | 120000.00 | 196080.00 | 114320.00 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 1.00 | 90000.00 | 109690.00 | 90000.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 1.00 | 162300.00 | 132105.37 | 130000.00 |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 1.00 | 50000.00 | 115000.00 | 50000.00 |
| MC0504-065 | | US50B FROM MP 318 TO MP 359 | 12/01/11 | 1.00 | 20000.00 | 58925.00 | 53775.00 |
| IM0703-368 | | GEORGETOWN HILL CHUTES 6,7,9, | 12/01/11 | 1.00 | 60000.00 | 32945.42 | 18700.00 |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 1.00 | 200000.00 | 487925.29 | 358000.00 |
| C2854-125 | | US 285, ASPEN PARK TO MORRISO | 12/08/11 | 1.00 | 16000.00 | 29666.67 | 26000.00 |
| FBR0252-415 | | NB I-25 SOUTH OF FOUNTAIN, MP | 12/15/11 | 1.00 | 95000.00 | 279110.13 | 225932.45 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 626-00000 | Mobilization | | LUMP SUM | | | |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 1.00 | 800000.00 | 632213.87 | 650000.00 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 1.00 | 225000.00 | 248833.33 | 180000.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 25.00 | 240532.03 | 322041.83 | 206360.71 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 93.00 | 324729.23 | 286927.20 | 190688.76 |
| ========== | 626-01000 | Public Info Services | | LUMP SUM | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 1.00 | 3000.00 | 3360.00 | 1700.00 |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 1.00 | 2000.00 | 3467.71 | 3100.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 1.00 | 30000.00 | 47487.31 | 20000.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 1.00 | 3000.00 | 3025.43 | 1900.00 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 1.00 | 25000.00 | 7450.46 | 8100.00 |
| NH 0241-056 | | US 24 BUENA VISTA NORTH | 03/03/11 | 1.00 | 5000.00 | 4609.17 | 3000.00 |
| STA0504-061 | | US 50 M.P.369.9 -M.P.373.2 | 03/03/11 | 1.00 | 2000.00 | 4981.39 | 4406.96 |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 1.00 | 5000.00 | 2799.49 | 3500.00 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 1.00 | 5000.00 | 21812.09 | 15000.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 1.00 | 25000.00 | 61357.76 | 42259.99 |
| NH 0402-079 | | US40 MP 165.0 - 179.0 GRAND C | 03/31/11 | 1.00 | 5000.00 | 5250.00 | 5000.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 11.00 | 14285.71 | 16988.96 | 10044.38 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 1.00 | 5000.00 | 7508.43 | 5000.14 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 1.00 | 2500.00 | 3123.04 | 3000.00 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 1.00 | 20000.00 | 14788.61 | 5000.00 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 1.00 | 5000.00 | 5966.67 | 5500.00 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 1.00 | 5000.00 | 9107.33 | 4844.00 |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 1.00 | 3000.00 | 2892.43 | 1510.00 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 1.00 | 5000.00 | 18692.46 | 15841.92 |
| SHE074A-001 | | SH 74 - EVERGREEN - JEFFERSON | 04/28/11 | 1.00 | 2000.00 | 4113.33 | 4840.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 1.00 | 10000.00 | 16253.82 | 6300.00 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 1.00 | 5000.00 | 11231.61 | 6859.00 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 1.00 | 4000.00 | 4870.86 | 3200.00 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 1.00 | 3000.00 | 6171.30 | 5153.46 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 1.00 | 10000.00 | 8466.67 | 7400.00 |
| C0241-055 | | SH 24 MP 148-152 | 05/26/11 | 1.00 | 1500.00 | 2182.92 | 935.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 1.00 | 10000.00 | 10777.94 | 10000.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 1.00 | 8000.00 | 26721.43 | 37100.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 1.00 | 10000.00 | 12335.93 | 2500.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 626-01000 | Public Info Services | | LUMP SUM | ========== | ========== | ========== |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 1.00 | 4000.00 | 14833.33 | 12500.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 1.00 | 5500.00 | 8381.67 | 5100.00 |
| FSA 0502-064 | | US 50 EAST OF SARGENTS | 06/23/11 | 1.00 | 5000.00 | 3653.51 | 2524.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1.00 | 50000.00 | 16117.86 | 5028.54 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 21.00 | 8261.90 | 9166.97 | 6056.06 |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 1.00 | 5000.00 | 5843.94 | 7500.00 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 1.00 | 7500.00 | 6350.02 | 9390.58 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 1.00 | 5000.00 | 7020.90 | 3900.00 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 1.00 | 2500.00 | 11944.00 | 9532.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 1.00 | 10000.00 | 9015.49 | 4600.00 |
| NH0403-053 | | US 40 RETAINING WALL REPAIR | 07/28/11 | 1.00 | 1000.00 | 3164.13 | 592.38 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 1.00 | 5000.00 | 13969.75 | 20000.00 |
| BR2706-036 | | I-270 BRIDGE DECK REHABILITAT | 08/11/11 | 1.00 | 6000.00 | 3873.00 | 1992.00 |
| NH5502-070 | | US 550 4 MILES SOUTH OF OURAY | 08/18/11 | 1.00 | 700.00 | 11986.16 | 17000.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 1.00 | 3000.00 | 3052.00 | 5000.00 |
| STR096A-040 | | SH 96 MP 193 TO MP 201 | 09/01/11 | 1.00 | 3000.00 | 3748.07 | 1219.21 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 1.00 | 5000.00 | 10002.76 | 17290.00 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 1.00 | 3000.00 | 4022.20 | 4000.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 13.00 | 4361.54 | 6542.92 | 6684.69 |
| NH0501-060 | | US50 MP 74.0 TO 81, 94.2 TO 1 | 10/20/11 | 1.00 | 1000.00 | 2320.80 | 100.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1.00 | 25000.00 | 33271.43 | 60000.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1.00 | 40000.00 | 25034.09 | 10000.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 1.00 | 10000.00 | 7939.47 | 8563.72 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1.00 | 10000.00 | 9589.28 | 10000.00 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 1.00 | 10000.00 | 11712.65 | 5800.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 1.00 | 5000.00 | 6146.89 | 7840.00 |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 1.00 | 700.00 | 11000.00 | 12000.00 |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 1.00 | 2000.00 | 5939.38 | 5725.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 1.00 | 15000.00 | 13885.04 | 15500.00 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 1.00 | 5000.00 | 6600.00 | 3500.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 11.00 | 11245.45 | 13006.54 | 12638.97 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 56.00 | 9388.14 | 10754.77 | 7992.85 |
| ========== | 627-00001 | Pvmt Mkg Paint | | Gallon | ========== | ========== | ========== |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 4,536.00 | 40.00 | 39.26 | 30.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 627-00001 | Pvmt Mkg Paint | | Gallon | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 96.00 | 25.00 | 33.33 | 48.00 |
| NH 2852-017 | | US 285 PONCHA PASS SOUTH RESU | 03/03/11 | 1,400.00 | 30.00 | 23.41 | 20.00 |
| NH 0241-056 | | US 24 BUENA VISTA NORTH | 03/03/11 | 1,518.00 | 40.00 | 27.04 | 33.00 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 1,706.00 | 30.00 | 28.61 | 30.00 |
| NH 0402-079 | | US40 MP 165.0 - 179.0 GRAND C | 03/31/11 | 1,806.00 | 37.00 | 30.51 | 26.80 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 11,062.00 | 36.57 | 30.14 | 28.24 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 1,805.00 | 30.00 | 33.70 | 27.00 |
| STA0343-032 | | US 34 EAST OF AKRON | 04/07/11 | 435.00 | 25.00 | 29.33 | 28.00 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 1,500.00 | 40.00 | 41.00 | 39.00 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 19.00 | 50.00 | 89.33 | 67.00 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 91.00 | 60.00 | 52.42 | 32.74 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 550.00 | 63.00 | 34.71 | 40.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 303.00 | 45.00 | 37.91 | 75.00 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 20.00 | 70.00 | 96.88 | 78.75 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 4,723.00 | 38.35 | 36.24 | 35.50 |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 25.00 | 50.00 | 73.91 | 71.00 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 100.00 | 40.00 | 73.27 | 38.00 |
| STR096A-040 | | SH 96 MP 193 TO MP 201 | 09/01/11 | 558.00 | 28.00 | 64.64 | 54.93 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 683.00 | 30.56 | 67.76 | 53.83 |
| STA0343-033 | | SH 34 ECKLEY | 11/10/11 | 666.00 | 28.00 | 34.62 | 30.00 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 1,672.00 | 45.00 | 28.00 | 25.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2,338.00 | 40.16 | 28.90 | 26.28 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 18,806.00 | 37.25 | 32.45 | 31.23 |
| ========== | 627-00002 | Thermoplastic Pvmt Mkg | | Sq Foot | | | |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 2,434.00 | 4.00 | 7.69 | 7.50 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 2,434.00 | 4.00 | 7.69 | 7.50 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,434.00 | 4.00 | 7.69 | 7.50 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 627-00003 | Thermoplastic Pvmt Mkg (Inlaid) | | Sq Foot | | | |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 53.50 | 20.00 | 14.70 | 18.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 53.50 | 20.00 | 14.70 | 18.00 |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 96.00 | 12.00 | 27.53 | 19.50 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 96.00 | 12.00 | 27.53 | 19.50 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 234.00 | 18.00 | 21.00 | 21.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 234.00 | 18.00 | 21.00 | 21.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 383.50 | 16.78 | 22.00 | 20.21 |
| ========== | 627-00005 | Epoxy Pvmt Mkg | | Gallon | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 19.00 | 100.00 | 122.42 | 146.50 |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 61.00 | 70.00 | 113.50 | 102.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 848.00 | 70.00 | 70.97 | 55.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 12.00 | 100.00 | 240.29 | 235.00 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 48.00 | 60.00 | 169.73 | 180.00 |
| NH 2852-017 | | US 285 PONCHA PASS SOUTH RESU | 03/03/11 | 350.00 | 50.00 | 73.09 | 75.00 |
| NH 0241-056 | | US 24 BUENA VISTA NORTH | 03/03/11 | 506.00 | 75.00 | 64.88 | 62.00 |
| STA0504-061 | | US 50 M.P.369.9 -M.P.373.2 | 03/03/11 | 298.00 | 75.00 | 82.73 | 85.19 |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 623.00 | 40.00 | 55.11 | 51.80 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 766.00 | 50.00 | 63.29 | 65.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 102.00 | 75.00 | 116.58 | 121.06 |
| NH 0402-079 | | US40 MP 165.0 - 179.0 GRAND C | 03/31/11 | 903.00 | 60.00 | 62.79 | 59.75 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 4,536.00 | 60.07 | 72.19 | 69.34 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 746.00 | 50.00 | 65.00 | 58.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 627-00005 | Epoxy Pvmt Mkg | | Gallon | | | |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 413.00 | 40.00 | 75.32 | 77.00 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 102.00 | 100.00 | 167.61 | 175.00 |
| STA0343-032 | | US 34 EAST OF AKRON | 04/07/11 | 604.00 | 60.00 | 60.00 | 58.00 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 595.00 | 75.00 | 81.03 | 77.50 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 19.00 | 75.00 | 142.00 | 113.00 |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 222.00 | 80.00 | 70.16 | 71.35 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 24.00 | 90.00 | 168.86 | 149.50 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 64.00 | 100.00 | 109.60 | 126.74 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 85.00 | 100.00 | 124.41 | 84.00 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 110.00 | 100.00 | 105.94 | 82.50 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 91.00 | 80.00 | 80.63 | 88.80 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 350.00 | 100.00 | 75.50 | 79.00 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 214.00 | 75.00 | 83.94 | 75.47 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 1,550.00 | 60.00 | 56.33 | 56.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 152.00 | 130.00 | 103.80 | 118.50 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 30.00 | 90.00 | 97.95 | 106.00 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 10.00 | 150.00 | 321.88 | 288.75 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 387.00 | 70.00 | 86.80 | 74.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 168.00 | 80.00 | 104.00 | 100.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 829.00 | 60.00 | 145.23 | 138.15 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 10.00 | 100.00 | 431.07 | 420.00 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 6.00 | 60.00 | 272.50 | 224.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 30.00 | 120.00 | 176.83 | 147.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 188.00 | 25.00 | 106.47 | 82.47 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 6,999.00 | 66.77 | 88.48 | 81.14 |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 25.00 | 80.00 | 218.13 | 120.00 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 8.00 | 130.00 | 159.43 | 120.00 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 300.00 | 60.00 | 87.29 | 95.54 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 400.00 | 58.00 | 77.99 | 77.45 |
| NH2872-018 | | US 287 RUSH CREEK NORTH | 07/21/11 | 91.00 | 65.00 | 79.02 | 80.00 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 3.00 | 100.00 | 142.67 | 143.00 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 10.00 | 200.00 | 372.50 | 535.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 245.00 | 75.00 | 75.10 | 74.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 145.00 | 50.00 | 84.54 | 85.70 |
| BR2706-036 | | I-270 BRIDGE DECK REHABILITAT | 08/11/11 | 20.00 | 150.00 | 133.25 | 77.00 |
| C0091-038 | | SH 9 MM 81.9 BLUE RIVER EMERG | 08/24/11 | 6.00 | 200.00 | 327.68 | 297.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 27.00 | 150.00 | 284.00 | 240.00 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 1,191.00 | 77.00 | 63.19 | 63.00 |
| STR096A-040 | | SH 96 MP 193 TO MP 201 | 09/01/11 | 279.00 | 70.00 | 87.01 | 92.04 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 132.00 | 90.00 | 100.12 | 155.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 2,882.00 | 72.67 | 90.04 | 95.09 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 27.15 | 80.00 | 190.49 | 209.69 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 627-00005 | Epoxy Pvmt Mkg | | Gallon | | | |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 158.00 | 100.00 | 93.51 | 88.25 |
| NH0501-060 | | US50 MP 74.0 TO 81, 94.2 TO 1 | 10/20/11 | 1,366.00 | 60.00 | 70.75 | 65.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 242.00 | 75.00 | 68.71 | 66.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 77.00 | 125.00 | 228.88 | 225.00 |
| STA0343-033 | | SH 34 ECKLEY | 11/10/11 | 692.00 | 58.00 | 69.58 | 65.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 238.00 | 100.00 | 77.53 | 73.90 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 43.00 | 100.00 | 158.05 | 172.64 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 1,554.00 | 80.00 | 73.32 | 60.00 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 59.00 | 110.00 | 161.75 | 180.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 280.00 | 115.00 | 77.01 | 84.00 |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 20.00 | 95.00 | 282.50 | 265.00 |
| MC0504-065 | | US50B FROM MP 318 TO MP 359 | 12/01/11 | 2,373.00 | 50.00 | 70.00 | 68.00 |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 1,253.00 | 65.00 | 71.26 | 67.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 272.00 | 80.00 | 76.23 | 81.00 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 418.00 | 90.00 | 76.33 | 79.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 9,072.15 | 68.38 | 74.54 | 70.36 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 23,489.15 | 66.82 | 80.16 | 76.70 |
| ========== | 627-00011 | Pvmt Mkg Paint (Waterborne) | | Gallon | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 19.00 | 50.00 | 55.43 | 58.50 |
| STA0504-061 | | US 50 M.P.369.9 -M.P.373.2 | 03/03/11 | 298.00 | 33.00 | 38.85 | 34.08 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 317.00 | 34.02 | 58.10 | 67.74 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 1,239.00 | 30.00 | 34.75 | 36.00 |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 444.00 | 35.00 | 39.82 | 34.20 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 1,100.00 | 35.00 | 30.50 | 32.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 90.00 | 60.00 | 42.49 | 31.75 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 504.00 | 35.00 | 40.67 | 40.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 152.00 | 30.00 | 44.34 | 41.23 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 3,529.00 | 33.67 | 37.86 | 36.89 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 8.00 | 200.00 | 96.00 | 75.00 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 902.00 | 30.00 | 33.41 | 35.08 |
| NH5502-070 | | US 550 4 MILES SOUTH OF OURAY | 08/18/11 | 20.00 | 35.00 | 40.66 | 41.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 45.00 | 125.00 | 70.80 | 47.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 627-00011 | Pvmt Mkg Paint (Waterborne) | | Gallon | | | |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 1,180.00 | 36.00 | 38.15 | 38.00 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 402.00 | 40.00 | 41.93 | 45.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 2,557.00 | 36.58 | 38.38 | 38.37 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 474.00 | 35.00 | 44.29 | 45.12 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1,020.00 | 35.00 | 34.07 | 43.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 26.00 | 50.00 | 64.06 | 45.00 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 3,108.00 | 35.00 | 38.10 | 30.00 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 118.00 | 45.00 | 39.63 | 39.00 |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 20.00 | 40.00 | 175.00 | 200.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 480.00 | 50.00 | 36.00 | 34.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 5,246.00 | 36.69 | 37.43 | 35.18 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 11,649.00 | 35.68 | 38.82 | 37.78 |
| ========== | 627-00012 | Pvmt Mkg Paint (Low VOC Solvent Base) | | Gallon | | | |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 260.00 | 25.00 | 30.51 | 27.00 |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 1,400.00 | 30.00 | 33.61 | 33.65 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 2,000.00 | 25.00 | 31.84 | 30.81 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 3,660.00 | 26.91 | 32.13 | 31.33 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 988.00 | 25.00 | 24.42 | 20.00 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 48.00 | 60.00 | 47.96 | 68.70 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 634.00 | 30.00 | 39.43 | 43.00 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 278.00 | 35.00 | 56.03 | 40.70 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 605.00 | 32.00 | 32.03 | 32.34 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 1,700.00 | 31.00 | 26.50 | 26.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 320.00 | 30.00 | 50.22 | 37.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 3,336.00 | 30.00 | 34.51 | 32.75 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 10.00 | 50.00 | 223.87 | 210.00 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 18.00 | 30.00 | 114.50 | 112.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 60.00 | 50.00 | 85.83 | 102.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 7,997.00 | 30.28 | 34.52 | 31.87 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 300.00 | 40.00 | 39.26 | 38.70 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 627-00012 | Pvmt Mkg Paint (Low VOC Solvent Base) | | Gallon | ========== | ========== | ========== |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 245.00 | 30.00 | 42.58 | 34.25 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 200.00 | 30.00 | 38.41 | 40.00 |
| BR2706-036 | | I-270 BRIDGE DECK REHABILITAT | 08/11/11 | 60.00 | 40.00 | 65.69 | 41.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 805.00 | 34.47 | 43.09 | 39.11 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 30.00 | 35.00 | 39.10 | 38.63 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 850.00 | 35.00 | 49.54 | 45.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 205.00 | 32.00 | 41.19 | 38.61 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 223.00 | 33.00 | 34.10 | 36.83 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 556.00 | 37.00 | 41.10 | 42.00 |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 3,285.00 | 32.00 | 30.25 | 24.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 5,149.00 | 33.10 | 35.26 | 30.63 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 17,611.00 | 30.59 | 34.54 | 31.77 |
| ========== | 627-00025 | 4 In Pvmt Mkg Tape (Rem) | | Lin Foot | ========== | ========== | ========== |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 22,601.00 | 3.00 | 2.10 | 2.01 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 22,601.00 | 3.00 | 2.10 | 2.01 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 22,601.00 | 3.00 | 2.10 | 2.01 |
| ========== | 627-00032 | Raised Flex Pvmt Marker (Temp) | | Each | ========== | ========== | ========== |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 354.00 | 3.00 | 6.07 | 6.50 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 354.00 | 3.00 | 6.07 | 6.50 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 354.00 | 3.00 | 6.07 | 6.50 |
| ========== | 627-00070 | Preform Thermoplastic Pvmt Mkg | | Sq Foot | ========== | ========== | ========== |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 340.00 | 15.00 | 10.10 | 8.40 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 650.00 | 12.00 | 9.07 | 6.80 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 990.00 | 13.03 | 9.33 | 7.35 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 627-00070 | Preform Thermoplastic Pvmt Mkg | | Sq Foot | | | |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 126.00 | 20.00 | 19.87 | 19.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 126.00 | 20.00 | 19.87 | 19.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,116.00 | 13.82 | 11.20 | 8.66 |
| ========== | 627-00090 | Pvmt Mkg (Spec) | | Sq Foot | | | |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 513.00 | 15.00 | 39.80 | 50.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 513.00 | 15.00 | 39.80 | 50.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 513.00 | 15.00 | 39.80 | 50.00 |
| ========== | 627-01001 | Preform Plastic Pvmt Mkg (Ty I) | | Sq Foot | | | |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 60.00 | 8.00 | 13.11 | 13.00 |
| C0703-363 | | CLEAR CREEK AND JEFFERSON COU | 02/17/11 | 3,000.00 | 10.00 | 11.98 | 8.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 3,060.00 | 9.96 | 12.00 | 8.10 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 206.00 | 10.00 | 21.50 | 20.50 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 5,096.00 | 9.00 | 11.50 | 11.00 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 1,833.00 | 10.00 | 12.64 | 12.50 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 13,095.00 | 9.00 | 9.54 | 9.70 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 19.00 | 15.00 | 16.10 | 15.85 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 2,319.00 | 9.00 | 9.79 | 9.31 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 22,568.00 | 9.10 | 10.48 | 10.24 |
| BR2706-036 | | I-270 BRIDGE DECK REHABILITAT | 08/11/11 | 250.00 | 12.00 | 19.84 | 21.00 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 425.00 | 15.00 | 15.82 | 15.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 675.00 | 13.89 | 16.65 | 17.22 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 627-01001 | Preform Plastic Pvmt Mkg (Ty I) | | Sq Foot | | | |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 2,877.00 | 10.00 | 12.71 | 12.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2,877.00 | 10.00 | 12.71 | 12.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 29,180.00 | 9.39 | 11.07 | 10.34 |
| ========== | 627-01010 | Preform Plastic Pvmt Mkg (TY I)(Inlaid) | | Sq Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 44,348.00 | 9.00 | 10.57 | 9.25 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 9,042.00 | 12.00 | 10.36 | 11.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 2,346.00 | 10.00 | 10.01 | 10.40 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 55,736.00 | 9.53 | 10.44 | 10.07 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 620.00 | 15.00 | 17.08 | 16.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 620.00 | 15.00 | 17.08 | 16.00 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 3,700.00 | 11.00 | 10.02 | 9.95 |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 2,170.00 | 13.00 | 15.75 | 16.50 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 5,870.00 | 11.74 | 11.11 | 12.37 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1,411.00 | 10.00 | 10.64 | 10.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 5,371.00 | 11.00 | 10.05 | 10.93 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 12.00 | 25.00 | 34.13 | 28.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 6,794.00 | 10.82 | 10.18 | 10.77 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 69,020.00 | 9.89 | 10.50 | 10.69 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 627-02001 | Preform Plastic Pvmt Mkg (Ty II) | | Sq Foot | | | |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 13,798.00 | 8.00 | 9.50 | 8.65 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 6,321.00 | 12.00 | 10.15 | 10.30 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 20,119.00 | 9.26 | 9.75 | 9.17 |
| NH2872-018 | | US 287 RUSH CREEK NORTH | 07/21/11 | 2,126.00 | 10.60 | 10.48 | 11.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 2,126.00 | 10.60 | 10.48 | 11.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 108.00 | 12.00 | 16.48 | 16.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 108.00 | 12.00 | 16.48 | 16.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 22,353.00 | 9.40 | 9.84 | 9.38 |
| ========== | 627-02010 | Preform Plastic Pvmt Mkg (Ty II)(Inlaid) | | Sq Foot | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 4,539.00 | 11.00 | 10.54 | 11.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 3,065.00 | 11.00 | 10.08 | 10.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 7,604.00 | 11.00 | 10.34 | 10.60 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 295.00 | 15.00 | 19.38 | 13.24 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 295.00 | 15.00 | 19.38 | 13.24 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 7,899.00 | 11.15 | 10.75 | 10.70 |
| ========== | 627-03003 | Preform Plastic Pvmt Mkg (Ty C) (Inlaid) | | Sq Foot | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 899.00 | 25.00 | 12.29 | 10.06 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 899.00 | 25.00 | 12.29 | 10.06 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 899.00 | 25.00 | 12.29 | 10.06 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 627-30324 | Preform Plastic Pvmt Mkg (WS) (TY I) | | Sq Foot | | | |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 1,476.00 | 24.00 | 20.55 | 23.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 512.00 | 10.00 | 21.50 | 24.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 1,988.00 | 20.39 | 19.83 | 22.28 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 107.00 | 12.00 | 18.47 | 17.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 107.00 | 12.00 | 18.47 | 17.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,095.00 | 19.97 | 19.76 | 22.06 |
| ========== | 627-30326 | Preform Plastic Pvmt Mkg (WS) (Ty II) | | Sq Foot | | | |
| NH 0241-056 | | US 24 BUENA VISTA NORTH | 03/03/11 | 1,072.00 | 20.00 | 17.40 | 15.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 1,072.00 | 20.00 | 17.40 | 15.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,072.00 | 20.00 | 17.40 | 15.00 |
| ========== | 627-30327 | Preform Plastic Pvmt Mkg (WS) (Ty III) | | Sq Foot | | | |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 2,170.00 | 10.00 | 14.26 | 14.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 2,280.00 | 11.00 | 13.69 | 12.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 4,450.00 | 10.51 | 14.10 | 13.58 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 11,100.00 | 10.00 | 9.06 | 7.25 |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 190.00 | 15.00 | 13.29 | 14.10 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 506.00 | 12.00 | 13.52 | 14.00 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 62.00 | 15.00 | 20.48 | 16.50 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 383.00 | 17.00 | 11.25 | 10.78 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 998.00 | 11.00 | 13.94 | 13.30 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 13,239.00 | 10.45 | 9.81 | 8.42 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 627-30327 | Preform Plastic Pvmt Mkg (WS) (Ty III) | | Sq Foot | | | |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 107.00 | 12.00 | 22.69 | 19.26 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 107.00 | 12.00 | 22.69 | 19.26 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 1,712.00 | 13.00 | 14.54 | 14.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 226.00 | 15.00 | 13.76 | 14.96 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1,938.00 | 13.23 | 14.43 | 14.11 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 19,734.00 | 10.75 | 11.13 | 9.85 |
| ========== | 627-30329 | Preform Plastic Pvmt Mkg (XS) (TY I) | | Sq Foot | | | |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 360.00 | 12.00 | 10.56 | 13.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 360.00 | 12.00 | 10.52 | 12.84 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 30.00 | 16.00 | 14.73 | 16.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 30.00 | 16.00 | 14.73 | 16.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 390.00 | 12.31 | 10.96 | 13.07 |
| ========== | 627-30332 | Preform Plastic Pvmt Mkg (XS) (Ty III) | | Sq Foot | | | |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 653.00 | 7.00 | 11.65 | 12.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 2,004.00 | 11.00 | 10.55 | 9.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 2,657.00 | 10.02 | 11.06 | 10.70 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 1,220.00 | 9.00 | 13.18 | 12.50 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 627-30332 | Preform Plastic Pvmt Mkg (XS) (Ty III) | | Sq Foot | | | |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 320.00 | 12.00 | 10.15 | 9.05 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 818.00 | 10.00 | 9.33 | 9.50 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 160.00 | 12.00 | 15.20 | 11.00 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 6,920.00 | 11.00 | 8.67 | 8.63 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 3,390.00 | 12.00 | 9.69 | 9.21 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 752.00 | 11.00 | 11.80 | 12.60 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 13,580.00 | 11.05 | 9.75 | 9.45 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 6,194.00 | 9.00 | 9.49 | 7.49 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 6,194.00 | 9.00 | 9.49 | 7.49 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 3,862.00 | 8.00 | 10.24 | 9.70 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 606.00 | 10.00 | 12.87 | 10.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1,490.00 | 10.00 | 9.60 | 10.36 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 5,958.00 | 8.70 | 10.25 | 9.90 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 28,389.00 | 10.01 | 9.91 | 9.18 |
| ========== | 627-30405 | Preform Thermoplastic Pvmt Mkg (WS) | | Sq Foot | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 176.00 | 19.00 | 16.07 | 17.55 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 117.00 | 9.00 | 16.64 | 20.00 |
| STA0504-061 | | US 50 M.P.369.9 -M.P.373.2 | 03/03/11 | 248.00 | 12.00 | 19.33 | 19.17 |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 15.50 | 15.00 | 17.51 | 18.65 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 556.50 | 13.67 | 17.12 | 17.13 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 41.00 | 12.00 | 15.61 | 15.00 |
| STA0343-032 | | US 34 EAST OF AKRON | 04/07/11 | 262.00 | 20.00 | 14.67 | 15.00 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 31.00 | 10.00 | 20.58 | 16.70 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 214.00 | 14.00 | 12.99 | 12.50 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 62.00 | 10.00 | 17.08 | 17.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 31.00 | 20.00 | 16.10 | 15.85 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 2,377.00 | 6.00 | 13.32 | 13.07 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 3,018.00 | 8.13 | 13.51 | 13.37 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 627-30405 | Preform Thermoplastic Pvmt Mkg (WS) | | Sq Foot | | | |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 758.00 | 15.00 | 14.45 | 15.11 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 906.00 | 8.00 | 15.69 | 15.50 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 62.00 | 11.00 | 15.77 | 17.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 388.00 | 12.00 | 16.53 | 16.75 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 1,740.00 | 10.00 | 14.00 | 15.00 |
| STR096A-040 | | SH 96 MP 193 TO MP 201 | 09/01/11 | 66.00 | 18.50 | 22.56 | 29.69 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 116.00 | 18.00 | 20.98 | 20.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 4,036.00 | 11.07 | 15.37 | 15.89 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 405.00 | 15.00 | 14.58 | 13.82 |
| NH0501-060 | | US50 MP 74.0 TO 81, 94.2 TO 1 | 10/20/11 | 107.00 | 18.00 | 18.36 | 17.00 |
| STA0343-033 | | SH 34 ECKLEY | 11/10/11 | 108.50 | 15.00 | 17.81 | 20.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 620.50 | 15.52 | 15.38 | 14.96 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 8,231.00 | 10.50 | 14.86 | 15.11 |
| ========== | 627-30407 | Preform Thermoplastic Pvmt Mkg (WS)(Sp) | | Sq Foot | | | |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 169.00 | 20.00 | 25.82 | 24.75 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 169.00 | 20.00 | 25.82 | 24.75 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 1,028.00 | 20.00 | 19.55 | 16.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 1,028.00 | 20.00 | 19.55 | 16.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,197.00 | 20.00 | 20.79 | 17.24 |
| ========== | 627-30410 | Preform Thermoplastic Pvmt Mkg (XS) | | Sq Foot | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 444.00 | 14.00 | 14.65 | 16.50 |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 324.00 | 15.00 | 10.76 | 10.35 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 768.00 | 14.42 | 12.32 | 12.17 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 627-30410 | Preform Thermoplastic Pvmt Mkg (XS) | | Sq Foot | | | |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 760.00 | 8.00 | 10.62 | 11.00 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 2,400.00 | 9.00 | 6.72 | 6.25 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 48.00 | 12.00 | 13.00 | 13.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 4,353.00 | 10.00 | 9.36 | 10.06 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 7,561.00 | 9.49 | 8.62 | 8.96 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 792.00 | 10.00 | 10.30 | 10.80 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 6,872.00 | 9.50 | 11.13 | 11.05 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 749.00 | 11.00 | 12.62 | 14.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 240.00 | 12.00 | 15.83 | 15.50 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 1,360.00 | 10.00 | 10.31 | 10.50 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 10,013.00 | 9.78 | 11.24 | 11.32 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1,162.00 | 20.00 | 12.11 | 11.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1,162.00 | 20.00 | 12.11 | 11.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 19,504.00 | 10.46 | 10.28 | 10.52 |
| ========== | 627-30411 | Preform Thermoplastic Pvmt Mkg (XS)(Sp) | | Sq Foot | | | |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 144.00 | 12.00 | 21.50 | 20.50 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 144.00 | 12.00 | 21.50 | 20.50 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 3,614.00 | 15.00 | 18.55 | 14.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 3,614.00 | 15.00 | 18.55 | 14.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3,758.00 | 14.89 | 18.72 | 14.25 |
| ========== | 627-40003 | Methyl Methacrylate Pvmt Mkg (Inlaid) | | Sq Foot | | | |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 3,350.00 | 15.00 | 15.75 | 16.50 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 3,350.00 | 15.00 | 15.75 | 16.50 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3,350.00 | 15.00 | 15.75 | 16.50 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 628-50001 | Design Services | | LUMP SUM | | | |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1.00 | 20000.00 | 35184.90 | 25000.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 20000.00 | 35184.90 | 25000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 20000.00 | 35184.90 | 25000.00 |
| ========== | 629-01001 | Survey Monument (Ty 1) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 8.00 | 300.00 | 197.33 | 110.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 14.00 | 300.00 | 204.79 | 125.78 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 22.00 | 300.00 | 203.75 | 123.81 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 84.00 | 100.00 | 86.23 | 25.50 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 2.00 | 300.00 | 105.16 | 81.87 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 86.00 | 104.65 | 86.45 | 26.81 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 4.00 | 130.00 | 475.48 | 722.00 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 30.00 | 180.00 | 145.70 | 180.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 34.00 | 174.12 | 180.64 | 243.76 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 6.00 | 125.00 | 122.66 | 110.30 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 6.00 | 125.00 | 122.66 | 110.30 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 148.00 | 150.47 | 125.62 | 93.21 |
| ========== | 629-01002 | Survey Monument (Ty 2) | | Each | | | |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 7.00 | 500.00 | 214.28 | 178.63 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 7.00 | 500.00 | 214.28 | 178.63 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 7.00 | 500.00 | 294.04 | 202.27 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 629-01003 | Survey Monument (Ty 3) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 8.00 | 400.00 | 533.83 | 160.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 8.00 | 400.00 | 533.83 | 160.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 8.00 | 400.00 | 533.83 | 160.00 |
| ========== | 629-01005 | Survey Monument (Ty 5) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 8.00 | 300.00 | 200.54 | 130.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 2.00 | 225.00 | 209.07 | 110.06 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 10.00 | 285.00 | 204.56 | 120.03 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 10.00 | 285.00 | 204.56 | 120.03 |
| ========== | 629-01031 | Survey Monument (Ty 3A) | | Each | | | |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 2.00 | 300.00 | 433.53 | 225.13 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 2.00 | 300.00 | 433.53 | 225.13 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 1.00 | 350.00 | 592.46 | 722.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 1.00 | 350.00 | 592.46 | 722.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3.00 | 316.67 | 513.00 | 390.75 |
| ========== | 629-01050 | Monument Box | | Each | | | |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 1.00 | 300.00 | 243.23 | 60.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 1.00 | 300.00 | 243.23 | 60.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 300.00 | 243.23 | 60.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 629-01065 | Survey Monument (Ty 5S) | | Each | | | |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 1.00 | 150.00 | 208.25 | 80.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 2.00 | 225.00 | 228.45 | 165.08 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 3.00 | 200.00 | 222.94 | 136.72 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3.00 | 200.00 | 222.94 | 136.72 |
| ========== | 629-01110 | Locate Monuments | | Hour | | | |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 8.00 | 130.00 | 118.06 | 110.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 8.00 | 130.00 | 118.06 | 110.00 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 8.00 | 125.00 | 346.65 | 107.81 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 8.00 | 125.00 | 346.65 | 107.81 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 16.00 | 127.50 | 209.49 | 108.91 |
| ========== | 629-01210 | Adjust Monument Box | | Each | | | |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 2.00 | 350.00 | 176.54 | 160.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 2.00 | 350.00 | 176.54 | 160.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 1.00 | 300.00 | 310.96 | 102.33 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 1.00 | 300.00 | 310.96 | 102.33 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 4.00 | 400.00 | 437.04 | 647.70 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 4.00 | 400.00 | 437.04 | 647.70 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 7.00 | 371.43 | 336.20 | 430.45 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 630-00000 | Flagging | | Hour | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 960.00 | 20.00 | 24.65 | 27.15 |
| C0704-225 | | I-70 EAST OF BENNETT | 01/06/11 | 40.00 | 25.00 | 21.59 | 19.35 |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 1,600.00 | 21.00 | 20.77 | 20.00 |
| ITS4701-121 | | C470 (SANTA FE TO I-25) AND R | 01/20/11 | 100.00 | 22.00 | 24.94 | 25.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 30,000.00 | 22.00 | 19.01 | 1.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 150.00 | 22.00 | 24.69 | 20.00 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 2,000.00 | 19.00 | 20.85 | 19.00 |
| C0703-363 | | CLEAR CREEK AND JEFFERSON COU | 02/17/11 | 200.00 | 20.00 | 13.33 | 15.00 |
| NH 2852-017 | | US 285 PONCHA PASS SOUTH RESU | 03/03/11 | 1,200.00 | 20.00 | 21.27 | 21.00 |
| NH 0241-056 | | US 24 BUENA VISTA NORTH | 03/03/11 | 2,000.00 | 21.00 | 21.17 | 22.00 |
| STA0504-061 | | US 50 M.P.369.9 -M.P.373.2 | 03/03/11 | 500.00 | 18.00 | 25.12 | 25.56 |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 1,800.00 | 25.00 | 21.84 | 19.00 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 5,220.00 | 21.00 | 24.73 | 27.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 9,600.00 | 22.00 | 21.01 | 22.01 |
| NH 0402-079 | | US40 MP 165.0 - 179.0 GRAND C | 03/31/11 | 3,500.00 | 22.00 | 24.45 | 23.70 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 58,870.00 | 21.73 | 21.15 | 16.32 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 4,000.00 | 24.00 | 22.57 | 20.00 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 1,000.00 | 21.00 | 21.25 | 22.00 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 5,000.00 | 22.00 | 21.79 | 18.00 |
| STA0343-032 | | US 34 EAST OF AKRON | 04/07/11 | 450.00 | 20.00 | 18.83 | 12.50 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 4,800.00 | 20.00 | 23.63 | 22.50 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 3,000.00 | 20.00 | 20.00 | 16.00 |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 2,000.00 | 20.00 | 20.05 | 19.10 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 100.00 | 25.00 | 21.82 | 23.70 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 5,000.00 | 20.00 | 20.30 | 22.18 |
| SHE074A-001 | | SH 74 - EVERGREEN - JEFFERSON | 04/28/11 | 20.00 | 25.00 | 22.67 | 24.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 3,600.00 | 22.00 | 22.02 | 23.00 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 2,000.00 | 20.00 | 25.00 | 24.50 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 1,760.00 | 20.00 | 21.62 | 20.80 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 5,000.00 | 20.00 | 20.50 | 21.00 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 3,000.00 | 22.00 | 23.80 | 25.34 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 3,500.00 | 24.00 | 23.27 | 25.00 |
| C0241-055 | | SH 24 MP 148-152 | 05/26/11 | 500.00 | 25.00 | 24.99 | 22.50 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 8,000.00 | 24.00 | 24.14 | 26.75 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 4,000.00 | 25.00 | 20.88 | 21.00 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 960.00 | 23.00 | 23.55 | 23.10 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 1,200.00 | 22.00 | 22.91 | 15.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 4,500.00 | 21.00 | 20.33 | 21.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 630-00000 | Flagging | | Hour | | | |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 3,840.00 | 22.00 | 23.83 | 22.51 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 24.00 | 22.00 | 23.85 | 21.00 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 100.00 | 25.00 | 22.13 | 22.00 |
| ITS0703-370 | | EAST OF EJMT ON I-70 EB LANES | 06/16/11 | 50.00 | 20.50 | 27.81 | 25.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 1,200.00 | 22.00 | 25.83 | 28.00 |
| FSA 0502-064 | | US 50 EAST OF SARGENTS | 06/23/11 | 100.00 | 22.00 | 24.64 | 20.70 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 12,500.00 | 23.00 | 17.59 | 12.07 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 600.00 | 25.00 | 25.00 | 27.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 81,804.00 | 22.08 | 21.26 | 19.77 |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 50.00 | 24.00 | 26.26 | 26.00 |
| C006A-051 | | US 6 (LOVELAND PASS), CLEAR C | 07/14/11 | 250.00 | 22.00 | 29.40 | 26.60 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 1,500.00 | 25.00 | 23.68 | 27.00 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 3,200.00 | 23.00 | 25.62 | 25.91 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 2,000.00 | 22.00 | 23.18 | 22.10 |
| NH2872-018 | | US 287 RUSH CREEK NORTH | 07/21/11 | 1,000.00 | 18.00 | 25.01 | 23.00 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 300.00 | 20.00 | 26.08 | 29.00 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 500.00 | 22.00 | 25.68 | 25.89 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 4,500.00 | 22.00 | 23.33 | 20.00 |
| NH0403-053 | | US 40 RETAINING WALL REPAIR | 07/28/11 | 100.00 | 25.00 | 25.67 | 23.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 18,700.00 | 23.50 | 14.20 | 17.75 |
| BR2706-036 | | I-270 BRIDGE DECK REHABILITAT | 08/11/11 | 525.00 | 25.00 | 13.00 | 10.00 |
| NH5502-070 | | US 550 4 MILES SOUTH OF OURAY | 08/18/11 | 1,875.00 | 21.00 | 24.50 | 22.00 |
| C0091-038 | | SH 9 MM 81.9 BLUE RIVER EMERG | 08/24/11 | 400.00 | 20.00 | 27.89 | 26.00 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 1,200.00 | 23.00 | 22.59 | 25.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 180.00 | 23.00 | 28.70 | 21.00 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 500.00 | 22.00 | 18.10 | 16.00 |
| STR096A-040 | | SH 96 MP 193 TO MP 201 | 09/01/11 | 2,400.00 | 18.50 | 20.89 | 18.66 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 7,000.00 | 21.00 | 22.11 | 20.00 |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 600.00 | 23.00 | 20.00 | 21.00 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 500.00 | 25.00 | 25.83 | 26.00 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 700.00 | 25.00 | 24.56 | 20.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 47,980.00 | 22.43 | 20.24 | 20.47 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 880.00 | 22.00 | 20.38 | 19.92 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 2,000.00 | 23.00 | 21.08 | 21.27 |
| NH0501-060 | | US50 MP 74.0 TO 81, 94.2 TO 1 | 10/20/11 | 1,200.00 | 24.00 | 22.37 | 10.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 15,000.00 | 22.00 | 21.81 | 22.15 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 4,000.00 | 22.00 | 24.99 | 19.00 |
| SHE0402-081 | | US 40 - MP 113 TO 120 ROUTT C | 10/27/11 | 1,500.00 | 22.00 | 25.90 | 26.19 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 630-00000 | Flagging | | Hour | | | |
| ITSSW00-928 | | NB I-225 AT MM 2.28 | 11/03/11 | 40.00 | 25.00 | 24.34 | 21.00 |
| STA0343-033 | | SH 34 ECKLEY | 11/10/11 | 250.00 | 20.00 | 24.50 | 23.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 2,000.00 | 22.00 | 23.91 | 22.06 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 3,500.00 | 22.00 | 20.14 | 21.20 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 3,720.00 | 25.00 | 27.86 | 28.00 |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 260.00 | 22.00 | 27.48 | 26.40 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 900.00 | 23.00 | 22.77 | 21.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 2,500.00 | 25.00 | 26.80 | 27.00 |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 1,800.00 | 25.00 | 25.00 | 23.00 |
| MC0504-065 | | US50B FROM MP 318 TO MP 359 | 12/01/11 | 200.00 | 20.00 | 22.17 | 18.50 |
| IM0703-368 | | GEORGETOWN HILL CHUTES 6,7,9, | 12/01/11 | 1,600.00 | 20.00 | 19.68 | 22.00 |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 4,750.00 | 22.00 | 23.06 | 22.00 |
| C2854-125 | | US 285, ASPEN PARK TO MORRISO | 12/08/11 | 100.00 | 22.00 | 20.33 | 17.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 7,000.00 | 23.00 | 24.79 | 24.00 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 2,400.00 | 23.00 | 29.00 | 28.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 55,600.00 | 22.63 | 23.18 | 22.72 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 244,254.00 | 22.19 | 21.46 | 19.82 |
| ========== | 630-00001 | Pilot Car Operation | | Hour | | | |
| NH 2852-017 | | US 285 PONCHA PASS SOUTH RESU | 03/03/11 | 400.00 | 35.00 | 36.47 | 36.00 |
| NH 0402-079 | | US40 MP 165.0 - 179.0 GRAND C | 03/31/11 | 420.00 | 37.00 | 39.81 | 34.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 820.00 | 36.02 | 38.55 | 36.53 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 100.00 | 50.00 | 35.90 | 35.00 |
| STA0343-032 | | US 34 EAST OF AKRON | 04/07/11 | 120.00 | 50.00 | 36.67 | 20.00 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 750.00 | 35.00 | 37.80 | 36.00 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 210.00 | 40.00 | 36.00 | 37.00 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 1,750.00 | 32.00 | 36.50 | 37.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 2,930.00 | 34.69 | 36.78 | 35.98 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 32.00 | 50.00 | 52.48 | 52.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 32.00 | 50.00 | 52.48 | 52.00 |
| STA0343-033 | | SH 34 ECKLEY | 11/10/11 | 60.00 | 30.00 | 39.80 | 38.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 630-00001 | Pilot Car Operation | | Hour | | | |
| MC0504-065 | | US50B FROM MP 318 TO MP 359 | 12/01/11 | 100.00 | 40.00 | 44.67 | 38.00 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 600.00 | 35.00 | 41.33 | 40.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 760.00 | 35.26 | 41.25 | 39.32 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4,542.00 | 35.14 | 38.35 | 36.72 |
| ========== | 630-00003 | Uniformed Traf Ctrl | | Hour | | | |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 160.00 | 65.00 | 54.96 | 48.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 18,480.00 | 60.00 | 37.24 | 1.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 4,000.00 | 60.00 | 46.18 | 51.72 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 22,640.00 | 60.04 | 41.31 | 24.96 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 1,500.00 | 55.00 | 46.79 | 50.69 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 400.00 | 50.00 | 57.04 | 58.00 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 2,000.00 | 45.00 | 63.75 | 60.50 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 256.00 | 50.00 | 63.08 | 62.40 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 450.00 | 60.00 | 50.95 | 53.91 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 360.00 | 60.00 | 62.23 | 77.00 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 8.00 | 60.00 | 66.77 | 57.75 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 64.00 | 60.00 | 72.00 | 75.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 5,038.00 | 51.25 | 56.10 | 58.04 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 32.00 | 60.00 | 96.00 | 91.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 400.00 | 60.00 | 47.25 | 14.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 432.00 | 60.00 | 49.13 | 19.70 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 800.00 | 50.00 | 57.07 | 70.00 |
| R600-395 | | REGION 6; VARIOUS LOCATIONS | 11/10/11 | 720.00 | 50.00 | 66.93 | 52.65 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 196.00 | 55.00 | 55.32 | 71.70 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 630-00003 | Uniformed Traf Ctrl | | Hour | | | |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 200.00 | 50.00 | 62.05 | 50.48 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1,916.00 | 50.51 | 60.85 | 61.62 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 30,026.00 | 57.95 | 47.31 | 39.70 |
| ========== | 630-00004 | Traf Ctrl Vehicle | | Each | | | |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 1.00 | 2000.00 | 1642.89 | 1000.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 8.00 | 5000.00 | 8413.88 | 8000.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 2.00 | 4000.00 | 13581.91 | 17608.33 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 11.00 | 4545.45 | 9465.44 | 10443.33 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 2.00 | 3000.00 | 5467.68 | 6000.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 2.00 | 10000.00 | 3412.49 | 3700.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 2.00 | 2000.00 | 1220.45 | 510.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 6.00 | 5000.00 | 3187.01 | 3279.29 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 2.00 | 8000.00 | 2065.29 | 2000.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 2.00 | 8000.00 | 2065.29 | 2000.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 10.00 | 3600.00 | 2157.20 | 3000.00 |
| R600-395 | | REGION 6; VARIOUS LOCATIONS | 11/10/11 | 4.00 | 2000.00 | 413.82 | 1052.60 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 2.00 | 4000.00 | 1847.07 | 3309.05 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1.00 | 8000.00 | 3378.35 | 3028.88 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 17.00 | 3529.41 | 1837.41 | 2579.85 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 36.00 | 4333.33 | 3735.09 | 3968.68 |
| ========== | 630-00005 | Uniformed Traf Ctrl (Vehicle) | | Hour | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 4,000.00 | 30.00 | 9.38 | 8.80 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 4,000.00 | 30.00 | 9.38 | 8.80 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 630-00005 | Uniformed Traf Ctrl (Vehicle) | | Hour | | | |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 8.00 | 20.00 | 37.27 | 21.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 8.00 | 20.00 | 37.27 | 21.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4,008.00 | 29.98 | 9.40 | 8.82 |
| ========== | 630-00007 | Traf Ctrl Inspection | | Day | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 24.00 | 80.00 | 71.31 | 64.35 |
| C0704-225 | | I-70 EAST OF BENNETT | 01/06/11 | 10.00 | 100.00 | 87.03 | 90.10 |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 15.00 | 100.00 | 89.90 | 52.00 |
| ITS4701-121 | | C470 (SANTA FE TO I-25) AND R | 01/20/11 | 4.00 | 100.00 | 157.69 | 307.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 1,840.00 | 110.00 | 76.75 | 1.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 75.00 | 110.00 | 126.86 | 100.00 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 100.00 | 110.00 | 100.09 | 80.00 |
| C0703-363 | | CLEAR CREEK AND JEFFERSON COU | 02/17/11 | 24.00 | 120.00 | 45.67 | 90.00 |
| NH 2852-017 | | US 285 PONCHA PASS SOUTH RESU | 03/03/11 | 14.00 | 90.00 | 92.00 | 103.00 |
| NH 0241-056 | | US 24 BUENA VISTA NORTH | 03/03/11 | 18.00 | 70.00 | 93.92 | 110.00 |
| STA0504-061 | | US 50 M.P.369.9 -M.P.373.2 | 03/03/11 | 20.00 | 35.00 | 36.56 | 21.30 |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 25.00 | 150.00 | 106.68 | 122.00 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 50.00 | 200.00 | 150.69 | 150.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 300.00 | 90.00 | 63.53 | 55.02 |
| NH 0402-079 | | US40 MP 165.0 - 179.0 GRAND C | 03/31/11 | 28.00 | 100.00 | 114.58 | 129.80 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 2,547.00 | 108.41 | 81.89 | 52.99 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 34.00 | 110.00 | 127.60 | 100.00 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 25.00 | 60.00 | 40.27 | 54.00 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 70.00 | 100.00 | 120.75 | 125.00 |
| STA0343-032 | | US 34 EAST OF AKRON | 04/07/11 | 7.00 | 80.00 | 91.67 | 75.00 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 32.00 | 100.00 | 107.83 | 103.00 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 36.00 | 80.00 | 62.25 | 67.00 |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 16.00 | 100.00 | 61.23 | 50.25 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 12.00 | 100.00 | 72.16 | 88.70 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 175.00 | 100.00 | 142.81 | 79.21 |
| SHE074A-001 | | SH 74 - EVERGREEN - JEFFERSON | 04/28/11 | 6.00 | 250.00 | 130.33 | 155.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 630-00007 | Traf Ctrl Inspection | | Day | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 172.00 | 110.00 | 79.91 | 77.00 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 40.00 | 100.00 | 33.45 | 27.50 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 30.00 | 100.00 | 61.46 | 57.20 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 30.00 | 50.00 | 87.50 | 90.00 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 40.00 | 100.00 | 58.42 | 48.52 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 40.00 | 100.00 | 141.67 | 158.00 |
| C0241-055 | | SH 24 MP 148-152 | 05/26/11 | 20.00 | 150.00 | 113.42 | 150.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 85.00 | 150.00 | 222.83 | 230.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 200.00 | 140.00 | 125.52 | 130.00 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 12.00 | 120.00 | 123.50 | 105.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 118.00 | 100.00 | 60.95 | 40.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 72.00 | 110.00 | 92.33 | 110.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 180.00 | 100.00 | 81.00 | 76.75 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 12.00 | 100.00 | 59.50 | 22.00 |
| ITS0703-370 | | EAST OF EJMT ON I-70 EB LANES | 06/16/11 | 36.00 | 105.00 | 67.52 | 5.25 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 25.00 | 80.00 | 73.33 | 68.00 |
| FSA 0502-064 | | US 50 EAST OF SARGENTS | 06/23/11 | 8.00 | 55.00 | 200.75 | 40.25 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 168.00 | 100.00 | 82.55 | 46.09 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 42.00 | 100.00 | 101.00 | 113.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1,743.00 | 107.53 | 114.55 | 98.39 |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 72.00 | 120.00 | 276.41 | 220.00 |
| C006A-051 | | US 6 (LOVELAND PASS), CLEAR C | 07/14/11 | 12.00 | 85.00 | 70.14 | 5.55 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 21.00 | 70.00 | 155.94 | 100.00 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 40.00 | 130.00 | 67.32 | 59.37 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 239.00 | 75.00 | 58.46 | 33.20 |
| NH2872-018 | | US 287 RUSH CREEK NORTH | 07/21/11 | 20.00 | 110.00 | 100.73 | 120.00 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 20.00 | 70.00 | 84.67 | 118.00 |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 10.00 | 60.00 | 32.94 | 60.00 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 52.00 | 100.00 | 206.95 | 75.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 175.00 | 100.00 | 95.79 | 95.00 |
| NH0403-053 | | US 40 RETAINING WALL REPAIR | 07/28/11 | 14.00 | 200.00 | 88.75 | 86.25 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 50.00 | 120.00 | 95.05 | 83.60 |
| BR2706-036 | | I-270 BRIDGE DECK REHABILITAT | 08/11/11 | 15.00 | 100.00 | 134.00 | 124.00 |
| NH5502-070 | | US 550 4 MILES SOUTH OF OURAY | 08/18/11 | 32.00 | 110.00 | 139.95 | 115.00 |
| C0091-038 | | SH 9 MM 81.9 BLUE RIVER EMERG | 08/24/11 | 4.00 | 200.00 | 173.39 | 268.00 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 19.00 | 75.00 | 103.52 | 141.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 14.00 | 85.00 | 80.80 | 75.00 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 10.00 | 130.00 | 273.11 | 320.00 |
| STR096A-040 | | SH 96 MP 193 TO MP 201 | 09/01/11 | 18.00 | 50.00 | 60.14 | 38.42 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 90.00 | 90.00 | 133.38 | 150.00 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 10.00 | 200.00 | 29.67 | 10.00 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 12.00 | 110.00 | 188.55 | 110.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 949.00 | 96.95 | 130.74 | 111.17 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 630-00007 | Traf Ctrl Inspection | | Day | | | |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 70.00 | 100.00 | 78.62 | 73.40 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 126.00 | 100.00 | 73.03 | 74.43 |
| NH0501-060 | | US50 MP 74.0 TO 81, 94.2 TO 1 | 10/20/11 | 24.00 | 100.00 | 119.22 | 75.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 150.00 | 120.00 | 56.93 | 54.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 260.00 | 100.00 | 81.89 | 10.00 |
| SHE0402-081 | | US 40 - MP 113 TO 120 ROUTT C | 10/27/11 | 20.00 | 70.00 | 133.03 | 143.65 |
| SHE025A-013 | | I 25 BETWEEN MP 122 AND MP 12 | 11/03/11 | 20.00 | 120.00 | 78.71 | 50.00 |
| STA0343-033 | | SH 34 ECKLEY | 11/10/11 | 9.00 | 100.00 | 133.67 | 100.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 137.00 | 100.00 | 176.38 | 104.79 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 250.00 | 100.00 | 151.33 | 60.00 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 12.00 | 100.00 | 261.63 | 350.00 |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 40.00 | 200.00 | 167.69 | 5.50 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 20.00 | 80.00 | 106.23 | 110.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 23.00 | 100.00 | 85.38 | 56.00 |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 24.00 | 110.00 | 120.00 | 110.00 |
| MC0504-065 | | US50B FROM MP 318 TO MP 359 | 12/01/11 | 24.00 | 90.00 | 85.67 | 100.00 |
| IM0703-368 | | GEORGETOWN HILL CHUTES 6,7,9, | 12/01/11 | 8.00 | 121.00 | 74.27 | 85.00 |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 45.00 | 100.00 | 114.01 | 110.00 |
| C2854-125 | | US 285, ASPEN PARK TO MORRISO | 12/08/11 | 8.00 | 100.00 | 96.67 | 120.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 80.00 | 75.00 | 48.67 | 41.00 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 27.00 | 125.00 | 60.00 | 57.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 1,377.00 | 103.81 | 108.08 | 62.31 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 6,616.00 | 105.58 | 107.78 | 83.43 |
| ========== | 630-00012 | Traf Ctrl Mgmt | | Day | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 60.00 | 520.00 | 628.42 | 700.00 |
| C0704-225 | | I-70 EAST OF BENNETT | 01/06/11 | 30.00 | 400.00 | 463.50 | 424.00 |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 25.00 | 500.00 | 475.74 | 520.00 |
| ITS4701-121 | | C470 (SANTA FE TO I-25) AND R | 01/20/11 | 70.00 | 550.00 | 532.75 | 564.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 4,000.00 | 500.00 | 342.35 | 1.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 15.00 | 600.00 | 579.43 | 525.00 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 245.00 | 500.00 | 726.90 | 550.00 |
| C0703-363 | | CLEAR CREEK AND JEFFERSON COU | 02/17/11 | 60.00 | 550.00 | 348.92 | 400.00 |
| NH 2852-017 | | US 285 PONCHA PASS SOUTH RESU | 03/03/11 | 30.00 | 450.00 | 552.00 | 540.00 |
| NH 0241-056 | | US 24 BUENA VISTA NORTH | 03/03/11 | 35.00 | 500.00 | 482.54 | 550.00 |
| STA0504-061 | | US 50 M.P.369.9 -M.P.373.2 | 03/03/11 | 40.00 | 400.00 | 471.65 | 447.25 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 630-00012 | Traf Ctrl Mgmt | | Day | | | |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 42.00 | 450.00 | 549.01 | 485.00 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 100.00 | 600.00 | 728.57 | 700.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 600.00 | 500.00 | 614.26 | 632.80 |
| NH 0402-079 | | US40 MP 165.0 - 179.0 GRAND C | 03/31/11 | 60.00 | 525.00 | 578.14 | 449.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 5,412.00 | 501.87 | 497.44 | 376.36 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 85.00 | 550.00 | 577.70 | 550.02 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 50.00 | 400.00 | 519.01 | 460.00 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 150.00 | 500.00 | 492.57 | 399.00 |
| STA0343-032 | | US 34 EAST OF AKRON | 04/07/11 | 6.00 | 400.00 | 466.67 | 150.00 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 80.00 | 500.00 | 486.50 | 463.50 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 90.00 | 500.00 | 542.17 | 481.00 |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 40.00 | 500.00 | 524.15 | 505.00 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 30.00 | 450.00 | 499.90 | 621.00 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 350.00 | 500.00 | 410.06 | 422.45 |
| SHE074A-001 | | SH 74 - EVERGREEN - JEFFERSON | 04/28/11 | 15.00 | 600.00 | 508.33 | 580.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 368.00 | 500.00 | 363.39 | 390.00 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 90.00 | 500.00 | 589.20 | 551.00 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 65.00 | 500.00 | 415.75 | 364.00 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 90.00 | 500.00 | 529.00 | 543.00 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 70.00 | 500.00 | 503.03 | 539.06 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 80.00 | 600.00 | 619.33 | 685.00 |
| C0241-055 | | SH 24 MP 148-152 | 05/26/11 | 16.00 | 450.00 | 551.32 | 435.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 200.00 | 550.00 | 731.66 | 806.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 190.00 | 550.00 | 403.30 | 395.00 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 40.00 | 600.00 | 548.00 | 441.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 295.00 | 500.00 | 375.52 | 150.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 180.00 | 525.00 | 523.00 | 620.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 240.00 | 500.00 | 616.58 | 562.82 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 120.00 | 510.00 | 545.48 | 580.00 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 30.00 | 575.00 | 493.25 | 440.00 |
| ITS0703-370 | | EAST OF EJMT ON I-70 EB LANES | 06/16/11 | 90.00 | 490.00 | 583.67 | 595.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 50.00 | 450.00 | 673.83 | 735.00 |
| FSA 0502-064 | | US 50 EAST OF SARGENTS | 06/23/11 | 20.00 | 500.00 | 533.50 | 402.50 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 359.00 | 500.00 | 430.06 | 321.00 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 140.00 | 450.00 | 567.00 | 534.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 3,629.00 | 507.41 | 481.55 | 466.83 |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 12.00 | 550.00 | 393.51 | 320.00 |
| C006A-051 | | US 6 (LOVELAND PASS), CLEAR C | 07/14/11 | 30.00 | 495.00 | 670.25 | 665.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 630-00012 | Traf Ctrl Mgmt | | Day | | | |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 25.00 | 550.00 | 528.21 | 600.00 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 81.00 | 470.00 | 622.58 | 663.89 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 65.00 | 460.00 | 547.88 | 470.00 |
| NH2872-018 | | US 287 RUSH CREEK NORTH | 07/21/11 | 50.00 | 500.00 | 961.00 | 700.00 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 40.00 | 550.00 | 518.00 | 555.00 |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 25.00 | 400.00 | 439.00 | 480.00 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 130.00 | 500.00 | 549.00 | 600.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 352.00 | 500.00 | 503.25 | 420.00 |
| NH0403-053 | | US 40 RETAINING WALL REPAIR | 07/28/11 | 35.00 | 550.00 | 532.92 | 488.75 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 200.00 | 500.00 | 495.54 | 455.00 |
| BR2706-036 | | I-270 BRIDGE DECK REHABILITAT | 08/11/11 | 29.00 | 550.00 | 654.00 | 566.00 |
| NH5502-070 | | US 550 4 MILES SOUTH OF OURAY | 08/18/11 | 75.00 | 525.00 | 596.75 | 450.00 |
| C0091-038 | | SH 9 MM 81.9 BLUE RIVER EMERG | 08/24/11 | 15.00 | 550.00 | 739.08 | 700.00 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 50.00 | 500.00 | 594.64 | 620.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 34.00 | 460.00 | 459.40 | 420.00 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 30.00 | 500.00 | 359.36 | 310.00 |
| STR096A-040 | | SH 96 MP 193 TO MP 201 | 09/01/11 | 50.00 | 340.00 | 485.71 | 417.13 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 180.00 | 500.00 | 668.42 | 650.00 |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 30.00 | 500.00 | 599.50 | 649.00 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 30.00 | 550.00 | 535.00 | 545.00 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 33.00 | 620.00 | 534.17 | 450.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1,601.00 | 498.81 | 570.15 | 532.94 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 160.00 | 500.00 | 396.74 | 377.47 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 303.00 | 450.00 | 400.59 | 404.04 |
| NH0501-060 | | US50 MP 74.0 TO 81, 94.2 TO 1 | 10/20/11 | 30.00 | 500.00 | 473.13 | 100.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 431.00 | 450.00 | 564.43 | 595.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 500.00 | 550.00 | 694.68 | 50.00 |
| SHE0402-081 | | US 40 - MP 113 TO 120 ROUTT C | 10/27/11 | 70.00 | 500.00 | 552.08 | 552.49 |
| SHE025A-013 | | I 25 BETWEEN MP 122 AND MP 12 | 11/03/11 | 110.00 | 450.00 | 439.51 | 365.00 |
| ITSSW00-928 | | NB I-225 AT MM 2.28 | 11/03/11 | 30.00 | 550.00 | 497.08 | 510.00 |
| STA0343-033 | | SH 34 ECKLEY | 11/10/11 | 8.00 | 400.00 | 673.00 | 650.00 |
| R600-395 | | REGION 6; VARIOUS LOCATIONS | 11/10/11 | 58.00 | 500.00 | 865.20 | 894.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 342.00 | 500.00 | 576.67 | 485.33 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 452.00 | 500.00 | 498.02 | 400.00 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 93.00 | 600.00 | 835.88 | 921.00 |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 80.00 | 500.00 | 875.00 | 880.00 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 45.00 | 550.00 | 462.22 | 450.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 57.00 | 600.00 | 680.13 | 680.00 |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 60.00 | 525.00 | 650.00 | 600.00 |
| MC0504-065 | | US50B FROM MP 318 TO MP 359 | 12/01/11 | 60.00 | 450.00 | 421.67 | 400.00 |
| IM0703-368 | | GEORGETOWN HILL CHUTES 6,7,9, | 12/01/11 | 60.00 | 455.00 | 565.33 | 475.00 |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 90.00 | 500.00 | 603.33 | 520.00 |
| C2854-125 | | US 285, ASPEN PARK TO MORRISO | 12/08/11 | 40.00 | 500.00 | 513.33 | 550.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 630-00012 | Traf Ctrl Mgmt | | Day | | | |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 200.00 | 550.00 | 562.41 | 530.00 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 60.00 | 550.00 | 669.67 | 653.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 3,339.00 | 502.86 | 554.55 | 444.69 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 13,981.00 | 503.19 | 517.79 | 451.19 |
| ========== | 630-00015 | Uniformed Traf Ctrl Coordination | | Hour | | | |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 400.00 | 20.00 | 47.31 | 65.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 150.00 | 15.00 | 14.86 | 5.03 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 550.00 | 18.64 | 38.32 | 48.38 |
| BR2706-036 | | I-270 BRIDGE DECK REHABILITAT | 08/11/11 | 10.00 | 65.00 | 22.25 | 21.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 10.00 | 65.00 | 29.36 | 22.60 |
| R600-395 | | REGION 6; VARIOUS LOCATIONS | 11/10/11 | 15.00 | 20.00 | 9.51 | 10.55 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 15.00 | 20.00 | 9.51 | 10.55 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 575.00 | 19.48 | 34.96 | 41.70 |
| ========== | 630-00020 | Traf Ctrl Vehicle | | Day | | | |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 180.00 | 80.00 | 103.80 | 99.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 180.00 | 80.00 | 103.80 | 99.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 180.00 | 80.00 | 103.80 | 99.00 |
| ========== | 630-00025 | Traf Ctrl Vehicle | | Hour | | | |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 1,500.00 | 15.00 | 14.71 | 10.56 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 450.00 | 20.00 | 10.96 | 5.39 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 1,950.00 | 16.15 | 14.22 | 9.37 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 630-00025 | Traf Ctrl Vehicle | | Hour | | | |
| R600-395 | | REGION 6; VARIOUS LOCATIONS | 11/10/11 | 620.00 | 12.00 | 7.35 | 5.25 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 620.00 | 12.00 | 7.35 | 5.25 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,570.00 | 15.15 | 12.96 | 8.37 |
| ========== | 630-80001 | Flash Beacon (Port) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 32.00 | 700.00 | 831.66 | 750.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 2.00 | 895.00 | 560.71 | 1625.00 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 3.00 | 500.00 | 903.38 | 420.00 |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 4.00 | 500.00 | 323.89 | 311.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 10.00 | 550.00 | 716.57 | 550.26 |
| NH 0402-079 | | US40 MP 165.0 - 179.0 GRAND C | 03/31/11 | 2.00 | 600.00 | 912.57 | 585.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 53.00 | 648.87 | 731.80 | 618.99 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 4.00 | 500.00 | 279.08 | 160.00 |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 4.00 | 550.00 | 149.09 | 100.50 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 6.00 | 925.00 | 794.90 | 792.10 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 6.00 | 700.00 | 699.24 | 530.00 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 4.00 | 550.00 | 623.88 | 551.00 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 8.00 | 800.00 | 499.03 | 520.00 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 8.00 | 800.00 | 400.14 | 53.91 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 2.00 | 400.00 | 494.33 | 950.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 2.00 | 400.00 | 230.33 | 230.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 2.00 | 1000.00 | 160.57 | 160.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 6.00 | 500.00 | 509.71 | 110.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 2.00 | 700.00 | 1084.58 | 1023.31 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 15.00 | 500.00 | 802.57 | 840.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 6.00 | 500.00 | 1483.23 | 2514.27 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 8.00 | 700.00 | 696.00 | 817.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 83.00 | 639.16 | 647.99 | 670.93 |
| NH2872-018 | | US 287 RUSH CREEK NORTH | 07/21/11 | 2.00 | 635.00 | 350.33 | 400.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 630-80001 | Flash Beacon (Port) | | Each | | | |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 4.00 | 500.00 | 1032.58 | 1000.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 6.00 | 800.00 | 640.89 | 735.00 |
| BR2706-036 | | I-270 BRIDGE DECK REHABILITAT | 08/11/11 | 4.00 | 500.00 | 802.75 | 721.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 2.00 | 500.00 | 348.40 | 260.00 |
| STR096A-040 | | SH 96 MP 193 TO MP 201 | 09/01/11 | 2.00 | 635.00 | 1182.19 | 1646.57 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 6.00 | 800.00 | 535.91 | 400.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 26.00 | 659.23 | 647.76 | 673.91 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 2.00 | 350.00 | 910.69 | 993.26 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 6.00 | 300.00 | 1104.72 | 1063.26 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 36.00 | 600.00 | 994.03 | 2000.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 2.00 | 550.00 | 663.29 | 661.81 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 8.00 | 700.00 | 983.66 | 302.89 |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 4.00 | 400.00 | 409.07 | 105.00 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 2.00 | 600.00 | 90.67 | 86.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 60.00 | 560.00 | 930.52 | 1411.75 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 222.00 | 622.43 | 737.86 | 863.91 |
| ========== | 630-80305 | Flagging Station Light | | Each | | | |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 2.00 | 200.00 | 535.33 | 480.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 2.00 | 200.00 | 535.33 | 480.00 |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 4.00 | 200.00 | 283.00 | 236.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 4.00 | 200.00 | 283.00 | 236.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 6.00 | 200.00 | 483.34 | 809.45 |
| ========== | 630-80335 | Barricade (3 M-A) (Temp) | | Each | | | |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 6.00 | 150.00 | 76.99 | 30.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 28.00 | 150.00 | 110.58 | 100.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 630-80335 | Barricade (3 M-A) (Temp) | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 10.00 | 300.00 | 98.71 | 190.00 |
| STA0504-061 | | US 50 M.P.369.9 -M.P.373.2 | 03/03/11 | 4.00 | 150.00 | 19.81 | 10.65 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 2.00 | 90.00 | 266.60 | 300.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 20.00 | 110.00 | 116.79 | 110.06 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 70.00 | 158.29 | 103.60 | 92.54 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 12.00 | 100.00 | 66.39 | 50.00 |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 6.00 | 100.00 | 41.01 | 40.20 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 8.00 | 150.00 | 118.88 | 110.00 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 8.00 | 100.00 | 115.79 | 110.00 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 8.00 | 150.00 | 74.16 | 53.91 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 2.00 | 300.00 | 107.24 | 106.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 2.00 | 100.00 | 116.38 | 110.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 6.00 | 150.00 | 108.46 | 102.33 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 4.00 | 60.00 | 177.48 | 105.00 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 3.00 | 100.00 | 58.13 | 54.50 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 2.00 | 150.00 | 143.08 | 201.14 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 61.00 | 123.61 | 94.88 | 85.30 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 2.00 | 95.00 | 75.91 | 55.30 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 13.00 | 150.00 | 82.45 | 185.00 |
| NH0403-053 | | US 40 RETAINING WALL REPAIR | 07/28/11 | 20.00 | 300.00 | 62.08 | 86.25 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 6.00 | 180.00 | 145.22 | 160.00 |
| BR2706-036 | | I-270 BRIDGE DECK REHABILITAT | 08/11/11 | 20.00 | 100.00 | 24.00 | 21.00 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 2.00 | 200.00 | 204.59 | 100.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 63.00 | 184.44 | 77.19 | 91.70 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 30.00 | 150.00 | 132.29 | 87.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 23.00 | 120.00 | 100.69 | 100.00 |
| SHE025A-013 | | I 25 BETWEEN MP 122 AND MP 12 | 11/03/11 | 8.00 | 95.00 | 101.32 | 17.00 |
| R600-395 | | REGION 6; VARIOUS LOCATIONS | 11/10/11 | 3.00 | 100.00 | 28.94 | 3.20 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 8.00 | 110.00 | 125.33 | 220.60 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 10.00 | 150.00 | 175.78 | 100.96 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 1.00 | 130.00 | 166.63 | 56.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 630-80335 | Barricade (3 M-A) (Temp) | | Each | | | |
| IM0703-368 | | GEORGETOWN HILL CHUTES 6,7,9, | 12/01/11 | 2.00 | 97.16 | 52.00 | 50.00 |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 4.00 | 180.00 | 87.06 | 10.25 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 89.00 | 131.96 | 123.28 | 90.19 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 283.00 | 148.35 | 103.54 | 90.03 |
| ========== | 630-80336 | Barricade (3 M-B) (Temp) | | Each | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 5.00 | 120.00 | 72.13 | 88.00 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 4.00 | 225.00 | 125.59 | 160.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 9.00 | 166.67 | 112.49 | 220.00 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 2.00 | 150.00 | 230.33 | 264.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 15.00 | 200.00 | 166.06 | 201.14 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 17.00 | 194.12 | 155.23 | 297.61 |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 8.00 | 200.00 | 235.40 | 210.00 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 8.00 | 350.00 | 175.96 | 60.00 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 3.00 | 160.00 | 117.21 | 82.95 |
| NH2872-018 | | US 287 RUSH CREEK NORTH | 07/21/11 | 2.00 | 120.00 | 111.92 | 150.00 |
| C0091-038 | | SH 9 MM 81.9 BLUE RIVER EMERG | 08/24/11 | 4.00 | 200.00 | 360.37 | 478.00 |
| STR096A-040 | | SH 96 MP 193 TO MP 201 | 09/01/11 | 2.00 | 120.00 | 64.65 | 21.95 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 27.00 | 228.15 | 179.45 | 161.01 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 3.00 | 300.00 | 148.09 | 110.36 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 7.00 | 135.00 | 192.83 | 186.07 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 10.00 | 184.50 | 174.63 | 163.36 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 63.00 | 203.25 | 159.78 | 212.84 |
| ========== | 630-80337 | Barricade (3 M-C) (Temp) | | Each | | | |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 1.00 | 1000.00 | 61.30 | 55.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1.00 | 1000.00 | 61.30 | 55.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 1000.00 | 193.28 | 431.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 630-80338 | Barricade (3 M-D) (Temp) | | Each | | | |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 1.00 | 600.00 | 175.40 | 105.61 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1.00 | 600.00 | 126.64 | 121.18 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 600.00 | 126.64 | 121.18 |
| ========== | 630-80341 | Const Traf Sign (A) | | Each | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 34.00 | 25.00 | 17.91 | 23.50 |
| C0704-225 | | I-70 EAST OF BENNETT | 01/06/11 | 6.00 | 40.00 | 23.05 | 21.20 |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 78.00 | 50.00 | 25.77 | 30.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 444.00 | 50.00 | 86.72 | 100.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 11.00 | 50.00 | 36.43 | 56.00 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 10.00 | 40.00 | 35.66 | 42.00 |
| C0703-363 | | CLEAR CREEK AND JEFFERSON COU | 02/17/11 | 4.00 | 50.00 | 10.33 | 9.00 |
| NH 2852-017 | | US 285 PONCHA PASS SOUTH RESU | 03/03/11 | 23.00 | 15.00 | 16.02 | 5.15 |
| NH 0241-056 | | US 24 BUENA VISTA NORTH | 03/03/11 | 72.00 | 40.00 | 38.00 | 38.00 |
| STA0504-061 | | US 50 M.P.369.9 -M.P.373.2 | 03/03/11 | 32.00 | 50.00 | 28.15 | 31.95 |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 24.00 | 35.00 | 49.08 | 8.30 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 24.00 | 20.00 | 40.86 | 40.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 100.00 | 60.00 | 78.27 | 82.53 |
| NH 0402-079 | | US40 MP 165.0 - 179.0 GRAND C | 03/31/11 | 49.00 | 50.00 | 36.39 | 32.60 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 911.00 | 47.13 | 53.37 | 49.75 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 24.00 | 15.00 | 30.04 | 15.00 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 34.00 | 40.00 | 19.22 | 33.00 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 86.00 | 55.00 | 40.55 | 40.00 |
| STA0343-032 | | US 34 EAST OF AKRON | 04/07/11 | 38.00 | 40.00 | 36.67 | 20.00 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 24.00 | 30.00 | 32.67 | 31.00 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 22.00 | 30.00 | 27.08 | 10.50 |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 72.00 | 50.00 | 36.57 | 40.20 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 2.00 | 50.00 | 30.70 | 29.60 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 18.00 | 50.00 | 60.32 | 68.65 |
| SHE074A-001 | | SH 74 - EVERGREEN - JEFFERSON | 04/28/11 | 4.00 | 30.00 | 19.50 | 13.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 66.00 | 50.00 | 74.81 | 79.00 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 46.00 | 50.00 | 69.44 | 66.00 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 44.00 | 50.00 | 35.15 | 31.20 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 630-80341 | Const Traf Sign (A) | | Each | | | |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 40.00 | 30.00 | 15.50 | 16.00 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 34.00 | 50.00 | 32.49 | 10.78 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 35.00 | 45.00 | 45.10 | 50.00 |
| C0241-055 | | SH 24 MP 148-152 | 05/26/11 | 16.00 | 40.00 | 19.35 | 17.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 36.00 | 100.00 | 28.76 | 29.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 27.00 | 70.00 | 21.30 | 21.00 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 4.00 | 45.00 | 54.75 | 52.50 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 18.00 | 60.00 | 38.12 | 21.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 16.00 | 10.00 | 37.67 | 52.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 104.00 | 50.00 | 53.92 | 51.17 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 20.00 | 45.00 | 66.98 | 63.00 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 6.00 | 50.00 | 24.25 | 28.00 |
| ITS0703-370 | | EAST OF EJMT ON I-70 EB LANES | 06/16/11 | 6.00 | 45.00 | 26.85 | 5.25 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 8.00 | 25.00 | 24.58 | 23.00 |
| FSA 0502-064 | | US 50 EAST OF SARGENTS | 06/23/11 | 6.00 | 10.00 | 26.10 | 27.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 209.00 | 65.00 | 56.43 | 50.29 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 56.00 | 40.00 | 47.50 | 69.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1,121.00 | 50.54 | 42.86 | 41.82 |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 22.00 | 65.00 | 44.05 | 43.00 |
| C006A-051 | | US 6 (LOVELAND PASS), CLEAR C | 07/14/11 | 18.00 | 55.00 | 28.25 | 11.00 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 14.00 | 15.00 | 24.67 | 6.00 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 32.00 | 30.00 | 27.32 | 21.59 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 22.00 | 35.00 | 44.78 | 33.20 |
| NH2872-018 | | US 287 RUSH CREEK NORTH | 07/21/11 | 12.00 | 52.00 | 110.02 | 175.00 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 5.00 | 7.00 | 34.50 | 39.00 |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 10.00 | 60.00 | 17.74 | 24.00 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 20.00 | 50.00 | 98.25 | 32.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 84.00 | 55.00 | 66.82 | 60.00 |
| NH0403-053 | | US 40 RETAINING WALL REPAIR | 07/28/11 | 3.00 | 35.00 | 21.00 | 23.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 8.00 | 60.00 | 142.78 | 200.00 |
| BR2706-036 | | I-270 BRIDGE DECK REHABILITAT | 08/11/11 | 78.00 | 55.00 | 22.75 | 21.00 |
| NH5502-070 | | US 550 4 MILES SOUTH OF OURAY | 08/18/11 | 14.00 | 10.00 | 45.49 | 45.00 |
| C0091-038 | | SH 9 MM 81.9 BLUE RIVER EMERG | 08/24/11 | 2.00 | 35.00 | 51.41 | 55.00 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 10.00 | 15.00 | 28.41 | 51.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 5.00 | 40.00 | 28.90 | 26.00 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 21.00 | 40.00 | 16.90 | 11.00 |
| STR096A-040 | | SH 96 MP 193 TO MP 201 | 09/01/11 | 14.00 | 50.00 | 18.16 | 5.49 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 41.00 | 30.00 | 37.23 | 20.00 |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 24.00 | 20.00 | 5.50 | 6.00 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 4.00 | 60.00 | 18.00 | 11.00 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 6.00 | 50.00 | 22.50 | 10.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 469.00 | 43.63 | 44.38 | 37.43 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 630-80341 | Const Traf Sign (A) | | Each | | | |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 22.00 | 500.00 | 40.67 | 49.66 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 4.00 | 35.00 | 21.66 | 37.21 |
| NH0501-060 | | US50 MP 74.0 TO 81, 94.2 TO 1 | 10/20/11 | 54.00 | 50.00 | 17.32 | 15.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 42.00 | 36.00 | 86.71 | 87.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 250.00 | 60.00 | 71.46 | 100.00 |
| SHE0402-081 | | US 40 - MP 113 TO 120 ROUTT C | 10/27/11 | 6.00 | 55.00 | 14.38 | 5.53 |
| SHE025A-013 | | I 25 BETWEEN MP 122 AND MP 12 | 11/03/11 | 15.00 | 33.00 | 24.45 | 12.00 |
| STA0343-033 | | SH 34 ECKLEY | 11/10/11 | 46.00 | 20.00 | 27.75 | 25.00 |
| R600-395 | | REGION 6; VARIOUS LOCATIONS | 11/10/11 | 24.00 | 55.00 | 24.46 | 10.30 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 138.00 | 65.00 | 28.46 | 38.61 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 80.00 | 50.00 | 45.47 | 25.24 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 8.00 | 30.00 | 31.95 | 34.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 8.00 | 25.00 | 16.88 | 11.00 |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 14.00 | 10.00 | 50.00 | 50.00 |
| MC0504-065 | | US50B FROM MP 318 TO MP 359 | 12/01/11 | 12.00 | 50.00 | 27.00 | 45.00 |
| IM0703-368 | | GEORGETOWN HILL CHUTES 6,7,9, | 12/01/11 | 14.00 | 33.00 | 10.73 | 11.00 |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 16.00 | 55.00 | 46.31 | 10.50 |
| C2854-125 | | US 285, ASPEN PARK TO MORRISO | 12/08/11 | 4.00 | 50.00 | 20.33 | 12.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 58.00 | 20.00 | 16.22 | 11.00 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 67.00 | 60.00 | 12.67 | 11.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 882.00 | 61.55 | 40.85 | 47.05 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3,383.00 | 51.53 | 45.05 | 44.23 |
| ========== | 630-80342 | Const Traf Sign (B) | | Each | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 19.00 | 30.00 | 17.91 | 23.50 |
| C0704-225 | | I-70 EAST OF BENNETT | 01/06/11 | 18.00 | 50.00 | 24.38 | 26.50 |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 70.00 | 60.00 | 30.11 | 30.00 |
| ITS4701-121 | | C470 (SANTA FE TO I-25) AND R | 01/20/11 | 28.00 | 60.00 | 24.00 | 10.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 188.00 | 60.00 | 94.17 | 140.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 24.00 | 60.00 | 79.29 | 100.00 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 28.00 | 60.00 | 94.36 | 160.00 |
| C0703-363 | | CLEAR CREEK AND JEFFERSON COU | 02/17/11 | 32.00 | 50.00 | 13.17 | 11.00 |
| NH 2852-017 | | US 285 PONCHA PASS SOUTH RESU | 03/03/11 | 52.00 | 20.00 | 18.60 | 5.15 |
| NH 0241-056 | | US 24 BUENA VISTA NORTH | 03/03/11 | 48.00 | 50.00 | 43.17 | 43.00 |
| STA0504-061 | | US 50 M.P.369.9 -M.P.373.2 | 03/03/11 | 42.00 | 60.00 | 36.76 | 42.60 |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 74.00 | 45.00 | 40.37 | 20.70 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 630-80342 | Const Traf Sign (B) | | Each | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 90.00 | 30.00 | 48.53 | 50.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 140.00 | 70.00 | 86.39 | 82.53 |
| NH 0402-079 | | US40 MP 165.0 - 179.0 GRAND C | 03/31/11 | 74.00 | 55.00 | 52.22 | 45.30 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 927.00 | 53.09 | 56.48 | 52.41 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 80.00 | 30.00 | 35.02 | 20.00 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 64.00 | 40.00 | 29.46 | 58.00 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 72.00 | 65.00 | 36.89 | 30.00 |
| STA0343-032 | | US 34 EAST OF AKRON | 04/07/11 | 66.00 | 50.00 | 50.00 | 35.00 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 133.00 | 35.00 | 37.80 | 36.00 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 38.00 | 35.00 | 30.04 | 10.50 |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 74.00 | 50.00 | 38.35 | 40.20 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 22.00 | 55.00 | 41.82 | 47.30 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 40.00 | 60.00 | 70.32 | 68.65 |
| SHE074A-001 | | SH 74 - EVERGREEN - JEFFERSON | 04/28/11 | 32.00 | 35.00 | 33.42 | 33.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 86.00 | 60.00 | 81.48 | 79.00 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 58.00 | 60.00 | 69.44 | 66.00 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 54.00 | 60.00 | 37.86 | 31.20 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 140.00 | 35.00 | 25.50 | 26.00 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 84.00 | 60.00 | 35.07 | 10.78 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 86.00 | 45.00 | 46.10 | 53.00 |
| C0241-055 | | SH 24 MP 148-152 | 05/26/11 | 30.00 | 40.00 | 32.47 | 46.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 81.00 | 110.00 | 28.76 | 29.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 7.00 | 80.00 | 21.30 | 21.00 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 42.00 | 50.00 | 45.88 | 57.75 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 36.00 | 60.00 | 50.98 | 21.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 68.00 | 20.00 | 42.67 | 62.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 74.00 | 60.00 | 81.00 | 76.75 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 128.00 | 50.00 | 72.97 | 63.00 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 28.00 | 55.00 | 36.00 | 28.00 |
| ITS0703-370 | | EAST OF EJMT ON I-70 EB LANES | 06/16/11 | 18.00 | 60.00 | 29.18 | 5.25 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 30.00 | 25.00 | 26.42 | 23.00 |
| FSA 0502-064 | | US 50 EAST OF SARGENTS | 06/23/11 | 21.00 | 15.00 | 24.60 | 16.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 76.00 | 75.00 | 142.23 | 251.43 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 54.00 | 50.00 | 56.25 | 81.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1,822.00 | 50.64 | 49.80 | 49.60 |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 12.00 | 75.00 | 49.30 | 48.00 |
| C006A-051 | | US 6 (LOVELAND PASS), CLEAR C | 07/14/11 | 12.00 | 65.00 | 32.00 | 11.00 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 43.00 | 20.00 | 26.29 | 6.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 630-80342 | Const Traf Sign (B) | | Each | | | |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 112.00 | 45.00 | 33.02 | 21.59 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 34.00 | 40.00 | 72.78 | 55.30 |
| NH2872-018 | | US 287 RUSH CREEK NORTH | 07/21/11 | 32.00 | 55.00 | 146.15 | 230.00 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 14.00 | 10.00 | 38.67 | 46.00 |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 20.00 | 60.00 | 29.20 | 36.00 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 40.00 | 60.00 | 117.75 | 32.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 49.00 | 65.00 | 79.32 | 160.00 |
| NH0403-053 | | US 40 RETAINING WALL REPAIR | 07/28/11 | 17.00 | 45.00 | 21.67 | 23.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 30.00 | 70.00 | 154.04 | 205.00 |
| BR2706-036 | | I-270 BRIDGE DECK REHABILITAT | 08/11/11 | 97.00 | 65.00 | 24.00 | 21.00 |
| NH5502-070 | | US 550 4 MILES SOUTH OF OURAY | 08/18/11 | 38.00 | 20.00 | 54.72 | 55.00 |
| C0091-038 | | SH 9 MM 81.9 BLUE RIVER EMERG | 08/24/11 | 22.00 | 45.00 | 55.07 | 44.00 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 46.00 | 20.00 | 36.48 | 57.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 44.00 | 50.00 | 40.60 | 37.00 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 60.00 | 50.00 | 20.65 | 11.00 |
| STR096A-040 | | SH 96 MP 193 TO MP 201 | 09/01/11 | 73.00 | 55.00 | 21.50 | 5.49 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 80.00 | 33.00 | 49.07 | 30.00 |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 59.00 | 30.00 | 23.00 | 24.00 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 21.00 | 60.00 | 22.00 | 11.00 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 17.00 | 55.00 | 26.02 | 10.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 972.00 | 46.59 | 51.69 | 49.61 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 11.00 | 300.00 | 86.20 | 110.36 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 36.00 | 75.00 | 83.55 | 79.74 |
| NH0501-060 | | US50 MP 74.0 TO 81, 94.2 TO 1 | 10/20/11 | 92.00 | 55.00 | 17.32 | 15.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 104.00 | 45.00 | 91.71 | 87.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 118.00 | 70.00 | 81.46 | 140.00 |
| SHE0402-081 | | US 40 - MP 113 TO 120 ROUTT C | 10/27/11 | 20.00 | 60.00 | 13.55 | 5.53 |
| SHE025A-013 | | I 25 BETWEEN MP 122 AND MP 12 | 11/03/11 | 40.00 | 42.00 | 31.59 | 15.00 |
| ITSSW00-928 | | NB I-225 AT MM 2.28 | 11/03/11 | 22.00 | 40.00 | 37.07 | 33.00 |
| STA0343-033 | | SH 34 ECKLEY | 11/10/11 | 52.00 | 35.00 | 24.13 | 28.00 |
| R600-395 | | REGION 6; VARIOUS LOCATIONS | 11/10/11 | 60.00 | 65.00 | 30.93 | 32.65 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 14.00 | 75.00 | 74.31 | 110.30 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 78.00 | 60.00 | 66.15 | 25.24 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 85.00 | 45.00 | 37.77 | 12.00 |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 48.00 | 15.00 | 29.63 | 11.00 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 50.00 | 35.00 | 39.28 | 56.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 83.00 | 27.00 | 19.38 | 11.00 |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 38.00 | 20.00 | 40.00 | 40.00 |
| MC0504-065 | | US50B FROM MP 318 TO MP 359 | 12/01/11 | 58.00 | 60.00 | 39.33 | 55.00 |
| IM0703-368 | | GEORGETOWN HILL CHUTES 6,7,9, | 12/01/11 | 60.00 | 43.00 | 25.40 | 55.00 |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 44.00 | 65.00 | 69.01 | 52.50 |
| C2854-125 | | US 285, ASPEN PARK TO MORRISO | 12/08/11 | 30.00 | 55.00 | 22.67 | 12.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 26.00 | 22.00 | 16.80 | 11.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 630-80342 | Const Traf Sign (B) | | Each | | | |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 47.00 | 80.00 | 12.67 | 11.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1,216.00 | 52.14 | 48.42 | 45.61 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4,937.00 | 50.67 | 51.42 | 49.30 |
| ========== | 630-80343 | Const Traf Sign (C) | | Each | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 6.00 | 35.00 | 17.91 | 23.50 |
| C0704-225 | | I-70 EAST OF BENNETT | 01/06/11 | 13.00 | 60.00 | 27.03 | 37.10 |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 8.00 | 70.00 | 31.11 | 30.00 |
| ITS4701-121 | | C470 (SANTA FE TO I-25) AND R | 01/20/11 | 4.00 | 70.00 | 24.25 | 10.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 104.00 | 70.00 | 102.28 | 200.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 4.00 | 75.00 | 84.29 | 135.00 |
| C0703-363 | | CLEAR CREEK AND JEFFERSON COU | 02/17/11 | 26.00 | 80.00 | 15.83 | 12.00 |
| NH 2852-017 | | US 285 PONCHA PASS SOUTH RESU | 03/03/11 | 8.00 | 25.00 | 29.43 | 21.00 |
| STA0504-061 | | US 50 M.P.369.9 -M.P.373.2 | 03/03/11 | 8.00 | 65.00 | 47.57 | 53.24 |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 8.00 | 45.00 | 46.53 | 29.00 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 70.00 | 40.00 | 68.45 | 70.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 10.00 | 80.00 | 91.02 | 82.53 |
| NH 0402-079 | | US40 MP 165.0 - 179.0 GRAND C | 03/31/11 | 6.00 | 60.00 | 54.02 | 48.40 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 275.00 | 60.11 | 63.24 | 67.23 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 12.00 | 35.00 | 43.18 | 30.00 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 8.00 | 60.00 | 29.46 | 58.00 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 8.00 | 75.00 | 33.57 | 20.00 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 8.00 | 40.00 | 43.08 | 41.25 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 34.00 | 40.00 | 32.67 | 10.50 |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 12.00 | 55.00 | 39.23 | 40.20 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 8.00 | 60.00 | 47.45 | 47.30 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 8.00 | 70.00 | 78.26 | 68.65 |
| SHE074A-001 | | SH 74 - EVERGREEN - JEFFERSON | 04/28/11 | 26.00 | 40.00 | 39.83 | 41.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 31.00 | 70.00 | 88.14 | 79.00 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 12.00 | 70.00 | 69.44 | 66.00 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 16.00 | 70.00 | 39.67 | 31.20 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 14.00 | 70.00 | 35.07 | 10.78 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 8.00 | 45.00 | 47.77 | 58.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 6.00 | 120.00 | 28.76 | 29.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 4.00 | 60.00 | 51.69 | 21.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 630-80343 | Const Traf Sign (C) | | Each | | | |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 4.00 | 25.00 | 51.00 | 72.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 12.00 | 70.00 | 81.00 | 76.75 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 28.00 | 55.00 | 77.55 | 63.00 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 18.00 | 60.00 | 37.50 | 28.00 |
| ITS0703-370 | | EAST OF EJMT ON I-70 EB LANES | 06/16/11 | 13.00 | 75.00 | 31.18 | 5.25 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 8.00 | 30.00 | 28.25 | 23.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 2.00 | 90.00 | 440.33 | 1005.71 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 24.00 | 60.00 | 66.00 | 95.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 324.00 | 57.85 | 53.22 | 45.89 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 16.00 | 25.00 | 33.22 | 6.00 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 7.00 | 50.00 | 78.18 | 55.30 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 8.00 | 12.00 | 42.50 | 52.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 8.00 | 75.00 | 82.45 | 185.00 |
| NH0403-053 | | US 40 RETAINING WALL REPAIR | 07/28/11 | 4.00 | 48.00 | 22.33 | 23.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 16.00 | 100.00 | 161.37 | 210.00 |
| BR2706-036 | | I-270 BRIDGE DECK REHABILITAT | 08/11/11 | 8.00 | 75.00 | 25.25 | 21.00 |
| NH5502-070 | | US 550 4 MILES SOUTH OF OURAY | 08/18/11 | 4.00 | 25.00 | 72.63 | 65.00 |
| C0091-038 | | SH 9 MM 81.9 BLUE RIVER EMERG | 08/24/11 | 4.00 | 48.00 | 57.41 | 50.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 4.00 | 65.00 | 41.60 | 37.00 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 8.00 | 55.00 | 26.90 | 11.00 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 2.00 | 35.00 | 73.85 | 50.00 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 12.00 | 80.00 | 27.00 | 11.00 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 4.00 | 60.00 | 44.13 | 10.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 105.00 | 58.10 | 59.97 | 62.83 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 6.00 | 300.00 | 43.42 | 49.66 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 4.00 | 85.00 | 43.99 | 42.53 |
| NH0501-060 | | US50 MP 74.0 TO 81, 94.2 TO 1 | 10/20/11 | 8.00 | 65.00 | 17.32 | 15.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 18.00 | 51.00 | 95.00 | 87.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 27.00 | 80.00 | 97.48 | 200.00 |
| SHE0402-081 | | US 40 - MP 113 TO 120 ROUTT C | 10/27/11 | 6.00 | 65.00 | 31.05 | 5.53 |
| ITSSW00-928 | | NB I-225 AT MM 2.28 | 11/03/11 | 6.00 | 50.00 | 42.65 | 38.00 |
| R600-395 | | REGION 6; VARIOUS LOCATIONS | 11/10/11 | 8.00 | 75.00 | 29.98 | 22.90 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 10.00 | 85.00 | 66.84 | 165.45 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 18.00 | 70.00 | 85.09 | 25.24 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 28.00 | 50.00 | 40.65 | 12.00 |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 20.00 | 15.00 | 36.63 | 11.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 22.00 | 30.00 | 21.13 | 11.00 |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 4.00 | 25.00 | 75.00 | 70.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 630-80343 | Const Traf Sign (C) | | Each | | | |
| IM0703-368 | | GEORGETOWN HILL CHUTES 6,7,9, | 12/01/11 | 31.00 | 47.00 | 25.40 | 55.00 |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 8.00 | 75.00 | 61.06 | 10.50 |
| C2854-125 | | US 285, ASPEN PARK TO MORRISO | 12/08/11 | 4.00 | 60.00 | 27.67 | 12.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 6.00 | 30.00 | 19.13 | 11.00 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 26.00 | 100.00 | 12.67 | 11.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 260.00 | 64.13 | 53.59 | 51.44 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 964.00 | 60.22 | 56.99 | 54.32 |
| ========== | 630-80344 | Const Traf Sign (Spec) | | Sq Foot | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 114.00 | 20.00 | 13.33 | 14.00 |
| C0704-225 | | I-70 EAST OF BENNETT | 01/06/11 | 28.00 | 10.00 | 15.50 | 12.99 |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 200.00 | 18.00 | 15.90 | 16.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 1,608.00 | 18.00 | 28.17 | 20.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 828.00 | 20.00 | 11.40 | 21.00 |
| C0703-363 | | CLEAR CREEK AND JEFFERSON COU | 02/17/11 | 55.00 | 15.00 | 16.50 | 22.00 |
| STA0504-061 | | US 50 M.P.369.9 -M.P.373.2 | 03/03/11 | 154.00 | 19.00 | 9.50 | 8.52 |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 935.00 | 15.00 | 14.94 | 12.45 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 1,900.00 | 20.00 | 21.64 | 22.01 |
| NH 0402-079 | | US40 MP 165.0 - 179.0 GRAND C | 03/31/11 | 173.00 | 21.00 | 17.86 | 16.50 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 5,995.00 | 18.53 | 18.17 | 17.59 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 200.00 | 18.00 | 16.64 | 16.00 |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 200.00 | 20.00 | 20.46 | 20.10 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 55.00 | 20.00 | 21.02 | 29.60 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 54.50 | 20.00 | 22.39 | 26.40 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 49.00 | 20.00 | 19.23 | 19.00 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 92.00 | 20.00 | 23.18 | 22.00 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 160.00 | 20.00 | 18.07 | 18.70 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 128.00 | 20.00 | 18.86 | 16.17 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 83.00 | 55.00 | 17.67 | 21.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 30.00 | 20.00 | 16.84 | 17.00 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 32.00 | 15.00 | 19.00 | 21.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 109.00 | 20.00 | 19.27 | 16.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 210.00 | 20.00 | 26.96 | 25.58 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 27.25 | 20.00 | 22.88 | 22.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 55.00 | 20.00 | 17.42 | 17.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 630-80344 | Const Traf Sign (Spec) | | Sq Foot | | | |
| FSA 0502-064 | | US 50 EAST OF SARGENTS | 06/23/11 | 2.00 | 20.00 | 398.20 | 311.00 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 184.00 | 18.00 | 18.50 | 19.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1,670.75 | 21.18 | 19.15 | 18.40 |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 57.00 | 15.00 | 22.36 | 21.00 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 73.00 | 25.00 | 21.94 | 18.00 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 25.00 | 20.00 | 18.79 | 16.60 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 128.00 | 12.00 | 19.58 | 23.00 |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 50.00 | 20.00 | 14.31 | 20.40 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 278.00 | 20.00 | 21.03 | 22.00 |
| NH0403-053 | | US 40 RETAINING WALL REPAIR | 07/28/11 | 27.25 | 20.00 | 25.67 | 23.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 785.00 | 10.00 | 14.07 | 15.00 |
| BR2706-036 | | I-270 BRIDGE DECK REHABILITAT | 08/11/11 | 64.00 | 22.00 | 17.38 | 15.50 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 33.00 | 25.00 | 21.30 | 21.00 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 4.00 | 200.00 | 246.36 | 320.00 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 40.00 | 30.00 | 15.81 | 14.00 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 54.50 | 10.00 | 20.00 | 20.00 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 80.00 | 25.00 | 17.47 | 18.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1,698.75 | 15.57 | 17.36 | 18.00 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 64.00 | 30.00 | 14.81 | 13.24 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 86.50 | 17.00 | 8.86 | 8.51 |
| SHE025A-013 | | I 25 BETWEEN MP 122 AND MP 12 | 11/03/11 | 72.00 | 15.00 | 10.70 | 6.00 |
| R600-395 | | REGION 6; VARIOUS LOCATIONS | 11/10/11 | 64.00 | 20.00 | 18.34 | 13.70 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 199.00 | 20.00 | 19.93 | 18.75 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 64.00 | 20.00 | 23.86 | 25.24 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 50.00 | 20.00 | 16.32 | 14.00 |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 687.00 | 20.00 | 11.97 | 13.50 |
| C2854-125 | | US 285, ASPEN PARK TO MORRISO | 12/08/11 | 54.50 | 20.00 | 14.67 | 12.00 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 192.00 | 20.00 | 18.33 | 17.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1,533.00 | 20.01 | 15.02 | 14.44 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 10,897.50 | 18.68 | 17.90 | 17.47 |
| ========== | 630-80348 | Const Info Sign | | Each | | | |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 2.00 | 2300.00 | 440.48 | 130.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 630-80348 | Const Info Sign | | Each | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 3.00 | 75.00 | 903.60 | 900.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 5.00 | 965.00 | 672.04 | 592.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 4.00 | 200.00 | 126.75 | 112.00 |
| MC0504-065 | | US50B FROM MP 318 TO MP 359 | 12/01/11 | 2.00 | 600.00 | 202.00 | 400.00 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 6.00 | 333.33 | 147.27 | 208.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 11.00 | 620.45 | 631.84 | 380.23 |
| ========== | 630-80350 | Vert Panel | | Each | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 6.00 | 20.00 | 27.80 | 27.51 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 6.00 | 20.00 | 27.80 | 27.51 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 100.00 | 20.00 | 34.33 | 22.00 |
| | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | | 100.00 | 20.00 | 35.74 | 31.40 |
| NH5502-070 | | US 550 4 MILES SOUTH OF OURAY | 08/18/11 | 50.00 | 20.00 | 30.99 | 32.00 |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 220.00 | 15.00 | 13.50 | 14.00 |
| | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | | 270.00 | 15.93 | 17.95 | 17.33 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 376.00 | 17.07 | 27.61 | 23.37 |
| ========== | 630-80351 | Vert Panel (Plastic) | | Each | | | |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 150.00 | 35.00 | 9.78 | 1.10 |
| | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | | 150.00 | 35.00 | 9.78 | 1.10 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 150.00 | 35.00 | 9.78 | 1.10 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 630-80353 | Vert Panel (Light) (F) | | Each | | | |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 50.00 | 45.00 | 12.53 | 1.10 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 50.00 | 45.00 | 12.53 | 1.10 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 50.00 | 45.00 | 12.53 | 1.10 |
| ========== | 630-80354 | Vert Panel (Light) (SB) | | Each | | | |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 10.00 | 20.00 | 17.25 | 18.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 10.00 | 20.00 | 17.25 | 18.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 10.00 | 20.00 | 17.25 | 18.00 |
| ========== | 630-80355 | Port Mesg Panel | | Each | | | |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 2.00 | 3000.00 | 1518.78 | 1300.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 24.00 | 5000.00 | 9124.06 | 8000.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 2.00 | 8000.00 | 3205.71 | 2300.00 |
| C0703-363 | | CLEAR CREEK AND JEFFERSON COU | 02/17/11 | 2.00 | 1500.00 | 3175.17 | 1800.00 |
| NH 2852-017 | | US 285 PONCHA PASS SOUTH RESU | 03/03/11 | 2.00 | 2500.00 | 1895.67 | 620.00 |
| NH 0241-056 | | US 24 BUENA VISTA NORTH | 03/03/11 | 2.00 | 5000.00 | 2125.00 | 3700.00 |
| STA0504-061 | | US 50 M.P.369.9 -M.P.373.2 | 03/03/11 | 2.00 | 5000.00 | 3086.93 | 3194.63 |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 2.00 | 4000.00 | 2724.44 | 3005.00 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 4.00 | 3000.00 | 5623.57 | 6000.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 10.00 | 8000.00 | 9139.76 | 9904.69 |
| NH 0402-079 | | US40 MP 165.0 - 179.0 GRAND C | 03/31/11 | 3.00 | 4000.00 | 4418.43 | 4759.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 55.00 | 5127.27 | 6194.01 | 5665.90 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 2.00 | 5000.00 | 3168.01 | 1000.03 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 2.00 | 3500.00 | 3893.64 | 5200.00 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 4.00 | 4000.00 | 3117.73 | 1750.00 |
| STA0343-032 | | US 34 EAST OF AKRON | 04/07/11 | 2.00 | 4000.00 | 2200.00 | 700.00 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 4.00 | 2500.00 | 3255.00 | 3100.00 |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 2.00 | 4000.00 | 1749.40 | 1510.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 630-80355 | Port Mesg Panel | | Each | | | |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 2.00 | 2000.00 | 2173.78 | 3311.00 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 4.00 | 3500.00 | 7375.77 | 7392.90 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 4.00 | 5000.00 | 7507.71 | 7900.00 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 2.00 | 3000.00 | 3245.33 | 3120.00 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 2.00 | 9000.00 | 2315.00 | 2380.00 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 8.00 | 3000.00 | 2674.42 | 2156.26 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 2.00 | 4500.00 | 2994.00 | 4200.00 |
| C0241-055 | | SH 24 MP 148-152 | 05/26/11 | 2.00 | 5000.00 | 1973.83 | 1300.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 2.00 | 8000.00 | 8279.57 | 8650.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 2.00 | 6000.00 | 5340.32 | 5300.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 5.00 | 4000.00 | 5554.84 | 4400.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 2.00 | 5000.00 | 5718.00 | 3600.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 6.00 | 5000.00 | 5952.56 | 5628.22 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 3.00 | 4000.00 | 5933.23 | 5775.00 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 1.00 | 1250.00 | 1353.25 | 1100.00 |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 2.00 | 3500.00 | 3565.67 | 4000.00 |
| FSA 0502-064 | | US 50 EAST OF SARGENTS | 06/23/11 | 2.00 | 4000.00 | 1720.00 | 2205.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 4.00 | 3500.00 | 8023.14 | 6100.00 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 2.00 | 1200.00 | 6614.00 | 9553.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 73.00 | 4063.70 | 3965.02 | 3790.66 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 4.00 | 4050.00 | 3635.70 | 4318.01 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 4.00 | 4000.00 | 8406.67 | 3540.00 |
| NH2872-018 | | US 287 RUSH CREEK NORTH | 07/21/11 | 2.00 | 5800.00 | 5116.83 | 5000.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 4.00 | 10000.00 | 5691.99 | 6300.00 |
| NH0403-053 | | US 40 RETAINING WALL REPAIR | 07/28/11 | 2.00 | 6000.00 | 2743.33 | 2530.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 2.00 | 5000.00 | 3720.96 | 4200.00 |
| BR2706-036 | | I-270 BRIDGE DECK REHABILITAT | 08/11/11 | 12.00 | 3000.00 | 2793.75 | 2575.00 |
| C0091-038 | | SH 9 MM 81.9 BLUE RIVER EMERG | 08/24/11 | 5.00 | 1000.00 | 1564.12 | 1100.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 2.00 | 2750.00 | 1206.00 | 1050.00 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 2.00 | 5000.00 | 2981.03 | 3200.00 |
| STR096A-040 | | SH 96 MP 193 TO MP 201 | 09/01/11 | 2.00 | 5500.00 | 2731.43 | 2744.28 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 4.00 | 7000.00 | 4051.37 | 4000.00 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 2.00 | 2000.00 | 2886.67 | 2700.00 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 2.00 | 5000.00 | 1133.75 | 600.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 49.00 | 4393.88 | 3772.66 | 3109.66 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 2.00 | 5000.00 | 3234.85 | 2427.97 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 2.00 | 7000.00 | 2189.44 | 2126.51 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 4.00 | 5400.00 | 9314.29 | 10000.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 630-80355 | Port Mesg Panel | | Each | | | |
| SHE0402-081 | | US 40 - MP 113 TO 120 ROUTT C | 10/27/11 | 2.00 | 5000.00 | 2931.24 | 2762.45 |
| SHE025A-013 | | I 25 BETWEEN MP 122 AND MP 12 | 11/03/11 | 2.00 | 4000.00 | 5180.41 | 5625.00 |
| STA0343-033 | | SH 34 ECKLEY | 11/10/11 | 2.00 | 1000.00 | 1702.50 | 5000.00 |
| R600-395 | | REGION 6; VARIOUS LOCATIONS | 11/10/11 | 2.00 | 6000.00 | 5090.00 | 5950.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 9.00 | 8000.00 | 4495.08 | 8824.13 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 10.00 | 5000.00 | 5913.03 | 3000.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 3.00 | 2900.00 | 3943.77 | 2800.00 |
| IM0703-368 | | GEORGETOWN HILL CHUTES 6,7,9, | 12/01/11 | 1.00 | 4047.00 | 3266.67 | 4500.00 |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 2.00 | 3100.00 | 2950.41 | 2100.00 |
| C2854-125 | | US 285, ASPEN PARK TO MORRISO | 12/08/11 | 1.00 | 5000.00 | 2066.67 | 1100.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 2.00 | 4000.00 | 7854.28 | 8100.00 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 3.00 | 6000.00 | 5166.67 | 4600.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 47.00 | 5309.51 | 5066.20 | 5041.65 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 224.00 | 4658.47 | 4632.55 | 4231.81 |
| ========== | 630-80356 | Flash Arrow Panel (A Ty) | | Each | | | |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 2.00 | 1000.00 | 32.06 | 31.75 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 2.00 | 3500.00 | 6106.57 | 15085.62 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 4.00 | 2250.00 | 2835.68 | 7558.69 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4.00 | 2250.00 | 2835.68 | 7558.69 |
| ========== | 630-80357 | Flash Arrow Panel (B Ty) | | Each | | | |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 2.00 | 1500.00 | 900.00 | 1600.00 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 2.00 | 1500.00 | 937.50 | 735.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 4.00 | 1500.00 | 979.58 | 1117.14 |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 2.00 | 600.00 | 431.40 | 900.00 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 2.00 | 600.00 | 1436.25 | 214.00 |
| NH0403-053 | | US 40 RETAINING WALL REPAIR | 07/28/11 | 1.00 | 500.00 | 1430.00 | 575.00 |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 2.00 | 200.00 | 285.00 | 295.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 7.00 | 471.43 | 722.50 | 426.40 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 2.00 | 850.00 | 1081.14 | 1100.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 630-80357 | Flash Arrow Panel (B Ty) | | Each | | | |
| C2854-125 | | US 285, ASPEN PARK TO MORRISO | 12/08/11 | 1.00 | 1000.00 | 875.00 | 550.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 3.00 | 900.00 | 1044.76 | 916.67 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 14.00 | 857.14 | 872.69 | 758.29 |
| ========== | 630-80358 | Flash Arrow Panel (C Ty) | | Each | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 2.00 | 800.00 | 1975.68 | 2340.00 |
| C0704-225 | | I-70 EAST OF BENNETT | 01/06/11 | 1.00 | 1000.00 | 374.50 | 583.00 |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 2.00 | 1000.00 | 407.73 | 270.00 |
| ITS4701-121 | | C470 (SANTA FE TO I-25) AND R | 01/20/11 | 2.00 | 1250.00 | 602.25 | 769.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 12.00 | 1250.00 | 1052.58 | 700.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| C0703-363 | | CLEAR CREEK AND JEFFERSON COU | 02/17/11 | 2.00 | 1200.00 | 658.50 | 400.00 |
| STA0504-061 | | US 50 M.P.369.9 -M.P.373.2 | 03/03/11 | 2.00 | 900.00 | 589.99 | 532.44 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 5.00 | 1000.00 | 956.41 | 900.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 10.00 | 2000.00 | 1049.14 | 1100.53 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 38.00 | 1350.00 | 923.59 | 918.49 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 2.00 | 500.00 | 1936.02 | 3000.08 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 4.00 | 750.00 | 501.06 | 930.00 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 4.00 | 800.00 | 377.90 | 100.00 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 2.00 | 1500.00 | 1631.67 | 1545.00 |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 4.00 | 950.00 | 499.28 | 505.00 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 2.00 | 1000.00 | 1587.79 | 1056.13 |
| SHE074A-001 | | SH 74 - EVERGREEN - JEFFERSON | 04/28/11 | 2.00 | 500.00 | 396.67 | 355.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 2.00 | 1250.00 | 1030.14 | 1100.00 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 7.00 | 600.00 | 2971.58 | 1102.00 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 4.00 | 1000.00 | 760.01 | 780.00 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 4.00 | 1000.00 | 1003.22 | 1078.13 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 2.00 | 1000.00 | 2219.37 | 3200.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 4.00 | 1250.00 | 1031.66 | 972.15 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 4.00 | 1100.00 | 1651.20 | 1050.00 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 1.00 | 1000.00 | 446.00 | 330.00 |
| ITS0703-370 | | EAST OF EJMT ON I-70 EB LANES | 06/16/11 | 1.00 | 1250.00 | 3057.67 | 1365.00 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 4.00 | 500.00 | 1939.00 | 2828.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 53.00 | 893.40 | 1288.98 | 1084.20 |
| C006A-051 | | US 6 (LOVELAND PASS), CLEAR C | 07/14/11 | 1.00 | 1200.00 | 634.50 | 11.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 630-80358 | Flash Arrow Panel (C Ty) | | Each | | | |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 2.00 | 1000.00 | 448.53 | 5.40 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 2.00 | 1000.00 | 1582.67 | 830.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 4.00 | 1200.00 | 1020.08 | 900.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 2.00 | 500.00 | 1031.99 | 1045.00 |
| BR2706-036 | | I-270 BRIDGE DECK REHABILITAT | 08/11/11 | 4.00 | 600.00 | 1125.00 | 1030.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 2.00 | 750.00 | 418.00 | 365.00 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 1.00 | 1000.00 | 268.95 | 110.00 |
| STR096A-040 | | SH 96 MP 193 TO MP 201 | 09/01/11 | 2.00 | 925.00 | 1022.57 | 1097.71 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 1.00 | 1500.00 | 346.67 | 215.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 21.00 | 916.67 | 797.15 | 622.90 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 2.00 | 300.00 | 1104.72 | 1063.26 |
| NH0501-060 | | US50 MP 74.0 TO 81, 94.2 TO 1 | 10/20/11 | 2.00 | 1000.00 | 673.39 | 500.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 8.00 | 1000.00 | 1367.48 | 700.00 |
| SHE025A-013 | | I 25 BETWEEN MP 122 AND MP 12 | 11/03/11 | 2.00 | 950.00 | 714.41 | 225.00 |
| ITSSW00-928 | | NB I-225 AT MM 2.28 | 11/03/11 | 2.00 | 700.00 | 694.33 | 525.00 |
| R600-395 | | REGION 6; VARIOUS LOCATIONS | 11/10/11 | 3.00 | 800.00 | 1020.00 | 1880.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 8.00 | 1250.00 | 1873.79 | 1312.52 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 2.00 | 1750.00 | 1914.50 | 1750.00 |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 2.00 | 300.00 | 861.25 | 550.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 2.00 | 700.00 | 529.31 | 6.00 |
| MC0504-065 | | US50B FROM MP 318 TO MP 359 | 12/01/11 | 4.00 | 1100.00 | 482.67 | 600.00 |
| IM0703-368 | | GEORGETOWN HILL CHUTES 6,7,9, | 12/01/11 | 2.00 | 963.00 | 2066.67 | 900.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 2.00 | 1000.00 | 369.50 | 320.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 41.00 | 978.68 | 1220.19 | 873.63 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 153.00 | 1032.85 | 1101.32 | 921.34 |
| ========== | 630-80359 | Port Mesg Panel | | Day | | | |
| ITS4701-121 | | C470 (SANTA FE TO I-25) AND R | 01/20/11 | 3.00 | 90.00 | 135.00 | 192.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 3.00 | 90.00 | 64.25 | 78.70 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 250.00 | 50.00 | 35.50 | 26.00 |
| SHE074A-001 | | SH 74 - EVERGREEN - JEFFERSON | 04/28/11 | 10.00 | 125.00 | 111.67 | 115.00 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 360.00 | 30.00 | 69.44 | 66.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 620.00 | 39.60 | 55.99 | 50.66 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 630-80359 | Port Mesg Panel | | Day | | | |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 250.00 | 100.00 | 80.31 | 59.00 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 70.00 | 55.00 | 86.40 | 36.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 25.00 | 100.00 | 77.45 | 145.00 |
| NH5502-070 | | US 550 4 MILES SOUTH OF OURAY | 08/18/11 | 75.00 | 100.00 | 49.15 | 51.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 420.00 | 92.50 | 78.41 | 58.86 |
| NH0501-060 | | US50 MP 74.0 TO 81, 94.2 TO 1 | 10/20/11 | 220.00 | 100.00 | 46.27 | 1.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 250.00 | 30.00 | 69.01 | 125.00 |
| ITSSW00-928 | | NB I-225 AT MM 2.28 | 11/03/11 | 5.00 | 140.00 | 125.93 | 135.00 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 200.00 | 85.00 | 78.32 | 70.00 |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 80.00 | 30.00 | 90.25 | 77.00 |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 60.00 | 100.00 | 37.50 | 35.00 |
| IM0703-368 | | GEORGETOWN HILL CHUTES 6,7,9, | 12/01/11 | 20.00 | 51.34 | 54.13 | 120.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 835.00 | 67.82 | 63.69 | 68.03 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,878.00 | 64.06 | 64.44 | 61.42 |
| ========== | 630-80360 | Drum Channel Dev | | Each | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 100.00 | 15.00 | 29.50 | 47.00 |
| C0704-225 | | I-70 EAST OF BENNETT | 01/06/11 | 20.00 | 30.00 | 14.52 | 19.08 |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 200.00 | 35.00 | 15.65 | 16.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 1,100.00 | 35.00 | 29.09 | 40.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 50.00 | 50.00 | 30.00 | 48.00 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 50.00 | 30.00 | 37.69 | 48.00 |
| C0703-363 | | CLEAR CREEK AND JEFFERSON COU | 02/17/11 | 100.00 | 30.00 | 8.25 | 18.00 |
| NH 2852-017 | | US 285 PONCHA PASS SOUTH RESU | 03/03/11 | 20.00 | 5.00 | 5.29 | 2.10 |
| STA0504-061 | | US 50 M.P.369.9 -M.P.373.2 | 03/03/11 | 100.00 | 30.00 | 3.12 | 1.60 |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 10.00 | 30.00 | 17.36 | 10.35 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 100.00 | 15.00 | 20.42 | 25.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 600.00 | 40.00 | 30.07 | 27.51 |
| NH 0402-079 | | US40 MP 165.0 - 179.0 GRAND C | 03/31/11 | 50.00 | 20.00 | 24.24 | 21.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 2,500.00 | 33.80 | 25.95 | 27.18 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 630-80360 | Drum Channel Dev | | Each | | | |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 400.00 | 28.00 | 20.87 | 56.00 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 350.00 | 35.00 | 22.46 | 25.00 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 50.00 | 40.00 | 8.83 | 8.25 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 100.00 | 40.00 | 10.96 | 15.50 |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 50.00 | 25.00 | 24.41 | 25.15 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 50.00 | 30.00 | 19.60 | 23.70 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 123.00 | 35.00 | 36.98 | 31.68 |
| SHE074A-001 | | SH 74 - EVERGREEN - JEFFERSON | 04/28/11 | 100.00 | 20.00 | 11.00 | 18.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 200.00 | 30.00 | 25.24 | 21.00 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 175.00 | 30.00 | 23.18 | 22.00 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 175.00 | 35.00 | 20.73 | 20.80 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 50.00 | 60.00 | 15.50 | 16.00 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 350.00 | 35.00 | 21.46 | 21.56 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 400.00 | 35.00 | 17.92 | 11.00 |
| C0241-055 | | SH 24 MP 148-152 | 05/26/11 | 20.00 | 45.00 | 10.57 | 6.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 200.00 | 80.00 | 44.67 | 46.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 100.00 | 45.00 | 21.30 | 21.00 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 50.00 | 15.00 | 21.63 | 26.25 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 212.00 | 35.00 | 41.32 | 42.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 100.00 | 10.00 | 9.67 | 10.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 200.00 | 30.00 | 21.64 | 20.47 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 125.00 | 25.00 | 36.20 | 21.00 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 50.00 | 30.00 | 20.00 | 17.00 |
| ITS0703-370 | | EAST OF EJMT ON I-70 EB LANES | 06/16/11 | 50.00 | 30.00 | 18.40 | 21.00 |
| FSA 0502-064 | | US 50 EAST OF SARGENTS | 06/23/11 | 30.00 | 15.00 | 20.67 | 5.75 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 241.00 | 25.00 | 27.81 | 10.06 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 50.00 | 20.00 | 47.00 | 44.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 4,001.00 | 33.82 | 25.64 | 25.79 |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 10.00 | 40.00 | 13.26 | 5.50 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 10.00 | 30.00 | 25.06 | 36.00 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 150.00 | 24.00 | 32.71 | 32.39 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 25.00 | 25.00 | 29.21 | 16.60 |
| NH2872-018 | | US 287 RUSH CREEK NORTH | 07/21/11 | 50.00 | 27.00 | 32.00 | 45.00 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 30.00 | 20.00 | 22.33 | 19.00 |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 20.00 | 20.00 | 19.07 | 42.00 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 100.00 | 25.00 | 26.24 | 5.35 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 150.00 | 40.00 | 33.86 | 52.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 250.00 | 12.00 | 40.29 | 47.00 |
| BR2706-036 | | I-270 BRIDGE DECK REHABILITAT | 08/11/11 | 150.00 | 30.00 | 22.25 | 21.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 630-80360 | Drum Channel Dev | | Each | | | |
| NH5502-070 | | US 550 4 MILES SOUTH OF OURAY | 08/18/11 | 50.00 | 10.00 | 30.32 | 40.00 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 40.00 | 3.00 | 17.91 | 17.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 100.00 | 36.00 | 28.70 | 26.00 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 50.00 | 22.00 | 26.49 | 27.00 |
| STR096A-040 | | SH 96 MP 193 TO MP 201 | 09/01/11 | 300.00 | 27.00 | 11.41 | 8.23 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 300.00 | 20.00 | 7.97 | 4.00 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 50.00 | 45.00 | 15.33 | 11.00 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 20.00 | 15.00 | 8.72 | 11.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 1,855.00 | 24.39 | 23.17 | 26.15 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 30.00 | 30.00 | 39.49 | 44.14 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 100.00 | 25.00 | 71.51 | 69.11 |
| NH0501-060 | | US50 MP 74.0 TO 81, 94.2 TO 1 | 10/20/11 | 100.00 | 45.00 | 4.61 | 1.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 400.00 | 20.00 | 32.86 | 27.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 84.00 | 40.00 | 28.68 | 30.00 |
| SHE0402-081 | | US 40 - MP 113 TO 120 ROUTT C | 10/27/11 | 50.00 | 25.00 | 9.09 | 11.05 |
| R600-395 | | REGION 6; VARIOUS LOCATIONS | 11/10/11 | 100.00 | 35.00 | 9.53 | 8.15 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 100.00 | 40.00 | 41.04 | 63.97 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 300.00 | 25.00 | 46.21 | 20.19 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 20.00 | 50.00 | 23.28 | 35.00 |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 50.00 | 5.00 | 15.88 | 11.00 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 200.00 | 60.00 | 14.83 | 22.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 80.00 | 21.00 | 33.38 | 34.00 |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 50.00 | 10.00 | 35.00 | 35.00 |
| MC0504-065 | | US50B FROM MP 318 TO MP 359 | 12/01/11 | 100.00 | 25.00 | 26.00 | 25.00 |
| IM0703-368 | | GEORGETOWN HILL CHUTES 6,7,9, | 12/01/11 | 20.00 | 26.07 | 39.53 | 55.00 |
| C2854-125 | | US 285, ASPEN PARK TO MORRISO | 12/08/11 | 50.00 | 30.00 | 9.33 | 12.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 72.00 | 20.00 | 31.80 | 32.00 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 100.00 | 40.00 | 24.67 | 23.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2,006.00 | 30.36 | 33.06 | 27.12 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 10,362.00 | 31.46 | 26.51 | 26.37 |
| ========== | 630-80363 | Drum Channel Dev (Light) (F) | | Each | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 10.00 | 20.00 | 35.81 | 47.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 120.00 | 30.00 | 76.50 | 70.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 6.00 | 50.00 | 102.86 | 72.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 630-80363 | Drum Channel Dev (Light) (F) | | Each | | | |
| NH 2852-017 | | US 285 PONCHA PASS SOUTH RESU | 03/03/11 | 10.00 | 6.00 | 10.61 | 11.00 |
| NH 0241-056 | | US 24 BUENA VISTA NORTH | 03/03/11 | 24.00 | 50.00 | 18.96 | 8.00 |
| STA0504-061 | | US 50 M.P.369.9 -M.P.373.2 | 03/03/11 | 6.00 | 35.00 | 8.02 | 10.65 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 100.00 | 20.00 | 29.76 | 37.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 10.00 | 30.00 | 75.12 | 82.53 |
| NH 0402-079 | | US40 MP 165.0 - 179.0 GRAND C | 03/31/11 | 10.00 | 25.00 | 34.36 | 24.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 296.00 | 27.43 | 43.96 | 40.10 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 10.00 | 55.00 | 11.00 | 10.50 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 24.00 | 55.00 | 12.53 | 15.50 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 4.00 | 50.00 | 68.18 | 79.21 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 20.00 | 30.00 | 67.96 | 69.00 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 4.00 | 30.00 | 74.62 | 67.60 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 10.00 | 45.00 | 21.50 | 11.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 25.00 | 90.00 | 44.67 | 46.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 4.00 | 65.00 | 21.30 | 21.00 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 20.00 | 40.00 | 27.13 | 31.50 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 24.00 | 40.00 | 59.23 | 42.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 25.00 | 15.00 | 23.67 | 30.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 170.00 | 46.38 | 42.11 | 37.82 |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 10.00 | 50.00 | 15.26 | 5.50 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 10.00 | 30.00 | 28.94 | 36.00 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 6.00 | 30.00 | 52.42 | 44.25 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 6.00 | 50.00 | 72.25 | 52.25 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 20.00 | 25.00 | 21.94 | 17.00 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 4.00 | 25.00 | 47.13 | 38.00 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 30.00 | 20.00 | 20.98 | 15.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 86.00 | 28.84 | 31.15 | 33.10 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 26.00 | 40.00 | 44.67 | 49.66 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 10.00 | 25.00 | 71.51 | 69.11 |
| NH0501-060 | | US50 MP 74.0 TO 81, 94.2 TO 1 | 10/20/11 | 10.00 | 50.00 | 4.61 | 1.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 20.00 | 30.00 | 67.71 | 65.00 |
| SHE0402-081 | | US 40 - MP 113 TO 120 ROUTT C | 10/27/11 | 10.00 | 45.00 | 9.09 | 11.05 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 10.00 | 75.00 | 45.82 | 66.18 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 630-80363 | Drum Channel Dev (Light) (F) | | Each | | | |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 20.00 | 60.00 | 23.28 | 35.00 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 25.00 | 45.00 | 24.27 | 28.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 5.00 | 24.00 | 33.38 | 34.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 9.00 | 22.00 | 31.47 | 32.00 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 10.00 | 50.00 | 24.67 | 23.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 155.00 | 43.44 | 40.16 | 39.69 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 707.00 | 35.67 | 40.20 | 37.77 |
| ========== | 630-80364 | Drum Channel Dev (Light) (SB) | | Each | | | |
| STA0504-061 | | US 50 M.P.369.9 -M.P.373.2 | 03/03/11 | 6.00 | 40.00 | 8.02 | 10.65 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 100.00 | 25.00 | 38.92 | 50.00 |
| NH 0402-079 | | US40 MP 165.0 - 179.0 GRAND C | 03/31/11 | 20.00 | 30.00 | 34.57 | 25.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 126.00 | 26.51 | 36.42 | 41.32 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 15.00 | 55.00 | 11.00 | 10.50 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 24.00 | 55.00 | 12.53 | 15.50 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 8.00 | 30.00 | 74.62 | 67.60 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 20.00 | 70.00 | 20.50 | 21.00 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 40.00 | 55.00 | 21.50 | 11.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 50.00 | 90.00 | 44.67 | 46.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 157.00 | 66.78 | 35.05 | 25.62 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 10.00 | 30.00 | 28.94 | 36.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 35.00 | 25.00 | 60.48 | 82.00 |
| BR2706-036 | | I-270 BRIDGE DECK REHABILITAT | 08/11/11 | 50.00 | 25.00 | 23.25 | 21.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 95.00 | 25.53 | 34.46 | 35.03 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 20.00 | 25.00 | 71.51 | 69.11 |
| NH0501-060 | | US50 MP 74.0 TO 81, 94.2 TO 1 | 10/20/11 | 10.00 | 60.00 | 4.61 | 1.00 |
| SHE0402-081 | | US 40 - MP 113 TO 120 ROUTT C | 10/27/11 | 10.00 | 45.00 | 9.26 | 11.05 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 10.00 | 27.00 | 33.38 | 34.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 630-80364 | Drum Channel Dev (Light) (SB) | | Each | | | |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 20.00 | 60.00 | 24.67 | 23.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 70.00 | 43.14 | 34.68 | 32.90 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 448.00 | 43.01 | 35.20 | 32.45 |
| ========== | 630-80367 | Port Traf Speed Monitor | | Each | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 2.00 | 4000.00 | 3778.49 | 4400.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 2.00 | 4000.00 | 3812.76 | 3825.00 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 2.00 | 2000.00 | 1962.02 | 3000.08 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2.00 | 2000.00 | 1682.37 | 1068.70 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4.00 | 3000.00 | 2641.05 | 2171.22 |
| ========== | 630-80370 | Conc Barrier (Temp) | | Lin Foot | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 66,560.00 | 30.04 | 23.59 | 40.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 100.00 | 80.00 | 34.76 | 27.00 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 3,000.00 | 22.00 | 30.26 | 21.00 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 3,500.00 | 40.00 | 36.59 | 8.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 6,000.00 | 30.00 | 26.83 | 17.98 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 79,160.00 | 30.24 | 26.37 | 29.50 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 300.00 | 30.00 | 30.64 | 32.00 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 200.00 | 35.00 | 28.89 | 40.07 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 3,200.00 | 20.00 | 41.05 | 26.30 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 2,200.00 | 25.00 | 37.50 | 39.00 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 6,285.00 | 20.00 | 21.40 | 17.35 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 5,000.00 | 25.00 | 19.15 | 20.00 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 100.00 | 35.00 | 40.84 | 38.50 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 630-80370 | Conc Barrier (Temp) | | Lin Foot | ========== | ========== | ========== |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 200.00 | 25.00 | 39.33 | 18.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 1,200.00 | 35.00 | 24.79 | 28.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 12,404.00 | 18.00 | 14.11 | 13.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 620.00 | 40.00 | 49.33 | 44.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 3,000.00 | 25.00 | 41.11 | 40.93 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 500.00 | 30.00 | 33.00 | 33.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 6,980.00 | 13.00 | 18.64 | 13.69 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 42,189.00 | 20.50 | 22.08 | 20.47 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 3,382.00 | 25.00 | 23.39 | 20.25 |
| NH0403-053 | | US 40 RETAINING WALL REPAIR | 07/28/11 | 350.00 | 30.00 | 34.30 | 37.91 |
| NH5502-070 | | US 550 4 MILES SOUTH OF OURAY | 08/18/11 | 200.00 | 40.00 | 84.61 | 115.00 |
| C0091-038 | | SH 9 MM 81.9 BLUE RIVER EMERG | 08/24/11 | 120.00 | 50.00 | 41.01 | 15.60 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 800.00 | 35.00 | 30.50 | 19.00 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 2,000.00 | 35.00 | 33.38 | 20.00 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 150.00 | 50.00 | 28.33 | 20.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 7,002.00 | 30.64 | 29.27 | 24.32 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 4,280.00 | 30.00 | 20.57 | 20.70 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 5,000.00 | 25.00 | 19.50 | 25.93 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 3,000.00 | 20.00 | 23.71 | 26.00 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 5,430.00 | 25.00 | 22.19 | 30.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 1,790.00 | 30.00 | 28.65 | 19.03 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 7,550.00 | 20.00 | 23.57 | 25.00 |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 300.00 | 50.00 | 70.00 | 80.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 8,000.00 | 25.00 | 27.90 | 29.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 35,350.00 | 24.58 | 24.25 | 26.53 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 163,701.00 | 26.52 | 24.49 | 24.94 |
| ========== | 630-80377 | Port Water Filled Barrier (Temp) | | Lin Foot | ========== | ========== | ========== |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 1,000.00 | 30.00 | 16.27 | 15.50 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 1,000.00 | 30.00 | 16.27 | 15.50 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,000.00 | 30.00 | 16.27 | 15.50 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 630-80378 | Glare Screen (Temp) | | Lin Foot | ========== | ========== | ========== |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 13,600.00 | 13.00 | 14.09 | 15.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 4,600.00 | 13.00 | 11.34 | 5.50 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 18,200.00 | 13.00 | 12.59 | 9.54 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 18,200.00 | 13.00 | 12.59 | 9.54 |
| ========== | 630-80380 | Traffic Cone | | Each | ========== | ========== | ========== |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 25.00 | 15.00 | 11.41 | 18.00 |
| C0704-225 | | I-70 EAST OF BENNETT | 01/06/11 | 100.00 | 8.00 | 5.90 | 5.83 |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 300.00 | 8.00 | 6.64 | 6.00 |
| ITS4701-121 | | C470 (SANTA FE TO I-25) AND R | 01/20/11 | 300.00 | 8.00 | 6.46 | 4.50 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 2,000.00 | 8.00 | 8.24 | 13.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR R100-183 | | US 24 EAST OF LIMON | 01/20/11 | 30.00 | 12.00 | 5.43 | 12.00 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 150.00 | 10.00 | 6.43 | 9.50 |
| C0703-363 | | CLEAR CREEK AND JEFFERSON COU | 02/17/11 | 400.00 | 7.00 | 3.42 | 1.00 |
| NH 2852-017 | | US 285 PONCHA PASS SOUTH RESU | 03/03/11 | 200.00 | 5.00 | 5.93 | 2.00 |
| NH 0241-056 | | US 24 BUENA VISTA NORTH | 03/03/11 | 450.00 | 5.00 | 4.68 | 8.00 |
| STA0504-061 | | US 50 M.P.369.9 -M.P.373.2 | 03/03/11 | 300.00 | 7.00 | 7.50 | 8.52 |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 300.00 | 5.00 | 8.18 | 7.25 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 500.00 | 7.00 | 2.83 | 1.20 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 1,000.00 | 8.00 | 10.85 | 11.00 |
| NH 0402-079 | | US40 MP 165.0 - 179.0 GRAND C | 03/31/11 | 200.00 | 10.00 | 9.51 | 6.50 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 6,255.00 | 7.51 | 7.53 | 7.24 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 200.00 | 8.00 | 6.67 | 6.00 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 500.00 | 8.00 | 7.17 | 7.00 |
| STA0343-032 | | US 34 EAST OF AKRON | 04/07/11 | 500.00 | 15.00 | 7.67 | 3.00 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 500.00 | 5.00 | 8.83 | 8.25 |
| STA 008A-007 | | SH 8 FROM MM 0.00 TO MM 2.031 | 04/21/11 | 400.00 | 8.00 | 5.60 | 5.05 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 50.00 | 10.00 | 6.05 | 8.30 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 500.00 | 8.00 | 6.53 | 5.28 |
| SHE074A-001 | | SH 74 - EVERGREEN - JEFFERSON | 04/28/11 | 200.00 | 3.00 | 5.67 | 9.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 630-80380 | Traffic Cone | | Each | | | |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 500.00 | 8.00 | 8.49 | 8.00 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 500.00 | 8.00 | 11.63 | 11.00 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 500.00 | 8.00 | 7.50 | 7.30 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 250.00 | 3.00 | 2.00 | 2.00 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 500.00 | 8.00 | 7.16 | 5.39 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 500.00 | 12.00 | 3.38 | 8.00 |
| C0241-055 | | SH 24 MP 148-152 | 05/26/11 | 30.00 | 8.00 | 2.86 | 6.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 250.00 | 6.00 | 8.83 | 9.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 300.00 | 10.00 | 1.05 | 1.00 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 100.00 | 10.00 | 7.58 | 9.45 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 600.00 | 8.00 | 4.65 | 1.10 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 300.00 | 4.00 | 5.67 | 6.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 500.00 | 8.00 | 5.39 | 5.12 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 200.00 | 8.00 | 6.77 | 5.25 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 50.00 | 10.00 | 6.13 | 6.00 |
| ITS0703-370 | | EAST OF EJMT ON I-70 EB LANES | 06/16/11 | 150.00 | 9.00 | 7.85 | 5.25 |
| FSA 0502-064 | | US 50 EAST OF SARGENTS | 06/23/11 | 30.00 | 7.00 | 5.73 | 1.15 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 200.00 | 8.00 | 8.80 | 12.60 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 8,310.00 | 8.14 | 6.70 | 6.33 |
| FBR0502-066 | | US50 GUNNISON COUNTY MM 155.3 | 07/14/11 | 25.00 | 12.00 | 6.76 | 5.50 |
| C006A-051 | | US 6 (LOVELAND PASS), CLEAR C | 07/14/11 | 150.00 | 13.00 | 14.00 | 11.00 |
| C 0063-037 | | US 6 MP 93.3 IN GARFIELD COUN | 07/14/11 | 30.00 | 10.00 | 8.47 | 12.00 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 150.00 | 6.00 | 9.62 | 10.80 |
| STA0831-113 | | LINCOLN AVE. TO COTTONWOOD DR | 07/21/11 | 250.00 | 8.00 | 6.49 | 5.55 |
| NH2872-018 | | US 287 RUSH CREEK NORTH | 07/21/11 | 200.00 | 7.25 | 9.59 | 11.00 |
| SHE0063-036 | | US6C & I70B, MESA CO., MAST A | 07/21/11 | 100.00 | 7.00 | 9.05 | 13.00 |
| STM085A-014 | | SH85 AND OHIO IN FOUNTAIN | 07/21/11 | 100.00 | 7.00 | 4.27 | 9.60 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 50.00 | 8.00 | 12.01 | 1.07 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 300.00 | 8.00 | 10.32 | 10.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 1,000.00 | 7.00 | 3.93 | 5.25 |
| BR2706-036 | | I-270 BRIDGE DECK REHABILITAT | 08/11/11 | 450.00 | 8.00 | 3.45 | 3.00 |
| NH5502-070 | | US 550 4 MILES SOUTH OF OURAY | 08/18/11 | 150.00 | 4.00 | 4.18 | 6.00 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 200.00 | 5.00 | 6.79 | 11.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 100.00 | 8.00 | 6.33 | 6.00 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 300.00 | 6.00 | 3.34 | 1.20 |
| STR096A-040 | | SH 96 MP 193 TO MP 201 | 09/01/11 | 500.00 | 7.50 | 2.95 | 1.10 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 150.00 | 8.00 | 2.97 | 1.00 |
| SHE 0350-019 | | DURANGO, CO | 09/15/11 | 50.00 | 5.00 | 11.00 | 2.00 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 100.00 | 10.00 | 2.37 | 1.10 |
| STA 145A-039 | | SH145 AT TROUT LAKE | 09/15/11 | 100.00 | 10.00 | 5.42 | 6.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 4,455.00 | 7.43 | 6.51 | 6.38 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 100.00 | 10.00 | 10.03 | 9.93 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 630-80380 | Traffic Cone | | Each | | | |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 200.00 | 10.00 | 11.05 | 10.63 |
| NH0501-060 | | US50 MP 74.0 TO 81, 94.2 TO 1 | 10/20/11 | 200.00 | 10.00 | 9.37 | 24.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 300.00 | 8.00 | 10.14 | 6.50 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 540.00 | 10.00 | 9.51 | 20.00 |
| SHE0402-081 | | US 40 - MP 113 TO 120 ROUTT C | 10/27/11 | 200.00 | 8.00 | 2.54 | 1.11 |
| SHE025A-013 | | I 25 BETWEEN MP 122 AND MP 12 | 11/03/11 | 220.00 | 5.00 | 3.50 | 1.20 |
| ITSSW00-928 | | NB I-225 AT MM 2.28 | 11/03/11 | 250.00 | 8.00 | 3.14 | 2.15 |
| STA0343-033 | | SH 34 ECKLEY | 11/10/11 | 500.00 | 8.00 | 4.38 | 1.00 |
| R600-395 | | REGION 6; VARIOUS LOCATIONS | 11/10/11 | 500.00 | 8.00 | 3.09 | 3.45 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 150.00 | 8.00 | 8.34 | 17.65 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 450.00 | 8.00 | 8.02 | 7.07 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 250.00 | 12.00 | 5.89 | 6.00 |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 50.00 | 4.00 | 14.13 | 11.00 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 100.00 | 5.00 | 5.54 | 6.00 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 100.00 | 7.00 | 4.93 | 5.00 |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 150.00 | 4.00 | 6.00 | 6.00 |
| MC0504-065 | | US50B FROM MP 318 TO MP 359 | 12/01/11 | 300.00 | 7.00 | 4.17 | 8.00 |
| IM0703-368 | | GEORGETOWN HILL CHUTES 6,7,9, | 12/01/11 | 300.00 | 6.54 | 2.25 | 2.50 |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 600.00 | 10.00 | 9.15 | 5.25 |
| C2854-125 | | US 285, ASPEN PARK TO MORRISO | 12/08/11 | 200.00 | 8.00 | 2.07 | 4.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 300.00 | 20.00 | 2.04 | 1.10 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 200.00 | 6.00 | 3.83 | 3.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 6,160.00 | 8.79 | 5.97 | 6.51 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 25,180.00 | 8.02 | 6.70 | 6.57 |
| ========== | 630-80384 | Tubular Marker | | Each | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 80.00 | 17.25 | 23.58 | 30.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 80.00 | 17.25 | 23.58 | 30.00 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 40.00 | 30.00 | 16.68 | 10.50 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 140.00 | 50.00 | 27.31 | 10.06 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 180.00 | 45.56 | 25.98 | 10.16 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 50.00 | 30.00 | 39.33 | 66.18 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 50.00 | 30.00 | 39.33 | 66.18 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 310.00 | 35.74 | 29.17 | 22.95 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 630-80390 | Channel Dev (Spec) | | Each | | | |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 1,000.00 | 12.00 | 48.09 | 60.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1,000.00 | 12.00 | 47.14 | 57.40 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 500.00 | 11.00 | 27.60 | 35.00 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 500.00 | 15.00 | 10.96 | 15.50 |
| C0241-055 | | SH 24 MP 148-152 | 05/26/11 | 160.00 | 15.00 | 14.68 | 6.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 1,160.00 | 13.28 | 18.21 | 22.59 |
| NH0063-039 | | US-6 MM 153.4 TO 158.2 IN EAG | 12/01/11 | 100.00 | 22.00 | 33.28 | 33.60 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 100.00 | 22.00 | 33.28 | 33.60 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,260.00 | 13.10 | 32.89 | 38.89 |
| ========== | 630-80393 | Stackable Vertical Panels | | Each | | | |
| SHEM515-004 | | GEORGETOWN, COLORADO | 06/16/11 | 150.00 | 15.00 | 26.08 | 23.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 150.00 | 15.00 | 25.55 | 23.46 |
| NH0403-053 | | US 40 RETAINING WALL REPAIR | 07/28/11 | 100.00 | 9.00 | 29.67 | 23.00 |
| C0091-038 | | SH 9 MM 81.9 BLUE RIVER EMERG | 08/24/11 | 200.00 | 10.00 | 23.86 | 11.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 300.00 | 9.67 | 25.44 | 15.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 450.00 | 11.44 | 25.50 | 19.09 |
| ========== | 630-80430 | Rumble Strip (Port) | | Each | | | |
| STA0504-061 | | US 50 M.P.369.9 -M.P.373.2 | 03/03/11 | 8.00 | 40.00 | 1338.87 | 1384.34 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 8.00 | 40.00 | 1572.03 | 1528.11 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 630-80430 | Rumble Strip (Port) | | Each | | | |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 36.00 | 500.00 | 975.45 | 470.89 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 36.00 | 500.00 | 975.45 | 470.89 |
| NH2872-018 | | US 287 RUSH CREEK NORTH | 07/21/11 | 8.00 | 1380.00 | 992.00 | 1500.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 8.00 | 1380.00 | 992.00 | 1500.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 52.00 | 564.62 | 1231.67 | 965.10 |
| ========== | 630-80510 | Mobile Pvmt Mkg Zone | | LUMP SUM | | | |
| NH 2852-017 | | US 285 PONCHA PASS SOUTH RESU | 03/03/11 | 1.00 | 2000.00 | 1181.67 | 110.00 |
| NH 0241-056 | | US 24 BUENA VISTA NORTH | 03/03/11 | 1.00 | 600.00 | 1663.33 | 2100.00 |
| STA0362-030 | | US 36, WEST OF WATKINS (@I-70 | 03/10/11 | 1.00 | 1000.00 | 1310.27 | 104.00 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 1.00 | 1100.00 | 3376.49 | 3500.00 |
| NH 0402-079 | | US40 MP 165.0 - 179.0 GRAND C | 03/31/11 | 1.00 | 1500.00 | 2056.14 | 1333.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 5.00 | 1240.00 | 1942.44 | 1429.40 |
| NH 172A-017 | | SH 172 MP 20 TO 24.5 | 05/12/11 | 1.00 | 1200.00 | 2500.00 | 1000.00 |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 1.00 | 2500.00 | 1350.00 | 1600.00 |
| STR131A-034 | | SH131 CHOKE CHERRY SOUTH | 06/09/11 | 1.00 | 4000.00 | 4471.23 | 6200.00 |
| BR R 500-114 | | US 160, US 550 | 06/09/11 | 1.00 | 5000.00 | 26100.00 | 2100.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 4.00 | 3175.00 | 4858.86 | 2780.00 |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 1.00 | 1250.00 | 1460.50 | 1079.51 |
| FSA 140A-001 | | SH 140 S/W OF DURANGO | 08/25/11 | 1.00 | 2000.00 | 5621.39 | 1100.00 |
| FSAC060-060 | | SAFETY IMPROVEMENTS ON US-287 | 08/25/11 | 1.00 | 10000.00 | 2393.56 | 3300.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 3.00 | 4416.67 | 3027.87 | 1826.50 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 1.00 | 1500.00 | 1959.34 | 2126.51 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 630-80510 | Mobile Pvmt Mkg Zone | | LUMP SUM | ========== | ========== | ========== |
| NH0501-060 | | US50 MP 74.0 TO 81, 94.2 TO 1 | 10/20/11 | 1.00 | 3000.00 | 2736.95 | 2500.00 |
| C 1602-129 | | INTERSECTION OF US160 AND ARC | 11/17/11 | 1.00 | 2000.00 | 1264.50 | 1100.00 |
| STAR100-147 | | SH 71 NORTH OF LIMON-NORTH | 12/08/11 | 1.00 | 1500.00 | 1595.09 | 2000.00 |
| NH0402-082 | | US 40 MP 108.100 TO MP 114.10 | 12/22/11 | 1.00 | 4000.00 | 2033.33 | 1100.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 5.00 | 2400.00 | 1969.07 | 1765.30 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 17.00 | 2597.06 | 2859.08 | 1964.06 |
| ========== | 630-80520 | Mobile Pvmt Mkg Zone | | Day | ========== | ========== | ========== |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 5.00 | 400.00 | 899.54 | 950.00 |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 1.00 | 1000.00 | 2488.40 | 530.00 |
| STA0504-061 | | US 50 M.P.369.9 -M.P.373.2 | 03/03/11 | 2.00 | 250.00 | 1624.43 | 692.17 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 8.00 | 437.50 | 1339.31 | 833.04 |
| STA0343-032 | | US 34 EAST OF AKRON | 04/07/11 | 6.00 | 1000.00 | 700.00 | 100.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 6.00 | 1000.00 | 1048.75 | 332.50 |
| NH2872-018 | | US 287 RUSH CREEK NORTH | 07/21/11 | 2.00 | 850.00 | 949.67 | 1100.00 |
| STR096A-040 | | SH 96 MP 193 TO MP 201 | 09/01/11 | 1.00 | 1400.00 | 1675.62 | 2226.87 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 3.00 | 1033.33 | 1094.86 | 1475.62 |
| STA0343-033 | | SH 34 ECKLEY | 11/10/11 | 4.00 | 750.00 | 556.67 | 500.00 |
| MC0504-065 | | US50B FROM MP 318 TO MP 359 | 12/01/11 | 5.00 | 550.00 | 260.00 | 250.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 9.00 | 638.89 | 321.88 | 446.67 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 26.00 | 705.77 | 824.39 | 601.51 |
| ========== | 630-80560 | Mobile Profilograph Oper Zone | | LUMP SUM | ========== | ========== | ========== |
| STA 0911-005 | | SH 91 COPPER MOUNTAIN TO COUN | 05/26/11 | 1.00 | 1500.00 | 900.00 | 1100.00 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 1.00 | 1500.00 | 900.00 | 1100.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 1500.00 | 900.00 | 1100.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 630-80570 | Mobile Profilograph Oper Zone | | Day | | | |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 2.00 | 800.00 | 1191.44 | 1655.43 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 800.00 | 1191.44 | 1655.43 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 800.00 | 1191.44 | 1655.43 |
| ========== | 630-85006 | Impact Atten (Sand Fill) (Temp) | | Each | | | |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 8.00 | 2000.00 | 1810.17 | 2231.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 8.00 | 2000.00 | 3639.23 | 4100.00 |
| NH5502-058 | | US 550B: RIDGWAY TO COLONA PA | 06/16/11 | 4.00 | 2000.00 | 3933.33 | 1800.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 20.00 | 2000.00 | 2858.99 | 2892.40 |
| C006A-051 | | US 6 (LOVELAND PASS), CLEAR C | 07/14/11 | 2.00 | 2500.00 | 2825.00 | 2550.00 |
| NH5502-070 | | US 550 4 MILES SOUTH OF OURAY | 08/18/11 | 2.00 | 3000.00 | 1732.75 | 2000.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 2.00 | 2000.00 | 1476.00 | 1050.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 6.00 | 2500.00 | 1989.85 | 1866.67 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 4.00 | 2500.00 | 5096.62 | 11914.00 |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 2.00 | 3000.00 | 1200.00 | 1100.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 6.00 | 2666.67 | 4447.18 | 8309.33 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 32.00 | 2218.75 | 2942.22 | 3552.00 |
| ========== | 630-85010 | Impact Atten (Temp) | | Each | | | |
| SHE0131-056 | | SH 13 & RAILROAD AVE MP 2-3 R | 01/06/11 | 2.00 | 3000.00 | 1844.89 | 1755.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 120.00 | 3000.00 | 2433.58 | 2500.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 2.00 | 3500.00 | 5881.98 | 7100.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 5.00 | 4500.00 | 4463.68 | 3301.57 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 129.00 | 3065.89 | 2840.05 | 2800.46 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 630-85010 | Impact Atten (Temp) | | Each | | | |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 2.00 | 6000.00 | 2236.99 | 2000.00 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 1.00 | 5000.00 | 4211.57 | 3696.45 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 2.00 | 3000.00 | 18701.84 | 18400.00 |
| NH0404-049 | | COLFAX AVE.: SABLE TO AIRPORT | 05/12/11 | 2.00 | 1500.00 | 2520.54 | 3433.00 |
| FBR0063-038 | | SH 6 IN EAGLE | 06/09/11 | 2.00 | 3000.00 | 2201.56 | 2118.00 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 12.00 | 2500.00 | 1867.82 | 850.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 6.00 | 3000.00 | 2486.91 | 2353.62 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 2.00 | 2800.00 | 2810.00 | 2730.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 11.00 | 3000.00 | 4162.32 | 2011.42 |
| | | WEIGHTED AVERAGE FOR THE SECOND QUARTER | | 40.00 | 2965.00 | 3680.19 | 2643.86 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 19.00 | 3000.00 | 1597.44 | 1900.00 |
| NH0403-053 | | US 40 RETAINING WALL REPAIR | 07/28/11 | 2.00 | 5000.00 | 3291.67 | 2875.00 |
| STA0131-058 | | SH 13 RIO BLANCO COUNTY ROAD | 09/08/11 | 4.00 | 2000.00 | 2507.20 | 750.00 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 25.00 | 3000.00 | 2022.01 | 2097.16 |
| FBR0243-081 | | SH 24 EAST, NEAR PEYTON, EL P | 10/06/11 | 4.00 | 3000.00 | 1818.53 | 1655.43 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 6.00 | 2000.00 | 1585.07 | 1594.88 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 2.00 | 2000.00 | 3524.91 | 4700.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 8.00 | 4500.00 | 1398.57 | 2134.52 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 4.00 | 3000.00 | 3508.03 | 3028.88 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 6.00 | 20.00 | 1698.08 | 1600.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 30.00 | 2537.33 | 1984.76 | 2146.09 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 224.00 | 2969.73 | 2683.13 | 2463.63 |
| ========== | 630-85020 | Mobile Attenuator | | Each | | | |
| STA 052A-033 | | SH 52 FROM SH 119 TO SH 287 | 07/14/11 | 2.00 | 10000.00 | 4571.30 | 53.98 |
| | | WEIGHTED AVERAGE FOR THE THIRD QUARTER | | 2.00 | 10000.00 | 4571.30 | 53.98 |
| C2854-125 | | US 285, ASPEN PARK TO MORRISO | 12/08/11 | 1.00 | 5000.00 | 8750.00 | 5500.00 |
| | | WEIGHTED AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 5000.00 | 8750.00 | 5500.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3.00 | 8333.33 | 11659.26 | 6681.59 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 630-85040 | Impact Atten (T-M-A) (Temp) | | Each | | | |
| C0704-225 | | I-70 EAST OF BENNETT | 01/06/11 | 1.00 | 9000.00 | 4310.50 | 5830.00 |
| STA007A-014 | | SH 7 US 287 TO RR EAST EDGE O | 01/13/11 | 1.00 | 6000.00 | 4934.86 | 3100.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 8.00 | 40000.00 | 19906.97 | 8000.00 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| C0703-363 | | CLEAR CREEK AND JEFFERSON COU | 02/17/11 | 1.00 | 19500.00 | 13833.33 | 10000.00 |
| IM0702-303 | | I-70 WEST VAIL PASS MP 170.00 | 03/17/11 | 5.00 | 12000.00 | 7261.64 | 6000.00 |
| BRR600-297 | | I-25 BRIDGE OVER SOUTH PLATTE | 03/24/11 | 2.00 | 12000.00 | 23202.86 | 22010.41 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 18.00 | 24361.11 | 10242.65 | 7502.82 |
| STA 0911-006 | | SH 91 MP 0 TO 12 | 04/07/11 | 2.00 | 7000.00 | 7341.02 | 3500.10 |
| STA0361-095 | | BROOMFIELD COUNTY | 04/07/11 | 2.00 | 3500.00 | 11919.03 | 8200.00 |
| STA 1211-069 | | 500' N. OF 88TH TO 104TH ON S | 04/07/11 | 1.00 | 20000.00 | 10201.47 | 4000.00 |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 2.00 | 15000.00 | 3780.83 | 3600.00 |
| BR0701-207 | | I-70 SKIPPERS ISLAND MULTIPLE | 04/14/11 | 2.00 | 10000.00 | 6125.50 | 5253.00 |
| C086A-050 | | SH 86 & DEERPATH RD. | 04/21/11 | 1.00 | 12000.00 | 6860.55 | 8868.50 |
| FBR0704-220 | | I-70 OVER SAND CREEK | 04/28/11 | 2.00 | 20000.00 | 24088.45 | 26403.20 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 2.00 | 24000.00 | 34424.88 | 37000.00 |
| IM0704-223 | | I-70:HOLLY TO SAND CREEK | 05/12/11 | 4.00 | 5000.00 | 20806.34 | 19843.00 |
| NHR600-376 | | SH 287: FEDERAL TO LAUREL | 05/12/11 | 2.00 | 10000.00 | 18629.91 | 21562.58 |
| FBR 0761-209 | | I-76 OVER S. PLATTE RIVER | 06/16/11 | 2.00 | 15000.00 | 11914.14 | 2900.00 |
| NH093A-008 | | SH93: SH 58 TO SH 128 | 06/16/11 | 2.00 | 15000.00 | 32361.35 | 30699.38 |
| FSA R600-387 | | VARIOUS LOCATIONS IN REGION 6 | 06/16/11 | 3.00 | 10000.00 | 16559.48 | 19950.00 |
| C083A-037 | | SH 83 & PINE DR. | 06/16/11 | 1.00 | 6000.00 | 6855.25 | 5500.00 |
| ITS0703-370 | | EAST OF EJMT ON I-70 EB LANES | 06/16/11 | 1.00 | 10000.00 | 14679.00 | 5250.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 29.00 | 11620.69 | 16258.44 | 14309.44 |
| FSA C110-032 | | SH72 & 48TH; SH121 & CROSS; S | 07/21/11 | 1.00 | 10000.00 | 10706.00 | 5000.00 |
| FBR 2873-160 | | SH 287 (FEDERAL BLVD.) OVER S | 07/28/11 | 2.00 | 25000.00 | 20079.13 | 14500.00 |
| NH C460-002 | | US 40/287 @ KIT CARSON | 08/11/11 | 2.00 | 15000.00 | 17551.96 | 4180.00 |
| BR2706-036 | | I-270 BRIDGE DECK REHABILITAT | 08/11/11 | 1.00 | 10000.00 | 14871.50 | 13591.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 6.00 | 16666.67 | 14242.31 | 9208.32 |
| NH1151-026 | | SH115A MP 38.3 TO 40.3 | 10/06/11 | 1.00 | 10000.00 | 13910.60 | 15948.84 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 630-85040 | Impact Atten (T-M-A) (Temp) | | Each | | | |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 6.00 | 5000.00 | 28671.60 | 7000.00 |
| SHE025A-013 | | I 25 BETWEEN MP 122 AND MP 12 | 11/03/11 | 1.00 | 10000.00 | 8767.68 | 2250.00 |
| FBR 1211-078 | | SH 121 (WADSWORTH AVE.) OVER | 11/17/11 | 2.00 | 15000.00 | 17580.30 | 27575.40 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1.00 | 25000.00 | 31799.29 | 25240.68 |
| NH 0821-098 | | SH 82 MP 20.5-39 EAGLE AND PI | 11/17/11 | 1.00 | 10000.00 | 9840.00 | 1200.00 |
| MC0504-065 | | US50B FROM MP 318 TO MP 359 | 12/01/11 | 2.00 | 14000.00 | 9166.67 | 4000.00 |
| IM0703-368 | | GEORGETOWN HILL CHUTES 6,7,9, | 12/01/11 | 1.00 | 13415.00 | 9794.67 | 12000.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 15.00 | 10427.67 | 21179.45 | 10786.02 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 68.00 | 15175.22 | 15090.19 | 11210.91 |
| ========== | 630-85041 | Mobile Attenuator | | Day | | | |
| ITS4701-121 | | C470 (SANTA FE TO I-25) AND R | 01/20/11 | 5.00 | 400.00 | 298.50 | 256.00 |
| NH 0402-079 | | US40 MP 165.0 - 179.0 GRAND C | 03/31/11 | 2.00 | 600.00 | 805.43 | 408.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 7.00 | 457.14 | 241.66 | 188.49 |
| SHE074A-001 | | SH 74 - EVERGREEN - JEFFERSON | 04/28/11 | 5.00 | 500.00 | 453.33 | 515.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 5.00 | 500.00 | 659.94 | 951.29 |
| C0703-371 | | CULVERT REPAIRS ON I-70 BETWE | 09/15/11 | 10.00 | 500.00 | 411.67 | 445.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 10.00 | 500.00 | 411.67 | 445.00 |
| ITSSW00-928 | | NB I-225 AT MM 2.28 | 11/03/11 | 5.00 | 300.00 | 526.93 | 520.00 |
| STA0343-033 | | SH 34 ECKLEY | 11/10/11 | 5.00 | 550.00 | 677.50 | 500.00 |
| R600-395 | | REGION 6; VARIOUS LOCATIONS | 11/10/11 | 58.00 | 300.00 | 483.60 | 718.00 |
| MC SW00-929 | | STATEWIDE - VARIES | 11/17/11 | 80.00 | 500.00 | 230.00 | 220.00 |
| IM0703-368 | | GEORGETOWN HILL CHUTES 6,7,9, | 12/01/11 | 60.00 | 389.25 | 333.13 | 215.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 208.00 | 408.68 | 375.57 | 380.60 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 230.00 | 416.11 | 414.79 | 491.29 |
| ========== | 630-86800 | Traffic Signal (Temp) | | LUMP SUM | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 1.00 | 50000.00 | 23611.51 | 500.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 630-86800 | Traffic Signal (Temp) | | LUMP SUM | ========== | ========== | ========== |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1.00 | 50000.00 | 23611.51 | 500.00 |
| STU 2254-082 | | US 40(COLFAX) / I-225 | 05/12/11 | 1.00 | 30000.00 | 7459.36 | 6200.00 |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 1.00 | 10000.00 | 9686.42 | 9084.56 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2.00 | 20000.00 | 8572.89 | 7642.28 |
| IM 0252-387 | | I-25 SPEER BOULEVARD TO 20TH | 10/27/11 | 1.00 | 5000.00 | 12004.21 | 9409.00 |
| IM 0702-310 | | I-70 MP 72.3 IN GARFIELD COUN | 12/22/11 | 1.00 | 35000.00 | 7970.21 | 7300.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 2.00 | 20000.00 | 9410.93 | 8354.50 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 5.00 | 35000.00 | 12286.49 | 6248.93 |
| ========== | 630-86810 | Traffic Signal (Temp) | | Each | ========== | ========== | ========== |
| STA141A-035 | | SH 141 UNAWEEP CANYON OVERLAY | 04/14/11 | 2.00 | 15000.00 | 3255.00 | 3100.00 |
| FSA002A-004 | | SH 2 @ 13TH AVE & 14TH AVE | 06/30/11 | 2.00 | 15000.00 | 34957.50 | 32000.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 4.00 | 15000.00 | 15936.00 | 17550.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 3.00 | 25000.00 | 22528.57 | 27000.00 |
| FBR-006A-049 | | US6 AT SHERIDAN BLVD. | 11/17/11 | 1.00 | 25000.00 | 19000.90 | 6036.43 |
| FSAR500-119 | | US 550 ON THE NORTH SIDE OF R | 12/01/11 | 2.00 | 20000.00 | 6000.00 | 5500.00 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 6.00 | 23333.33 | 19669.91 | 16339.41 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 10.00 | 20000.00 | 18801.56 | 16823.64 |
| ========== | 630-86820 | Traffic signal(Temp.)(State Furnished) | | Each | ========== | ========== | ========== |
| FBR089A-013 | | ON SH 89 FROM MP 33.21 TO MP | 01/27/11 | 2.00 | 1000.00 | 2544.34 | 1600.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 2.00 | 1000.00 | 2544.34 | 1600.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 1000.00 | 2544.34 | 1600.00 |

| PROJECT NUMBER | ITEM NUMBER/ | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|---|---|---|---|---|---|---|
| ========== | 631-00100 | Hwy Design & Const | | LUMP SUM | | | |
| FBR0252-415 | | NB I-25 SOUTH OF FOUNTAIN, MP | 12/15/11 | 1.00 | 1121176.00 | 1696386.79 | 1116878.47 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 1121176.00 | 860254.47 | 535626.16 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 1121176.00 | 1940234.00 | 1269030.52 |
| ========== | 631-10000 | Alt Brdg Design and Const | | LUMP SUM | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | 01/20/11 | 1.00 | 8029009.90 | 8310110.35 | 6588686.87 |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| BR0252-407 | | SOUTH OF DOWNTOWN DENVER | | | | | |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1.00 | 8029009.90 | 8310110.35 | 6588686.87 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 8029009.90 | 8310110.35 | 6588686.87 |
| ========== | 631-10002 | Bridge Design and Construction | | LUMP SUM | | | |
| FBR0252-415 | | NB I-25 SOUTH OF FOUNTAIN, MP | 12/15/11 | 1.00 | 1096800.00 | 1365953.64 | 1185461.34 |
| | WEIGHTED | AVERAGE FOR THE FOURTH QUARTER | | 1.00 | 1096800.00 | 899167.60 | 706820.45 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 1096800.00 | 2309600.23 | 1673213.32 |
| ========== | 641-10000 | Shotcrete | | Sq Yard | | | |
| IM 392A-012 | | I-25 AT SH 392 INTERCHANGE LA | 06/23/11 | 2,217.00 | 200.00 | 61.03 | 60.00 |
| | WEIGHTED | AVERAGE FOR THE SECOND QUARTER | | 2,217.00 | 200.00 | 61.03 | 60.00 |
| C0931-030 | | SH 93 SOUTH BOULDER | 08/25/11 | 10.00 | 150.00 | 712.80 | 650.00 |
| | WEIGHTED | AVERAGE FOR THE THIRD QUARTER | | 10.00 | 150.00 | 712.80 | 650.00 |
| STA0072-010 | | PARTIALLY IN BOULDER, FROM CH | 10/27/11 | 835.00 | 150.00 | 170.43 | 163.00 |