

PERMANENT CHANGES TO PROJECT DATED SPECIAL PROVISIONS

REVISION OF SECTION 202 REMOVAL OF EXPANSION DEVICE

DATE	AUTHOR	DESCRIPTION OF CHANGE
12/20/91	MAL	Revised subsection references to conform with the 1991 Standard Specifications Book.
9/17/1999	M.Nord	Verified the specification references for conformance with the <i>1999 Colorado DOT Standard Specifications for Road and Bridge Construction</i> . No exceptions were found. Converted to Microsoft Word 97 SR-2

REVISION OF SECTION 202
REMOVAL OF EXPANSION DEVICE

Section 202 of the Standard Specifications is hereby revised for this project as follows:

Subsection 202.01 shall include the following:

This work shall consist of removing existing bridge expansion devices at locations shown on the plans in accordance with the applicable portions of Section 202 of the Standard Specifications or as amended by these Special Provisions and in conformity with the plans or as directed.

Subsection 202.02 shall include the following:

Removal operations shall be coordinated with the stage construction shown on the plans, indicated in the Special Provisions, or as directed by the Engineer.

The methods and equipment used for the concrete removal shall be approved by the Engineer. The Contractor shall take all steps necessary to avoid damage to all reinforcing steel designated to remain in place. Any reinforcing bars damaged by the Contractor's operation shall be repaired or replaced at the Contractor's expense with no allowance for contract time extension.

Following the removal of the concrete, all exposed reinforcing steel to remain in place, shall be straightened as required and thoroughly cleaned to sound metal by sandblasting. Any structural steel (top of girders and top of diaphragms) damaged by the Contractor during removal, shall be repaired at the Contractor's expense. Exposed concrete surfaces within the removal limits shall be sandblasted to remove all fractured or loose particles in order to promote good bond with the new concrete.

-2-

REVISION OF SECTION 202
REMOVAL OF EXPANSION DEVICE

Subsection 202.11 shall include the following:

Expansion devices removed shall be measured by the linear foot between faces of curbs and parallel to the expansion joint. Saw cutting will not be measured separately but will be included with the work.

Subsection 202.12 shall include the following:

Payment shall be made at the contract unit price per linear foot for the accepted quantity removed.

Payment will be made under:

Pay Item

Pay Unit

Removal of Expansion Device

Linear Foot

Payment will be full compensation for all work necessary to complete the item including saw cutting, and sandblasting.