

Revision of Section 202 Removal of Fence

Revise Section 202 of the Standard Specifications for this project as follows:

Description

This work shall include removing the existing [YY] ■ inch chain link fence per these specifications and conforming with the lines and details shown on the plans or as approved by the Engineer.

Construction Requirements

The Contractor shall remove the full length of existing chain link fence as shown on the plans. The removal shall include all components of the fence except for the existing anchorages, or any components designated to remain in the plans. ◆

Repair in kind any damage caused by the Contractor to any portion of the structure not intended for repair at the Contractor’s expense using means and methods approved by the Engineer with no allowance for contract time extension.

The Contractor is responsible for disposing of all removed material and debris.

Method of Measurement

Removal of Fence will be measured by the actual quantity removed and accepted.

Basis of Payment

The accepted quantities of Removal of Fence will be paid at the contract unit price.

Payment will be made under:

Pay Item	Pay Unit
Removal of Fence	Linear Foot

Payment for Removal of Fence will be total compensation for all labor, materials, tools, equipment and incidentals necessary to complete the item.

Disposal of removed materials and debris will not be paid for separately; include it in the work.

Instructions to Designers (delete instructions and symbols from final draft):

Use this project special provision when removing existing chain link fence from structures where the existing anchors will be reused.

- Edit for height of fence, Bridge Rail Type, and edge/side of structure, as appropriate.

◆ Revise as required if not reusing existing anchorages

Add this requirement to the Fence Worksheet:

Once the fence is removed and the existing anchorage assemblies are exposed, the contractor shall either survey or field measure the layout and spacing of the existing anchorage assemblies to ensure the new fence is fabricated.

to accommodate existing conditions. The survey or field measurement activities shall occur before ordering or fabricating any materials.

Revision of Section 202 Removal Of Fence

<u>Date</u>	<u>Author</u>	<u>Description of Change</u>
1/14/19	BPM Cons.	Initial Website Issue
11.1.21	M. Kayen	Revisions to grammar, format as per CDOT Style Guide (4.22.21)
04.06.2023	M. Kayen	Revisions to make spec online accessibility-compliant. 5.22.23 Additional accessibility work.