

Revision of Section 210 Replace Structure Sign

Revise Section 210 of the Standard Specifications for this project as follows:

Subsection 210.01 shall include:

Description

This work consists of replacing a damaged or missing structure sign to be manufactured and installed in accordance with standard S-614-12.

Subsection 210.12 shall include:

Method of Measurement

Replace Structure Sign will be measured by the quantity of missing or damaged signs as designated in the plans and accepted.

Subsection 210.13 shall include:

Basis of Payment

The accepted quantities of Replace Structure Sign will be paid for at the contract unit price.

Payment will be made under:

Pay Item	Pay Unit
Replace Structure Sign	Each

All work and materials necessary and incidental to replacing structure signs will not be measured and paid for separately but shall be included in the work.

Colorado Project No. Xxxxxx
Project Code Xxxxx

Date

Instructions to Designers:

Use this project special provision when structure signs are missing or damaged and need to be replaced.

Permanent Changes to Project Dated Special Provisions

Revision of Section 210 Replace Structure Sign

<u>Date</u>	<u>Author</u>	<u>Description of Change</u>
9/2024	DC	Initial Web Issue